This is a digital copy of a book that was preserved for generations on library shelves before it was carefully scanned by Google as part of a project to make the world's books discoverable online.

It has survived long enough for the copyright to expire and the book to enter the public domain. A public domain book is one that was never subject to copyright or whose legal copyright term has expired. Whether a book is in the public domain may vary country to country. Public domain books are our gateways to the past, representing a wealth of history, culture and knowledge that's often difficult to discover.

Marks, notations and other marginalia present in the original volume will appear in this file - a reminder of this book's long journey from the publisher to a library and finally to you.

Usage guidelines

Google is proud to partner with libraries to digitize public domain materials and make them widely accessible. Public domain books belong to the public and we are merely their custodians. Nevertheless, this work is expensive, so in order to keep providing this resource, we have taken steps to prevent abuse by commercial parties, including placing technical restrictions on automated querying.

We also ask that you:

+ *Make non-commercial use of the files* We designed Google Book Search for use by individuals, and we request that you use these files for personal, non-commercial purposes.

+ *Refrain from automated querying* Do not send automated queries of any sort to Google's system: If you are conducting research on machine translation, optical character recognition or other areas where access to a large amount of text is helpful, please contact us. We encourage the use of public domain materials for these purposes and may be able to help.

+ *Maintain attribution* The Google "watermark" you see on each file is essential for informing people about this project and helping them find additional materials through Google Book Search. Please do not remove it.

+ *Keep it legal* Whatever your use, remember that you are responsible for ensuring that what you are doing is legal. Do not assume that just because we believe a book is in the public domain for users in the United States, that the work is also in the public domain for users in other countries. Whether a book is still in copyright varies from country to country, and we can't offer guidance on whether any specific use of any specific book is allowed. Please do not assume that a book's appearance in Google Book Search means it can be used in any manner anywhere in the world. Copyright infringement liability can be quite severe.

About Google Book Search

Google's mission is to organize the world's information and to make it universally accessible and useful. Google Book Search helps readers discover the world's books while helping authors and publishers reach new audiences. You can search through the full text of this book on the web at `http://books.google.com/`

A168

PROCEEDINGS

OF THE

ACADEMY OF NATURAL SCIENCES

OF PHILADELPHIA.

VOL. V. 1850 & 1851.

PHILADELPHIA:
PRINTED FOR THE ACADEMY
By Merrihew & Thompson, 7 Carter's Alley.
1852.

LIBRARY
OF THE
LELAND STANFORD JUNIOR
UNIVERSITY.

A

ERRATA IN VOL. V.

Page 14, line 16 from bottom, for *Zeuker* read *Zenker.*
" 22, " 10 " top, for *February* read *August.*
" 55, " 23 " bottom, for *Plumus* read *Plumos.*
" 117, " 16 " " for *Vol.* 5 read *Vol.* 4.
" 154, " 12 " top, for *necessarily* read *unnecessarily.*
" 157, " 4 " bottom, for *Heidinger* read *Haidinger.*
" 169, " 10 " top, for *Dikaj* read *Dijak.*
" 209, " 7 " " for *isossoles* read *isosceles.*
" 209, " 10 " " for *joints* read *points.*
" 210, " 5 " bottom, for *papulus* read *Passalus.*
" 210, " 4 " " for *gulus* read *Julus.*
" 212, " 21 " " for 8 read 13, and for 34 read 54.
" 224, " 10 and 11 from bottom, for *Aspidagaster* read *Aspidogaster.*
" 227, " 2 from bottom, insert John H. Brinton.
" 256, " 5 " " for *Sowerly* read *Sowerby.*
" 259, " 13 " " for *Statisque* read *Statistique.*
" 275, " 10 " top, for *Longstreth* read *Langstroth.*
" 276, " 19 " " for *robustum* read *priscum.*
" 276, " 23 " " for *i.* ½ read *i.* ½.
" 276, " 2 " bottom, before "by" insert "read."
" 295, " 8 " top, for *were* read *are.*
" 296, " 5 " " for *Silliquaria* read *Sigillaria.*
" 297, " 13 " " for *Ireland* read *Iceland.*
" 297, bottom line, for *Arctos* read *maritimus.*
" 301, line 21 from bottom, for *cinqe* read *cinque.*
" 345, top line, for *punctiecollis* read *poricollis.*
" 357, line 21 from top, for *Coaco* read *Cocoa.*
" 357, " 11 " bottom, for *Borneo* read *Africa.*
" 357, bottom line, for *Fiuns* read *Finns.*

[illegible], don. to mus., 357.
Boston Soc. of Nat. History, don. to lib., 40, 41, 63, 162, 231, 298, 301, 358.
Boguslawski, Dr., don. to lib., 232.
Cantor, Dr. Theodore, don. to mus. 255; don. to lib. 256.
Christman, J., don. to mus., 71.
Chipman, Isaac, don. to mus., 358.



Charleston Med. Journal and Review, don. of by Editors, 232, 257, 301, 302, 361.
Coates, Dr. B. H., don. to mus., 133.
Coleman, Dr., don. to mus., 357.
Committees, standing, for 1850, 2; for 1851, 144.
Committee on Mr. Conrad's description of new species of Eocene shells, 2; on P. A. Browne's description of tegumentary appendages of the Ornithorynchus paradoxus, 2: on Mr. Conrad's new species of fresh water shells from Arkansas and from Australia, 7; on Dr. Lewis R. Gibbes' Catalogue of Crustacea in the Cabinet of Academy, 22; on P. A. Browne's description of hair of head of Albinos, 22; on Dr. Leidy's new species of Entophyta, 33: on Dr. Leidy's new American species of Annelida abranchia, 34; on Mr. Cassin's new sp. of Vidua, Hirundo, &c., 56; on Mr. Moss's new Carpolite from Arkansas, 56; on Mr. Cassin's new sp. of Pastor, Paridisea, and Buceros, 66; on Drs. Owen and Shumard's new Crinoidea from Iowa, 66, 235; on Dr. Leidy's description of a new species of Ligula, 83; on Dr. Deane's fossil footprints of Connecticut river, 95; on Dr. Townsend's description of Lupus gigas, 95; on Mr. Cassin's description of new Birds from California, collected by J. G. Bell, 95; on Dr. Leidy's description of three Filariæ, 117; on Dr. Leidy's new genera of Vermes, 119; on Dr. T. C. Henry's new species of Centrarchus, 121; on Mr. Cassin's new species of duck, 123; on Dr. Woodhouse's descr. of Canis frustror, 139; on Mr. R. C. Taylor's Notes of a geolog. exam. in the aurif. porphyry region next the Caribbean Sea, in Veraguas and the Isthmus of Panama, 139; on Dr. B. H. Coates's paper on the antiquity of Tin, 142; on Dr. Leidy's new Entozoa, 142, 201; on Mr. Cassin's sketch of the genera Vireo and Vireosylvia, 149; on Mr. Cassin's new species of Bucco, 149; on do.'s Notes on the Caprimulgidæ in Mus. A. N. S. 173; on Col. M'Call's paper on the Birds of Western Texas and New Mexico, 210; on Dr. Leidy's Contributions to Helminthology, 212, 237, 275, 331; on Prof. J. D. Dana's Conspectus of the Crustacea of the Am. Explor. Exp., 237, 264; on Dr. Fisher's new sp. of Cicada, 237; on Mr. Cassin's description of Laniadæ, 237; on Dr. Le Conte's paper on the Longicorn Coleoptera of the U. S., 263, 329; on Mr. Cassin's Catalogue of Caprimulgidæ in Col. A. N. S., 276; on Ch. Girard's sketch of the Gordiaceæ, 276; on Mr. Lea's paper on the genus Acostæa of D'Orbigny, 277; on Dr. Le Conte's Synopsis of the sp. of Donacia, 307; on Dr. L.'s Zoological Notes, 307; on Dr. Leidy's Amer. fresh-water Polyzoa and on a new sp. of fossil Crocodile, 310; on Dr. Owen's description of a new mineral and a new earth, 323; on Mr. Girard's new genera of Planariæ, 329; on Mr. Cassin's description of new species of Laniarius, Dicrurus, Graucalus, &c., 329; on Dr. Le Conte's synopsis of the Lampyridæ of temperate North America, 331.
Committee on the occasion of the decease of Dr. S. G. Morton, 204, 205.
Committee on the Cicada Septendecim, 209.
Committee to solicit subscriptions for enlarging Hall of the Academy, 355.
Conrad, T. A., don. to mus., 159, 191; description of new fresh-water shells from Arkansas and from Australia, 10.
Cooke, John, don. to mus., 160.
Couper, J. Hamilton, don. to mus., 159.
Correspondents elected:
Bartlett, John R., New York, 66.
Diesing, Dr. C. M., Vienna, 147.
Dewey, H. Bond, Para, Brazil, 54.
Evans, Dr. John, Indiana, 106.
Girard, Charles, Washington, 157.
Haidinger, Wm., Vienna, 157.
Henry, Dr. T. C., New York, 66.
Hough, Dr. F. B., do., 209.
Hyrtl, Prof. Joseph, Vienna, 157.
Lagos, Chev. Manoel Ferreira, Rio Janeiro, 4.
Malherbe, M. Alfred, Metz, 30.
McMichael, Capt. Wm., New York, 59.
Swift, Robert, St. Thomas, 254.
Tardieu, Ambrose, Paris, 236.
Von Hauer, Baron, Vienna, 157.
Culbertson, Joseph, don. to mus., 37.
Curator's Report for 1850, 129; for 1851, 354.
Cresson, Elliott, don. to mus., 37.

Dana, Prof. J. D., don. to lib., 16.
Conspectus of the Crustacea of the U. S. Exploring Expedition, 247, 267.

Hopkinson, Dr. J., don. to mus., 191.
Hough, Dr. Franklin B., don. to mus., 72.
Hull, Mrs., don. to mus., 37.
Hutton, William, don. to mus., 229.

Imperial Soc. of Naturalists of Moscow, don. to lib., 257, 300.

Jamieson, Capt., don. to mus., 297.
Jardine, Sir Wm., don. to lib. 135.
Jay, Dr. John C., don to lib., 136.
Johnson, Dr. Wm. P., don. to mus., 38.
Johnson, Prof. W. R., don. to lib., 39, 47, 51, 77.
Jones, Joseph, don. to mus., 159.
Jones, Dr. Wm. L., don. to mus., 61.
Journal of Indian Archipelago, &c., don. of by Editor, 39, 78, 113, 135, 192, 196, 256, 301.

Kane, Dr. E. K., don. to mus., 298, 357.
Kaup, Dr. J. J., don. to lib., 301.
Kern, E. H., don. to mus., 297.
Kilvington, Robert, don. to mus., 14, exhibition by of Australian plants, 81.

Lacordaire, M. Th., don. to lib., 18.
Lambert, John, don. to mus., 71; don. to lib., 16.
Lankaster, Dr. E., don. to lib., 198.
Lasbury, Mr., don. to lib., 76.
Land, Capt. John, don. to mus., 107.
Lea, Isaac, don. to mus., 191, 229, 255, 297, 298, 357; don. to lib., 358, 361; on the fossil locality in Lehigh Co., Penn., 171, 173, 205; on a new locality for Zircon, 211; Necrological notice of Richard C. Taylor, 290; on the Wave Theory, 261; on the genus Acostæa d'Orbigny, 277.
Le Conte, Dr. John L., don. to mus., 298, 358; don. to lib., 362; on some fossils from California, 264; synopsis of the species of Donacia of the U. States, 310; Zoological Notes, 316; Synopsis of the Lampyrides of temperate North America, 331.
Leeds Literary and Philosoph. Soc., don. to lib., 18, 40, 256.
Leidy, Dr. Joseph, don. to mus., 13; don. to lib., 16, 17, 40, 41, 134, 160, 162, 196; on Entophyta in the bodies of animals, 7, 8; on crystalline bodies in the tissues of plants, 32; on new Entophyta, 35; on Eucrotaphus Jacksoni and Archæotherium Mortoni, 90: Contributions to Helminthology, 96, 205, 224, 239, 284, 349; development of the Gordius aquaticus, 98; on two new species of infusorial Entozoa, 98; on some Nematoid Entozoa infesting insects, 100; description of three Filariæ, 117; on Rhinoceros occidentalis, 119; on the nettling organs of the hydra, 119; on some fossils from Missouri, 121; on new genera of Vermes, 124; on some fossils from Big-bone Lick, Kentucky, 140: new species of Entozoa, 155; on some fragments of Palæotherium Proutii, 170; on a fossil tortoise from Nebraska, 172, 173; on the transplantation of animal tissues, 201; on fungus growth in the mole-cricket, 204, 210; on the introduction of cancerous matter into the integument of the frog, 212; on fungus disease in Cicada septendecim, 235; on some fossil ruminants from Nebraska, 237; on the genus Plumatella, 261; on the Gordiaceæ, 262, 275; on Cristatella, 265; on Oreodon robustum, 276; on some fossils from Nebraska, 278; on Spongilla fragilis, 278; on Crocodilus antiquus, 307; on two fossil species of Balæna, 308; on some American Fresh-water Polyzoa, 320; on various fossil reptilian and mammalian remains, 325; on some fossils from the green sand of New Jersey, 329; on two species of fossil Rhinoceros from Nebraska, 331.
Letters from Individuals:—
Baird, Prof. S. F., 1.
Becker, T. J., 8.
Berlandier, Dr. Louis, 149.
Browne, Peter A., 53.
Burtt, Dr. J. L., 308.
Chipman, Isaac, 307.
Cresson, Elliott, 21.
Deane, James, 30, 33.
Dewey, H. Bond, 145.
Drinker, Sandwith, 1.
Evans, Dr. John, 123, 139.
Executors of Dr. A. Binney, 261.
Gliddon, George R., 139.
Gossler, J. S., 172.
Graham, Col. J. D., 81.
Grex, J. A., 90.
Haidinger, Wm., 235.
Harris, A. C., 83.
Henry, Dr. T. C., 121.
Hooper, John, 173, 211.
Hough, Dr. F. B., 66.

Brinton, John H. 227.
Buck, Francis N., 4.
Burtt, Dr. J. L. 296.
Caldcleugh, Robert A, 323.
Fisher, Dr. James C., 66.
Fox, Samuel M., 11.
Jordan, John, Jr., 144.
Langstroth, Rev. L. L., 275.
Lennig, Francis, 236.
Patton, Rev. John, 356.
Rand, Dr. B. Howard, 144.
Remington, Richard P., 118.
Rosengarten, Samuel G., 54.
Sherman, Dr. Wm. L., 296.
Smith, Aubrey H., 83.
Smith, Charles E., 227.
Wheatley, Charles M., 30.
Wister, Dr. Caspar, 227.
Mercantile Lib. Assoc. of New York, don. to lib., 196.
Metternich, Prince, don. to lib., 304.
Mitchell, Prof. J. K., don. to mus., 230.
Mitchell, Dr. J. Wier, don. to mus., 357.
Miller, Edward, don. to mus. 357.
Morris, Miss E. C., don. to mus., 61.
Morris, F. O., don. to lib., 137.
Morton, Dr. S. G., don. to lib., 16, 18, 51, 72, 79, 109, 134, 135, 160, 196; dep. in mus., 107, 160, 191, 220; continuation of memoir on size of brain in the races of man, 1, 2, 30, 33; on the conformation of the Egyptian cranium, 4; announcement by of decease of Dr. Gerard Troost, 70; remarks on the term "species," 81; on Mr. Layard's plates of the camel and dromedary from ruins of Ninevah, 84; on the antiquity of some races of dogs, 85; on embalmed Egyptian crania, 122; on the races of dogs, 139: on the cranium of a Dijak, 146; announcement by of decease of J. J. Audubon, 146; on the cranium of the mummy dissected by George R. Gliddon, 170; on the infrequency of mixed European and Australian races, 173.
Moultrie, Dr. James, don to lib., 361.
Moss, Theodore F., don. to mus., 61, 71; don. to lib., 50, 63; description of a new Carpolite from Arkansas, 59.

Nash, Robert H., don. to mus., 298.
National Institute, don. to lib., 196.
Neill, Dr. John, don. to mus., 197.
Netherlands Institute of Science, don. to lib., 51.
Newport, George, don. to lib., 301.
New York State Library, Trustees of, don. to lib., 18, 46, 191, 301.
Norris, J. Parker, don. to mus., 72.

Officers for 1851, 132; for 1852, 356.
Ogden, David, don. to mus., 133.
Ord, George, don. to lib., 160, 165, 166 232, 301; portrait of received, 201 resolution by, in relation to decease of Wm. Hembel, 213.
Owen, Dr. D. D., on the fossils from the "mauvaises terres" of Missouri, 66, 328.
Owen, Prof. Richard, don. to lib., 76.

Palæontographical Society, don to lib., 301.
Pearsall, Robert, don to lib., 192.
Pennsylvania Farm Journal, don. of, by editors, 256, 299, 302, 360, 362.
Philadelphia Museum, don. to lib., 61.
Piddington, Henry, don. to lib., 113.
Powel, Col. J. Hare, don. to lib., 302.
Powel, Samuel, don. to mus., 159, 229, 230, 255; don. to lib., 302; dep. in lib, 198.
Powel, J. Hare, Jr., don. to mus., 191.
Potier, M., don. to lib., 301.
Procter, Wm., Jr., don to mus., 133.
Publication Committee of Acad. Nat. Sci. don. to lib., 17, 135; announcement by, of publication of part 4, vol. 1, new series of Journal; do. of part 1, vol. 2, do.

Rand, Dr. B. H., don. to mus., 229, 298.
Ransome, George, don. to lib., 198.
Ravenel, H. W., don. to mus. 37; don. to lib., 41.
Recording Secretary, report of, for 1850, 142.
Regents of Univ. of State of New York, don. to lib., 39, 62, 301.
Redfield, J. H., don. to lib., 74, 160.
Reeve, Lovell, don. to lib., 256.
Retzius, Prof. A., don. to lib., 360.
Report of Committee on Mr. Conrad's new Eocene fossils, 4; on Mr. P. A. Brown's paper on the hair of the Ornithorynchus paradoxus, 30; on Dr. Leidy's new American Annelida abranchia, 36; on Drs. Owen and Shumard's new species of crinoidea from Iowa, 69, 235: on Mr. Deane's fossil foot-prints of the Connecticut river, 96, on Dr. Townsend's description of Lupus gigas 96; on Mr. R. C. Taylor's notes of a geological reconnoisance of the auriferous porphyry region next the Ca-

Strickland, H. E., don. to mus., 37; don. to lib., 51, 76, 135, 192, 196, 256, 301.
Swiss Nat. Hist. Soc., don to lib., 198.

Taylor, Richard C., don. to mus., 298; don. to lib., 298; meterolog. observations made at the Isthmus of Panama, &c., 94.
Taylor, Frederick, don. to mus., 133.
Thompson, Wm., don. to lib., 79.
Townsend, Dr. J. K., don. to mus., 13, 107 : life membership conferred on, 30.
Trautwine, J. C., don. to mus., 159, 297.
Treasurer of the Academy, announcement by, of receipt of Mrs. Stott's legacy, 190.
Troschel, Dr., don. by, of Archiv für Naturgeschichte, 77, 256.
Tuckerman, E., don. to lib., 192.
Turnbull, Dr. L., don. to lib., 192.

U. S. Departments, don. to lib., 41, 192, 232, 302, 360, 361.

Vaux, Wm. S., don. to mus., 191, 229, 297, 357, 358; don. to lib., 40; decease of Dr. R. E. Griffith announced by, 65.
Verreaux, M. Edouard, don. to mus., 37.
Verreaux, M. Jules, don. to mus., 71, 133; don. to lib., 137.

Ward, Wm., don to. mus., 358.
Waterhouse, Geo. R., don. to lib., 76.
Watson, Dr. Gavin, don. to mus., 107, 133, 159, 191, 255.
Warwick, Mr , don. to mus., 71.
Western Journal of Agriculture, don. of by editors, 15.
Wetherill, J. Price, don. to mus., 297, 358; announcement by, of decease of Dr. Morton, 203.
Wilson, Dr. Thomas B., don. to mus. 13, 14, 38, 39, 61, 72, 107, 133. 159, 297, 357; don. to lib., 14, 15, 16, 17, 18, 19, 40, 41, 42, 43, 44, 45, 46, 47, 48, 49, 50, 51, 52, 62, 63, 64, 72, 73, 74, 75, 76, 77, 78, 79, 108, 109, 110, 111, 112, 113, 114, 115, 134, 135, 136, 162, 166, 192, 194, 230, 232, 256, 257, 298, 301, 302, 358, 359, 360, 361, 362.
Wilson, Edward, don. to mus., 133, 255, 297, 357, 362; don. to lib., 77, 135, 137, 138, 160, 161, 162, 163, 164, 165, 166, 167, 168, 192, 193, 194, 195, 196, 197, 198, 199, 200, 230, 231, 257, 258, 259, 299, 300, 304, 305.
Wilson. E. T. & C. W., don. to mus. 71, 255.
Wood, Prof. Geo. B., don. to mus., 133.
Wood, Geo. B., don. to mus., 37.
Wood, Wm., don. to lib., 76.
Wood, Wm., don. to mus., 71, 160, 256, 296.
Woodhouse, Dr. S. W., on the North American Jackal, Canis frustror, 147.

Yorkshire Philosoph. Soc., don. to lib., 76.

Zantzinger, Dr. Wm. S., don. to mus., 256; announcement by, of decease of Wm. Hembel, 212.
Zeublin, Mr., don. to mus., 160.
Zoological Soc. of London, don to lib., 51, 113, 196.

PROCEEDINGS

OF THE

ACADEMY OF NATURAL SCIENCES

OF PHILADELPHIA.

January 1, 1850.

Dr. MORTON, President, in the Chair.

A letter was read, dated New York, December, 1849, accompanying the donation made this evening of the Python, from Mr. Sandwith Drinker, of Hong Kong, China.

Also a letter from Mr. J. M. Richardson, of London, dated November 30, 1849, desiring information of a mode of transmitting to the Academy certain Nos. of the Journal of the Indian Archipelago.

Dr. Morton, having resigned the Chair to Mr. Ashmead, read a continuation of his Memoir on the size of the Brain in the various races and families of Man; which was referred to the Committee on the previous portions of the paper.

A communication was read from Prof. Spencer F. Baird, Correspondent of the Academy, dated December 21, 1849, desiring to be considered as a *Member* from that date.

January 15*th.*

Dr. MORTON, President, in the Chair.

Dr. Morton read a continuation of his paper on the size of the Brain in the various races of Man, which was referred to the Committee on the previous portions.

He then followed with some remarks on the volume of the brain in the savage tribes, which he stated to be greater than in the half civilized races of Mexico and Peru. He mentioned some facts proving the antiquity of the characteristics of the several groups of the human race, and exhibited some plates from the forthcoming work of Dr. Lepsius, representing purely Egyptian forms copied from bas-reliefs in tombs at the base of the great Pyramid, dating back 3400 years before Christ. Also some copies of pictures in temples more than 2000 years later, still exhibiting the same well marked characters of

the race: the greater the antiquity, the more decided were these characters.

Dr. Morton thought that it would be now admitted that at the earliest period known, the groups of the human family presented as great diversity as at present. The Egyptian crania in his collection, taken from the identical tombs referred to, at the base of the great Pyramid, as well as those from Thebes and Memphis, when compared with the figures in Dr. Lepsius' plates, exhibited a most marked resemblance. The Egyptian tombs, although occupied by successive families, still contained the original occupants, and in all places presented skulls possessing the same peculiarities of type. The modern Egyptian Fellahs are the old Egyptians crossed with the Arabs. The skull of the old Egyptian cannot be confounded with that of any other race.

January 22d.

Dr. MORTON, President, in the Chair.

Mr. Conrad read a paper, intended for publication in the Journal, entitled, "Descriptions of eight new species of Eocene Shells." Referred to Mr. Phillips, Dr. Griffith and Dr. Wilson.

A paper by Mr. Peter A. Browne, entitled "Examination and descriptions of the tegumentary appendages of the Ornithorynchus paradoxus," was read and referred to Mr. Phillips, Dr. Morton and Mr. Cassin.

Dr. Morton having resigned the Chair to Dr. Ruschenberger, made some remarks supplementary to those offered at the last meeting, and also in continuation of the subject of his Memoir on the size of the Brain in Man.

January 29th.

Mr. PHILLIPS in the Chair.

The Publication Committee announced that Part 4, Vol. 1, New Series of the Journal, would be ready for distribution at the next meeting, February 5th, 1850.

The Society, after the transaction of some other business, then proceeded to an election for Standing Committees for the ensuing year, with the following result:—

COMMITTEES FOR 1850.

Ethnology.

S. G. Morton, J. S. Phillips,
Charles Pickering.

Comparative Anatomy and General Zoology.

Joseph Leidy, S. G. Morton,
Edward Hallowell.

Mammalogy.

J. S. Phillips, Joseph Leidy,
Samuel W. Woodhouse.

Ornithology.

Edward Harris, John Cassin,
John K. Townsend.

Herpetology and Ichthyology.

E. Hallowell, R. E. Griffith,
John Cooke.

Conchology.

R. E. Griffith, T. A. Conrad,
Henry C. Lea.

Entomology and Crustacea.

S. S. Haldeman, R. Bridges,
Wm. S. Zantzinger.

Botany.

R. Bridges, Wm. S. Zantzinger,
Gavin Watson.

Palæontology.

T. A. Conrad, Richard C. Taylor,
Thomas B. Wilson.

Geology and Mineralogy.

J. Price Wetherill, Samuel Ashmead,
Wm. S. Vaux.

Physics.

Thomas C. Percival, Samuel Powel,
Robert Kilvington.

Library.

Robert Bridges, Thomas B. Wilson,
John Lambert.

Committee on Proceedings.

S. G. Morton, Wm. S. Zantzinger,
Joseph Leidy.

The Treasurer of the Publication Committee read the Annual Report, which was adopted.

The Auditors reported that the Treasurer's account for 1849 had been examined by them, and found correct.

The Committee to which was referred Mr. Conrad's paper, describ-

ing eight new species of Eocene fossils, reported in favor of its publication in the Journal.

The following resolution, offered by Dr. Bridges, was adopted:

Resolved, That the resolution, passed June 29th, 1847, allowing the Publication Committee to supply subscribers to the Journal with the Proceedings gratis, be rescinded.

On motion of Mr. Vaux, it was

Resolved, That the Publication Committee be authorised to present Vol. 1, New Series of the Journal, to the Royal Historical and Geographical Society of Rio Janeiro.

ELECTION.

Francis N. Buck, Esq., of Philadelphia, was elected a *Member;* and the Chevalier Manoel Ferreira Lagos, of Rio Janeiro, was elected a *Correspondent* of the Academy.

February 5th.

Dr. Morton, President, in the Chair.

Letters were read:

From the Secretary of the Linnean Society, of London, acknowledging the receipt of Part 3, Vol. 1, New Series of the Journal.

From the Principal Librarian of the British Museum, returning acknowledgments for Nos. 9 and 10, Vol. 4, of the Proceedings.

From the Corresponding Secretary of the National Institute at Washington, acknowledging the receipt of Nos. 9, 10, and 11, Vol. 4, of Proceedings.

Dr. Morton, in confirmation of some remarks made on several previous occasions, on the characteristic conformation of the Egyptian cranium, exhibited several skulls from his collection, taken from tombs dating upwards of 3000 years before the Christian Era. These skulls showed a remarkable delicacy of structure of the whole cranio-facial region; the cranium being of an elongated oval form, the facial angle averaging 78°, and the internal capacity 80 cubic inches; in the last respect corresponding to the modern Fellah of the Nile.

The expression of the bones of the face of the ancient Egyptian is neither European nor Asiatic, but peculiar, *sui generis*. The Arab-Egyptian, or Fellah of the present day, is the Arab engrafted on the Ancient Egyptian, and dates from the sixth century of our Era. All the Coptic heads of the present period have some negro characters: they are those of the population of the towns which are notoriously licentious. The Fellahs, or rural population, are free from this taint.

February 12th.

Dr. MORTON, President, in the Chair.

Dr. Leidy read the following, being a report by Prof. Haldeman, Chairman of the Committee on Entomology, on the progress of that science during the past year.

Report on the Progress of Entomology in the United States during the year 1849.

By S. S. HALDEMAN.

Whilst the progress of Entomology during the year 1849 has been sufficiently encouraging, it cannot be doubted that it would advance more rapidly if there were one or more general works upon the subject, adapted to this country. The student is now retarded either by the extent of the subject, or because he cannot consult standard collections, works, or figures of American genera and species; whilst such as have passed through the preliminary difficulties, generally prefer original research to the preparation of works which partake in some degree of the nature of compilations; and on account of the expense of figures, authors usually limit them to their own discoveries.

Another cause which retards the natural sciences in general, in a country where the amount of material to be investigated is extensive, is the want of instruction in them in our educational institutions, in but few of which their claims to a place among the sciences are acknowledged. Such causes tend to limit the number of observers, and must be taken into consideration in estimating the condition of certain sciences in this country.

1. J. L. LECONTE M.D. *Synopsis of the Coleopterous Insects of the group Cleridae* which inhabit the United States. 28 pages 8vo. Annals of the Lyceum of N. Y. This synopsis, besides a full synonymy, contains the characters of ten new species. Many of the American species are figured in a very neat and beautiful style in Spinola's Essai monographique sur les Clerites, the last work of this active entomologist.

2. Dr. LeConte has also produced a *Catalogue of Coleoptera*, including diagnoses of a considerable number of new species, collected in a journey to Lake Superior with Prof. Agassiz and his companions. On the point of publication.

3. ——— On the Pselaphidae of the United States. Bost. J. nat. hist. 1849. vol. 6. p. 64—110.

4. ——— General Remarks on the Coleoptera of Lake Superior. In Agassiz Excursion. P. 201—242. 8vo.

5. S. S. HALDEMAN. *Cryptocephalinarum Boreali-americae diagnoses*, etc. J. Acad. nat. sci. 1,245. 20 pages 4to. The synonymy and full descriptions of the species known to the author are given. Short diagnoses of the 24 new species are given in the Proceed. Acad. for April, 1849; 4,170.

6. ——— *New Hymenoptera of the genera Ampulex, Sigalphus, Chelonus, and Dorylus.* Pr. Acad. 4,203.

7. ——— *On the larva of Physocoelus* inflatus *Dej.* (Helops contractus *Mels.* 1846. Pr. Ac. 3,61. H. contractus *Beauv.* H. striatus Oliv.?) Read before the

Am. Assoc., of the proceedings of which various reports were made. This larva is much like that of Tenebrio, but the mandibles differ somewhat, and the anal segment is truncated in a slope, the surface of the truncation being cupshaped.

8. ——— *History of Phalangopsis*, a genus of Orthoptera, with three new species, two of which form a subgenus. Am. Assoc.

9. M. A. Morris who has carefully studied the genus Cecidomyia, has announced a new species (Pr. Acad. 4,194) named C. culmicola, from its habit of living within the stem of the grain.

10. J. W. Dawson Esqr. of Pictou, Nova scotia, has announced the appearance of the European *Cecidomyia tritici* in that province. Pr. Acad. 4,210.

11. T. S. Savage M.D. has given some valuable details (Pr. Acad. 4,194) relative to the economy of the *driver ants* of Africa, hitherto regarded as a distinct genus under the name of Anomma; but the observations of Dr. S. show that they are neuters of the genus Dorylus.

12. ——— The same observer furnishes a full account of the habits of *Termes fatalis*, extending to ten closely printed pages. Pr. Acad. 4,211.

13. Jos. Leidy M.D. has an anatomical paper on the odoriferous glands in the Invertebrata, illustrated with a plate. Pr. Acad. 4,234.

14. ——— The same author has a paper on Entophyta, and new Entozoa, in the Articulata. id.

15. *Prof. L. Agassiz* announced at the last meeting of the American Association that the respiratory tracheae of insects terminate in an enlargement or sac which may be considered minute lungs. The circulatory or fluid-bearing tracheae terminate in minute threads.

16. Asa Fitch M.D. The second Annual Report of the Regents of the university of N. Y. on the condition of the State cabinet of Natural history (Albany, 1849) contains a catalogue by Dr Fitch, of about 350 species of insects, mostly Coleoptera, intended to form the nucleus of a collection in a department which had been previously neglected in forming the cabinet, and preparing the zoology of the State.

17. During the year, *Economic entomology* has been enriched by the discovery by Miss Morris, of a new destroyer of the peach tree, which proves to be the *Tomicus liminaris* of Say. It wounds the bark by boring through it and feeding upon the living portion. I have found another bark borer (*Hylesinus aculeatus* Say) feeding upon the inner living bark of the white ash, *Fraxinus* acuminata. Miss Morris has communicated to me a curculionid, the *Baris tripunctatus* of Say, which a friend of hers discovered to be one of the destroyers of the potato, in the stem of which the larva bores passages and undergoes its transformations.

The Crustacea have been enriched during the past year by the elaborate and valuable papers of Prof. Dana.

18. J. D. Dana. *Synopsis of the family Gammaracea.* Am. J. Sci. 8,135—140 (and 428) including characters of the families, subfamilies and genera. Five new genera are given.

19. ——— *Conspectus Crustaceorum quae in Orbis Terrarum Circumnavigatione, Carolo Wilkes e Classe Reipublicae Foederatae Duce, lexit et descripsit Jacobus D. Dana.* Proceed. Am. Acad. Boston 1,150—154, and 2,9—61. Am. J. Sci. 8,276—285. This paper contains a revision of the generic characters of

from Acheta abbreviata, etc. He remarked that when such plants were found in animals they were usually very abundant.

Dr. L. then stated that very slight modifications in the five essential conditions of life were sufficient to produce the vast variety of living beings upon the globe. As an instance, he mentioned he had lying upon his table a saucer with a cork bottom, in which lay a partly dissected Passalus cornutus half immersed in water. Two days afterwards he noticed upon the part of the insect above the water a quantity of Mucor mucedo? growing, and from the part within the water numerous fine, stiff filaments, which upon examination proved to be Achyla prolifera; upon the cork around the insect grew a third genus, consisting of fine cottony filaments, which were articulated, of which he exhibited a drawing; and upon the insect at the surface of the water, but not within the latter, grew a fourth genus, of which he also exhibited a drawing.

He also stated he had had the good fortune of observing in a single morning all the stages of development of Achyla prolifera growing from some individuals of Ascarides which had been lying in a dish of water for a few days.

In reply to some remarks made by members, Dr. Leidy said he could not admit the doctrine of spontaneous generation, but rather thought modifications in the essential conditions of life favorable to the development of different, and always pre-existing germs derived from a parent.

February 19th.

Dr. Morton, President, in the Chair.

A letter was read from Mr. J. T. Becker, dated Paris, 10th December, 1849, proposing exchanges with the Academy in Entomology. Referred to the Committee on Entomology.

Also a letter from H. Lecog, dated Clermon-ferrand, January 10, 1850, proposing exchanges in Conchology with the Academy, or with individual members of the Society. Referred to the Committee on Conchology.

Dr. Leidy offered the following observations:

Dr. Leidy presented to the examination of the Society a colored and several other drawings of what he termed an entophytic forest, taken from a portion of the mucous membrane of the ventriculus of Passalus cornutus. He remarked that at least six species of entophyta were found growing upon the mucous membrane of the ventriculus of P. cornutus, which were often present in great quantity, frequently some thousands, and which from their number, polymorphous appearance of several species, and attachment to various appendages of the mucous membrane, resembled very strikingly a miniature Brazilian forest, which was heightened in some degree by the existence of a nematoid worm, which recalled to mind the idea of one of the serpents of such a forest.

A somewhat similar drawing he exhibited, taken from the small intestine of Julus marginatus.

Other drawings were also presented. Dr. L. stated that among his collection of living Julides, he had a number of times observed individuals to become dull

in color, and become almost motionless, which phenomena were followed by the death of the animal. It occurred to him that, in such a state, there might be exhibited some change in the character of its entophyta, as usually found in the active condition of the animal. Upon removing the intestine of an individual which had just died, he noticed that the entozoa which usually occupied the small intestine, had passed into the rectum, and upon the surface of the mucous membrane of the former, was developed a new plant. This is an oblate spheroidal body, white in color, translucent, embossed upon the surface, and presenting, when viewed by transmitted light, some resemblance to a minute bleached shell of an Echinus; by reflected light, it resembled a minute, white Lycoperdon. This plant was strewed all over the mucous membrane, but grew in greatest quantity along the course of filaments of Enterobrus, which appeared attached to the mucous membrane throughout their length by it. When compressed it opened, and spread into several leaf-like segments, and exuded a clear fluid with faint granules. He thought that probably this plant might be another stage in the existence of Enterobrus, for in the large number of individuals of Julus which he had examined, upwards of 130, although he had observed the development of Enterobrus from spore-like bodies, even to the formation of what he supposed to be the sporangia, yet he had never been able to detect the formation of spores, and when he saw this new plant enveloping the Enterobrus filaments, he suspected that there might be a phenomenon here presented analogous to the alternation of generation in certain animals, but had not yet satisfied himself that such was the case.

He also stated he had discovered a fourth species of Enterobrus in Polydesmus virginiensis, and another entophyte analogous to Enterobrus growing in Polydesmus granulatus. The latter differs from Enterobrus in having numerous globular cells at the free extremity of the principal cell. He adverted to the several theories of cell formation, and said that in the last mentioned plant, in the development of the globular terminal cells, the division of the permanent cell wall followed the division of the cell contents. In conclusion, he observed, that these matters would be more fully treated of hereafter, in a memoir which he was preparing on the subject.

February 26th.

Dr. MORTON, President, in the Chair.

The Committee on Conchology presented a report, recommending that M. Lecoq's proposition, for an exchange of shells, be declined. Adopted.

The Committee on Mr. Conrad's paper, read February 12th, 1850, reported in favor of publication in the Proceedings.

*Descriptions of new species of fresh water Shells.**

By T. A. Conrad.

UNIO.

U. cultelliformis. Oblong, compressed, thin posteriorly, slightly thickened anteriorly, contracted obliquely from beak to base; umbonal slope rounded, ventricose; ligament and basal margins parallel; posterior margin slightly contracted, oblique; extremity rather obtusely rounded; basal margin nearly straight or slightly contracted; epidermis olive-brown with strong concentric lines; within bluish-white; cardinal teeth oblique, compressed, disposed to be double in each valve; lateral teeth compressed, slightly arched. 2¼. 1¼.

Local. Bogan river, Australia.

U. Napeanensis. Oblong-suboval; anterior margin regularly rounded; posterior margin obtusely rounded and nearly direct, extremity acutely rounded, situated but little above the basal line; ligament and basal margins parallel; basal margin slightly contracted; disk contracted obliquely from beak to base; umbo with irregular angulated wrinkled plicæ concentrically arranged; epidermis blackish-brown, obscurely rayed towards the base; within bluish-white, with wax-colored stains; cardinal teeth compressed, disposed to be double in each valve. 1¼. 1¼.

Local. Napean river, Australia.

U. Balonnensis. Suboval or somewhat trapezoidal; disk contracted from beak to base; posterior side inflated; posterior margin obliquely truncated, extremity acutely rounded and much above the line of the base; ligament and basal margins parallel; basal margin nearly straight in the middle; umbonal slope rounded; posterior submargin with transverse wrinkled lines; epidermis olivaceous, strongly lined concentrically; within white; lateral teeth compressed; cardinal teeth elongated, compressed, very oblique, single in each valve, or slightly disposed to be double in the right valve.

Local. Balonne river, Australia.

The posterior slope in two specimens is furnished with transverse wrinkled prominent lines, but this does not appear to be a constant character of the species. 2¼. 1¼.

U. Aberti. Suboval, much compressed, contracted from beak to base; posterior margin truncated, direct; basal margin contracted posteriorly; beaks submedial; umbonal slope prominent or ridged, rounded; middle of disk with irregular plicæ, running from umbo to base, becoming obsolete at base; posterior slope with wrinkled lines and small plicæ; epidermis olive-yellow, with small, very numerous green dots, and a few broad rather indistinct rays; within pale pink; cardinal teeth thick, direct. 1¼. 1¼.

Local. Chambers' Ford, rapids of Verdigris river, Arkansas. Dr. Woodhouse.

Dedicated to Col. J. J. Abert.

PALUDINA.

P. sublineata. Ventricose-conoidal; subumbilicated; volutions 5, somewhat

* Received by the Academy in exchange from the Australian Museum.

scalariform, ventricose; epidermis olive, polished, with minute obsolete revolving lines; body whorl subcarinated in the middle; aperture suboval. ½. ¼.

Local. Darling river, Australia.

PHYSA.

P. pectorosa. Subovate; volutions 4 or 5; spire short; apex eroded; penultimate whorl ventricose; columella with a prominent, compressed, triangular, oblique tooth or fold; epidermis olivaceous, clouded with brown. ½. ¼.

Local. Bogan river, Australia.

P. Australiana. Elliptical, thin, diaphanous; volutions 4 or 5, regularly convex; spire short; epidermis amber-colored; columella with a slender prominent fold, which revolves within to the apex; margin of labrum regularly curved or rounded. ½. ¼.

Local. Bogan river, Australia.

MELANIA.

M. tetrica. Turreted; volutions 9, with oblique angular ribs, crossed by sharp prominent lines, giving the ribs an acutely tuberculated character; whorls of spire angulated above the middle, and destitute of revolving lines above the angle; ribs on body whorl not continued to the middle of the volution; the revolving lines about 12 in number; 4 on the penultimate volution; aperture ovate-acute, slightly oblique. 1.

Local. Rivers of Australia.

M. Balonnensis. Ovate-elongate, thin, diaphanous; volutions 6, those of the spire angulated, obliquely ribbed; revolving lines distinct, but little prominent; the ribs on body whorl short; aperture elliptical, nearly half the length of the shell; epidermis pale straw-color, with unequal spots of reddish-brown. ½.

Local. Balonne river, Australia.

LYMNEA.

L. perlevis. Ovate, thin and fragile, pellucid; volutions 5; spire very short, the whorls convex; body whorl slightly flattened on the side and also near the suture; epidermis straw-colored; columella with a prominent slender very oblique fold revolving within to the apex; aperture large, patulous, ovate, regularly rounded at base.

Local. Salamanca and Balonne rivers, Australia.

The following resolution was adopted:

Resolved, That in future, visitors will not be admitted to the Museum on other than public days, (Tuesdays and Fridays,) unless accompanied by a member of the Society.

ELECTION.

Mr. Samuel M. Fox, of Philadelphia, was elected a *Member* of the Academy.

Buteo; Psittacus, 3; Hirundo, 2; Turdus, 2; Totanus; Mergus; Gallinula, 3; Alcedo, 2; Lestris, 2; Cypselus; Oriolus; Upupa; Ardea, 2; Otis; Platalea; Bubo; Ciconia; Crax; Uria, 3; Strix, 2.

Three Tracheæ of Birds: Kitta, Glareola, and Caprimulgus.

Ten Crania of Birds: Diomedia, 1; Rhamphastos, 2; Macrocercus, 1; Platalea, 2; Phœnicopterus, 1; Rhynchops, 1; Buceros, 1; Numenius, 1.

In all 230 species. From Dr. T. B. Wilson.

Eleven nests: six with ten eggs, two with two young each, and one with the female bird, of eleven species of Trochilus, from South America; three nests: two with three eggs, of three species of Orthotomus; from India. From Dr. T. B. Wilson.

Fruit of Banksia serrata. From Mr. Kilvington.

February 12th.

Sulphate of Baryta, with honey-colored Fluor, from Lake Superior. From Mr G. K. Smith.

DONATIONS TO LIBRARY

In January and February, 1850.

January 1st.

Recherches anatomiques et physiologiques sur l'organe de l'audition chez les Oiseaux. Par G. Breschet.

Dissertation sur la famille des Poissons Cyclostomes. Par A. M. Constant Dumeril.

Talpæ Europææ anatome ab F. G. J. Jacobs.

Ueber das Universum als Fortsetzung des Sinnensystems. Ein Pythagoräis ches Fragment von Oken.

Dissertatio inauguralis circa partes genitales masculas Avium. Auctore G. G. Tannenberg.

Dr. G. G. Tannenberg's Abhandlung über die Männlichen Zeugungstheile der Vögel.

Dissertatio inauguralis sistens Limnei stagnalis anatomen. Edidit Salomo Steubel.

Anatomische Beschreibung einer monströsen, sechsfüssigen, Wasser-Frosches. Von D. J. Van Deen.

De organis motoriis Boæ caninæ dissert. inaug. ab F. L. Huebner.

De coloribus corporum naturalium præcipue animalium vegetabiliumque determinandis: comment. physiog. ab Dr. F. G. Hayne.

Samuelis Méches de respiratione Animalium commentatio.

Dissertatio anatomica de Helice pomatia. Auctore W. Wohnlich, M. D.

Batrachymyologia. Dissert. inaug. anatomico-physiologica myologiam Ranarum Thuringièarum exhibens comparatum: Auctore J. C. Zeuker.

De Metamorphosi Rostri Pici et de generatione mucoris in organismo animale vivente. Ab C. F. Heusinger.

De animalculis infusoriis. Ab J. A. Lorent.

H. Rathke de Bopyro et Nereide commentationes anatomico-physiologicæ duæ.

Tabulæ (12) anatomiam Entozoorum illustrantæ: ab Eduardo Schmalz.

United States Exploring Expedition. Geology; by James D. Dana. 4to., and Atlas, folio.

Fauna littoralis Norvegiæ, von M. Sars. Liv. 1.

H. A. Wrisberg observationum de Animalibus infusoriis satura.

Versuch über die Schwimblasse der Fische: von G. Fischer.

Historia physiologica Ascaridium. Auctore M. Van Philsum, M. D. 8vo.

Lectures on the comparative Anatomy and Physiology of the invertebrate animals. By Richard Owen. 8vo.

Esperienze intorno alla generazione degl'Insetti fatte Da Francisco Redi. 4to.

Spicilegia adenologica. Auctore Philippus Seifert. 4to.

Palæontologie Française. Par M. Alcide D'Orbigny. Terrains cretacés, livs. 1–138: Terrains jurassiques, livs. 1–51. 8vo.

Note sur des oeufs de Mollusques receuillis en Patagonie. Par M. Alcide D'Orbigny.

Considerations sur l'ensemble des Mollusques Gastéropodes des Terrains cretacés. Par M. D'Orbigny.

Considerations zoologiques, geologiqués, et géologies-géographiques sur les Ammonites du Terrain crétacé. Par M. D'Orbigny.

Mémoire sur des espéces et des genres nouveaux de l'ordre des Nudibranches obsérvees sur les cotés de France. Par M. D'Orbigny.

January 15th.

Casparis Bauhini Brasiliens Archiatri de lapidis Bezoaris oriental et occidental. 12mo.

Description generale, &c. de la colonie de Surinam. Par Philip Fermin, D. M. 2 vols. 8vo.

Catalogus Bibliothecæ historico-naturalis Josephi Banks. Auctore J. Dryander. 5 vols. 8vo.

Catalogues of the very select and valuable libraries of William Roscoe, Isaac Ambrose Eccles, and General Charles Vallencey.

Catalogue of the Library of the Athenæum, Liverpool, 1820. By George Burrell. 8vo.

Catalogue of the Library of the Royal College of Surgeons in London, 1843, 8vo.; of a collection of Books on Natural History, by W. Wood of London, 1832, 8vo.; the same for 1840; of the Library of the Linnean Society of London. 8vo. 1827.

Bibliotheca Londinensis: a classified index to the literature of Great Britain during thirty years. 8vo.: and supplement to the same from 1816 to 1849. 8vo.

Bibliotheca regni animalis atque Lapidei, conscripta et edita a Laurento T. Gronovio. 4to.

Discours de M. Alfred Malherbe á l'Academie Nationale de Metz de 14 Mai, 1848.

De Lapicidinæ microcosmic: auctore J. C. Hoffmanus. 4to.

Hints to assist the enquiries of visitors: being brief notices of local antiquities in Southampton and its vicinity. By John Buller.

A letter to the Earl of Ellesmere, on the management of the Library of printed books in the British Museum.

D. Jacob Schæfferi Entwurf einer allgemeinen Farbenverein.

The above were presented by Dr. Wilson on the usual condition.

The voyages and travels of the Ambassadors sent by the Duke of Holstein to the Grand Duke of Muscovy and the King of Persia. By Adam Oleareus; rendered into English by John Davies. Folio. From Dr. S. G. Morton.

Illustrations of the Geology of Sussex. By Gideon Mantell. 4to. From the same.

Ueber die fossilen Säugethiere welche in Würtemberg in verscheidenen Formationen aufgefunden worden sind von Dr. G. F. Jäger. Nor. 1 and 2. Folio. From the same.

Conspectus Crustaceorum quæ in orbis Terrarum circumnavigatione C. Wilkes e classe Reipublicæ Federatæ duce, lexit et descripsit J. D. Dana. Isopoda No. 1. Schizopoda No. 1. From the author.

Annals of the Lyceum of Natural History of New York. Vol. 5. No. 1. From the Lyceum.

Descriptions of two species of Distoma, with the partial history of one of them. By Joseph Leidy, M. D. From the author.

January 22d.

System der Physiologie. Von C. G. Carus: 2 vols. 8vo. From J. Lambert.

Archiv skandinavischer Beiträge zur Naturgeschichte. Von C. F. Hornschuch. Part 1. Nos. 1 and 2. 8vo. From Dr. Morton.

Description des Mollusques de France, et particuliérement de Department de L'Isére. Par M. Albin Gras.

Systéme des animaux sans vertebrés. Par J. B. Lamarck. 1mo. edition. 8vo.

Histoire naturelle et mythologique de l'Ibis, par Jules Cæsar Savigny: Journal du dernier voyage de Dolomier dans les Alpes, par T. C. Brun-Neergaard, (in one vol. 8vo.)

Tableau élémentaire de l'histoire naturelle des Animaux. Par G. Cuvier. 8vo.

Considerations genérales sur la classe des Crustacés. Par Anselm-Gœten Desmarest. 8vo.

Traité élémentaire de Zoologie, ou histoire naturelle du regne animal. Par F. A. Pouchet. 8vo.

Voyage autour du Caucase. Par F. Dubois de Montpéreux. 6 vols. 8vo.

Considérations générales sur l'Ichthiologie. Par H. Cloquet. 8vo.

February 12th.

The London Athenæum for Dec. 1849. From Dr. Wilson.

Contributions to Conchology. No. 4. By C. B. Adams. From the author.

Twenty-eighth Report of the Leeds Literary and Philosophical Society, 1847–'48. From the Society.

Report of the Proceedings of the Geological and Polytechnic Society of the West Riding of Yorkshire, 1848. From the Society.

February 19th.

Annual Report of the Trustees of the State Library of New York, January 15, 1850. From the Trustees.

Celestial Wonders and Philosophy. By Prof. Rafinesque. 8vo. From Dr. Morton.

Indice d'Ittiologia Siciliana: del Sig. C. S. Rafinesque. 8vo. From the same.

Caratteri di alcuni nuovi generi e nuovi specie di animali e Pianti della Sicilia. Del Sig. C. S. Rafinesque. 8vo. From the same.

Nouveau manuel d'Anatomie comparée par MM. de Siebold et Stannius, traduit de l'Allemand par MM. Spring et Lacordaire. 2 vols. 12mo. From M. Lacordaire.

Gleanings from the Menagerie and Aviary at Knowsly Hall. Part 1. Folio. From Mr. J. E. Gray.

Ornithology of the United States. The descriptive part by J. K. Townsend. Nos. 1 and 2. 8vo. From Mr. Cassin.

Essai d'une nouvelle maniére de grouper les genres et les éspeces de l'ordre de Passereaux. Par M. La Fresnaye. From M. O. Des Murs.

Catalogo di Uccelli Messicani e Peruviani di Carlo L. Bonaparte, Principe di Musignano. From the same.

Notice sur le Papyrus. Par M. Alfred Malherbe. From the author.

Du role des Oiseaux chez les anciens et chez les modernes. Par Alfred Malherbe. From the author.

The American Journal of Science and Arts. Second series. No. 25. January, 1850. From the editors.

Dr. Wilson presented the following, on the usual condition:

The Natural History of Birds. 3 vols. 8vo.

Manual of British Ornithology. By Wm. Macgillivray. 2 vols. 8vo.

American Ornithology. By Alexander Wilson and Charles L. Bonaparte. Edited by Robert Jameson. 4 vols. 12mo.

The History of Singing Birds; translated from the French of Count de Buffon. 12mo.

The Book of Parrots. By Sir T. Dick Lander and Capt. Thomas Brown. 12mo.

Traité élémentaire d'Ornithologie. Par M. Mouton-Fontenille. 2 vols. 8vo.

Beiträge zur Vogelkunde in vollständigen Beschreibungen mehrerer neuentdeckter und vieler seltener, oder nicht gehörig beobachteter deutscher Vögel. Von C. L. Brehm. 3 vols. 8vo.

Ornithological rambles in Sussex. By A. E. Knox. 8vo.

offering in return such volumes of the Memoirs of the American Academy as may be wanting in the Library of this Society.

A letter from Maximilian Prince de Wied, dated Neu-wied on the Rhine, January 8th, 1850, offering to exchange specimens of European Quadrupeds, Birds, &c., for those of this country. Referred to the Zoological Committee.

A communication from Dr. Lewis R. Gibbes, dated Charleston, March 5th, 1850, accompanying "A Catalogue (prepared by himself) of the Crustacea in the Cabinet of the Academy of Natural Sciences of Philadelphia, February 20th, 1847, with notes on the most remarkable." The latter being intended for publication, was referred to a Committee consisting of Drs. Bridges, Zantzinger, and Leidy.

On motion of Mr. Vaux it was *Resolved*, That the Publication Committee be authorized to transmit to the American Academy of Arts and Sciences, such numbers of the first series of the Journal as the Committee may deem expedient.

March 19th.

DR. MORTON, President, in the Chair.

A communication was read from Peter A. Browne, Esq., entitled "Microscopic description of some piles on the head of Albinos." Referred to Mr. Fisher, Dr. Elwyn, and Prof. Haldeman.

On leave granted the Zoological Committee, to which was referred the Messrs. Short's communication to Mr. Elliott Cresson, of Philadelphia, in relation to their proposed scientific expedition to Africa, reported that it was inexpedient to recommend any action on the subject at this time by the Academy.

March 26th.

The Committee to which was referred Prof. Gibbes' Catalogue of the Crustacea in the Cabinet of the Academy, reported in favor of its publication in the Proceedings, with observations by the Committee.

Catalogue of the Crustacea in the Cabinet of the Academy of Natural Sciences of Philadelphia, August 20th, 1847, with Notes on the most remarkable.

By Prof. LEWIS R. GIBBES, Charleston, South Carolina.

In August, 1847, the collection of Crustacea in the Cabinet of the Academy was kindly laid open to me for inspection and study; and as the specimens were not all labelled, I endeavored to make some return for the favor by labelling the whole collection, as far as practicable, in the few days I spent in the city, in a mode uniform with that I adopted for the collection belonging to the Boston Society of Natural History. No labels were attached, of course, to those speci-

XVI. ETISUS, M. Edw.
23. E. lævimanus, Randall.
XVII. PLATYCARCINUS, Latr.
24. P. irroratus, M. Edw.
25. P. productus, Randall.
XIX. ERIPHIA, Latr.
26. E. gonagra, M. Edw.
XX. PILUMNUS, Leach.
27. P. aculeatus, M. Edw.
XVI. TRAPEZIA, Latr.
28. T. cymodoce, Guerin.
XXII. CARCINUS, Leach.
29. C. mænas, Leach.
XXIII. PLATYONICHUS, Latr.
30. P. ocellatus, Latr.
XXIV. LUPA, Leach.
31. L. sanguinolenta, Desm.
32. L. dicantha, M. Edw.
33. L. cribraria, M. Edw.
34. L. rubra, M. Edw.
35. L. pelagica, Say.
XXV. THALAMITA, Latr.
36. T. pulchra, Randall.
XXVI. PODOPHTHALMUS, Lamk.
37. P. vigil, Leach.

3. Family CATOMETOPA.

XXVII. POTAMIA, Latr.
38. P. dentata, Latr.
39. P. latifrons, Randall.
XXVIII. ORTHOSTOMA, Randall.
40. O. dentata, Randall.
XXIX. UCA, Latr.
41. U. una, Latr.
XXX. CARDISOMA, Latr.
42. C. carnifex, Latr.
43. C. guanhumi, Latr.
XXXI. GECARCINUS, Latr.
44. G. ruricola, Lin.
45. G. lateralis, M. Edw.
XXXII. PINNOTHERES, Latr.
46. P. byssomiæ, Say.
XXXIII. OCYPODA, Fabr.
47. O. arenaria, Say.
XXXIV. GELASIMUS, Latr.
48. G. vocans, M. Edw.
XXXV. MACROPHTHALMUS, Latr.
49. M. compressipes, Randall.
XXXVI. SESARMA, Say.
50. S. cinerea, Say.
51. S. reticulata, Say.
52. S. recta, Randall.
XXXVII. GRAPSUS, Lamk.
53. G. cruentatus, Latr.
54. G. pictus, Latr.
55. G. rudis, M. Edw.
XXXVIII. PACHYGRAPSUS, Randall.
56. P. crassipes, Randall.
57. P. parallelus, Randall.
XXXIX. NAUTILOGRAPSUS, M. Edw.
58. N. minutus, M. Edw.
XL. PLAGUSIA, Latr.
59. P. clavimana, Latr.
60. P. squamosa, Latr.

4. Family OXYSTOMA.

XLI. CALAPPA, Fabr.
61. C. marmorata, Fabr.
62. C. cristata, Fabr.
63. C. tuberculata, Fabr.
XLII. HEPATUS, Latr.
64. H. fasciatus, Latr.
XLIII. GUAIA, M. Edw.
65. G. punctata, M. Edw.
66. G. ornata.

B. Anomoura.

XLIV. DROMIA, Fabr.
67. D. lator, M. Edw.
XLV. RANINA, Lam.
68. R. dentata, Latr.
XLVI. ALBUNEA, Fabr.
69. A. symnista, Fabr.
XLVII. BLEPHARIPODA, Randall.
70. B. occidentalis, Randall.

of our naturalists regard it as identical with Hyas coarctata of the British coasts. I have had no opportunity of comparing specimens from both shores of the Atlantic, but the American species appears to me to resemble most Hyas aranea, judging from the figure in Herbst's work.

9. Mithrax spinosissimus. The specimen in the collection is of unusual size. Carapace 7 inches in length, as many in breadth, and 3 inches thick; hand and finger 7 inches long, 2½ broad; whole length of one of the first pair of feet 13 inches.

12. Pericera cornuta. This specimen has been described by Dr. Randall (Jour. Acad. Nat. Sci., vol. viii., p. 108) as Chorinus armatus. It does not belong to the genus Chorinus, as the orbits of the eyes are not incomplete, as they are in that genus, but embrace the peduncle of the eye on all sides like a tube, allowing no other motion to the eye than that of retraction or protrusion. On comparison, Dr. R.'s description will be found to agree in general with that given by M. Edwards of Pericera cornuta, (Hist. Crust., tome I, p. 335,) and a reference to the figure given in Hughes' Nat. Hist, of Barbadoes, pl. 25, fig. 3, or to Herbst, pl. 59, fig. 6, will complete the proof.

13 and 14. Epialtus Nuttalii and productus Randall appear to be new and well marked species.

22. Pseudocarcinus mercenaria is the Cancer mercenaria of Say, (Jour. Acad. Nat. Sci., vol. I, p. 448,) abundant along our southern coast. It is referred by M. Edwards, with some doubt, to the genus Xantho of Leach, (M. Edw. Hist. Crust., tome I, p. 399,) but I have no hesitation in referring it to his own genus Pseudocarcinus, and am disposed to think that he had it before him when writing his description of Pseudocarcinus ocellatus, (op. cit., p. 409.) His description applies in every particular, but is short. The country of his specimens he says is unknown.

25. Platycarcinus productus, Randall, is a distinct species from the three others known.

28. Trapezia cymodoce. The specimens in the collection agree exactly with Guerin's figure, (Voy. Coq. Crust., pl. 1, fig. 4.) M. Edwards' remarks are very just with regard to the difference between Guerin's Trapezia cymodoce, and the Cancer cymodoce of Herbst.

33. Lupa cribraria. The crab of our southern coast described by Say as Lupa maculata, (J. A. N. S., vol. I, p. 445,) appears, by Edwards' description and figure, (op. cit., tome 1, p. 452, pl. 17,* fig. 1,) to be same as Lamarck's Portunus cribrarius, (Anim. sans Vert., tome V., p. 259, and 2me. edit., t. V., p. 476.) Say's paper was read Dec. 1st, 1818, and Lamarck's fifth volume was published, as declared by the title page, in July, 1818, and his name has right of priority, and I have therefore adopted it.

35. Lupa pelagica. This specimen has Say's original label affixed, and is doubtless one of the specimens described by him in the Jour. Acad., vol. I, p. 97. It is not the L. pelagica of M. Edwards, and does not appear to be the young of the L. dicantha common along our coast; but further examination is requisite to determine what claims it has to be considered new.

---

*He refers, through mistake, to pl. 18, fig. 1.

39. Potamia latifrons, Randall, is distinct from Boscia dentata, M. Edw. Potamia, as generic name, ought to take precedence of Boscia.

40. Orthostoma dentata, Randall, forms a genus distinct from the others of the same group.

49. Macrophthâlmus compressipes, Randall, is a distinct species, and is the same as the M. podophthalmus figured in the *Voyage of the Bonite*. Priority of publication must determine which name shall prevail. The text of the work I have not seen.

53. Grapsus cruentatus. The individuals in the Collection of the Academy, belonging to this species, were erroneously regarded by Dr. Randall as new, and were described by him as G. longipes, in the Journal of the Academy, (vol. viii, p. 125.) It was doubtless a mistaken supposition that they were brought from Surinam, as stated p. 126, and this error probably misled Dr. R.

55. Grapsus rudis, M. Edw., is the same as G. hirtus, Randall, (J. A. N. S., vol. viii, p. 124.) Milne-Edwards' name has priority. With him I regard G. rudis as distinct from G. pictus, though it differs only in the following particulars: the carapace is clothed with numerous but distant transverse lines of hairs; the front is not so perpendicularly turned down; the four lobes of the front are more tuberculous, and the limbs smaller when compared with the body. There is but one specimen in the collection, but that is in good condition.

56 and 57. Pachygrapsus crassipes and P. parallelus appear to be distinct from the described species of the genus Grapsus.

66. Guaia ornata. This is a very distinct and pretty species of the genus Guaia, described by Dr. Randall as Ilia ornata, (J. A. N. S., vol. viii, p. 129,) but it really belongs to the genus to which I have referred it. This error, of confounding the two genera, Ilia and Guaia, has been committed by others besides Dr. R., until specimens really belonging to the genus Ilia fell into their hands, when a distinctive character is at once perceived in the peculiar contorted form of the hands in this genus. For want of attention to this point, Myra fugax and Guaia punctata have been confounded with Ilia punctata, many points in the description of each being common.

68. Ranina dentata. Two fine specimens. Dimensions of largest: carapace 4½ inches long, 4½ broad; carapace and abdomen extended, 7 inches; breadth of hand, finger excluded, 1½ inch, including finger, 2½ inches; length of thumb or moveable finger, 1½ inch; length of one of the first pair of feet, thumb extended, is 7 inches.

70. Blepharipoda occidentalis, Randall. A well marked genus. The individual is a female; abdomen with appendages, first pair of feet cheliform; hence it is near Albunea, but quite distinct.

74. Porcellana sociata, Say. In Say's article (J. A. N. S. vol. i. p. 456) the name of this species is given P. soriata. Say's original specimen is still in the collection of the Academy, but the label could not be found to determine how he wrote the name; there can be but little doubt that the name as printed is a typographical error arising from an imperfection in the manuscript, and that Leach, Desmarest, and Milne Edwards are right in regarding *sociata* as the true specific name; an imperfectly formed *c* connected with the preceding letter being easily mistaken for one of the manuscript forms of *r*. Another example of deviation

from the original orthography is furnished by Leach's genus Lupa, but in this case the deviation is unjustifiable. In Leach's article Crustaceology, in the Edinb. Encycl., he uses Lupa throughout, and Desmarest does the same in the Consid. Gen. Crust. Milne Edwards, misled apparently by the orthography of the name in French, *Lupée*, erroneously uses Lupea in his Hist. Nat. Crust. tom i. p. 445, (text and note), while in the references in the notes in the following pages, he uses Lupa; in his notes to the second edition of Lamarck's Anim. sans Vert. tom. v. p. 473, he gives Leach's genus as Lupea, while in the references to his own work (Hist. Nat. Crust.) on page 476, he uses thrice Lupa, and once Lupea. Lastly, in the Appendix to Leach's own article in Edinb. Encyc., the genus is called Lima!

89. Ibachus antarcticus. One individual marked as "brought from Santa Cruz by R. E. Griffith," agrees with Milne Edwards' character for I. antarcticus, the spine being *present* on the fifth pair of feet, the *absence* of which marks his I. Parræ, a native of the Antilles. Is I. Parræ a distinct species? or is it only imperfectly distinguished by the character he assigns to it?

98. Alpheus dispar, Randall, is hardly distinct from A. brevirostris, M. Edw.

101. Hippolyte gracilipes. The specimen thus labelled was in bad condition, but certainly belongs to the genus Palemon; probably some interchange of labels had taken place.

103. Palemon Gaudichaudii, M. Edw. Two fine specimens of this species of Milne Edwards, first brought from Chili by Gaudichaud.

111. Squilla empusa. The specimen I labelled thus, was said to be brought from the Pacific, and does not perceptibly differ from S. empusa, Say, from the Atlantic coast; if it really came from the Pacific, direct comparison with S. empusa of our Coast ought to be made, which I was not able to do for want of specimens of the latter at hand.

113. Squilla Cerisii. This specimen was brought from the Pacific, and agreed with M. Edward's description of the S. cerisii of Roux, inhabiting the Mediterranean; direct comparison is necessary to determine in what points they really differ. It is more probably the same as S. Lessonii, of Guérin.

There were also some eight or ten undetermined species, and several of Say's original specimens of the lower orders of the Crustacea.

Several of the species described by Dr. Randall were wanting, and have been omitted of course in the preceding catalogue.

—

Additions and Observations by the Committee.

In cases where the additions are of species in genera already in the collection, the numbers for the genera in Prof. Gibbes' paper are used, while higher numbers are employed for the additional genera.

LXV. STENORHYNCHUS, M. Edw.
116. S. phalangium, Pennant.
LXVI. INACHUS, Fabr.
117. I. Dorsettensis, Leach.
LXVII. MAIA, Lam.
118. M. squinado.
LXVIII. HYAS, Leach.
119. H. coarctata, Leach.
120. H. avanea, Leach.

LXIX. Eurynome, Leach.
121. E. aspera, Pennant.
XIV. Panopeus, M. Ed.
122, 123. P. (undetermined) from Brazil.
LXX. Daira, De Haen.
124. D. perlata.
LXXI. Xantho, Leach.
125. X. intonsus, Rand.
126. X. floridus, Montagu.
XV. Pseudocarcinus, M. Ed.
127. P. Rhumphii.
XVII. Platycarcinus, Latr.
128. P. pagurus, Linn.
129. P ? (cancer) decorus, Herbst. (a carapax only, from Tampa Bay, Florida.)
LXXII. Piremela, Leach.
130. P. denticulata, Leach.
LXXIII. Portunus, Fab.
131. P. pusilus, Leach.
132. P. puber, Leach.
133. P. arcuatus, Leach.
XXIV. Lupa.
134. L. (undetermined.)
XXXII. Pinnotheres, Latr.
135. P. pisum, Pennant.
XXXIII. Ocypode, Fabr.
136. O. Rhombea, Fabr.
137. O. Urvillii, Guerin.
XXXIX. Gelasimus, Latr.
138. G. platydactylus, Latr.
139. G. minor, Owen.
140, 141, 142. G. (undetermined.)
XXXV. Macrophthalmus, Latr.
143. depressus, Rupp.
144. transversus ?
XXXVI. Sesarma, Say.
145. S. tetragona, Fab.
146. S. ——————?
XXXVII. Grapsus, Lam.
147. G. plicatus.
LXXIV. Corystes, Leach.
148. C. cassivelaunus, Pennant.
XLIV. Dromia, Fabr.
150. D. Rhumphii, Bosc.
LI. Porcellana, Lam.
151. P. cristata.
152. P. longicornis, Penn.
153. P. platycheles, Penn.
154, 155, 156, P. (undetermined.)
LII. Pagurus, Latr.
157. P. longicarpus, Say.
158. P. Prideauxii, Desm.
159. P. vittatus, Bosc.
160. P. striatus, Bosc.
LXXV. Galathea, Fabr.
161. G. strigosa, Lin.
162. G. squamifera, Montagu.
LXXV. Thenus, Leach.
163. T. orientalis, Fab.
LXXVI. Gebia, Leach.
165. G. affinis, Say.
LXXVII. Homarus, M. Ed.
166. H. vulgaris, M. Ed.
LVII. Astacus, Fabr.
167. A. pellucidus, Tellkampf.
168. A. Weigmanni, Erichson.
LXXVIII. Crangon, Fabr.
169. C. vulgaris, Fabr.
LXI. Palæmon, Fabr.
170. P. vulgaris, Say.
171. P. serratus, Fabr.
172. P. Jamaicensis, Oliv.
173. P. squilla, Fabr.
174. P. spinimanus, M. Ed.
LXIII. Squilla, Latr.
175. S. monoceros, M. Ed.

Making the whole number of genera in the collection seventy-eight, and of species, one hundred and seventy-five.

Macrophthalmus compressipes, Rand., is Gelasimus telescopicus, Owen, Voy. Blossom, pl. 24, fig. 1, and M. podophthalmus, Voy. Bonite, pl. 3, fig. 6, 7.

Pachygrapsus parallelus, Rand., is Grapsus Thukuhar, Owen, l. c., fig. 3.

Pagurus decorus, Rand., is P. pictus, Owen, l. c. fig. 2.

Voyage de la Bonite bears date of 1841, and is posterior to both the others, the Voyage of the Blossom being dated in 1839, and Dr. Randall's paper having been

read before the Academy, June 18th, 1839, although not actually published in the Journal until January, 1840.

Prof. Gibbes in stating that several of Dr. Randall's specimens had been lost, has overlooked Xantho intonsus, Rand., which is still in the cabinet of the Academy. But one other species is omitted in Prof. Gibbes' list, Astacus Oregonus, which was lost or destroyed while in the hands of the artist by whom the drawing, published in the eighth volume of the Journal, was made.

—

The Committee to which was referred Mr. Peter A. Browne's paper on the hair of the Ornithorynchus paradoxus, reported that in consequence of the author's observations having been already anticipated by a number of distinguished naturalists and others, the Committee deem it inexpedient to recommend Mr. Browne's paper for publication.

In accordance with a resolution offered at last meeting of business, a life membership was conferred on Dr. J. K. Townsend, in return for his numerous valuable contributions to the Cabinet, at various times.

ELECTION.

M. Alfred Malherbe, President of the National Academy of Metz, in France, was elected a *Correspondent*, and Charles M. Wheatley, Esq., of New York, was elected a *Member* of the Academy.

April 2d.

DR. MORTON, President, in the Chair.

A letter was read from the Lyceum of Natural History of New York, dated March 26th, 1850, acknowledging the receipt of Vol. 3, No. 3, and Vol. 4, Nos. 9—12, of the Proceedings, and Vol. 8, Part 2, first series of the Journal.

Also a letter from Mr. James Deane, offering to prepare for publication in the Journal of the Academy, a paper on the fossils of the new red sandstone of the Connecticut valley. Referred to the Publication Committee.

Dr. Morton, on resigning the chair to Mr. Vaux, then read a further continuation of his paper on the size of the brain in the various races of Man.

The following is an analysis of this portion of the Memoir :—

In regard to the diversity of the human species, some ethnologists account for it by supposing changes to be effected by varieties in food, vicissitudes of climate, and other physical agents. Others again attribute the differences to the rise of accidental varieties, by which individuals have been produced, from whom, at first, tribes, then races and nations have sprung in succession.

If, therefore, we suppose all mankind to have been originally white, the hypothesis would necessarily require that negroes must be a mere accidental variety. This is Dr. Prichard's view of the case.

Dr. Morton said analogical reasoning, based upon the known changes which occur among the lower animals, would lead us into error if applied to Man. For instance, the Reindeer of Lapland do not change in the slightest particular after long domestication. The Peacock, also, has not varied during thousands of years, unless some few tints originally perfectly *blue* may have become greenish. Other instances of this kind might be enumerated.

Again, some animals in a very short time, in two or three generations, become entirely changed in color, as the Guinea pig and the turkey. Sometimes even the anatomical structure undergoes material changes under the influence of domestication; for instance, in the common pigeon, (*Columba livia*,) the sheep and the dog. He particularly directed attention to the fact that some animals in the *wild state* undergo remarkable changes; the Black squirrel and the Red squirrel for instance, while some other species of the same genus are unchangeable.

Some animals are not less remarkable for being liable to change than others are remarkable for resisting every impression from vicissitude or difference of climate and other causes. For instance the Bengal tiger, *Felis Tigris*, is precisely the same in every tint, whether inhabiting the frozen shores of Lake Baikal in Siberia, or the jungle of Ceylon. The greatest extremes of climate appear alike congenial to this animal.

In the north western province of Delhi, Bishop Heber saw a *shaggy Elephant;* and he states that in the course of one or two winters, dogs brought from Europe become woolly in that region, and even horses undergo a similar change; but this tendency does not extend to the human race, for the inhabitants are remarkable for the length and straightness of their hair.

Dr. Morton also adverted to the fact that the wool of sheep becomes long and hairy in Guinea, where human hair is naturally woolly.

From these and many other facts he inferred that causes which produce changes in the lower animals cannot change man.

Differences in modes of life have been considered productive of changes in man. But if we examine the aborigines of America, from Canada to Terra del Fuego, we seek in vain for a woolly head; men are found with skins lighter or darker in color, but all are *Indians* in every characteristic, and this throughout a range of 10,000 miles. He questions whether any one ever saw a true Indian who could be mistaken for a being of any other race.

In Europe we trace families through many generations, either living in the extremes of affluence or of misery, yet never does one race merge into another nor does a new race rise up among them.

Mr. W. B. Hodgson, Consul of the United States at Algiers, states there is a tribe of white men supposed to be derived from the lost tribes of Israel, now existing in the heart of the Negro territory; yet they have acquired no negro peculiarity, but are remarkable for all the characteristics of the white race—skin, hair and form. This is one of many similar examples.

Again; how does it happen that no Negro has ever been born as an accidental variety, among the Caucasian, Mongolian or other races?

It is vain to seek for the origin of Negro races in morbid change. No morbid change tends to perpetuity, but, on the contrary, it wears out sooner or later.

Dr. Morton conceives that there is a constant tendency in nature to restore and preserve a primitive type. A black man and white woman, or a black woman

and white man, produce a hybrid offspring, and that hybrid reproducing in turn, one or other of the original types will sometimes occur in such progeny.

In Peru some Spanish families, two or three centuries since, intermarried with the Inca, or purely Indian race; and notwithstanding no further cross with the Indian stock has subsequently occurred in these families, the Indian characteristics are said occasionally to reappear even at the present time.

Asiatics may have landed ages ago upon this continent; but if they did so, they have all been swallowed up and lost, in the indigenous population; and no unequivocal trace of them remains in our Indian population. Before the landing of Columbus, as well as since, the New World has presented every possible vicissitude of climate which could be supposed to produce a negro or any other race, but not an individual of such a race has ever appeared.

Dr. M. added, that such was the effect of the blending of dissimilar types on the American continent, that he could produce, from among the colored population of this city, many of the diversified forms and colours that exist in Africa itself.

In the case of seven species of domestic fowl, Temminck has shown that five out of the seven cross among each other, and produce prolific hybrids, and then branch out into innumerable varieties: and the varieties of the domestic pigeon differ more among each other than some distinct genera of other animals.

Domestic cattle if bred *in and in*, dwindle. In Paraguay it is necessary to refresh the stock by importations from other pastures. Other domestic cattle also exhibit this peculiarity of hybrids.

If mulattoes were bred *in and in*, without resorting to the parent stock, they would soon become extinct.

A circular was read from the Committee of reception of the National Pacific Rail Road Convention, now in session in Philadelphia, asking permission of the Academy for the members of the Convention to visit the Museum; whereupon a resolution was adopted granting the desired permission.

April 9th.

DR. MORTON, President, in the Chair.

Dr. Leidy remarked that crystalline bodies had been detected in most of the tissues of many plants, but that their occurrence in animal tissues was much more rare. The deposit of earthy salts in many tissues, such as bone, enamel and shell, though analogous, was not homologous with crystallization. The earthy deposit in the shell of the egg of many animals is probably an instance of true crystallization within an animal tissue, for in those animals which have eggs with a semi-membranous shell, as many helices, &c., we can detect the carbonate of lime deposited in the form of regular rhombohedrons. He stated that he lately met with a remarkable instance of crystallization within animal organic cells. In examining the stomach of the larva of Arctia Isabella, a Lepidopterous insect, he found that the nucleus of every epithelial cell contained an octohedral crystal, the axes of which measured about the 1-3750th of an inch. The cells were colorless, (not white,) containing some faintly granular matter, which, in many instances, was collected into distinct rounded masses. The nuclei were round,

elliptical, or lenticular, transparent, and measured the 1-1666th of an inch when round. The following day, upon examining some of the cells, which had been preserved between two slips of glass hermetically sealed, the crystals had disappeared, and the nuclei had become distinctly and opaquely granular. Acetic acid rendered the granular matter more translucent, and brought into view the nucleolus, which, not being visible the preceding day, probably served as the nucleus of the crystalline body. The animal, when examined, was in a state of hybernation, at which period organic activity is reduced, which would predispose to the crystallization of any salt in solution in an organic cell, for it appears that the frequency of the existence of crystalline bodies in the organic kingdom, is, to a considerable extent, dependant upon an inverse ratio of activity of life.

Dr. Morton then resumed the subject of the plurality of origin of the human race. In evidence of its orthodoxy, and of its being in accordance with a liberal interpretation of the Pentateuch, he adduced the last edition of the work of the Rev. Dr. John Pye Smith, on the Relations of Geology and Revelation. This author designates the Deluge as a local phenomenon, and circumscribes its limits. Geologists are in general convinced that it was not universal.

As regards the opinion that the various races of the human family were *primordially distinct*, Dr. Morton is convinced that the tendency of investigation goes every year to strengthen it. In other words, Man was aboriginally suited by his Creator for the various localities in which he has placed him. Dr. M. also read some interesting quotations from Dr. Pye Smith's work, in further support of this opinion. Mr. White, of England, fifty years since, also maintained that the plurality of the human race was in accordance with the text of Genesis, and Mr. E. King strenuously takes the same ground. In 1835, Rev. Dr. Thomas Arnold remarks in a letter to Archbishop Wheatley, "that he fears the physiological question is not yet settled."

Dr. Morton distinctly disclaimed any desire to enter into controversy on the biblical view of the question; but he was glad to show, from clerical authors, that the naked facts of zoological science, and the statements of Genesis, are in harmony with each other.

April 16th.

Dr. Morton, President, in the Chair.

Dr. Leidy read a description of new species of Entophyta, which was referred to Drs. Bridges and Zantzinger, and Mr. Powel.

A letter was read from Mr. James Deane, dated Greenfield, Mass., April 8, 1850, in reference to the publication in the Journal of the Academy, of a paper by him on the Sandstone fossils of the Connecticut valley. Referred to the Publication Committee.

Two communications were read from the Geological Society of London, dated Somerset House, 8th Nov. and 22d Nov., 1849, severally acknowledging the receipt of late numbers of the Proceedings, and of Part 3, new series of the Journal.

A communication from the Royal Society of Van Dieman's Land was read, dated Hobart Town, 15th September, 1849, presenting a copy of Part 1, Vol. 1, of their Proceedings, a collection of seeds of 150 species of plants, indigenous to Tasmania, and a specimen of *Phascolomys wombatus*, and also requesting that a correspondence and a system of exchanges be opened between the two Societies.

Whereupon, on motion of Dr. Leidy, it was *Resolved*, That the Academy will reciprocate the favor extended to it by the Royal Society of Van Diemen's Land, and that the Curators be empowered to act accordingly.

Mr. Peter A. Browne said that he had recently had an opportunity of examining the hair on the head of a human fœtus of five months, and found it wanting in several peculiarities of the adult hair.

On motion, it was *Resolved*, That the 8th volume of the Journal of the Academy be presented to Hugh E. Strickland, Esq., of England.

April 23d.

DR. MORTON, President, in the Chair.

Letters were read:

From the Zoological Society of London, dated Dec. 22d, 1849, acknowledging the receipt of recent numbers of the Proceedings of the Academy, and also of parts 1, 2 and 3 of vol. 1 of the Journal.

Two letters from the "K. L. C. Akademie der Wissenschaften," dated severally Breslau, 13th and 17th December, 1849, acknowledging the receipt of the Proceedings of the Academy.

Also two letters from the "Institute Royal des Sciences, &c. des Pays Bas," dated Amsterdam, December, 1849, acknowledging the receipt of the Proceedings of the Academy, and presenting a copy of its Memoirs, 3d series, vol. 1, parts 3 and 4, its Journal of the same, vol. 3, parts 1 and 2, and Annuaires of the same for 1847, '48 and '49.

Dr. Leidy read a paper, intended for publication in the Journal, describing the following new American species of Annelida abranchia:

1. Nais gracilis, *Leidy*. 50 articulations. Length 5 lines.
2. Nais rivulosa, *Leidy*. 20 articulations. Length 3 lines.
3. Pristina longiseta, *Ehrenb.*

   Strephuris, n. g., *Leidy*. Podal spines alternating with setæ, in two rows; upper lip moderately projecting; girdle well marked; number of articulations not over 70; no muscular stomach; blood bright red.
4. S. agilis, *Leidy*. Length 1 to 1¼ inches.
5. Aeolosoma venustum, *Leidy*. 8 articulations. Length 1-40th inch.
6. Enchytraeus vermicularis, *Henle*.
7. E. socialis, *Leidy*. Articulations not over 52. Length 5 to 10 lines.
8. Lumbriculus limosus, *Leidy*. 170 to 224 articulations. Length 2 to 4 in.

Referred, on motion, to a committee consisting of Drs. Hallowell and Morton, and Prof. Haldeman.

April 30th.

DR. MORTON, President, in the Chair.

The committee to which was referred Dr. Leidy's paper on some new Entophyta, reported in favor of publication in the Proceedings.

Descriptions of new Entophyta growing within animals.

By JOSEPH LEIDY, M. D.

ECCRINA.* (Gen. Nov.) Characters same as Enterobryus,† except that it divides into numerous cells at the free extremity.

Eccrina longa. Filaments long and delicate, hyaline, or faintly brownish, at first forming a simple curve, or a single spiral turn, and then passing in a straight line to the free extremity. Peduncle very short. Frond cell usually filled with globules, and a few granules, except at free end where it is usually filled with granules to the exclusion of the globules. End cells as high as thirty in number, at first consisting of elongated divisions of the frond cell contents, but becoming distinct elliptical cells, from two to three times longer than the breadth; contents usually granular, occasionally with a few globules. End cells finally separating from the parent. Length from three to seven lines, breadth 1-2000th to the 1-517th in., not usually corresponding to the length. End cells 1-517th to the 1-357th in. in length.

Habitat.—Grows in very great profusion from the mucous membrane of the posterior part of the intestine of Polydesmus virginiensis.

(Dr. L. exhibited to the Academy a preserved fragment of mucous membrane, with filaments of this species six lines in length growing from it.)

Eccrina moniliforma. Filaments hyaline or yellowish, forming a double or treble spiral. Peduncle short. Frond cell filled with globules and granules, except towards its free extremity, where it is filled with granular matter divided into distinct and separate masses, usually a little shorter than broad, and containing each a globular nucleolated nucleus. Divisions progressively passing towards the end into globular cells with granular contents. Divisions and globular cells from 20 to 50 in number.

Length from 1 to 1½ lines, breadth average 1-1500th in. Divisions of frond cell contents and globular cells from 1-1875th 1-1500th in. Nucleus of cells 1-3750 in.

Habitat.—Grows in moderate quantity from the mucous membrane of the intestine of 50 per cent. of Polydesmus granulatus.

Arthromitus nitidus. Filaments very long, hyaline, grows usually in twos or fours, pointed at the origin, rounded at the termination. Articuli very distinct, length equal to the breadth of the filament. Sporuli formed within the articuli, solitary, usually oblique, oval, amorphous.

Length 1 line by 1-5000th in. broad. Spores 1-7.111th in. long, by 1-12.500th in. broad.

Habitat.—Grows in considerable quantity with a profusion of young of Entero-

---

* Εκκρινω segrego. † Proc. Acad. Oct. 9, 1849.

bryus elegans from the mucous membrane of the posterior portion of the rectum of Julus marginatus.

Remarks.—Since I established the genus Arthromitus* I have observed the formation of its sporuli. These originate in the amorphous matter of the articuli, apparently by a very gradual aggregation and condensation of the contents. They are always single, and usually lie oblique, and frequently alternate with each other in this position in the different articuli. When they first appear they are larger than when fully formed, are frequently bent, or clavate in form, and very indistinct, but as they ripen they become more regular, oval, distinct, and quite refractile of light. Usually they are observed at the extremity of the filaments only, but frequently they are found existing in the whole length of the latter.

A species of Arthromitus, and also of Cladophytum is found in the intestine of Polydesmus virginiensis.

The Higrocrocis intestinalis found by Valentin in the Blatta orientalis, I could not find in our domestic cockroach, although I found numerous simple, phytoid, inarticulate filaments, growing from an oxyuris infesting this animal.

The committee on Dr. Leidy's paper, describing some new American Annelida abranchia, reported in favor of publication in the Journal.

The following amendment to Art. 1, Chapter 6th, of the By-Laws, proposed by Mr. Moss, was adopted:

"There shall be sixteen standing committees," (instead of fifteen.)

The object in the amendment being to make the Committees on Geology and Mineralogy distinct.

---

* Proc. Acad. Oct. 9th, 1849.

April 9th.

Anadonta Wahlamatensis and A. angulata, California. Presented by Dr. Heerman.

Forty-four specimens, 17 species fresh water and marine shells; 5 species crustacea, (Sesarma, Lupa, Peneus, Balanus;) 60 specimens, 44 species Coleoptera; 66 specimens, 35 species Lepidoptera; 80 other insects; 2 species Alcedo; 8 Serpents, 8 Lizards, 3 Fishes; 3 Myriapoda; 15 specimens Rocks. From China. Presented by D. B. McCartee, M. D., Ningpo, China.

Anastatica hierochuntia, or the Rose of Jericho; Fossilized wood, from the petrified forest near Cairo, Egypt. Presented by Dr. R. Eppes, of Virginia.

Cranium of a Chinese. Presented by Dr. J. Carson.

Cranium of a Chinese. Deposited by Dr. W. P. Johnson.

A collection of Plants from Madeira and the adjoining Islands. Presented by Henry Etting, Esq., Purser, U. S. N., through Dr. Hays.

April 16th.

Fifty-one Bird Skins, from Van Dieman's Land, of the following genera: 2 species Astur, Jeracidea, Podargus, Athene, Artamus; 3 Pardalotus, Strepera, Graucalus, Pachycephala, Colluriocincla, Myiagra, Erythrodryas, 2 Petroica, Malurus 2, Acanthiza, Estrelda, Cinclosoma 2, Oreocincla, 2 Meliphaga, Ptilotis, 2 Anthochæra 3, Acanthorhynchus, Melithreptus, Myzantha 2, Zosterops Cuculus, Chalcites, Calyptorhynchus, 2 Platycercus 3, Euphema, Pezoporus, Trichoglossus, Lathamus, Peristera, Hiaticula, Recurvirostra, Scolopax, Rallus, Porzana, 6 skins of Mammalia: Dromica gliriformis, Phalangista viverrina, Dasyurus Maugei, Antechinus Swainsoni, 2 undetermined. Also, 2 living specimens of Parameles ——? from Van Dieman's Land; a silurian fossil Productus; fragment of Fossil wood, and 4 specimens Malachite; 2 specimens of Sphaeria, (distinct from S. Robertsii or S. sinensis,) growing upon the larva of a Lepidopterous insect. From Van Dieman's Land. Presented by Capt. Wm. McMichael.

Seeds of 150 species of indigenous plants of Tasmania. Presented by the Royal Society of Van Dieman's Land.

April 23d.

Fossil remains of Dinornis giganteus, and other species of Dinornis, and several specimens of the deposit in which they were found. Collected in New Zealand, by Walter Mantell, Esq., of Wellington Government Commission for the settlement of native claims, and presented to the Academy by Dr. Thomas B. Wilson:

List of Dinornis Remains.

1, Ribs of Dinornis. 2, Specimen of the turbary deposit at Waikonaiti in the Middle Island, in which the bones of the largest species of Dinornis occur. 3, Proximal middle phalangeal bone of Dinornis. 4, Proximal phalangeal. 5, 6, 7, 8, Do. 9, Phalangeal, from Waingongoro, in the North Island. (In this locality the bones occur in a bed of volcanic sand, containing crystals of augite, titaniferous iron, &c. See Geological Journal for 1849.) 10, 11, Do. 12, Ungual bone. 13, Phalangeal. 14, Cervical vertebræ, Waingongoro. 15, Cervical do. 16, Two vertebræ, (very rare,) genus undetermined; query, if allied to the Penguin. 17, 18, Ungual bone. 19, Do. and phalangeal. 20, Ungual. 21, 22, Proximal phalangeal of Palapteryx. 23, 24, Middle proximal phalangeal. 25, Inner proximal. 26, 27, Inner and outer proximal phalangeal. 28, Second and third phalangeal. 29, Third phalangeal. 30, Second phalangeal of Dinornis. 31, Third phalangeal. 32, Phalangeal and Ungual Waingongoro. 33, Ischium of Dinornis. 34, Ribs of Dinornis. 35, Rib of do. 36, Ischium of Dinornis. 37, Portions of Ischium and Pubis. 38, Ischium of Dinornis. 39, Ribs of do. 40, Portions of fibulæ. 41, Three unguals of Dinornis didiformis. 42, Three unguals do. 43, Two do. 44, Head of tibia of Din. curtus? or otidiformis. 45, Specimen of some of the bed in which the bones of the Dinornis, &c. occur, near the embouchure of the river Waingongoro, in the North Island. 46, Twelve phalangeals, (including the three unguals, numbered to place together, with the

Twenty-third and twenty-ninth Reports (1842, '43, and 1848, '49) of the Council of the Leeds Philosophical and Literary Society. From the Society.

Boston Journal of Natural History. Vol. 6, No. 1. From Boston Society of Natural History.

C. A. Linné Systema Vegetabilium. Editio 15, a C. H. Persoon. 8vo. From Dr. Joseph Leidy.

McElroy's Philadelphia Directory for 1850. From Mr. Wm. S. Vaux.

The following were presented by Dr. Wilson, on the usual condition:

Die Schmetterlinge von Europa. Von Ferdinand Ochsenheimer. 4. vols. 8vo.

Die Schmett. von Europa: Fortsetzung des Ochsenheimer's schen. Berks, von Friederich Trietschke. 6 vols. 8vo.

J. G. Georgi Geographische-physikalische und natur historische Beschreibung des Russischen Reichs zur übersicht bisheriger Kenntnisse von demselben. 8 vols 8vo.

Beiträge zur Gebirgskunde Brasiliens von W. L. von Eschwege. 8vo.

Helvetiæ historia naturalis. Von J. J. Scheuchzer, M. D. 3 vols. 4to.

Faune des Medecins. Par H. Cloquet. 6 vols. 8vo.

P. Casparis Schotti Physica curiosa. 4to.

Die Lehre von den Haaren in der gesammten organischen Natur. Von D. Burkhard Eble. 2 vols. 8vo.

Iconographie der Land und Süsswasser Mollusken. Von Prof. E. A. Rossmässler. 12 hefts, 4to.

Theorie experimentale de la formation des Os. Par. P. Flourens. 8vo.

Magazin für Insectenkunde. Von Karl Illiger. 5 vols. 8vo.

Essai sur l'art d'observer et de faire des experiences. 2d ed. 3 vols. 8vo.

Illustrations of the Zoology of South Africa. By Andrew Smith, M. D. No. 28, 4to.

Reise in Chili, Peru, und auf dem Amazonenstrom. Von Ed. Poeppig. 2 vols. 4to., and Atlas folio.

Prodrom einer Monographie der böhmischen Trilobiten. Von Ignaz Hawle, und A. J. C. Corda. 4to.

Comptes rendus. Nos. 23—26, Tome 29.

The London Athenæum, for January, 1850.

Revue et Magasin de Zoologie. No. 11, 1849.

Conchologia iconica. By Lovell Reeve. Nos. 79, 80, 81. 4to.

Annals and Magazine of Natural History. Vol. 4, new series. Nos. 23, 24.

History of British Mollusca and their shells. By Prof. Forbes and S. Hanly. Parts 23 and 24.

Phycologia Britannica. By Wm. H. Harvey, M. D. No. 45.

The Quarterly Journal of the Geological Society. No. 20.

Illustrations Conchyliologiques. Par M. Chenu. No. 80, folio.

Paxton's Magazine of Botany and Gardening. Vols. 1—16, and parts 1—11, Vol. 17, 8vo.

Osteografische Beiträge zur Naturgeschichte der Vögel. Von Chr. Ludwig Nitzsch. 8vo.

Verzeichniss der in Ferdinand H. Frisch Vorstellung der Vögel in Deutschland.

Berichte über die Zoographia Rosso-Asiatica von Pallas. Von Dr. v. Baer.

Analecten für Vergleichende Anatomie; Part 2. Von Dr. Mayer.

Cours d'Entomologie. Par M. Latreille. 8vo., and atlas.

Statistique géologique et minéralogique du Departement de l'Aube. Par M. A. Leymerie. 8vo., and Atlas.

Neuste Entdeckung dass die Frunen in Schweinfleish Keine Drusenkrankheit. Von J. A. E. Goeze.

Monographie der Norddeutschen Wealdenbildung. Von Dr. W. Dunker und H. von Meyer. 4to.

Systematische Auszählung der Vögel Würtembergs. Von Chr. L. Landbek.

Beiträge zur Zoologie und Vergleichenden Anatomie. Von Henrich Kuhl. 4to.

Recherches sur l'anatomie et les métamorphoses de differentes espéces

The following were presented by Dr. Wilson, on the usual condition:

Trattato delle cose naturali e dei loro ordine conservatori &c.: del Dottore Gaspare Brugnatelli. 4 vols. 8vo.

Coup d'œil général sur les Possessions Neerlandaises dans l'Inde Archipélagique. Par C. J. Temminck, 3 vols. 8vo.

Prodromo della Grande Anatomia opera postuma del Paolo Mascagni. 2e. ed. Par J. Farnese. 4 vols. 8vo.

Magazin für die Liebhaber der Entomologie. Von J. D. Fuessly, 3 vols. 8vo.

Zoologie zu seinen Vorlesungen entworfen. Von D. F. Teidemann, 3 vols. 8vo.

Traité des Phenoménés Electro-physiologiques des Animaux. Par C. Matteuci. 8vo.

Portraits des Naturalistes. 8vo.

Essai de Phytostatique appliquée á la Chaine du Jura et aux Contrées voisines. Par Jules Thurmann. 2 vols. 8vo.

Anatomie comparée du systéme dentaire chez l'Homme et chez les principaux animaux. Par L. Rousseau. 8vo.

Nuovi osservazioni microscopiche del P. D. Della Torre. 4to.

J. C. Peyeri Merycologia. 4to.

Elephantographia curiosa. Authore D. G. C. Petri. 4to.

Traité du Physiologie comparée de l'homme et des animaux. Par Antonio Dugés. 3 vols. 8vo.

Essai sur les genres d'Insectes appartenants á l'ordre des Hémiptéres Lin. et á la section des Hétéroptéres Dufour. Par Max. Spinola. 8vo.

Lethea Geognostica. Von H. G. Bronn. 2 vols. 8vo., and atlas 4to.

Historia Insectorum. Auctore Joanne Raio. Opus posthumum. 4to.

Memoires de la Société d'Hist. nat. de Paris. 4to.

Zeitschrift für Physiologie. Vols. 1—5. 4to.

Insectorum Liguriæ species novæ aut rariores quas in Agro Ligustico nuper detexit, descripsit &c., Max. Spinola. 2 vols. 4to.

Neue Denkschriften der Allg. Schweizerischen Gesellschaft für die gesammten Naturwissenschaften. Vol. 9. 4to.

Physiologie de l'espece, histoire de la génération de l'Homme. Par M. M. Grimaud de Caux et Martin St. Ange. 4to.

Delle uova e dei nidi degli Uccelli libro primo del Conte Guiseppe Zinanni Ravenante. Osservazioni generali sopra le Cavalletti fatte dal Conte G. Zinanni. (in one vol. 4to.)

Histoire de la Mouche commune de nos appartemens. Par J. C. Keller. 4to.

Beschreibung und Abbildung der Eier und Kunstlichen Nester der Vögel welche in der Schweitz, &c. Von H. R. Schintz, M. D., 4to.

Das Entwickelungsleben im Wirbelthier-Reich. Von Dr. Reichert. 4to.

Animalcula infusoria fluviatilia et marina quæ detexit, &c., Otho F. Müller. 4to.

Beknopte Natuurlijke historie af Beschreiving en afbeeldingen der Voortbrengselen van de drie Rijken der Natuur. 4to.

Journal des Observations physiques-mathemat. et botaniques. Par le R. P. Louis Feuillée. 3 vols. 4to.

Descrizione anatomica degli organi della circolazione della larve delle Salamandra aqatice fatta dal Dott. Mauro Rusconi e communicata al Sig. G. B. Broechi. 4to.

Memoires pour l'histoire naturelle de la Province de Languedoc. 4to.

Recueil de divers traités sur l'histoire naturelle de la terre et des fossiles. Par M. E. Bertrand. 4to.

Abhandlungen zur Bildungs-und Entwickelungs-Geschichte des Menschen und der Thiere von Dr. Heinrich Rathke. Parts 1 and 2. 4to.

Del Proteo anguino di Laurenti Monografia publicata da Pietro Configliachi e da Mauro Rusconi. 4to.

Recherches anatomiques et physiologiques sur l'organe de l'ouie des Poissons. Par Gilbert Breschet. 4to.

Naturgeschichte der Bandwurmgattung überhaupt und ihrer Arten insbesondere nach den neuern Beobachtungen in einen systematischen Auszuge verfasst von A. J. G. Carl Batsch. 8vo.

Johannis de Laet Antwerpiani de Gemmis et Lapidibus. 8vo.

Catalogue des livres, &c. de la bibliotheque de feu M. J. B. Huzard. 3 vols 8vo.

Memoires pour servir á l'histoire naturelle des Sangsues. Par P. Thomas D. M. 8vo.

Specimen anatomiæ zoologicum de Phocis, speciatim de Phoca vitulina. Auctore W. Vrolik. 8vo.

Die Fische in den Scheeren von Mörkö beschreiben von C. W. Eckström. 8vo

Essai sur l'origine des corps organisés et inorganisés. Par J. B. Fray. 8vo.

Handbuch der Naturgeschichte der skelettlosen ungegleiderten Thiere von Dr. A. F. Schweigger. 8vo.

Dissertatio anthropologica-medica inauguralis de cranio ejusque ad faciem ratione. Auctor W. H. Crull. 8vo.

Commentatio de Tænia hydatigea anomala et de vermium visceralium physiologia. Auctore J. G. Steinbuck. 8vo.

Versuch einer veigleichenden Anatomie des Auges und der Thiänenorgane des Menschen. Von C. H. T. Schreger. 8vo.

Musæum N. G. Luskeanum. Pars entomologica cura J. J. Zschachii. 8vo.

Histoire philosophique des progres de la Zoologie générale depuis l'antiquité jusqu'a nos jours. Par Victor Meunier. Vol. 1. pt. 1. 8vo.

Études Geologiques dans les Alpes par M. L. A. Necker. Vol. 1. 8vo.

Handbuch der Vergleichenden Osteologie. Von Dr. M. J. Weber. Part 1. 8vo.

Grundriss der Physiologie. Von Dr. Karl A. Rudolphi. 2 vols. 8vo.

Der Geschichte der Natur als zweite gunzlich umgearbeitete Auflage der Allgemeinen Naturgeschichte von D. G. H. V. Schubert. 4 vols. 8vo.

Das System der Circulation in seiner Entwicklung durch die Thierreiche und im Menschen, &c. Von Carl H. Schultz. 8vo.

Histoire naturelle des Crustacés. Par L. A. G. Bosc. 2d ed. par M. Desmarest. 5 vols. 12mo.

Hist. Nat. des Coquilles. Par L. A. G. Bosc. 2d edition. 2 vols. 12mo.

Aphorismi physiologici et anthropologici. 12mo.

Bibliotheca Scriptorum Historiæ naturalis omnium Terræ regionum interventium. Historiæ Naturalis Helvetiæ prodromus. Collegit J. J. Scheuchzer, M. D. 8vo.

Vie de Buffon. 12mo.

Traduction d'un article des Transactions Philosophiques sur le Corail. Par Peysonnal. 12mo.

Essai sur l'organisation externe et interne des Insectes. Par Charles Peretti. 12mo.

Homines enudrobioi, h. e. sub aquis viventes: à Salomone Sprangero Voightlando. 12mo.

Conchyliologie nouvelle et portative. Par D'Argenville. 12mo.

Observations sur la formation du Poulet. Par M. Antoine Maitre-Jan. 12mo.

Observations sur la structure des yeux de divers insectes et sur le trompe des Papillons; contenues in deux lettres au R. P. Lamy. Par M. Puget. 12mo.

Histoire générale des Races Humaines ou Philosophie Ethnographique. Par E. Fr. de Salles. 12mo.

Anatomie du cerveaux dans les quatre classes d'animaux vértébrés. Par Laurencet, de Lyon. 8vo.

Bibliotheca helminthologica: edita ab Adolpho Modeer. 8vo.

Memoria sul fenomeno della generazione del Giambatista Marone. 8vo.

Le naturaliste du second âge. Par J. B. Pujoulx. 8vo.

Bibliothéque physique de la France. Par feu M. L. A. P. Hérissant. 8vo.

Genera et index methodicus Europeorum Lepidopterorum. A Dr. J. A. Boisduval. 8vo.

H. Verloren catalogus systematicus ad Cramerum. 8vo.

De modo cavendæ corruptionis corporum naturalium in Museis. Auctor J. D. Reichel.

Mémoire sur le developpement des organes de la respiratione dans les oiseaux et les Mammiféres. Par le Prof. Rathkè.

De Penitiori auris in amphibiis structura. Auctor C. J. Windischmann.

Ichthyo-theologiæ primæ lineæ. Auctor Nicolaus Malm.

Observationes pathologico-anatomicæ Auctarium ad Helminthologiam humani corporis continentes. Auctore F. A. . reutler.

Ueber den innern Bau der Arachniden. Von G. R. Treviranus. Part 1.

Saggio sopra la vera struttura del cervello dell'uomo e degl'animali e sopra la funzioné del sistema nervoso di Luigi Rolando. 8vo.

Symbolæ ad anatomiam et physiologiam organorum Bulbum adjuvantium et præcipue membranæ nictitantis. Auctore H. A. Trapp.

Specimen Annotationum Helmintologicarum quæ naturalen spectant historiam Lumbricorum. Auctore Samuele Verestoi.

Exercitatio academica de lethargo Hirundinis. Auctore J. B. Weinhagen.

Recherches sur l'organisation, la fructification, et la classification de plusieurs genres d'Algues. Par J. F. Chauvin.

H. G. Waardenberg commentatio de historia naturale Animalium Molluscorum regno Belgico indigenorum.

Xaverii Wulfen descriptiones quorundam Capensium Insectorum.

Beiträge zur Vergleichenden Zoologie, Anatomie und Physiologie. Von Dr. Oken und Dr. Kieser. Nos. 1, 2. 4to.

Micrographia nova: Ab J. F. Grindelio. 4to.

Naturalis de Ruminantibus historia Joannis Æmyliani Ferrariensis. 4to.

Disquisitiones Anatomicæ Psittacorum. Auctor M. J. Thuet.

Anatomia Animalium tabulis illustrata: Ab A. J. Volkmann. Vol. 1. Nos. 1 and 2. 4to.

D. C. Gottwaldt's physikalisch-anatomische Bemerkungen über die Schildkröten aus dem Lateinischen übersezt. 4to.

Memorabilium Saxoneæ subterraneæ pars prima. Ab. —— Mylius. 4to.

De Animalibus nocuis Alsatiæ specimen. Auctore J. F. Weiler.

Dissert. inaug. med. de Insectorum in corpore humano genitorum varia forma et nidole. Auctor Georgius Vaghi.

Exercitium academicum de ortu Petrifactorum. Auctore J. Wallenius.

Dissert. physico-med. de Monocerotis cornu fossili. Auctore Jacobus Neuchter.

Dissert. historico-politica de Ferro Suecano Osmund. Auctore Petrus Saxholm.

Dissert. physica de Salmonun natura, &c. Auctore Daniel Bonge.

Specimen Geurgiæ Fennicæ. Ab J. Malleen Fil.

Commentatio de respiratione Animalium. Auctore C. L. Nitzsch.

J. F. Blumenbachii specimen Physiologiæ comparatæ inter animantia calidi sanguinis vivipara et ovipara.

Dissert. philosoph. inaug. de respiratione Insectorum. Auctore J. F. Martinet.

Les genres des Plantes fossiles compares avec ceux du monde moderne. Par H. Goeppert. Livs. 1—5.

Recueil de figures des Vers intestinaux redigé par Th. Van Lid de Jeude. Folio.

Nachrichten von den vornehmsten Lebensumständen und Schriften Jetzlebender Aerzte und Naturforscher in und um Deutschland. Von D. F. Borneen. 3 vols. 8vo.

April 9th.

Catalogue of the New York State Library, January 1, 1850. From the Trustees.

Elements of Natural History. By W. S. W. Ruschenberger, M. D. 2 vols. 8vo. From the Author.

Illustrations of fossil foot-prints of the Valley of the Connecticut. By James Deane, M. D. From the Author.

Mémoires du Museum d'Hist. Naturelle. Tomes 8—20. 4to.
Annales du Museum d'Hist. Nat., Tome 21, contenant table des Auteurs dans les 20 volumes. 4to.
Nouvelles Annales du Mus. d'Hist. Nat. Tomes 1—4. 4to.
Archives du Mus. d'Hist. Nat. Tomes 1, 2, 3; et pts. 1, 2, 3, Tome 4; 4to.
Caroli Marini Giltay comment. ad questionem Zoologicum.

April 16th.

Dr. Wilson presented the following, on the usual condition:

Histoire naturelle des Lepidoptéres exotiques. Par H. Lucas. 8vo.
Hist. Nat. des Lepidoptéres d'Europe. Par. H. Lucas. 8vo.
Hist. Nat. des Oiseaux exotiques. Par C. L. Lemaire. 8vo.
Hist. Nat. des Oiseaux d'Europe. Par C. L. Lemaire. 8vo.
Das Steinreich systematisch entworfen von J. E. J. Walch. 8vo.
Deutschlands Insecten Fauna oder Entomologisches Taschenbuch für das Jahr 1795.
Synopsis of the Natural History of Great Britain and Ireland. By John Berkenhorst, M. D. 2 vols. 8vo.
Natural history of the quadrupeds of Paraguay and the river La Plata. Translated from the Spanish of Don Felix de Azara, by Wm. P. Hunter, Esq. Vol. 1.
Catalogue de la Faune de l'Aube. Par Jules Ray. 12mo.
Aristotelis de longitudine et brevitata vitæ liber. Auctore Carolus Zell. 4to.
A chart of British Ornithology. By T. W. Barlow.
A critical examination of the first principles of Geology. By G. B. Greenough. 8vo.
The Geology of the Avon. By Jos. Sutcliffe. 8vo.
A treatise on domestic Pigeons. 8vo.
Voyage Agronomique en Auvergne. Par M. de Pradt. 8vo.
Recherches experimentales sur les causes du mouvement du Sang dans les veines. Par David Bany, M. D. 8vo.
The Natural History of England. By Benjamin Martin. 2 vols. 8vo.
Traité des Dragons et des Escarboucles. Par M. Pauthot. 12mo.
Index Fossilium quæ collegit et in classes et ordines disposuit Ignatius á Born. 8vo.
Catalogue of the Library of the Royal Dublin Society. 8vo.
Globe du Monde. Table de plusieurs Roys et Monarques qui out posside la Terre. Discours du coeur du petit monde et de la composition du Corps humain. Par G. Girault Langrois, (in one vol. 4to.)
Antonii le Grand Historia Naturæ. 4to.
Narrative of an expedition into Southern Africa in 1836, '37. By Capt. W. C. Harris. 8vo.
The private Journal of Capt. G. F. Lyon, of H. M. S. Hecla, during the recent voyage of discovery under Capt. Parry. 8vo.
Corallina: or a classical arrangement of the flexible coralline Polypidoms. Selected from the French of J. V. E. Lamouroux. 8vo.
Voyage dans l'Indostan. Par M. Perrin. 2 vols. 8vo.
Natural and civil history of California. From the Spanish of M. Varregas. 2 vols. 8vo.
The Entomological Magazine. Vols. 1—5. 8vo.
The Eastern Seas: or voyages in the Eastern Archipelago in 1832-'33-'34. By George Windsor Earl. 8vo.
Dialogo de la Caccia de Falconi, Astori et Sparuieri. Di Francisco Codioipo. 4to.
Storia naturale dei Terreni ardente dei Vulcani Fangos, delle Sorgenti inflammabili, dei Pozzi idropirice e di altri fenomeni geologici operati dal Gas Idrogene a della origine de esso gas del Dott. Giuseppe Bianconi. 8vo.
Tergestina, oder Beobachtungen und Untersuchungen über einige bei Triest

and natural curiosities belonging to the British Museum. By John and Andrew Van Ramsdyk. Folio.

The Natural History of British Fishes. 5 vols. 8vo. By G. Donovan.

Faune de la Moselle, ou Manuel de Zoologie. Par M. Fournel. 1re. partie. 12mo.

Etudes géologiques aux environs de Quimper et sur quelques autres points de la France Occidentale. Par A. Riviére.

Catalogue des Preparations anatomiques laissées dans le cabinet d'anatomie comparée du Museum d'histoire naturelle. Par G. Cuvier.

Observations anatomiques sur la structure du Sphinx Nerii et autres insectes. Par M. le Dr. Louis Rolando.

Osservazioni anatomico-fisiologiche sull' Epidermide: di B. Mojon, M. D.

Memoria sulla contrattilita della fibra animali: da B. Mojon, D. M.

Beiträge zur Monographie der Pteromalium Nees. Von H. Foerster. Heft. 1. 4to.

De Epidermide humana. Auctor Alphonsus Wendt. 4to.

J. G. Kern vom Schneckensteine oder der Sachsisschen Topasfelsen. 4to.

De Nervorum regeneratione, Ab C. O. Steinruck.

Recherches sur l'influence que la lumière exerce sur la propagation du Son. Par Modeste Paroletti.

Joh. Ellis de Dionæa muscipula. J. F. Bolton, M. D. ad C. Linné epistola de novo quodam Zoophytorum genere. J. F. Bolton Nachricht von einer neuen Thierpflanze. (In one vol. 4to.)

Des accidens produits dans les trois premiérs classes des animaux vértébrés et plus particulierement chez l'homme par le vénin de la Vipére Fer de Lange. Par F. Z. G. Guyon.

Considerations geologiques rélatives á la Medecine. Par Louis Eugene Robert.

Du degré d'utilité de l'Anatomie comparée dans l'etude de l'anatomie humaine. Par J. A. C. Giraldes.

Systema fossilium analysibus chemicis examinatorum secundum partium constitutiarum rationes ordinatorum. Ab Joanne Gadolin. 4to.

Anatomie et Physiologie de la Corneille (Corvus corone) prisé comme type de la classe des Oiseaux. 1me. partie. Par Emile Jacquemin.

Ueber die Blutformer. Von Joh. C. Schmidt.

Observations sur quelques-uns des Mineraux soit de l'Ile de Ceylon, soit de la cote de Coromandel. Par Le Conte Bournoy.

Observations sur les phenomenes periodiques du regne animal, et particulierement sur les migrations des Oiseaux en Belgique de 1844 et 1846. Par Ed. de Selys Longchamps. From Charles L. Bonaparte, Prince de Canino.

Per la memoria del Cardinale Fransoni a Carlo L. Bonaparte, Principe di Canino. From the Author.

Ornamental and domestic Poultry, their history and domestic management. By the Rev. E. Saul Dixon. 12mo. From Mr. Yarrell, of England.

The following were presented by Mr. Edward Wilson, of Wales:

Catalogue of miscellaneous literature in the Library of the Royal Society. 8vo.

Nouveaux infusoires des Environs de Carlsbad decrits par M. A. C. J. Corda.

Introduction to the catalogue of the Ashmolean Museum.

Magasin de Zoologie. Par J. E. Guerin Meneville. Livs. 9—12, 1845.

List of Quadrupeds brought by Mr. Burchell from Southern Africa, and presented by him to the British Museum, Sept. 1817.

Catalogue of the contents of the Royal Museum, No. 28 Leadenhall St., London. By Mr. C. Du Bois.

Sketch of a journey through the Western States of North America. By W. Bullock. 12mo.

The Stars and the Earth, or thoughts upon space, time and eternity. Third edition.

Description d'une nouvelle espéce de Crustacé, l'Hippolyte de Desmarest. Par M. Millet.

Abbild. und Bescreib. neuer oder wenig gekannter Conchylien. Von Dr. R. A Philippi. Vol. 3. No. 6.

Palæontographica. Beiträge zur Naturgeschichte ver Vorwelt. Von Dr. W Dunker und H. von Meyer. Vol. 1. Part 5.

Annals and Mag. of Nat. Hist. New series. Nos. 22, 25, 26, 27.

The Genera of Birds. By George R. Gray. Part 50.

Thesaurus Conchyliorum. By G. B. Sowerby, Jr. Part 10.

The Mammals of Australia. By John Gould. Part 2.

The Birds of Asia. By John Gould. No. 1.

Transactions of the Royal Society of London. Part 2. 1849.

Annales des Sciences Naturelles. August and September, 1849.

First and Second Report on the Coals suited to the Steam Navy. By Sir H de la Beche and Dr. L. Playfair. Folio.

The Natural History of Ireland. By Wm. Thompson. Vol. 2. 8vo.

Memorie sulla storia et notomia degli animali senza vertebre del regno d Napoli: di Stefano delle Chiaje. 4 vols. 4to, and atlas folio.

History of British fossil Reptilia. By Richard Owen. Parts 1 and 2. 4to.

Lectures on the comparative Anatomy and Physiology of the vertebrate Ani mals. By Richard Owen. Vol. 2. 8vo.

Transactions of the Tyneside Naturalists' Field Club. Vol. 1. Parts 1 and 2

Journal of the Royal Agricultural Society of England. Vol. 10. Part 2.

Annales de la Société Entomologique de France. 1me. serie, tomes 8—11 2e. ser., tomes 1—6. 8vo.

Histoire naturelle des Lepidoptéres ou Papillons de France: par MM. Godar et Duponchel. 16 vols. and Supplement. 8vo.

Iconographie et histoire naturelle des Chenilles, pour servir de complement l'hist. nat. des Lepidop. de France par MM. Godart et Duponchel. 2 vols. 8vo

Catalogue Methodique des Lepidoptéres d'Europe. Par M. Duponchel. 8vo

Iconographie et. hist. nat. des Coléopteres d'Europe. Par M. Le Compt Dejean et M. le Dr. Boisduval. 5 vols. 8vo.

Memoires de la Soc. Linneénne de Paris. 6 vols. 8vo. and atlas 4to.

A Voyage towards the South Pole in 1822, '24. By James Weddell, Esq. 2 edition.

A journey to Paris in 1698. By Dr. Martin Lister. 2d edition. 8vo.

Die Königl. Schwedischen Akad. der Wissenschaften neue Abhandlungen. 1 vols. 8vo.

Commentarii de rebus in scientia naturali et medicina gestis. 44 vols. 8vo.

Dictionnaire des Sciences naturelles; et planches. 75 vols. 8vo.

Catalogue of the Mollusca of Northumberland and Durham. By Joshua Alder 8vo. From the Author.

Catalogue of the Insects of Northumberland and Durham. Coleoptera. Part 1 8vo. By Jas. Hardy and Thos. J. Bald. From Mr. Alder.

Catalogue of the Fossils of the Permian System of the counties of Northumber land and Durham. By Richard Howel. 8vo. From the same.

May 28th.

Dr. BRIDGES in the Chair.

The Committee appointed at a meeting of the Society in January, to have such alterations made in the room adjoining the Library, as would adapt it to the extension of the latter, and the better accommodation of the books, reported that they had performed that duty according to the plan submitted to the Society, and that said room was now ready for the reception of the books.

Mr. J. D. Sergeant read a memorial, praying that a geologist be attached to the party accompanying the Commissioners appointed to survey the boundary of Mexico, and moved that copies signed by the officers of the Academy be forwarded to both Houses of Congress; which was agreed to.

Dr. Zantzinger offered the following, which was adopted: *Resolved*, That the thanks of the Society be tendered to Henry Bond Dewey, Esq., of Para, Brazil, for the elegant collection of insects from that country, presented by him at the last meeting. (See page 61.)

ELECTION.

Clement Biddle, Jr., Esq., of Philadelphia, and Mr. Samuel G. Rosengarten, of Philadelphia, were elected *Members;* and Henry Bond Dewey, Esq., of Brazil, was elected a *Correspondent* of the Academy.

June 4th.

Dr. CARSON in the Chair.

On leave granted, Mr. Vaux, on behalf of Dr. Morton, offered the following resolutions.

Resolved, That this Society has learned with sincere regret, the death of their esteemed and venerable fellow member, Alexander Maclure, at New Harmony, in Indiana, on the 9th of April last.

Resolved, That his name should be indelibly recorded in the annals of our Institution, as well for his various personal benefactions, as for his faithful and literal fulfilment of those most important objects which his brother, William Maclure, had designed, but did not live to accomplish.

Resolved, That we further cherish the memory of Alexander Maclure for the moral excellence of his character, his exacting probity, and his practical benevolence.

The resolutions were unanimously adopted.

Mr. Vaux read from the North American and United States Gazette, the following printed letter relating to the death of Dr. William Gambel.*

---

* Dr. Gambel's death was announced at a former meeting of the Academy, but the information was not then sufficiently authentic to authorize any action on the subject by the Academy.

June 11th.

Dr. MORTON, President, in the Chair.

Mr. P. A. Browne expressed his views in relation to the peculiarities of the hair in man and other mammalia, and more particularly on the absence of a central canal in the hair of certain races of the former, on which he proposes to found specific differences. After some conversation among the members on the organization of hair, Mr. Browne offered a resolution that a committee be appointed to make microscopic investigations on the subject, which was adopted, and the following committee appointed, viz: P. A. Browne, Prof. Haldeman, and Dr. Morton.

June 18th.

Dr. MORTON, President, in the Chair.

A letter was read from the Royal Society of London, dated Somerset House, March 20, 1850, returning acknowledgments for recent numbers of the proceedings of the Academy.

Mr. Cassin read a paper entitled, "Descriptions of new species of the genera Vidua, Hyphantornis, Hirundo, Atticora, Acanthylis, and Cypselus, specimens of which are in the Academy of Natural Sciences of Philadelphia," which was referred to the following committee, Drs. Wilson, Townsend, and Heerman.

Mr. Moss read a description, with a figure, of a new Carpolite from Arkansas, which was referred to the following committee, Dr. Bridges, Mr. Conrad, and Dr. Hallowell.

June 25th.

Dr. MORTON, President in the Chair.

The committee to whom was referred Mr. Cassin's descriptions of Birds in the collection of the Academy, read at last meeting, reported in favor of publication in the Proceedings.

Descriptions of new species of Birds, specimens of which are in the collection of the Academy of Natural Sciences of Philadelphia.

BY JOHN CASSIN.

Vidua Verreauxii, nobis. Vieill. Ois. Chant. pl. 37?

♂. *Form.*—Generally resembling Vidua paradisea, (Linn.) Swains. B. of W. Af. I, pl. 11, but is larger, the two longest tail feathers taper gradually to the end from near the middle of the feather, the outer (or upper) webs are very nar-

shorter primaries slightly sinuated at their points on the inner webs, tips of secondaries emarginate. External edge of the first primary (or edge of the wing) furnished with a row of hooks or reversed bristles very obvious to the touch and discernable with the naked eye. Tail long and broad, deeply emarginate. Legs slender.

Dimensions.—Total length of skin from tip of bill to end of tail 5¾ in. Wing 4 4-10. Tail 3¼ inches.

Color.—Entire plumage fine black with a green gloss, inferior surface of the wings and tail paler and without lustre.

Hab.—Port Natal, Eastern Africa.

Obs.—Four specimens of this species are in the collection of the Academy, several of which from the Rivoli collection were labelled "Hirundo velox, Vieill." It is not the bird figured by Le Vaillant, which belongs to another genus, and is not therefore the species intended by Vieillot.

Cypselus leucopygialis, nobis.

Form.—Robust, wings long, exceeding the tail, primaries slightly curved with the second longest. Tail rather short, truncate, scarcely emarginate.

Dimensions.—From tip of bill to end of tail 5¼ inches. Wing 5¼. Tail 2 inches.

Colors.—Rump white, throat pale, nearly white; back and upper surface of the wings and tail brownish black with a green gloss, head and entire under parts dull sooty brown. Inferior tail coverts with a slight subterminal black band and minutely tipped with white.

Hab.—Sumatra?

Obs.—This species resembles the Cypselus affinis, Gray, but is much larger. It is quite distinct from that or any other species known to me. One specimen only is in the museum of the Academy, which bears a label having Sumatra as the locality, and was received from Europe in a collection sent by Mr. Edward Wilson.

Acanthylis cinereocauda, nobis.

Form.—Wings very long, with the second primary longest. Tail rather short with the feathers broad and the terminal acute points conspicuous, upper tail coverts long and ample.

Dimensions.—Total length of skin from tip of bill to end of tail 4 inches. Wing 4 8-10. Tail 1 3-10.

Colours.—Rump, upper and under tail coverts and tail above and below pale brownish cinereous, or mouse color; shafts of the tail feathers black. All other parts of the plumage brownish black, deeper and with a greenish lustre above, dull and paler below.

Hab.—South America.

Obs.—The species now described resembles Acanthylis spinicauda, (Temm.) Pl. Enl. 726, but may readily be distinguished by the entirely black plumage of the under parts and by the pale colour of the tail. Though not so large a bird as the *A. spinicauda*, its wings are longer. Two specimens are in the museum of the Academy, one of which, sent from Paris by Mr. Edward Wilson, is marked as coming from South America.

DONATIONS TO LIBRARY

IN MAY AND JUNE, 1850.

May 7th.

Contributions to Conchology. No. 7. By C. B. Adams. From the Author.

Reports of the Joint Commissioners, and of Col. Graham, U. S. Engineers, in relation to the boundary between the States of Pennsylvania, Delaware, and Maryland, (corrected copy.) From Col. Graham.

The classification of mankind by the hair and wool of their heads. By Peter A. Browne. From the Author.

May 14th.

A response to a professor, and a speculation on the Sensorium. By B. Dowler, M. D. From the Author.

Third annual report of the Regents of the University of New York on the condition of the State Cabinet of Natural History, and the historical and antiquarian collection. From the Regents.

Report of the Select Committee of the Legislature of 1849, on the publication of the Natural History of the State of New York; made January 2, 1850. From the same.

The American Journal of Science and Arts. 2d series. No. 27. May, 1850. From the Editors.

The following were presented by Dr. Wilson on the usual condition:—

Annales de la Société Entomologique de France. No. 3, for 1849.

Revue et Magasin de Zoologie. No. 12, 1849, and No. 1, 1850.

Archiv für Naturgeschichte. Von F. A. Weigmann. No. 4, 1848, Nos. 1, 2, 1849.

Zeitschrift für Malakozoologie: von K. T. Menke, M. D., und Dr. L. Pfeiffer. Nos. 2, 5, 6, 7, 8, 9, 1849.

Comptes rendus. Tome 29, No. 7. Tome 30, Nos. 1—8.

The London Athenæum for February and March, 1850.

Illustrations Conchyliologiques. Par M. Chenu. No. 81.

Monographie des Odynéres de la Belgique. Par G. Wesmael.

De Stalactites Souterraines ou pretendus Fulgorites. Par M. Desvaux.

Tableaux synoptiques et methodiques des genres des Nemazoaires. Par B. Gaillon.

Catologo de los Moluscos terrestres y de Agua dulce observados en Espana. Por el Doctor M. P. Graells.

Monographiæ Libellulinarum Europæarum specimen. Auctore P. L. Vander Linden.

Lectiones publicæ de Vermibus intestinalibus imprimis humanis quas habuit in Museo Rer. Nat. Acad. Lund. 1784 A. J. Retzius.

Note sur des Polypiers fossiles: par M. Alcide D'Orbigny.

Observations sur les Apiaires Melipomides: par Max. Spinola.

Descrizione d'un nuovo rettile fossile della famiglia dei Paleosauri, e di due pesci fossili trovati nel calcareo nero, sopra Varenna sul Lago di Como dal Nob. Sig. Lud. Trotti; con alcune lessione geologiche del Prof. Guiseppe Balsamo-Crivelli.

Saurorum tabula analytica; Chelonorum tab. analyt.; Prodromus systematis Herpetologiæ. (C. L. Bonaparte.)

Catalogue methodique des Crustacés terrest. fluviat. et marines, receuilles dans le departement du Calvados. Par M. de Brébisson.

Tableau de la distribution methodique des espéces minérales suivie dans le cours de Mineralogie fait au Muséum Royal d'Hist. Nat. en 1827. Par M. Alex. Brongniart.

Description des Entomostracés fossiles de la Craie de Maestricht. Par J. Bosquet.

Sur la multiplication des Sangsues. Par M. Huzard Fils.

Monographie des Sangsues med. et officin. Par A. Charpentier.

Clavis systematicæ distributionis generum Testaceorum in Museo Mediolanensi extantium.

Comptes rendus. Nos. 9—12. Tome 30.
Isis von Oken. No. 12. 1848.
Revue et Magasin de Zoologie. No. 2. 1850.
Zeitschrift fur Malakozoologie. Nos. 10, 11, 12. 1849.
Études sur les Echinides fossiles du Departement de l'Yonne. Par M. Gustave Cotteau. Livs. 1, 2, 3.
De animalibus quibusdam e classe Vermium Linnæana, in circumnavigatione terræ auspicante Comite N. Romanzoff duce O. De Kotzebue an. 1815—'18 peracta, observatis A. de Chammisso. No. 1. 4to.
Histoire naturelle, gen. et partic. des Mollusques. Par M. de Ferussac: continue par G. P. Deshayes. Livs. 35 et 36. Folio.
Memoirs of the Literary and Philosophical Society of Manchester. Vols. 3, 4, 6, 7, and 8.
Natural History of the British Entomostraca. By William Baird, M. D. 8vo.
Reports and Papers on Botany. Edited by Arthur Henfrey. 8vo.
Recherches sur les Poissons fossiles. Par M. Louis Agassiz. Texte tomes 5, 4to.; Planches tomes 5, folio.
Nouveau Manuel d'Anatomie descriptive, d'aprés les cours de MM. Beclard, Blandin, Cloquet, &c. 12mo.
Nouvelle Flore des Environs de Paris. Par F. V. Merat. 3me ed. Vol. 2. 12mo.
Traité d'Anatomie descriptive. Par Hippolyte Cloquet. 4me ed. 2 vols. 8vo.
De l'influence des agens physiques sur la Vie. Par W. F. Edwards, D. M. 8vo.
Univers Pittoresque; histoire et description de tous les Peuples. Europe tome 1; Asie tomes 4; Afrique tomes 2. 8vo.
Précis d'Anatomie pathologique. Par G. Andral. 3 vols. 8vo.
Traité d'Anatomie chirurgicale, ou Anatomie des regions considérée dans ses rapports avec la chirurgie. Par Alf. A. L. M. Velpeau. 2 vols. 8vo.
Cours de Pharmacologie, ou traité élémentaire d'Hist. nat. medicale de Pharmacie et de Therapeutique. Par. F. Foy. 2 vols. 8vo.
Physiologie des Passions, ou nouvelle doctrine des sentimens moraux. Par J. L. Alibert. 2d edition. 2 vols. 8vo.
Narrative of a Mission to Bokhara in 1843—'46. By the Rev. Joseph Wolf, D. D. 8vo.
Memoirs official and personal, with sketches of travel among the Northern and Southern Indians. By T. L. McKenney. 2 vols. in one. 8vo.
Travels over the table lands and Cordilleras of Mexico in 1843 and '44. By Albert M. Gilliam. 8vo.
Letters and Notes on the manners, customs, and condition of the N. American Indians. By George Catlin. 2 vols. 8vo.
Incidents of Travel in Yucatan. By John L. Stephens. 2 vols. 8vo.
History of the Life and Voyages of Christopher Columbus. By Washington Irving. 2 vols. 8vo.
Narrative of a Journey through the upper provinces of India, from Calcutta to Bombay, in 1824–'25. By the late Rt. Rev. Reginald Heber, D. D. 2 vols. 8vo.
Incidents of Travel in Central America, Chiapas, and Yucatan. By John L. Stephens. 2 vols. 8vo.
Voyages and discoveries of the companions of Columbus. By Washington Irving. 8vo.
Journal of the Royal Agricultural Society of Great Britian. Vols. 1—10. 8vo.
The American edition of the new Edinburgh Encyclopædia; conducted by David Brewster, LL. D. 18 vols. 4to.
American Ornithology. By Alexander Wilson. With a sketch of the author's life. By George Ord. Text 3 vols. plates 1 vol. 4to. (Edition of 1828.)
History of the Indian tribes of North America. By T. L. McKenney and James Hall. 3 vols. Folio.
Journal of the Franklin Institute from 1837 to 1850, 27 vols. 8vo. (Completing the series in the Library.)
Encyclopædia of Chemistry. By James C. Booth. 8vo.
Conspectus generum Avium. By Charles L. Bonaparte. pp. 1—160.

On motion of Mr. Phillips it was

Resolved, That the Society, at the Business meeting in September next, proceed to the election of a Vice President in place of Dr. Griffith, deceased.

ELECTION.

Dr. James C. Fisher, of Philadelphia, was elected a *Member*, and the following were elected *Correspondents* of the Academy:—John R. Bartlett, Esq., of New York, and T. Charlton Henry, M. D. of Syracuse, N. Y.

August 20th.

Dr. Morton, President, in the Chair.

A letter was read from M. Alfred Malherbe, President of the Nat. Hist. Soc. of Metz, France, dated May 29th, 1850, acknowledging the receipt of his notice of election as a Correspondent.

A letter was read from Dr. Franklin B. Hough, dated Somerville, New York, August 12th, 1850, accompanying the donation of a collection of minerals from that vicinity, and stating his desire to make further contributions in this and other departments, if agreeable to the Society.

A paper by Mr. Cassin, describing new species of Birds of the genera Paradisea, Pastor and Buceros, and intended for publication in the Proceedings, was read and referred to Dr. Wilson, Dr. Townsend, and Mr. E. Harris.

A paper was read entitled, "Descriptions of ten new species of Crinoidea, from the sub-carboniferous Limestone of Iowa, collected during the U. S. Geological survey of Iowa, Wisconsin, and Minesota, in the years 1848–9, by David Dale Owen, and B. F. Shumard, M. D.:" which being intended for publication in the Journal, was referred to Mr. Conrad, Dr. Wilson, and Dr. Morton.

A paper was also read entitled, "Notice of fossil remains brought by Mr. J. Evans from the 'Mauvais Terres,' or bad lands of White River, 150 miles west of the Missouri, by D. D. Owen, J. G. Norwood, and John Evans," of which the following is an abstract:—

This remarkable collection consists of numerous teeth, fragments of bones, and twenty skulls, some of which last are in an excellent state of preservation. They belong to the orders *Ruminantia* and *Pachydermata*. For the present, the authors of the memoir propose to give only a general and provisional description, as the basis of a full report on a future occasion. The following species are particularly noticed.

1. Palæotherium? Proutii. These remarkable remains are thus named in compliment to Dr. Prout, of St. Louis, who first noticed them in the American Journal of Science and Arts. The generic characters, however, are not yet satisfactorily decided.

2. Another species is allied to *Charopotamus*, and still more to *Hyracotherium*, but is probably distinct. The bones, skulls, and teeth of this animal were found, with the greater part of the other remains, in a flesh-colored calcareous marl.

Obs.—This very handsome Paradise bird is one of the most valuable and interesting of the many contributions to the collection of this Academy, made by Mr. Edward Wilson, of Lydstip house, Pembrokeshire, to whom I have taken the liberty of dedicating it, as a slight acknowledgment of his valuable services to the cause of the zoological sciences in this country.

This species is a congener of Paradisea magnifica, Lath., but does not resemble that, nor any other known species to an extent sufficient to render special designation necessary. All the species are in the collection of the Academy.

The specimen now described was obtained by Mr. Wilson in England, but bears no label indicating locality. It is probably not fully adult.

Pastor nigrocinctus, nobis.

Form.—Specimen now about to be described much mutilated, cranium destroyed and skin of the head much injured, nearly the whole of the wing feathers and legs wanting. Feathers of the hind head somewhat elongated, exposed portion of the plumage of the rump and tail coverts filiform, tail feathers broad, rather abruptly terminated and slightly acuminated. Aberrant, possibly a Gracula.

Dimensions.—Total length of skin from tip of bill to end of tail about 8 inches, tail 3 inches.

Colors.—Head (entirely ?), broad band completely encircling the middle of the body; (wings ?) and tail black with a greenish metallic lustre.

Broad band encircling the anterior third portion of the body, including breast and neck above and below, and another broad band encircling the posterior third portion of the body including abdomen, rump, and tail coverts, saffron yellow, paler on the under tail coverts. Bill yellow.

Hab.—New Guinea ?

Obs.—I have seen two specimens only of this bird, one of which is in a museum at Albany; the other is the property of the Academy, and is the specimen now before me. Both were imported by Mr. J. G. Bell, of New York, deservedly well known as a naturalist and taxidermist, by whom the species was first pointed out to me as probably undescribed, and who has also had the kindness to inform me that he received them with skins of Paradise birds. They are mutilated in the same manner as those usually are, and have been subjected to similar methods of preservation; from which facts I have inferred that they may be from New Guinea.

3. *Buceros Fistulator*, nobis.

Form.—Very similar to that of Buceros Buccinator, Temm., but is much smaller. Specimen now described probably not fully adult, bill nearly simple.

Comparative Dimensions.

	B. Buccinator.	B. Fistulator.
Total length of skin from tip of bill to end of tail	25 inches,	17 inches.
Wing,	12 "	9½ "
Tail,	10½ "	7½ "

Colors.—Very similar to those of Buceros Buccinator, Temm. Lower medial part of breast, abdomen, thighs, under tail coverts, inferior wing coverts, tips of secondary and tertiary quills, and tips of external tail feathers, white, all other parts black with a greenish lustre.

Hab.—Western Africa.

it was on motion ordered, that the Editor of the "Archiv. für Naturgeschichte" be placed upon the exchange list of the Journal.

Dr. Morton announced the late decease of Prof. Gerard Troost, at Nashville, Tenn., at a very advanced age. The deceased was the first elected President of this Institution.

Skeleton of Turacus albocristatus; Eggs of Strix aluco, from Algiers, Aquila audax, Certhia familiaris, France, Certhia costa, Italy. Also skins of Vulpes velox, Lepus californicus, Mephitis marpurito? Sciurus Douglasii, Mus leucopus?; all from California. From Dr. Thomas B. Wilson.

August 13th.

Very beautiful specimen of Crystallized Sulphate of Barytes, from Eldridge mine, Buckingham county, Virginia. From Mr. J. Parker Norris, through J. Dickinson Sergeant, Esq.

Specimen, in spirits, of Octopus ———. Presented by Mr. Cassin.

August 20th.

Dr. Wilson presented seventeen cases containing 757 bottles of fishes and reptiles in spirits, 177 fishes in skin, nine Serpents, eight toads, ten tortoises, and one hundred Quadrupeds, in skin; being the types of the figures and descriptions in the Fauna Italica of Prince C. L. Bonaparte.

A collection of minerals from St. Lawrence county, New York. From Franklin B. Hough, M. D., of Somerville, N. Y.

DONATIONS TO LIBRARY

In July and August, 1850.

July 2d.

Notice of the Gypsum of Plaister Cove in the Strait of Canseau. By J. W. Dawson, Esq. From the author.

A lexicon of Terms used in Natural History. By W. S. W. Ruschenberger, M. D. 8vo. From the author.

New species of Myliobates from the Eocene of South Carolina, with other genera not hitherto observed in the United States. By R. W. Gibbes, M. D. From the author.

F. C. Haugsted, M. D. Thymi in homine ac per seriem animalium descriptio anatomica. 12mo. From Dr. Morton.

Marcelli Malpighi de structura Viscerum. 12mo. From the same.

Bernardi S. Albani historia Musculorum Hominis. 4to. From the same.

Nicolai Hobokeni anatomia Secundinæ Humanæ. 12mo. From the same.

Antonii Nuck Sialographia et ductuum aquosorum anatome nova. 12mo. From the same.

Halleri opuscula anatomica de respiratione, de Monstris, &c. 12mo. From the same.

Benedicti Stilling disquisitiones de structura Protuberantiæ annularis vel Pontii Varolii. Folio. From the same.

An illustrated system of Human Anatomy. By S. G. Morton, M. D. Royal 8vo. From the same.

The following were presented by Dr. T. B. Wilson, on the usual condition:—

Narrative of a Whaling voyage round the World from 1833 to 1835. By F. D. Bennett, Esq. 2 vols. 8vo.

A familiar introduction to the History of Insects. By Edward Newman. 8vo.

Petralogy: a treatise on Rocks. By J. Pinkerton. 2 vols. 8vo.

A descriptive catalogue of the fossil organic remains of Scarborough and its vicinity. 8vo.

Geological and mining report on the Leinster Coal District. By Richard Griffith, Jr., Esq. 8vo.

Geological and Mining Survey of the Connaught Coal District in Ireland. By R. Griffith, Jr.. Esq. 8vo.

A brief narrative of an unsuccessful attempt to reach Repulse Bay in H. M. Ship Griper in 1824. By Capt. G. F. Lyon, R. N. 8vo.

A Geographical, Statistical and Historical description of the District or Zila of Dinajpur, in Bengal. By Dr. F. Buchanan (Hamilton.) 8vo.

History of the voyages and discoveries made in the North: translated from the German of J. R. Forster. 4to.

A voyage towards the North Pole undertaken in 1773. By Constantine J. Phipps. 4to.

Descriptive and illustrated catalogue of the Physiological series of Comparative Anatomy contained in the Museum of the Royal College of Surgeons in London. 5 vols. 4to.

Catalogue of Calculi and other animal concretions contained in the Museum of the Royal College of Surgeons. 4to.

Lectures on Natural Philosophy. By Richard Barton, B.D. 4to.

A Missionary Voyage to the South Pacific Ocean in 1796—'97 and '98, in the Ship Duff, Capt. James Wilson. 4to.

Voyage Minéralogique et Géologique en Hongarie pendant l'annee 1818. Par F. S. Beudant. 4 vols. 4to.

Letter to the Earl of Derby on the management of the Zoological Society of London. By Lovell Reeve.

Remarks on the Anglo-Asiatic Society of British India: addressed to William Wilberforce, Esq.

Instructions for collecting and preserving Insects, particularly Moths and Butterflies.

Catalogue of the Animals of North America. By John R. Forster.

Catalogue of British Lepidopterous Insects, (Haworth.)

Catalogue of the collection of British and Foreign Insects of the late A. H. Haworth, Esq.

Jacobi A. Melle de Lapidibus figuratis Agri Littorisque Lubecencis.

Mr. Lee's lecture on the affinities of Plants and Animals.

An address delivered at the first annual meeting of the Geological Society of Dublin, 8th February, 1832. By the Rev. Bartholomew Lloyd, D. D.

Remarks on the probable origin and antiquity of the aboriginal natives of New South Wales.

Observations on the Natural History of two species of Wasps. By the Rev. E. Bigge.

Facts and arguments in favor of a new expedition to the shores of the Arctic Ocean. By Richard King.

Speculations in Astro-Geology. By D. Nicol, Esq., M. D.

Narrative of the Proceedings of the Committee appointed by the adventurers to procure the discovery of the passage to the Western Coast of America.

Statistical Notes on Chusan. By Lieut. Ouchterlong.

The inaugural address delivered by Rod. Impey Murchison, Esq., at the first meeting of the Dudley and Midland Geological Society, January 17, 1842.

Supplement to the Flora Metropolitan. By Daniel Cooper.

The pleasures of Ornithology. A Poem. By James Jennings.

Observations and reflections on the migration, &c., of the Swallow.

Bewick's portraits of the Lion, Tiger, Zebra, and Elephant.

July 16th.

Catalogue of operculated Land-shells in the collection of John H. Redfield, 1850. From the author.

Zeitschrift für Malacozoologie. Von K. T. Menké, M. D., und L. Pfeiffer. Nos. 1, 2, 1850. From Dr. Wilson.

The London Athenæum for May, 1850. From the same.

A system of Mineralogy. By J. D. Dana. 3d edition. 8vo. From the author.

American Journal of Science and Arts. 2d series. No. 28. July, 1850. From the Editors.

Sixty-third Annual Report of the Regents of the University of New York. 8vo. From the Regents.

Journal of the Franklin Institute. 3d series. Vol. 20. No. 1. July, 1850.

Quarterly Journal of the Geological Society. No. 22.

Journal of the Royal Asiatic Society. Vol. XI. Part 1.

Études sur les Echinides fossiles. Par M. Gustave Cotteau. 4me. Liv.

The annals and magazine of Natural History. Vol. 5. 2d series. Nos. 29 and 30.

A History of British Mollusca and their Shells. By Prof. Forbes and S. Hanley. Parts 27 and 29.

Annales des Sciences naturelles. 3me serie. Oct. Nov., 1849.

Contributions to Ornithology. By Sir William Jardine. Parts 1 and 2. 1850.

Histoire naturelle des Mollusques. Par M. Ferussac; continue par G. P. Deshayes. 37me. liv.

Zoology of the Voyage of the Samarang. No. 6. Mollusca, part 2.

Conchologia iconica. By Lovell Reeve, Esq. Nos. 85, 86.

The genera of Diurnal Lepidoptera. By E. Doubleday: continued by J. O. Westwood. Part 32.

Cours élémentaire de Paléontologie et de Géologie statigraphiques. Par M. Alcide D'Orbigny. Vol. 1. 8vo., and Atlas.

Prodrome de Paléontologie statigraphique universelle des animaux mollusques et rayonnés, faisant suite au Cours élémentaire de Paléontologie par M. A. D'Orbigny. Vol. 1. 8vo.

Musæum Adolpho-Fridericanum. Auctore Laurentius Balk fil. Sponsalia Plantarum. Auctore J. G. Wahlborn. (in one vol. 4to.)

Entomostraca; seu insecta testacea, quæ in aquis Daniæ et Norvegiæ reperit, descripsit, &c. Otho Frid. Muller. 4to.

British Moths and their transformations. Arranged &c. by J. N. Humphreys, with descriptions by J. O. Westwood, Esq. 2 vols. 4to.

Denkschriften der k. Akad. der Wissenschaften zu Munich, 1808—1824. 9 vols. 4to.

August 20th.

Journal of the Indian Archipelago and Eastern Asia. Vol. 3, Nos. 9—12; Vol. 4, Nos. 1—4. From the editor.

Dr. Wilson presented the following on the usual condition:—

Essai sur l'histoire naturelle de l'ile de St. Domingue. Par —— Nicholson. 8vo.

Tableau des Mollusques terrestres et fluviatiles de la France. Par J. Draparnaud. 8vo.

Nouvelles expériences sur la Vipere. Par Moyse Charas. 2d edition.

Œuvres Entomologiques de Eschscholtz. Tome 1. Entomographien. 8vo.

Centurie d'Insectes, contenant plusieurs genres nouveaux décrits dans sa collection. Par G. Kirby. 8vo.

Agri Romani historia naturalis; a Philippo A. Gilij concinnata. Part 1. Tome 1. Ornithologia. 8vo.

Histoire naturelle des Salamandres de France. Par P. A. Latreille. 8vo.

Monographiæ Ammoniteorum et Goniatiteorum specimen. Auctore Gulielmo De Haan. 8vo.

Anatomia comparata Nervi sympathetici. Auctore E. H. Weber, M. D. 8vo.

Philosophie entomologique. Par. J. Flor St. Amans. 8vo.

Epistolæ ineditæ Caroli Linnæi: addita parte Commercii litterarii inediti, imprimis circa rem botanicam, J. Burmani, Dillenii, J. Gesneri, Pallasii, &c.: annees 1736—'93. Edidit H. C. Van Hall. 8vo.

Versuch einer vollständigen Conchylienkenntniss nach Lin. Syst. Herausgeg: von Karl Schreibers. 2 vols. 8vo.

De la Physiologie dans ses rapports avec la Philosophie. Par J. J. Virey. 8vo.

Philosophie de l'Histoire naturelle. Par J. J. Virey. 8vo.

Bibliographie Entomologique. Par A. Percheron. 2 vols. 8vo.

Monographie des Passales, et des genres qui en ont été séparés. Par A. Percheron. 8vo.

Somewhat allied to this is the opinion of Swainson and others, that permanent varieties constitute species, or in other words, that variations of climate, food and treatment produce specific distinctions.

Species is defined by Buffon, "a succession of similar individuals which re-produce each other." Cuvier's definition is nearly the same; but he adds that "the apparent difference of the races of our domestic species are stronger than those of any species of the same genus. The fact of the *succession*, therefore, and of the constant succession, constitutes alone the validity of the species."

An objection to these definitions arises from the fact that they apply as readily to mere varieties as to acknowledged species. Certain albino animals re-produce, *inter se*, to an indefinite extent; such also is the case with some fanciful varieties of the dog, pigeon, &c., which are capable of multiplying by the law of succession, and yet have no claim to specific distinction, in the restricted acceptation of that term.

I have brought together these definitions, in the first place to show that naturalists are by no means agreed upon what constitutes a species, and secondly, to offer some views of my own.

As the result of much observation and reflection, I now submit a definition which I hope will obviate at least some of the objections to which I have alluded. SPECIES—*a primordial organic form*. It will be justly remarked that a difficulty presents itself, at the outset, in determining what forms are primordial; but independently of various other sources of evidence, we may be assisted in the inquiry by those monumental records, both of Egypt and Assyria, of which we are now happily possessed of the proximate dates. My view may be briefly explained by saying, that if certain existing organic types can be traced back into the "night of time," as dissimilar as we see them now, is it not more reasonable to regard them as aboriginal, than to suppose them the mere accidental derivations of an isolated patriarchal stem of which we know nothing? Hence, for example, I believe the dog family not to have originated from one primitive form, but from many. Again, what I call a species may be regarded by some naturalists as a *primitive variety*; but, as the difference is only in name, and in no way influences the zoological question, it is unnecessary to notice it further.

These views appear to correspond with those of Mr. Linnæus Martin, who expresses himself in the following terms:

"We are among those who believe that, as there are degrees in the relationship of species to species, some may, although distinct, approximate so nearly as not only to produce *inter se*, mules incapable of interbreeding, but *a progeny of fertile hybrids, capable of admixture, even to the most unlimited extent*?

Species may therefore be classed according to their disparity or affinity, in the following provisional manner:

Remote species of the same genus, are those among which hybrids are never produced.

Allied species produce, *inter se*, an infertile offspring.

Proximate species produce with each other a fertile offspring.

the tail. It was with a flock of other birds, and as it slowly left the bank of the river, I remarked that there was a peculiarity in its gait. It pondered over the ground as it walked with eccentric pace, as if it were measuring angles; and it struck me that it is this trait to which Plutarch alludes, and which gave to the *Ibis* the character of Hierogrammaticus or Geometer. If any one else has had the good fortune to see this bird in its natural state, he will perhaps have noticed the singularity which I have described."

In confirmation of Mr. Harris's remark about the scarcity of the real *Ibis religiosa* at the present day in Egypt, Mr. Gliddon observed, that although he had shot over the length and breadth of the land at all times of the year, he had never seen a *living Ibis* during twenty three years residence there. The only modern specimen of the *Ibis* he had ever seen was a dead one, offered for sale by a Moghrebbee hunter at Cairo, about 1835. Mr. Harris has been familiar with Egypt for twenty-seven years, and besides being a profound hierologist, is a keen and observing sportsman. His experience is therefore authoritative; and a sufficient refutation of the accounts of tourists, who talk of seeing *Ibises* on the Nile as if they were common birds there—confounding this with that commonest of all birds, the *buffalo crane*, called by the Arabs *Aboo-gerdàn*.

The *black* Ibis, though very rare, has been shot by Mr. Gliddon near lake Bourlos in the Delta. Both species are still abundant above Dongola.

Dr. Morton called attention to two plates, which he exhibited, of Layard's folio illustrations of the ruins of Nineveh, whereon are figured the Camel (C. bactrianus,) and Dromedary (C. dromedarius,) with as much distinctive accuracy as if they had been drawn but yesterday, and yet they date, according to Mr. Layard, 2600 years before our era, or, according to Rawlinson, more than a thousand years later. In either case, they are additional evidence of the distinctness of species, a point which has been disputed, simply because they are said to produce with each other a fertile hybrid offspring.

The following resolution was adopted: *Resolved*, That a copy of the Proceedings, as far as published, be presented to the Agricultural Society of Lyons.

October 8th.

Dr. Morton, President, in the Chair.

Two letters were read from the Secretary of the Geological Society of London, dated severally, May 8th and May 23d, 1850, acknowledging the reception by that Society, of Part 4, Vol. 1, new series, of the Journal, and of recent Nos. of the Proceedings.

Also a letter from Col. J. D. Graham, dated Washington, September 20th, 1850, desiring the renewal of his certificate of membership in the Academy, which had been lost. On motion, the request was granted.

ears. Now the present Nubian greyhound, as seen in the beautiful plates of M. Prisse's *Oriental Album*, appears to be the very same animal; and it is a curious fact, mentioned to me by Mr. Gliddon, that the Modern Nubians habitually crop the ears of this dog.

4. The third form of antique greyhound has a bushy tail. It is figured by Hamilton Smith from the monuments, but I have not yet met with it, and consequently cannot at present determine its age. A similar form, called the *Akaba greyhound*, is yet common in Syria and Arabia.*

But what is not less remarkable than the permanence and vast antiquity of the preceding forms, is the fact that what we call the *English greyhound* is figured with every distinctive characteristic, even to the semi-pendant ears, on a supposed antique statue now preserved in the Vatican at Rome. †

The first three of this series are probably primordial forms; but the English greyhound may be a derivative from some partial intermixture, in the same manner that the Irish greyhound is said to be derived from an infusion of the great Danish dog with the common breed. ‡

5. The Bloodhound—(*C. Sagax.*)—Several varieties of the stag and bloodhound are very closely allied. In the tomb of Roti, at Beni Hassan, is a painting representing a spirited deer-hunt, and the dogs, two of which are represented, are admirable illustrations of this variety. They are common on the latter monuments: for example, in the *Grand Procession* of Thotmes III, (B. C. 1700,) where several of them are associated with people and productions of the interior of Africa. § Again, yet later, it is seen in a tomb at Gourneh, near Thebes; and if I mistake not, through various later epochs. Now if we compare the oldest of the delineations—viz.: those of Beni Hassan, with the bloodhounds of Africa lately (and perhaps yet) living in the Tower Menagerie in London, we cannot deny their identity, so complete is the resemblance of form and instinct. ‖

6. The Turnspit—(*C. vertagus.*)—Wilkinson and Blainville have both acknowledged that a variety of this dog is figured in the tomb of Roti, at Beni Hassan. ¶ It is yet common both in Europe and Asia.

7. The Watch Dog—(*C.*————.)—Several of these animals, or at least their analogues, are figured in the tomb just mentioned,** They bear a striking resemblance to one figured on a Roman mosaic pavement at Pompeii, and are frequently met with in the East. It is possibly this dog which represents a second canine symbol in the hieroglyphic alphabet; but the figure is too small to enable me to speak with confidence.††

8. House Dog.—(*C. hybridus.*)—I take this identification and provisional specific name, as I have also most of the others of this series, from Blainville. ‡‡‡

---

* La Borde, Trav. through Arabia Petræa, p. 118. Russell's Alleppo, II, p. 179.
† Blainville, Osteographie, Canis, pl. XIV.
‡ Bell, British Quadrupeds, p. 241.
§ Hoskins's Ethiopia, Grand Procession, Part I.
‖ Bennett. Tower Menagerie, p. 83.
¶ Rosellini, Tav. XVII, fig. 4.
** Idem. Tab. XVII, fig. 2,4,9. See Martin on the Dog, p. 49.
†† Bunsen, ut supra, p. 417.
‡‡‡ Osteographie, Canis, pl. XIV. Blainville calls it *chien domestique*. It is also the *Roguet* of the French.

12. Shepherd's Dog—(C. *domesticus.*)—The earliest effigy of this animal, which is also mentioned by Aristotle, is preserved on ancient Etruscan medals of unknown date. The probability is that it was familiar to man in the earliest ages, and may yet be found on the Egyptian monuments. It is doubtless one of the primordial forms of the canine race.

In allusion to the illustrations derived from the monuments, Blainville truly remarks that "we here see a large number of our existing breeds of dogs;" and inasmuch as they have preserved their identity through such vast periods of time not only in the most diversified climates, but also under the influence of the greatest variety of circumstances, is it not reasonable to believe that a part at least of these forms, constitute essential primeval types? We trace them back into the "night of time," and find them as distinct as they yet are in the living *Fauna;* and it remains for those persons who insist that they have all been derived from an aboriginal pair, to give us something more in proof than analogical reasoning, or inferences drawn from arbitrary views of the laws of Nature.

But an evidence of the great antiquity of the animal we call the domestic dog, and one to which I have already alluded, is the fact that it has been recently found in a fossil state in two localities very remote from each other. First in Germany by Schmerling, and secondly, in New Zealand by Mr. W. Mantell, (son of the celebrated geologist,) who there found it associated with the bones of the gigantic *Dinornis.* Now from these facts I conceive we must conclude, either that some forms of this animal are primordial and independent of human domestication; or, that man himself, having existed contemporaneously with these now fossilized animals, claims a vast antiquity as a denizen of the earth.

It is shrewdly observed by Azara, that if the differences among dogs were the result of climate, all the dogs of each separate country should be alike. To this I may add, that if they are all descended from a single primal type, they ought, on resuming the wild state, to return to this type. Yet in America, where the experiment has been observed on the largest and most unequivocal scale, we see no such result. In Jamaica, they have in some instances reverted to the shepherd's dog—in others, to the great Danish dog; and this last variety is the dominant one in the wild packs of Paraguay. In Cuba they have sometimes resembled greyhounds, and in the pampas of Brazil they are more like terriers. *In other words, they constantly tend to recur to that primitive element which is most dominant in their physical constitution;* and it is remarkable that in the old world this restored type is never the wolf, although it is sometimes, as we have seen, a lupine dog, owing to the physiological cause just mentioned.

The blending of the opposite extremes of these types, and these hybrids again with each other, gives rise, as every one knows, to those degenerate animals known as pugs, shocks, spaniels, &c., which Cuvier justly calls "the most degenerate productions," and which are found "to possess a short and fleeting existence—the common lot of all types of modern origin."

Among the North American Indians, the original forms are very few and closely allied; whence it happens that these grotesque varieties never appear. Neither have they any approximation to that marked family we call *hounds;* and this fact is the more remarkable since the Indian dogs are employed in the same manner of hunting as the hounds of Europe, Asia and Africa. Yet, this similarity of employment has caused no analogy of exterior form. No varieties, like those so familiar in Europe, spring up among them. They are as homogeneous as the

Also a letter from the Linnean Society of Lyons, dated July 1, 1850, presenting the Annals of that Society for 1847–49.

A letter was also read from J. A. Grex, Esq., addressed to the Librarian, dated New York, October 3, 1850, transmitting the above works, and acknowledging the reception of a copy of the Journal, Vol. 1, new series, and of a copy of the Proceedings, for the Agricultural Society of Lyons.

Dr. Leidy presented two papers, one describing two new species of Infusorial Entozoa, and the other entitled "descriptions of some nematoid Entozoa infesting insects," both of which were referred to the committee having charge of previous communications by Dr. Leidy read at late meetings of the Society, viz., Drs. Hallowell, Keller, and Zantzinger.

Dr. Leidy also made the following observations on two new genera of mammalian fossils, which he designates under the names of Eucrotaphus Jacksoni, and Archaeotherium Mortoni:

The two fragments of mammalian crania, which I exhibit this evening to the Academy, are part of those specimens a short time since presented to our Cabinet by Mr. Joseph Culbertson, of Cumberland, Co., Penna., whose son obtained them from that region of country, in the vicinity of Fort Laramie on the Platte river, known as the "mauvais terres," or "bad lands," a locality, which, according to recent researches made by Dr. John Evans, is rich in such remains. Both fragments belong to new genera of mammalia. The smaller of these I have named Eucrotaphus, on account of the comparatively very large size of the temporal bones. It consists of the central portion only of the cranium, and is a little longer than the corresponding portion of the skull of the beaver (Castor fiber.) In general outline it resembles the posterior part of the cranium of the American mink, (Mustela lutreola) or more particularly that of the opossum, (Didelphis virginiana;) being broad posteriorly, cylindroid anterior to the ossa tempora, but is not as bulging at the sides as in the latter mentioned animals.

The bones still existing in the specimen consist of the right temporal, except its zygoma and posterior superior portion; a portion of the left squamous bone; the middle portion of the ossa parietalia, ossified into one, except the sagittal crest; the right para-mastoid, or paroccipital process, except the tip, with a small fragment of the occiput above it; the posterior sphenoid, somewhat mutilated; a fragment of the presphenoid; and a fragment of the basioccipital.

The most remarkable characteristics of this head are:—first, the comparatively enormous size of the squamous portion of the ossa tempora; second, the great advancement of the ossa parietalia;* third, the deep groove in the ossa parietalia just in advance of the squamous suture; fourth, the strength of origin of the zygoma; and fifth, the form of the glenoid cavity.

* I for some time hesitated before I applied this name to the symmetrical bone occupying the upper part of the cranium. I thought at first it was the frontal extending very far back, but upon considering the advanced position of the squamous portion of the temporal bone, and observing in the Erinaceus ecaudatus, a considerable prolongation forward of the ossa parietalia, I concluded that it belonged to the latter category.

bulla and the root of the pterygoid processes is the foramen ovale. The latter mentioned basis of support to the pterygoid processes is a triangular prominence, and placed immediately on a line with it in front is a large round spheno-orbitar foramen. The basisphenoid is cylindrical in form, a little over an inch in length, and joins the presphenoid on a line with the spheno-orbitar foramina. The mutilated commencement of the presphenoid in the specimen is alone sufficient to indicate that it undergoes little diminution in diameter from that of the basisphenoid. The basioccipital is also cylindroid in form, a little broader than the basisphenoid and articulates with the latter on a line with it. The para-mastoid process or paroccipital joins the mastoid process, and affords an abutment posteriorly to the auditory bulla; it is rough and strong, and in the specimen descends two-thirds the length of the latter process, the tip being broken off. The ossa parietalia, ossified into one symmetrical bone, in advance of the ossa tempora are nearly cylindrical and antero-inferiorly join the alisphenoid. Between the ossa squamosa, the two at their narrowest portion measure only 7-10ths of an inch across. They are surmounted by a strong sagittal crest with a broad base, which in the specimen has been broken away. Laterally in advance of the squamous suture, is a remarkable and vertical, moderately deep and broad groove, the office of which I cannot conjecture. The squamous suture partakes of the serrated form.

Measurements.—From one lateral groove of the parietalia to the other measures 1 and 7-10ths of an inch; the distance between the glenoid cavities, 1 and 3-10ths inch; from the posterior face of the posterior glenoid tubercle to the anterior boundary of the anterior glenoid tubercle is 1 and 2-10ths inch; from one foramen ovale to the other 4-10ths of an inch.

Remarks.—From the very great strength of the base of support of the zygomatic process; the comparative size and concealed position of the glenoid cavity; the great size of the posterior glenoid tubercle; and the great extent of the temporal fossa, (for although it is shortened by the very rapid ascent of the superior root of the zygoma and advancement of the occiput, yet it is increased in extent by the very great vertical development of the squamous bone, and in depth by the comparatively depressed or flattened surface of the latter,) the Eucrotaphus has been endowed with very great power in the muscles of mastication and great freedom of movement in the articulation of the lower jaw.

The position of this genus I have not been able satisfactorily to determine from the specimen, and we must wait, therefore, until other parts of the cranium of the animal are found before we can be able to detect its true place among the orders.

The species I have named Eucrotaphus Jacksoni, in honor of my esteemed friend Dr. Samuel Jackson, the eminent teacher of the Institutes of Medicine in the University of Pennsylvania.

The second fossil fragment, which I have named Archaeotherium, appears to have belonged to an animal not remotely allied to the Anoplotherium. The specimen is part only of the face, consisting of the middle portion of the left os maxillare superius, with the corresponding portion of the palate process, containing two premolar teeth and the alveolus for a third, a fragment of the upper part of the right os maxillare superius, the central portion of the two ossa nasi, and the anterior extremity of the left os mala. In general form this part of the face is prolonged like that of the Anoplotherium, and in size was at least one-half greater than the A. commune.

October 22d.

Dr. Morton, President, in the Chair.

Mr. Richard C. Taylor presented the following meteorological observations made at the Isthmus of Panama, at Port Royal, Jamaica, and at sea, in October, 1849.

Table constructed from a few Meteorological Notes, chiefly in regard to the daily temperature at noon, on the east coast of the Isthmus of Panama, Port Royal, in Jamaica, and on the return voyage to New York; for the month of October, 1849.

By Richard C. Taylor.

Date.	Position.	Observations at noon.		
		Latitude.	Thermometer.	Barometer.
Oct. 6	On shore, at Escribanos, Prov. Veragua.	9° 04′	82°	
7	do. do.	9 04	83	
8	Off shore,	9 04	86	
9	On shore at Chagres,	9 24	88	
10	do. do.	9 24	90	
11	do. do.	9 24	90	29° 70′
12	At anchor, one mile from Chagres,	9 24	88	29 70
15	do.	9 24	85	29 70
17	do.	9 24	92	29 50
18	Caribbean Sea,		88	29 50
19	do.		88	29 60
20	Port Royal, Jamaica,	18 00	85	29 20
21	do.	18 00	85	29 20
22	At sea, close under St. Domingo,	19 52	83	29 60
23	do. off Maraguana Island,	22 20	83	29 60
24	do.	26 26	78	29 50
25	do.	29 06	76	29 50
26	do.	34 25	72	30 10
27	do. off Cape Henlopen,	38 45	66	29 80
31	At New York,	40 42	43	

There appear to be some peculiarities, not readily accounted for, in the periods of Rainy and Dry seasons upon the Isthmus of Panama, at points which are not very far distant from each other, on the same coast.

Thus, the rainy season at Escribanos, in the Province of Veragua, we understand, is the reverse of that at Chagres, which place is situated at only sixty or seventy miles distance.

At Chagres, the *dry* season begins in December and ends in May, and the principal *rainy* months are those between May and November.

On the other hand, at Escribanos, the most *rainy* months are those which extend from November to the end of March. The inhabitants at this time are confined to their houses and have few opportunities of getting out of their doors. What is called the *dry* season in this vicinity, is from April to the end of October. Still, storms and showers occur almost daily in those months; and, in reference to the entire year at Escribanos, we remember the somewhat vague remark of the French Negro proprietor there—"it rains *every* time."

October 27th.

Dr. Morton, President, in the Chair.

The Committee on Mr. Deane's paper, "On the Fosil Foot-prints of the Connecticut River," reported in favor of publication in the Journal.

The Committee on Dr. Townsend's description of a new American Wolf, (Lupus gigas, Townsend,) reported in favor of publication in the Journal.

The Committee on the following papers by Dr. Leidy, read at the meetings of October 1, Oct. 8th, and Oct. 15th, 1850, reported in favor of their publication in the Proceedings.

—

Contributions to Helminthology.

By Joseph Leidy, M. D.

1. Ligula Tritonis.—Body ribbon-like, thin, translucent, nearly smooth, faintly yellowish white, posteriorly obtusely rounded. Head thickened, rounded, transversely corrugated, yellowish; extremity triangularly rounded, laterally compressed, front and back, with a short, longitudinal, contracted depression.

Whole length 1 in. 9 lines; breadth of body 1-3d line, thickness 1-12th line; length of head 1 line, breadth 1-4th line, thickness 1-9th line.

Habitation and Remarks.—This species was sent to me by my friend Prof. S. F. Baird, of Carlisle, with the note "Found embedded in the muscles of the back of Triton (Cynops) dorsalis." It is the smallest species which has as yet been discovered, and the first among batrachian reptilia. The specimen sent to me consisted of two fragments of the same individual preserved in alcohol. Examined beneath the microscope it presented no trace of articulation or interior definite organs.

2. Pentastomum *Didelphidis Virginianæ.*—Body subcylindrical, curved one third or one-half a circle, dorsum convex, bentrum concave, posteriorly narrowed and constricted a short distance from the extremity, which is rounded. Color white, opaque. Composed of forty or fewer annulations. Head posteriorly convex, anteriorly plain or slightly concave; mouth nearly round; hooks simple, situated in a curved line of which the mouth forms the centre.

Whole length 3 to 5 lines, breadth 3-5th of a line; annuli generally 1-80th inch wide; mouth 1-200th inch in diameter; hooks 1-200th inch long.

Habitation and Remarks,—I found 9 individuals of this entozoon, in C shaped cysts, the circle being 2 lines in diameter, imbedded in the liver just beneath the peritoneal surface, in Didelphis virginiana. It may probably be the *Pentastomum subcylindricum* of Diesing,* which was found in cysts upon the liver of two South American species of Didelphis, and several other animals, but the largest of those found in our D. virginiana, is equal only to the smallest of P. subcylindricum, and has not more than one-half the number of annulations.

* Annal. d. Wien. Mus. 1 p. 21. *Dujardin:* Hist. Nat. des Helminthes p. 305. *Diesing:* Systema Helminthum, Vol. I, p. 611.

Habitation.—Found with the anterior 3 lines of its length buried in an oval tumor, 4 lines in diameter, in the mesentery of a Didelphis virginiana.

7. Echinorhynchus *Pici collaris.*—Body white, opaque, subcylindrical, subcompressed and curved posteriorly, transversely corrugated, and slightly so longitudinally, moderately dilated anteriorly. Neck very short. Proboscis short, cylindrical, contracted in the middle, with the free extremity rounded and furnished with 4 rows of simple, recurved booklets.

Length 1 inch 8 lines, breadth anteriorly 1-10 inch, thickness 1-12 inch; posteriorly 4-5 line broad by 3-5 line thick. Proboscis 4-5 line long, thickness ½ line.

Habitation.—Intestine of Picus collaris.

Remarks.—Differs from the E. Pici, *Goeze*[*] which has a long linear proboscis with 8 or 10 ranges of booklets, and is narrower in front than behind, just the reverse of the species just described.

Notes on the Development of the Gordius aquaticus.

By Joseph Leidy, M. D.

Just four years ago I exhibited to the Academy a mass of living hair-worms or Gordius aquaticus, consisting of fourteen individuals strangely knotted together, and recalling the appropriateness of the Linnean name.

It is a vulgar opinion that the Gordius is a horse hair which has become vivified from maceration for several weeks in a spring or pool of fresh water, an error which has probably arisen from their frequently being found in water filling a wagon rut, or the drinking trough of a horse. I have even been informed by some persons, though by those not given to observe such matters, that they had perceived the direct transmutation of horse hairs into writhing worms, and I was at one time so silly as to be led to try the experiment, with what success it is unnecessary for me to state.

The Gordii alluded to in the mass, were blackish-brown in color, from 6 to 10 inches in length, and most of them had attached to the posterior extremity of the body a long, white, opaque cord, in several instances nearly as long and as thick as the worms themselves. These cords some of the members may recollect I pointed out at the time as being strings of the ova of the Gordii, but I then was not so well acquainted with the history of the Gordius as at present; that is to say, I did not know that we have no knowledge whatever of its origin or development, and although through curiosity I traced for a few days the development of the embryo in ovo, yet I did not do it with that care which its importance demanded. But however imperfect have been the observations made, with this acknowledgment, I have thought it would be well to record them, with the hope that they may not only throw some light upon the obscure nature of the Gordius, but also lead others to the discovery of a similar opportunity of investigating this animal under more favorable circumstances of locality and information. The observations I have withheld for a length of time in the hope that I might be able to verify or correct them, but failing to do so to the present time, I now reluctantly put them forth from my notes taken at the time.

The white cords before mentioned consisted of numerous oval ova closely

[*] Naturgeschichte S. 151, Taf. 11.

were deeply reflected upon the outside of the body, and the inner circle projected obliquely outward and upward. The proboscis was clavate in form or cylindrical and moderately dilated at its free end, and more so at its base. The following six days no perceptible change was observable in the development of the animal, and after this the eggs showed evident appearances of decay, and I gave them no further attention.

—

Two new species of Infusorial Entozoa.

By Joseph Leidy, M. D.

1. Nycotherus ovalis.—Body translucent oval, posteriorly obtuse. Anterior granular areola three sided. Posterior fissure passing downwards.

Length 1-100th inch, breadth 1-33d inch.

Habitation.—The intestinum tenue of the Blatta orientalis, occasionally in considerable numbers.

2. Bodo Julidis.—Body translucent, faintly greenish, faintly granular with one or two large round vacuolæ and numerous minute ones; form changing, usually globular, oval, or pyriform; caudæ twice the length of the body, very active, frequently twisted into a ring at the extremity. Diameter of body 1-3000th of an inch.

Habitation.—The large intestine of Julus marginatus, in company with Nycotherus velox, often in millions.

—

Description of some Nematoid Entozoa infesting Insects.

By Joseph Leidy, M. D.

Genus *Aorurus*. Sub-genus *Streptostoma*. Proc. Acad. Nat. Sci. 1849 p. 230.

1. Streptostoma gracile.

Oxyuris Diesingii. *Hammerschmidt*. Isis von Oken J. 1838, S. 354, Taf. iv. Fig. 6.

Body attenuated from the middle anteriorly and posteriorly, white, translucent, shining. Anterior annuli very broad and moveable upon one another. Oral annulus short, truncate; second annulus long, constricted in the middle. Tail nearly one-third the length of the body, shining, straight or curved. Pharynx short. Oesophagus consisting of two elongated, pyriform, muscular bulbs. Neck of first œsophageal bulb dilated at commencement and middle; neck of second, long, narrow and cylindrical. Ventriculus largely dilated and oval at commencement, afterward cylindrical.

Length of body 1 line; breadth opposite ventricular dilatation 1-136th inch; just above anus 1-300th inch; greatest do., 1-107th in; length of tail 1-40th inch; breadth at middle 1.1360th inch; length of first pyriform bulb of œsophagus 1-150th inch; breadth of neck of do. 1-1100th inch; do. of body of do. 1-400th inch; length of second bulb 1-214th inch; breadth of neck 1-1300th inch; do. of body 1-340th inch; do. of dilated commencement of ventriculus 1-214th inch. do. of cylindrical portion 1-330th inch.

Ova oval, 1-300th inch long by 1-625th inch broad.

Habitation.—Found in numbers of one to half a dozen in the small intestine of our domestic cockroach, (Blatta orientalis.) This species was discovered by

Hammerschmidt, who named it Oxyuris Diesingii, but as it is considered a doubtful compliment to name intestinal worms after persons, in placing it in the genus Streptostoma, I have also changed the specific name. The individuals from which my description is taken were the largest I found.

Sub-genus *Thelastoma*. Proc. Acad. Nat. Sci. 1849 p. 231.

2. THELASTOMA APPENDICULATUM.—Body cylindrical, narrowed anteriorly and posteriorly, white, translucent, shining, strongly annulated. First division of the œsophagus moderately long, cylindrical; second portion short, broad, and pyriform, ventriculus dilated cordiform at commencement, becoming rapidly narrowed and cylindrical, and sending off posteriorly a large and long pyriform diverticulum or coecum, afterward cylindrical to termination, and forming a single short convolution just posterior to the generative aperture. Tail straight, spiculate, one-fourth the length of the body. Eighty five annulations to the body of which there are twenty-eight from the mouth to the commencement of the ventriculus. Generative aperture twenty-six annulations from the anal aperture. Last annulation furnished with two short spines projecting backward.

Length of body 1 line to 1-10th of an inch; breadth at ventricular commencement 1-100th inch, at middle 1-80th inch, at anus 1-160th inch; tail 1-50th inch long, breadth at middle 1-888th inch; first portion of œsophagus 1-80th inch long, 1-533d inch broad; second portion 1-240th inch long; neck of do. 1-666th inch broad; body of do. 1-250th inch; commencement of ventriculus 1-200th inch broad; cylindrical portion 1-400th inch; diverticulum of ventriculus 1-66th inch long by 1-266th inch broad.

Ovum semi-oval, 1-258th inch long, by 1-666th inch broad.

Habitation.—Found in the intestinum tenue of the domestic cockroach (Blatta orientalis,) with the former.

3. THELASTOMA LABIATUM.—Body white, translucent, anteriorly strongly annulated. Papilla of the mouth dilated, six lobed. First portion of œsophagus cylindrical, second portion broad, pyriform; ventriculus sub-cordiform at commencement. One hundred and fifty annulations, of which there are forty from the mouth to the commencement of the ventriculus.

Length of body 1-22d inch; greatest breadth 1-200th inch: length of tail 1-40th inch; length of first portion of œsophagus 1-120th inch; breadth 1-1000th inch; second portion 1-320th inch long by 1-400th broad; breadth of ventricular dilatation 1-266th inch.

Ovum oval, 1-333d inch long, by 1-500th inch broad.

Habitation.—Found in numbers of from one to a dozen in the intestine of Polydesmus virginiensis.

4. THELASTOMA ROBUSTUM.—Body white, cylindrical, narrowed anteriorly and posteriorly. First portion of œsophagus long, cylindrical; second portion broad, pyriform. Commencement of ventriculus dilated, oval, afterwards cylindrical. Articulations of body 212, of which there are forty from the mouth to the commencement of the ventriculus, 102 from the latter to the generative aperture, and from this to the tail 70.

Length of body 2 lines; breadth at ventricular dilatation 1-75th inch; at sixth annulation from mouth, only 1-320th inch; at middle 1-66th inch; just above anus 1-75th inch; tail 1-22d inch long by 1-1000th inch broad at middle; first portion of œsophagus 1-50th inch long by 1-500th inch broad; second portion 1-178th inch long by 1-200th inch broad; ventricular dilatation 1-105th inch broad.

Ovum oval, 1-306th inch long by 1-500th inch broad.

Habitation.—Found in the intestine, in numbers of from one to three, in the larva of a lamellicorn insect.

Remark.—The descriptions of the above are entirely taken from females, considerable numbers of which I have found and possess, but I have never yet been able to discover a single male.

5. Oxyuris socialis.—Body white, narrow, cylindrical, elastic, posteriorly attenuated; mouth projecting, with a short pharynx; œsophagus consisting of two portions: first portion long, cylindrical, dilated at its posterior part; second portion, narrow, pyriform; ventriculus moderately dilated at commencement, capacious, cylindrical; tail long, narrow, acute.

Female.—From 1 line to 2 and 1-5th lines in length; breadth 1-266th inch. First portion of œsophagus 1-66th inch long, 1-800th inch broad; second portion 1-200th inch long by 1-666th inch broad. Generative aperture projecting, just anterior to middle. Tail simple pointed, 1-57th inch long from anus, 1-400th inch broad at base.

Ovum oval, white, 1-363d inch long, 1-666th inch broad.

Male.—Length 4-5ths to 3-5ths of a line; breadth 1-400th inch; posteriorly recurved. Tail pointed, furnished with five minute epidermoid prominences on the inner side, 1-133d inch long from anus. Spiculum of penis single, simple, curved, 1-400th inch long.

Habitation.—Found in numbers of from five to twenty, of which one-fifth are males, in the large intestine of the large black cricket (Acheta abbreviata.)

Genus *Hystrignathus.*—Body cylindrical, anteriorly furnished with transverse rows of simple spines projecting backward; mouth surmounting a large naked papilla; œsophagus of two portions: the first long, cylindrical, the second short and pyriform; annulations indistinct posteriorly; tail long.

6. Hystrignathus rigidus.—Body straight, rigid, cylindrical, narrowed anteriorly and posteriorly; anteriorly furnished with 106 transverse rows of simple spines projecting obliquely backward, each row corresponding to an annulation and containing about sixteen spines; anterior spines longest, equal to the width of the annulations, becoming shorter posteriorly and decreasing to mere points. First annulation of the mouth truncated, conical, smooth; second annulation smooth. Pharynx extending through the first two annulations. First portion of œsophagus long, cylindrical; second portion with a narrow cylindrical neck and globular body; ventriculus cylindrical, slightly dilated anteriorly, narrowed anteriorly; rectum elongated conical. Tail long, curved. Generative aperture very near the middle of the body.

Length 2 lines; greatest breadth 1-140th inch; tail 1-40th inch long from anus, 1-1000th inch broad at middle; anterior or spinous portion of body 1-26th inch long or one fourth of the whole length. First portion of œsophagus 1-50th inch long, 1-520th inch broad; second portion 1-190th inch long, 1-320th inch broad at body. Anterior spines 1-2000th inch long. Fifty-eight spinous annulations corresponding to the first portion of the œsophagus, twelve to the second portion. Annuli posteriorly indistinct.

Ova oval, 1-214th inch long, by 1-545 inch broad.

Habitation.—The female only I have found in numbers of one to five within, and adhering by the mouth to the parietes of, the ventriculus of Passalus cornutus.

Lanius ludovicianus. Cassin.

Published by J. Bowen, Philada.

Parus atricristatus. Cassin.

Lith. of Pendleton, Cor.d by J. T. Bowen Phila.da

The Committee on the following paper by Mr. Cassin, read at last meeting, reported in favor of publication in the Proceedings.

Descriptions of new species of Birds of the Genera Parus, Linn.; Emberiza, Linn.; Carduelis, Briss.; Myiothera, Ill.; and Leuconerpes, Sw., specimens of which are in the collection of the Academy of Natural Sciences of Philadelphia.

By John Cassin.

1. *Parus annexus*, nobis.

Form.—Crested; bill strong, conical; fourth and fifth quills longest and equal, wings and tail rather long, crest pointed.

Dimensions.—Total length (of skin) from tip of bill to end of tail about 5 inches, wing 2¼, tail 2½ inches.

Colors.—Sex unknown. Anterior feathers of the crest black at their bases and cinereous at their tips, the most elongated of the succeeding entirely black, others margined with white, shorter occipital feathers, black; chin and throat black. Wide line from above the eye running into the crest, thence around upon the side of the neck, white. Line commencing behind the eye, running thence around and uniting with the space of the same color upon the throat, black, cheeks white. Entire superior surface cinereous, tinged with olive, quills and tail feathers brownish black, primaries narrowly edged externally with white, secondaries and tail feathers edged externally with ashy olive. Body beneath ashy white, darker upon the breast. Bill black.

Hab.—Texas, upon the Rio Grande, discovered by Mr. John Woodhouse Audubon.

Obs.—This very remarkable species, discovered in Texas by a son of the illustrious naturalist of the same name, is marked upon the head more like the *P. cristatus* of Europe than any other American species yet known. It does not resemble that species in any other character, however, being more strictly related to P. bicolor, Linn. and P. inornatus, Gamb., and like them belonging to the genus Lophophanes, Kaup.

2. *Parus stricristatus*, nobis.

Form.—Crested, wings and tail rather long. Crest pointed as in P. bicolor, Linn., bill strong, conical. Specimen now described not in mature plumage.

Dimensions.—Total length of skin from tip of bill to end of tail about 5 inches, wing 2½, tail 2½ inches.

Colors.—Sex unknown. Crest black, front and under parts of the body ashy white, flanks ferrugineous; entire superior surface cinereous, darker upon the wings and tail, and inclining to olivaceus upon the back. Bill and legs black. Shafts of primaries reddish at their bases, those of the tail feathers white beneath.

Hab.—Texas, on the Rio Grande, discovered by Mr. John Woodhouse Audubon.

Obs.—This species is of the same general form and color as P. bicolor, Linn. and P. inornatus, Gamb.; smaller than the former, but about the size of the latter. It may be easily recognized by its black pointed crest and white front, which, so far as I know, are peculiar characters. This species, like the preceding, was discovered in Texas by Mr. Audubon, and belongs to the same genus.

3. *Emberiza bilineata*, nobis.

Form.—Bill strong; wings short, with the second, third and fourth primaries longest and nearly equal, some of the secondaries emarginate. Legs and feet rather long. Aberrant, may not belong to this genus.

Dimensions.—Total length of skin from tip of bill to end of tail about 5 inches, wing 2 and 4-10ths, tail 2 and 2-10th inches.

Colors.—Sex unknown. Line from the nostril running above the eye towards the occiput, and another from the angle of the lower mandible running upon the side of the neck, white, space between those lines including the nares and plumage under the eye and the ears, nearly black. Throat from the base of the bill, black, which color is bounded on each side by the white lines from the angles of the lower mandible, and continues to a somewhat rounded point upon the breast. Head and body above dark cinereous, inclining to brownish upon the back and wing coverts. Quills brownish. Tail brownish black, external feathers having their outer webs pure white and tipped with the same color, the brown color of these feathers extending narrowly along the shafts into the white tips. Body beneath white, tinged with cinereous. Bill bluish horn color.

Hab.—Texas, on the Rio Grande; discovered by Mr. John Woodhouse Audubon.

Obs.—This is one of the most remarkable finches yet discovered in America, and is quite unlike, even in general appearance, any other species of this country with which I am acquainted This bird was also brought from Texas by Mr. Audubon.

4. *Emberiza Belli*, nobis.

Form.—Wings rather short, second, third and fourth quills longest and nearly equal. Tail and legs rather long.

Dimensions.—♂ Total length of skin from tip of bill to end of tail about 5¼ inches, wing 2¾, tail 3 inches.

Colors.—♂ Head and neck above cinerous, shading into olive upon the back and neck.

Frontal spots on each side of the base of the bill, (scarcely united) narrow ring around the eye, and entire under surface white. Edge of the wing at flexure, yellow; superior wing coverts brown tinged with ferruginous, quills and tail brownish black, nearly all the feathers of both narrowly edged with whitish, most apparent upon both webs of the external tail feathers. Conspicuous spot upon the breast, nares, and lines from the external angles of lower mandible running downwards upon the sides of the neck, deep brownish black. Flanks tinged with rufous and with a few longitudinal stripes of brown.

♀ Slightly smaller, flanks and interior tail coverts more tinged with rufous.

Hab.—California, near Sonoma and San Diego; discovered by Mr. John G. Bell.

Obs.—This species resembles in rather a remarkable degree the Emberiza hypochondria, D'Orb. Voy. Merid. Ois. pl. 45, fig. 1, but is smaller and without the deep castaneous flanks of that species. In the bird now described, the dark spot upon the white breast is a striking feature, and is much more strongly pronounced than in any other with which I am acquainted.

I have named this species in honor of Mr. John G. Bell, of the city of New York, a gentleman possessing a very extensive knowledge of natural history, and whose attachment to the pursuit of which, induced him to make the visit to California, which resulted in the discovery of this and other interesting birds.

Acad Nat Sci Vol V.

Emberiza bilineata, Cassin

Drawn by H. L. Stephens.

Lith. Printed & Col^d by J. T. Bowen.

Emberiza Bellii Cassin

Drawn by H. L. Stephens

Lith. Printed & Col.d by J.T. Bowen Philad.a



Myiothera, mudicaps. Cassin.

Drawn by H. L. Stephens

Drawn on Stone by Wm E. Hitchcock

Lith. Printed & Col. by J. T. Bowen, Phila.





Carduelis Lawrencei Cassin.

Drawn by R. L. Stephens.

Lith. of Wm. Rease, Phila.

Printed by Sherman & Co.

The following is Mr. Bell's note relating to this species: "This bird I shot first near Sonoma, and afterwards at San Diego; its habits much resemble those of the painted bunting, (*S. ciris.*) I observed several of them amongst the wormwood at the edge of the hills, sitting on the tops of the small bushes, singing, and when disturbed would dart downwards. The song is quite unlike that of any of our finches, rather low and plaintive, and perhaps most resembles that of the Swamp sparrow, (Amm. palustris.) It is neither a very active nor a shy bird, and was not rare at the localities mentioned."

In a collection of birds deposited in this Academy by Mr. E. L. Kern, and collected by him while with the expedition of Col. Fremont in 1846, there is a specimen of a young bird very much resembling that now described, but much larger, being about the size of the E. hypochondria D'Orb., and is, I think an unknown species. The specimen is not only in bad plumage, but so much injured as scarcely to admit of being mounted.

5. *Carduelis Lawrencei*, nobis.

Form.—Bill rather conical, three outer primaries longest and nearly equal; tail coverts long, tail emarginate.

Dimensions.—Total length of skin from tip of bill to end of tail about 4¼ inches, wing 2 and 8-10ths, tail 2 inches.

Colors.—♂. Head above and a small space around the bill and upon the throat, black; head behind and sides of the neck pale cinereous, shading into fine brownish olive upon the back, and into a paler cinereous upon the sides under the wings, nearly white upon the abdomen and inferior tail coverts. Lesser and exposed portion of greater wing coverts, rump, breast and belly fine pale yellow; upper tail coverts cinereous. Spurious wing, black, conspicuous.

Quills brownish black, primaries and succeeding secondaries externally edged with yellow; shorter secondaries edged and tipped with ashy white. Tail brownish black, the external feathers each with a large spot of white on its inner web, very conspicuous.

Hab.—Sonoma and San Diego, California, discovered by Mr. John G. Bell.

♀. Without black upon the head or throat, those parts being brownish olive; the yellow color upon the inferior surface more restricted.

Obs.—This beautiful little bird resembles no other Carduelis which has come under my notice. Mr. Bell's note respecting it is as follows: "This bird I first observed at Sonoma. In habits it much resembled our common Goldfinch (*C. tristis.*) The flock, out of which I shot these two, was feeding in company with the small black headed species (*C. psaltria,*) on the seeds of plants growing near the ground, and when disturbed alighted upon the nearest bushes. When flying, they keep up a constant chattering or calling like our common species. I also saw this bird at San Diego, feeding as above in company with the crimson fronted Bullfinch, (*Erythrospiza frontalis,*) in the open prairie. I never saw it in the mountains."

I have named this bird in honor of Mr. George N. Lawrence, of the city of New York, a gentlemen whose acquirements, especially in American Ornithology, entitle him to a high rank amongst naturalists, and for whom I have a particular respect, because, like myself, in the limited leisure allowed by the vexations and discouragements of commercial life, he is devoted to the more grateful pursuits of natural history.

6. *Myiothera nudiceps*, nobis.

Form.—Upper part of head bald or with a few bristle like feathers, wings with the fifth quill slightly longest, tail short, legs long. General form much like M. longipes, (Vieill.)

Dimensions.—Total length of skin from tip of bill to end of tail about 6¼ inches, wing 3 and 1-8th, tail 2¼ inches.

Colors.— ♂. Naked space upon the head blue. Entire plumage black. Wing coverts delicately edged with white, which is also the color of the basal portion of the feathers of the back, (apparent only upon raising them.) Irides white.

Hab.—Panama; discovered by Mr. John G. Bell.

Obs.—This species may readily be distinguished from others of its genus by its bald head, the naked skin of which in the living bird is, as Mr. Bell informs me, "Mazarine blue." His note is as follows: "These birds kept on the ground, running and scratching among the leaves, like the others of the same family which I send, and somewhat like our small Thrushes, (M. mustelina and solitaria.) They were constantly calling and singing a short, loud, and very curious song, which varied in several of its notes at different times, and is entirely different from that of any of our birds. This species appeared to me to be rather a stupid bird, and was easily approached; it has a habit of puffing up the feathers on its back; the head in recently killed specimens is beautiful Mazarine blue. It was represented to me as a very rare bird by several residents at Panama."

7. *Leuconerpes albolarvatus*, nobis.

Form.—Robust, wings with the fourth primary longest, secondaries broad, abruptly terminated, sub-emarginate; tail rather long, with the feathers soft at the ends. Legs and feet rather slender.

Dimensions.—Total length of skin from tip of bill to end of tail about 9 inches, wing 5, tail 3¼ inches.

Colors.— ♂. Wide mask including greater part of the head and extending upon the breast, white, which is also the color of a basal portion of both webs of the primaries, and upon the outer webs in a few feathers extends for two thirds of their length. Narrow occipital band scarlet. All other parts, including body above and below, wings and tail, black.

♀. Similar, but rather smaller, and without the occipital band of scarlet.

Hab.—Near Sutter's mill, California, discovered by Mr. John G. Bell.

Obs.—Mr. Bell's note accompanying this very interesting species is as follows: "I shot this bird at the Oregon canon, near Georgetown, about 12 miles from Sutter's mill; it seemed to prefer the tall pine trees, and generally kept very high. In habits it appeared very much like the P. villosus. Its note is clear and sharp, and it is very active and lively in its movements." Has no near relative yet discovered in North America, and resembles in general characters only the L. dominicanus, (Vieill.) Spix. Av. Bras. pl. 50.

ELECTION.

Dr. John Evans, of New Harmony, Indiana, was elected a *Correspondent* of the Academy.

DONATIONS TO MUSEUM

In September and October, 1850.

September 3d.

Thirty-four hundred and forty-nine specimens of Birds' Eggs from the collection of M. O. Des Murs, 976 do. from the collection of John Gould, Esq., and 207 do. from other sources, comprising 1500 species. Also ten Birds' nests from M. Des Murs' collection, thirty-three do. from Mr. Gould's, and twenty do. from other sources. Presented by Dr. T. B. Wilson.

September 10th.

Three specimens of Hippopus maculatus; one Tridacne, one Cytherea; three serpents from the China sea; a large living Tortoise from Java; and ten Bird skins. Presented by Capt. John Land.

Numerous specimens, in spirits, of American Reptilia. From Mr. Samuel Ashmead.

October 1st.

A batrachian reptile from New Mexico, probably a young Axolotyl. Presented by Col. J. J. Abert.

Cranium of Cynocephalus porcarius, from the Cape of Good Hope, presented by Dr. Watson to Dr. Morton, and deposited by the latter in the Academy.

Scarabæus tityus ♂, from Cape May. From Dr. Townsend.

October 8th.

Crystallized Mica, from Chester Co., Pennsylvania. Presented by Mr. F. F. Seal.

Petromyzon ——?, from the Atlantic Ocean. From Dr. Wilson.

Coal Fossils from the Pennsylvania Mines. From Mr. Dewey, of Philadelphia.

Chelonura serpentina. From Dr. Morton.

Dr. Morton also deposited the following Crania:—Two ancient Egyptians, four Swedes, one Ostrogoth, two Californians, one Greek, two Brazilians, one Seneca, one Mexican. Also the heads of Ovis montana, fem., and Cervus macrotis.

October 15th.

Living specimen of Crotalus durissus. From Mr. Ash.

Specimens of Palæmon, Elaps and Cyclura. From Dr. John Neill.

October 22d.

Dr. Morton deposited Crania of Chelonia midas (2,) Simia (2,) two species of Gulo, one Lupus, one Arctomys, one Procyon.

Horn of Rhinoceros bicornis? from South Africa. From Mr. Watson through Dr. G. Watson.

A collection of American Coleoptera, in spirits. From Dr. Watson.

DONATIONS TO LIBRARY

In September and October, 1850.

September 3d.

First Biennial Report on the Geology of Alabama. By M. Tuomey. 8vo.

Dr. Wilson presented the following on the usual conditions:

Observations sur les devellopement et la disposition des œufs de plusieurs espoces ovipares appartenent au genre Hirudo. Par M. Rayer.

De la Muscardine (maladie des vers à soie.) Par M. le Comte Jacques Barbo, de Milan.

Notice sur la Sangsue officinale, &c. Par M. J. Achard.

Recherches géographiques sur l'Afrique centrale. Par M. Latreille.

Recherches sur la formation de la fibre musculaire. Par M. Dutrochet.

Mémoire sur la generation des animaux à bourse.

Ovologie du Kangaroo. Par M. Costi.

Lagographia, ab M. Wolffg. Waldungo.

Notice des Insects de la France réputés venemeux. Par M. Amoreux. 8vo.

Vade Mecum für Naturaliensammler. Von F, W. L. Suckow. 8vo.

Avis pour la transport par mer des Arbres, des plantes vivaces, &c. Second ed. 12 mo.

Ensayo de una historia de los Peces y otras producticnes marinas de la Costa de Galicia. Por Dr. Joseph Cormade. 12 mo.

Nouvelle relation d'un voyage fait aux Indes Orientales. Par M. Dillon, M. D. 12 mo.

Souvenirs d'un voyage à Sydney fait pendant l'annee, 1845. Par M. Eugene Delessert de Havre. 8vo.

Description du Cape de Bonne Esperance. Par M. Pierre Kolbe, 3 vols, 12mo.

Catalogue Systematique de la collection de Coquillages, &c., de feu Sieur Michel Oudann. 8vo.

Les Pigeons de voliére et de Colombier. Par MM. Boitard et Corbie. 8vo.

Les Ages de la Nature et histoire de l'espéce humaine. Par M. le Comte de Lacépede. Tome 1me. 8vo.

Dissertatio physiologica inàug. de circulatione et respiratione Animalium pulmonibus instructorum, Auctore G. J. van der Boon Mesch.

Precis d'anatomie comparée. Par H. Holland, 8vo.

Descripcion de differentes piezas de historia natural, Las mas del Ramo maritimo representadas en setenta y cinco laminas. Su autor Don Antonio Parra, 4to.

Ornithologiæ specimen novum, Auctore Petro Barrere, 4to.

Fabii Columnæ Opusculum de Purpura. Ab Johann Dan Majoris, M. D. 4to.

Nuova Filosofia de la naturaleza del Hombre, &c.; por Dona Oliva Sabuco de Nantes Barrera. 4to.

Relazione del Ritrovamento dell 'uova di Chioccioli di A. F. M, in una lettera al Sig M. Malpighi. 12mo.

Specimen Zoologicum, sistens observationes præsertim osteologicas de Casuario Novæ Hollandiæ. Auctore P. I. I. de Fremery.

Die naturliche historie des Nashorns. Von Dr. Georg L. Huth. 4to.

Die Conchylien in dem Natural-kabinet seiner Hochfürstlichen Gnaden des Hernn Fürsten und Bischofs von Konstanz. 8vo.

Experiences servant á démontrer que la pathologie des animaux á sang froid est exempte de l'acte morbide qui dans les animaux á sang chaud a reçu le nom d'Inflammation. Par le Dr. Robert Latour.

De l'utilité de la culture des Feves et des Pommes de terre, dans le departement du Calvados.

Mémoire sur un Insecte et un Champignon, qui ravagent les Cafiers aux Antilles. Par Mess. Guerin-Meneville, et Perrottet.

Over het nieu geslacht Nyctophilus Leach. Door C. J. Temminck.

Recherches sur la géneration des Mammiféres. Par M. Victor Coste.

Lettre de M. Coste a M. Raspail sur l'Embryogénie.

Observationes microscopiques sur les Animalcules des eaux et des thermes de Carlsbad. Par A. C. J. Corda.

Aperçu d'histoire naturelle.

Journal of the Franklin Institute, 3d series, Vol. 20, No. 2. August 1850.

September 10th.

Report of the Joint Committee on Levees. From Prof. C. G. Forschey.

The American Journal of Science and Arts, 2d series, No. 28. Sept. 1850. From the Editors.

Address delivered at the Anniversary meeting of the Geological Society of London, 15th Feb., 1850. By Sir Charles Lyell. From Dr. Morton.

Dr. Wilson presented the following on the usual condition:

Historia naturalis curiosa Regni Poloniæ, &c., desumpta opera P. G. Rzaczynski. 4to.

Cynographia curiosa seu Canis descriptio, et mantissa curiosa complectente J. C. Libell de Canibus Britannicis et J. H. Meibonn epistola de Kounophora. Aucta a C. Paullin. 4to.

Voyages dans les Deux Oceans, 1844 a 1847. Par M. Eugene Delessert. 8vo.

Voyage en Angleterre, en Écosse, et aux Iles Hebrides. Par B. Faujas St. Fond. 2 vols. 4to.

L'Ambassade de la Compagnie Orientale des Provinces Unies vers l'Empereur de la Chine; fait par les St. Pierre de Goyer et Jacob de Keyser. Folio.

Description des Plantes de l'Amerique. Par le R. P. Charles Plumier. Folio.

Systematischer Catalog der Preparate des Anatomischen Museums der König-Rhinischen F. W. Univer. zu Bonn. Von Dr. A. F. J. C. Meyer.

System dentaire des Mammiféres et des Oiseaux. Par E. Geof. St. Hilaire.

Sulla Epistola Zootomica del Prof. Otto al celeb. Blumenbach Brevi Cenni del Prof. Guiseppe Mangili.

Essai de classification naturelle et d'analyse des phénomenes de la vie. Par P. N. Gerdy.

Mémoire pour servir a l'histoire des insectes ennemis de la Vigne et a l'indication des moyens propres a prevenir leurs ravages. Par J. Vallot, M. D.

Discorso sulla Antroposofia del Dr. Lucio Cipriano.

Observations sur les rapports de la mére et du père, avec les produits relativement au sexe et a la resemblance. Par M. Girou de Buzareingues.

Nécessité d'introduire l'etude de la Zoologie dans l'enseigment agricole. Par M. F. E. Guerin-Meneville.

Recherches microscopiques sur l'Acarus Scabiei. Par MM. Laroi et Vandenbecke.

Considerations sur la Peau et en particulier sur le Derme. Par le Dr. de Buzareingues.

Mémoire sur les rapports des sexes dans les naissances de l'éspece humaine. Par le Dr. de Buzareingues.

Nouveaux coups de Fouet scientifiques.

Recherches anatomiques et physiologiques sur la maladie contagieuse qui attaque les Vers a Soie, et qu'on designe sous le nom de Muscardine. Par M. Victor Audouin; et Nouvelles experiences sur la meme (la Muscardine,) par le meme.

Forschungen über Geschlechts-natur. Von Karl Aug. Erb.

Rapport fait au nom de la commission chargée d'indiquer la Société les moyens les plus efficaces pour la destruction du ver Blanc et du Hanneton.

Discours relatifs a l'histoire naturelle. Par J. Draparnaud.

Observations nonnullæ microscopicæ fila (quæ primitiva dicunt) in inflammatione spectantes. Auctore Theophilus Gluge.

Notice historique sur les découvertes faites dans les Sciences d'observation par l'étude de l'organisation des Grenouilles. Par M. C. Dumeril.

C. Ph. F. Groshaus, M. D., specimen anatomico-physiologicum de systemate uropoietico, quod est Radiatorum, Articulatorum et Molluscorum acephalorum.

J. Van der Hoven oratio de aucta et emendata Zoologica post Linnæi tempora, &c.

Mémoire sur la structure élémentaire des principaux tissues organiques des animaux. Par H. Milne Edwards.

Analyse de la philosophie anatomique. Par M. Flourens.

Notice sur l'histoire, les mœurs et l'organisation de la Giraffe. Par M. Joly.

Recherches d'anatomie et de physiologie sur un embryon monstreuse de la Poule domestique, circonscrit dans l'existence solitaire d'un cœur. Par Charles le Blond.

Andentungen über den Gang der bei Bearbeitung der Naturgeschichte besonders der Zoologie von ihrem Beginne bis auf unsere Zeiten genommen ist. Von Dr. F. S. Leuckart.

Mémoire sur les organes de l'absorption chez les Mammiféres. Par M. Magendie.

Systematisches Verzeichniss der Petrefacten-Sammlung des Verstorbenen wirkleichen Geh.-Raths Freihernn v. Schlotheim.

Nouvelles instructions sur les eaux minérales de Chateldon en Bourbonnois.

Catalogus Conchyliorum terrestrium fluviatiliumque Europæ collectionis Caroli Porro.

Mémoire pour servir d'introduction a un ouvrage sur la respiration des animaux. Par G. Fischer.

De la nature des Étres. Par Ch. Girou de Buzareingues.

September 17th.

The following were presented by Dr. Wilson on the usual condition:

Archiv für Naturgeschichte. Herausgeg. von Dr. F. H. Troschel. No. 5, 1848., Nos. 3 and 4, 1849.

Annales de la Société Entomologique de France: 2d series, No. 4, 1849.

Zeitschrift für Malakozoologie. Von K. T. Menke, M. D., und Dr. Pfeiffer. No. 3, 1850.

Comptes rendus. Nos. 13—25, Tome 30. No. 1, Tome 31, et index du Tome 29.

The London Athenæum, for June and July, 1850.

Journal of the Franklin Institute, Vol. 20, 3d series, No. 3.

Revue et Magazin de Zoologie. Nos. 3, 4, 5, 1850.

Notice sur George Cuvier. Par M. Victor Audouin.

Essai sur l'histoire naturelle des Serpens de la Suisse. Par J. F. Wyder.

Mémoire sur les Os anciens et fossiles, et sur d'autres residus solides de la petrefaction. Par M. J. Girardin et M. F. Preis.

Remarques sur les oiseaux fossiles. Par Paul Gervais.

Muscardine—Mission confiée par M. Cunin-Gridaine a M. Guerin-Meneville.

Recueil de Planches des Coquilles fossiles des environs de Paris. Par M. De la Marck. 4to.

Catalogus Librorum quibus usus vir clarus Gerardus Sandifort. 8vo.

Histoire de Botany Bay. Par M. Jules de la Pilorgerie. 2d edition. 8vo.

Summi polyhistoris G. G. Leibnitzii Protogea: a C. L. Scheideo. 4to.

Di Crostacei e degli altri Marini Corpi che si truavaceo su monti libri duæ di Anton-Lazzaro Moro. 4to.

Observations sur les Insectes. Par Marcel de Serres. 4to.

Encefalotomia di alcuni .quadrupedi, communicata da Vincenzo Malacarne. 4to.

Anatomie und naturgeschichte des Drachens. Von Dr. F. Teidemann. 4to.

Beyträge sur anatomie und Physiologie der Thiere. Von Dr. J. A. Albers. Part 1. 4to.

Catalogo ragianato e descrittivo della Raccolta de Serpenti del Museo dell J. R. Universita de Pavia del Dr. Fillippo de Filippe.

Sopra a vestigi di Crostacei Entomostraci del genere Ciclopo di Muller in uno schisto marnoso ittiolitico, &c. Di Ramillo Ranzani.

Recherches sur les Coquilles fossiles de la Province d'Anvers. Par H. Nyst.

Testacea novissima Insulæ Cubanæ et Americæ Centralis. Auctore Arthur Morelet.

Catalogue des Coquilles trouvées sur les Cotés du departement de la Manche. Par M. Greville.

Mémoire sur des Cygnes qui chantent. Par M. A. Mongez.

Observations sur les mœurs et les habitudes des oiseaux de la Savoie. Par M. J. B. Bailly.

Catologo degli animali invertebrati marini del Golpho di Geneva e Nizza observata da Gio. Batta Verany.

Histoire naturelle et iconographie des Insectes coléoptéres d'Europe. Par M. Latreille et M. le Comte Dejean. Nos. 1, 2, 3.

Mémoire sur les Podurelles. Par M. l'Abbé Bourlet.

Mémoire sur le mécanisme de la respiration des Poissons. (Dumeril.) 8vo.

Catologo metodico del Mammiferi Europei di Carlo L. Principe Bonaparte.

Specchio generale dei sistemi Erpetologico, Anfibiologico ed Ittiologico di C. L. Principe Bonaparte.

Beobachtungen aus der Zootomie und Physiologie. Von G. R. Treviranus. Part 1. 4to.

Dissert. anatomico-physiolog. inaug. de Manducatione Hominis ceterorumque Mammalium. Auctore P. H. O. Canzius.

Mémoire sur quelques nouveaux genres de Mollusques et de Vers Lithophages. Par le Cit. Flourien-Bellevue.

Rapport fait a la Société sur les moyens de prévenir et d'arreter les ravages de l'alucite des grains; au nom de la Commission composée de MM. Busche, Darblay, &c.; Husard fils rapporteur.

Sulla malattia attualmente Regnante ni Bovini e sulla scielta del metodo curativo. Lettera del Dott. Pietro Debo al Sig. Sommariva.

October 1st.

Della Mnemotechnia orvero del modo di meravigliosamente facilitar la memoria mediante l'associazone delle idee. Del Prof. Consoni Malanese. From the author.

Reports of Lieut. Simpson and Capt. Marcy to the War Department, on the route from Fort Smith to Santa Fe. 8vo. From Col. J. J. Abert.

Du Système nerveux chez les Invertébrés (Mollusques et Annelidés) dans ses rapports avec la classification de ces animaux. Par M. Émile Blanchard. From the author.

De l'appareil circulatoire et des organes de la respiration dans les arachnides. Par M. Blanchard. From the same.

Second Mémoire sur l'organisation des Malacobdelles. Par M. Blanchard. From the same.

Dr. Wilson presented the following on the usual conditions:

Nouveau systeme sur la generation de l'Homme et celle de l'oiseau. Par Charles Denys de Launay. 12mo.

Histoire des Indes Orientales. Par M. Soucher de Rennefort. 12mo.

De Hyena odorifera ἔξτασις Petri Castelli Romani: ed. nouv. 12mo.

Éloge de M. le Baron Georges Cuvier. Par M. le Baron Pasquier.

Promenades du Jardin des Plantes. Par MM. Rousseau et Céran Lémonnier. 12mo.

Voyage et avantures de Francois Leguat et de ses compagnons en deux isles desertes des Indes Orientales. 2 vols. 12mo.

Letters a un Americain sur l'histoire naturelle de Buffon (Delignac.) 12mo.

Éléments d'histoire naturelle. Par F. de Guernel. Parts 1 and 2. 12mo.

Études sur la Muscardine; maladie des Vers a Soie: faites par MM. Guerin Meneville et Robert.

De la Peche du Parcage et du commerce des Huitres en France, Par M. P. A. Lair. 8vo.

Experiences et observations sur la reproduction des animaux domestiques. Par M. de Buzareingues.

Dell 'uomo considerato come un proprio regno del 'Istoria naturelle: Del Prof. Georgio Jan.

Prodromus Systematis Ichthyologiæ C. L. Bonaparte Principe di Musignano.

Bijdragen tot de Natuurlijke Geschiedenis von dem Negerstein: door J. Van der Hoeven. 4to.

P. M. Augusti Broussonet, M. D. Ichthyologia; sistens Piscium descriptiones et icones.

Prodromus Icthyologiæ Scandinaviæ: Auctore S. Nillson. 8vo.

Description d'une Crane colossal de Dinotherium giganteum trouve dans la Province Rhénane du Grand Duché de Hesse Darmstadt. Par MM. de Klipstein et Kaup.

Gulielmi Pisonis M.D. de Medicina Brasiliensi libri quatuor, et Geo. Marcgravi de Leibstad historiæ rerum naturalium Brasiliæ libri octo. Folio.

Les dons marveilleux et diversement colorées de la Nature dans le regne mineral, &c. Par M. Buchoz. Folio.

Untersuchungen über die Gefaessverbindung zwischer mutter und frucht in dem Saugiethieren. Von Karl Ernst von Baer. Folio.

Egenhandiga Anteckninger af Carl Linnæus orn Sig Sjelf med Anmarkningar och Tillagg. 4to.

October 8th.

Otia Ægyptiaca. Discourses on Egyptian Archæology and hieroglyphical discoveries. By George R. Gliddon. 8vo. From the Author.

Hand-Book to the American Panorama of the Nile. By G. R. Gliddon. From the same.

Dr. Wilson presented the following on the usual condition:

Précis d'une voyage au Cap-de-Bonne-Esperance. Par M. P. Delalande.

Memorias sobre la Purpura de los Antiguos. Par D. Juan Pablo Canals y Marti.

Sopra un nuova genere di Spongiali Silicei. Dal Da. Giovanni Domenico Nardo.

Fragments sur les organes génito-urinaires des Reptiles et leurs produits. Par G. L. Duvernoy.

Delphinus leucopleurus; nova species descripta ab H. Rasch.

Mémoire sur plusieurs nouveaux organes propres aux Oiseaux et aux Reptiles. Par F. Magendie.

Essai pour servir a l'histoire des animaux du Midi de la France. Par M. de Serres.

Breves animalium quorundam maxima ex parte marinorum descriptiones. Auctore F. S. Leuckart.

Histoire d'une petit Crustacé (Artemia salina Leach) auquel on a faussement attribué la coloration en rouge des Marais salans Méditterranéens. Par M. Joly.

De l'Amnios chez les Oiseaux. Par Henri Jacquart.

Propositions sur la Monstrosite consideree chez l'Homme et les auimaux. Par Isidore Geoffroy St. Hilaire.

Prodrome d'une histoire naturelle, &c., de Cantharides. Par I. Victor Audouin.

Disquisitio anatomica de Pinguedine animali. A. C. H. E. Allmer.

Dissertation sur la place que la famille des Ornithorhynques et des Echidnes doit occuper dans les series naturelles. Par H. M. Ducrotay de Blainville.

Centurie de Lepidoptéres de l'Ile de Cuba contenant la description et les figures colorees de cent espéces de Papillons nouveaux ou peu connus. Par Ph. Poey. Nos. 1 and 2. 4to.

Féte Séculaire de Ch. de Linne celébrée par la Société Imperiale des Nat. de Moscou le $\frac{2}{14}$ Juin 1835. Par G. Fischer de Waldheim.

Sur l'huitre des Cotes de France. Par M. Carbonnel.

Notice sur le Musée Conchylogique de M. le Baron Benj. Delessert. Par M. Chenu.

Notice sur plusieurs nouvelles espéces de Cyclades decouvertés dans les environs de Valenciennes. Par N.-A.-J.-Normaud.

C. J. Temminck observations sur la classification methodique des Oiseaux, et remarques sur l'analyse d'une nouvelle Ornithologie élémentaire. Par L. P. Veillott.

Tableau méthodique des Mollusques terrestres et fluviatiles vivants, observés dans le Department de Maine-et-Loire. Par M. Millet.

Rapport fait à l'Acad. des Sci. de Paris sur un ouvrage inedit ayant pour titre 'Tableau Methodique de la classe des Cephalapodes.' M. Latreille, rapporteur.

Considerationes génerales sur les Faluns: description des Terrains tertiaires de la Bretagne et des principaux fossiles qui s'y trouvent. P. P. Duchassaing.

Memoire sur des Roches Coquillières trouvées a la Cime des Alphes Dauphinoises et sur des Colonnes d'un Temple de Sérapis a Pouzzol près de Naples. Par M. B^{oo}.

De l'Huitre et de son usage comme aliment et comme reméde. Par Etienne St. Marie.

Catalogue des Oiseaux du Departement de la Manche. Par Emanuel Canivet.

Sur les Nummulites. Par Dr. Scortegagna de Lorrigo.

Catalogo dei Molluschi della Lombardia compilato di Fratelli Antonio G. Gio. Battista Villa.

Dispositio systematica Conchyliarum terrest. et fluviat. quæ adserventur in collectione fratrum Ant. et Jo. Bapt. Villa.

Osservazioni sullo stato della Zoologia in Europa in quanto ai Vertebrati nell' anno 1840 '41. Da Carlo Luc. Principe Bonaparte.

Descriptive catalogue of the Lepidopterous Insects contained in the Museum of the Hon. E. I. Co. By Thos. Horsfield, M. D. Parts 1 and 2. 4to.

Catalogue des livres composant la Bibliothèque de feu M. Fred. Cuvier; do. de feu M. le Baron de Gérando; do. de feu M. Dumont de St. Croix; do. de Mr. A. M. L. De Nantes; do. de feu M. D'Arcet; do. de MM. L. et B.; do. de M. Felix de Russy; do. de feu M. De Lamarck; do. de feu M. le Dr. Breschet; do. de feu M. le Baron R. Desgenettes; do. de feu M. Alex. Lauth; do. de feu Chas. Nodier.

October 15th.

Journal of the Indian Archipelago and Eastern Asia. Vol. 4. Nos. 5 and 6. From the Editor.

Proceedings of the Zoological Society of London. Part 17, 1849. From the Society.

Reports of the Council and Auditors of the Zoolog. Soc. of London. April 29, 1850. From the same.

Conspectus Systematum Herpetologiæ et Amphibiologiæ Caroli L. Bonaparte. Ed. alt. reformata, 1850. From the Author.

Conspectus generum Avium. C. L. Bonaparte: pp. 233—344, et pp. 353—400. From the Author.

Annales de la Société Linnéenne de Lyon. An. 1847—1849. 8vo. From the Society.

Mémoires de l'Académie des Sciences, &c., de Lyon. Classe des Sciences. Tomes 1 et 2. 8vo. Classe des Lettres. Tomes 1 et 2. 8vo. From the Society.

Annales des Sciences physiques et naturelles d'agriculture et d'industrie publiées par la Société Royale d'Agriculture, &c., de Lyon. Tomes 10 et 11. 8vo. From the Society.

Eighteenth memoir with reference to the law of Storms in India. By Henry Piddington. From the Author.

Dr. Wilson presented the following on the usual condition.

Contributions to Ornithology. By Sir William Jardine. Part 3, 1850.

Transactions of the Botanical Society of Edinburgh. Vol 4. Part 1.

Phycologia Britannica. By W. H. Harvey, M. D. Parts 48, 49.

Systematisches Verzeichniss der Europäischen Schmetterlinge von Heydenreich.

Proceedings of the Zoological Society of London, with illustrations. Part 3. July to December, 1849.

Monographie des Poissons fossiles du vieux grés rouge, ou Systéme Dévonien, des Iles Britanniques et de Russie. Par L. Agassiz. 4to. and Atlas folio.

Rhea; Zeitschrift für die gesammte Ornithologie. Von Dr. Thienemann. Part 2.

Journal of the Royal Geographical Society of London. Vol. 20, pt. 1, 1850.

Annales des Sciences naturelles. 3me. serie. Tome 12, Dec. 1849.

History of British Mollusca and their shells. By Prof. Forbes, and W. S. Hanley. Parts 30 and 31.

Quarterly Journal of the Geological Society. Vol. 6. No. 23.

Annals and Magazine of Natural History. Vol. 6. 2d series. Nos. 31, 32.

Transactions of the Royal Society of Edinburgh. Vol. 19, pts. 1 and 2. 4to.

Abbildungen und Beschreibungen neuer oder wenig gekannter Conchylien herausgegeben von Dr. R. A. Philippi. 3d Vol., pt. 7.

Philosophical Transactions of the Royal Society of London. Part 1, 1850.

The Birds of Asia. By J. Gould. Part 2, folio.

General Zoology: or systematic Natural History. By George Shaw, M. D. 14 Vols. 8vo.

Caroli Linnæi Systema Naturæ. Editio decima reformata. 2 vols. 8vo.

Report of the nineteenth meeting of the British Association for the advancement of Science. 8vo.

Handbuch der Zoologie. Von Georg Aug. Goldfuss. 2 vols. 8vo.

The Genera of Diurnal Lepidoptera. By Edward Doubleday, continued by O. Westwood. Parts 33 and 34.

October 22d.

Dr. Wilson presented the following on the usual condition:

Catalogue des Testacés vivans envoyés d'Alger par M. Rozet au cabinet d'histoire naturelle de Strasbourg. Par M. Michaud.

Bestimming der hundsart krokute und der Barenart Saribur samt deren Abbildung. Von Prof. Zauschner.

De Apodis cancriformis Shæf. anatome et historia evolutionis. Dissert. inaug. zootomica. Auctore Ernestus G. Zaddach.

Dissertatio anatomica-physiologica de peculiari arteriorum extremitatum in nonnullis animalibus dispositione. Auctore H. Vrolik.

Vier Abbildungen des Schädels der Simia satyrus, von verschidenem Alter zur Aufklärung der fabel vom Oran utan; herausgegeben von Dr. C. F. Heusinger.

Beskrivelser over en Flaggermuus henhörende tel Slægten Thiroptera (Spix.) Af. A. Rasch.

P. Belloni Cenomani de Arboribus coniferis, resiniferis, &c.

Histoire d'une larve aquatique du genre Simulium. Par J. E. Planchon.

Commentatio anatomico-physiologica de monstris duplicibus verticibus inter se junctis. Auctore Jo. Car. Leop. Barkow.

Observationes anatomicæ de Orthragorisco mola. Auctore Petrus H. J. Willenberg.

Tabillen über die Vergleichende Geognosie. Ein versuch von Christian Keferstein.

Traité de Taxidermie. Par M. Dupont.

De caloris animalis origine. Auctore Ed. Hochgeladen.

Jac. Chr. Schæffer de Studii Ichthyologici faciliori ac tutiori methodo.

Dissertatio anatomico-pathologica de mutato vasorum sanguiferorum decursu in Scoliosi et Cyphosi, &c. Auctore W. Vrolik.

Disquisitio Ampullularum Lieber-Kühnhn phisico-microscopica. Auctore Romanus Adolph Hedwig.

Dissertatio physico-medica: complectens experimenta varia calorem animalem spectantia. Auctore Arnold Duntze Bremensis.

Beschreibung und Abbildung von 24 Arten kurzschwänzigen Krabben als Beiträg zur Naturgeschichte des rothen Meeres. Von Dr. E. Rüppell.

Vers solitaires et autres de diverses especes dont il est traité dans le livre de la generation des Vers. (Andry.)

Symbolæ ad Ovi Mammalium historiam ante prægnationem. Scripsit Dr. A. Bernhardt.

Des Fibres élémentaires animales. Par MM. Cherest et Bouvaist, D. M. P.

Discours d'ouverture et de cloture du Cours de Zoologie donné dans le Museum **National** d'histoire naturelle, Ans. 6 et 9. Par M. Lacépède.

M. Cornelii Verloren commentatio de organis generationis in Molluscis gasteropodis pneumonicis.

Comment. anat. physiol. sistens disquisitionem an verum organorum digestioni inserventium discrimen inter animalia herbivora, carnivora, et omnivora reperiatur. Auctore Jano W. Neergaard.

Verhandeling over de Drentsche Slangen et Adders door Mr. J. Van Lier. 4to.

Bulletin Zoologique, publié sous la direction de F. E. Guérin. Nos. 1, 2, 3.

Rede bei Eröffnung der Versammlung deutscher Naturforscher und Aerzte in **Heidelberg** am 18 Sep. 1829, gehalten von F. Teidemann.

Nota del Dott. Francesc'Orazio Scortegagna sopra le Nummoliti.

Mollusca terrestria et fluviatilia edit. J. Curante C. Porro. 1846.

Abbildungen zur Schlangenkunde. Von Dr. H. D. Lenz.

Explication des Planches de l'ouvrage sur les Papillons d'Europe (par Ernst.) **A Madame** de Genlis. 4to.

November 5th, 1850.

Dr. MORTON, President, in the Chair.

Dr. Leidy read a communication, intended for publication in the Proceedings, entitled "Descriptions of three Filariæ," which was referred to Drs. Zantzinger, Hallowell, and Morton.

The Curators exhibited a mounted specimen of Lupus gigas, Townsend, being one of the individuals which formed the subject of a paper, read at a late meeting of the Academy, by Dr. Townsend, and published in the last number of the Journal.

November 12th.

Dr. MORTON, President, in the Chair.

A letter was read from Mr. Edward Wilson, dated Lydstip House, Pembrokeshire, Wales, Oct. 21st, 1850, giving information of several cases of books and specimens of Natural History, which had been shipped from England, and were presented to the Academy by himself and others.

A letter was read from M. Von den Buch, dated Bremen, Sep. 14th, 1850, addressed to the late Dr. Griffith, in relation to exchanges in Conchology. Referred to the Conchological Committee.

November 19th.

Dr. MORTON, President, in the Chair.

A letter was read from the Royal Society of London, dated Aug. 9th, 1850, acknowledging the reception of Part 4, Vol. 1, New Series of the Journal, and of No. 12, Vol. 5, of the Proceedings.

The Curators exhibited mounted skeletons of Testudo ——, from Java, presented by Mr. Ash, and of Hypsiprymnus cuniculus, from Tasmania, presented by Captain Wm. McMichæl.

Mr. Vaux, from the Publication Committee, announced the publication of Part 1, Vol. 2, New Series of the Journal, which was ready for distribution to subscribers.

November 26th.

Dr. MORTON, President, in the Chair.

The Committee, to which was referred the following by Dr. Leidy, reported in favor of publication in the Proceedings:

Descriptions of three Filariæ.

By JOSEPH LEIDY, M. D.

1. FILARIA *Hominis oris.*—Body white, opaque, linear, thread-like; mouth round, simple; posterior extremity obtuse, furnished with a short, curved, epidermal hooklet 1-500th in. in length, by 1-2000th in. in diameter at base.

Length 5 inches 7 lines, greatest breadth 1-66th in.; breadth at mouth 1-230th in.; at posterior extremity 1-80th in.

Remarks.—The description is taken from a single specimen preserved in alcohol, in the collection of the Academy, labelled "obtained from the mouth of a child."

Is it a young individual, or perhaps a male of the Filaria medinensis, or Guinea-worm? The latter, as is well known, infests the human body, often growing to an enormous length, several yards or more, in the intertropics of Asia and Africa. It is frequently brought in the body of negro slaves from Africa to America, where no entozoon of the kind has ever been noticed to be parasitic in man as an indigenous production. From some late observations on the course of life of entozoa, helminthologists have been led to suspect that most, and probably all entozoa pass different stages of their existence in different animals. If such be the fact, may the Filaria medinensis not owe its introduction into the human body, from the custom which prevails in those countries, where the worm is found, of using insect food? Insects are well known to be infested with Filariæ, probably more than any other class of animals. In Egypt, Arabia, &c., the locust is eaten; in Guinea, &c., the larger coleoptera; in the raw state, and in this condition Filariæ may often be swallowed, and reach a higher developement of their existence in the human body.

2. Filaria *Canis cordis.*—Body white, opaque, linear, nearly uniform throughout, posteriorly subulate, pointed; mouth simple, round.

Length 10 to 10½ inches, greatest breadth 2-5th of a line, anteriorly 1-5th of a line; half an inch from posterior end, 1-10th of a line.

Remarks.—The description is taken from two individuals preserved in alcohol, in the collection of the Academy, presented by Dr. R. Coates, who obtained them, according to the label upon the bottle, from the parietes of the heart of a dog.

3. Filaria *Boa constrictoris.*

♀. Body white, cylindrical; integument translucent, longitudinally striated; mouth simple, round; œsophagus cylindrical, opaque white; intestine opalescent, cylindrical, tortuous, corrugated, wider than the œsophagus; anus terminal, round; generative aperture close to the mouth; ovaries two, very long and very tortuous.

Remarks.—The description is taken from two specimens; one 10 inches long, by 4-5ths of a line wide, the other 6½ in. long by 3-5ths of a line wide. In the former the œsophagus is 9 lines long and 1-3d of a line wide, the intestine 13 in. long and 3-5ths of a line wide.

Habitation.—Found in the areolar tissue, in an irregular or tortuous position, between the muscles of the ribs and the integument of a Boa constrictor.

Note.—In the same Boa constrictor, which was dissected by my friend Dr. Hallowell and myself, we found in the right lung 6 females, 4 males, and a very young individual of Pentastomum proboscideum, and in the ureters of the kidnies 26 individuals of Distomum horridum.

ELECTION.

Mr. Richard P. Remington, of Philadelphia, was elected a *Member* of the Academy.

December 3d.

Dr. Morton, President, in the Chair.

A communication was read from the Minister of Public Works of France, dated Paris, Sept. 5th, 1850, accompanying a number of Vols. of the "Journal des Mines," and of the "Annales des Mines," which had been deficient in the series of that Work in the Library of the Academy;—and also asking in return, certain numbers of the Journal and Proceedings of this Institution.

A letter was read from Professor Nillson of Sweden, dated Lund, Sept. 30th, 1850, returning acknowledgments for his election as a Correspondent of the Academy, and stating his intention to present a copy of his work on the Fauna of Scandinavian Vertebrata; and also offering to procure for the Academy, Zoological specimens of that country, if desirable. Referred to the Zoological Committee.

Dr. Leidy read a paper entitled "New genera of Vermes," which, being intended for publication in the Proceedings, was referred to Drs. Zantzinger, B. H. Coates and Hallowell.

December 10th.

Vice-President Bridges, in the Chair.

Dr. Leidy exhibited several molar teeth and fragments of maxillæ of a fossil Rhinoceros, from Missouri territory, received from the Smithsonian Institution through Prof. Baird, which indicate a species little more than half the size of the recent R. indicus. He characterized it under the name of R. occidentalis.

Dr. Leidy also exhibited drawings, and offered the following remarks on the nettling organs of the Hydra:—

There are three different forms of these organs. The first are of comparatively large size, and are pyriform in shape, measuring about 1-1700ths in. in length, by 1-3125ths in. in breadth. They are found principally upon the arms, and anterior two thirds of the surface of the body, although they are found upon the posterior third also, but few in number. Colorless and transparent, they contain within them an elongated pyramidal body about 1-3400ths in. in length, the apex of which is in contact with, or slightly protrudes from, the projecting extremity of the nettling cell; the base is divided into four lobes and rests upon a prolate spheroid body which has its other extremity applied to the middle of the concavity of a cup-shaped mass of faintly yellowish matter occupying the inferior third or bas-fond of the receptacle. The pyramidal body is described by Corda* as being a calcareous dart capable of protrusion from the cell, but incorrectly, for when it is forced from its receptacle, it divides into four spine-like processes, which project outward nearly at right angles to the extruded mass. The intervals unoccupied, and the bodies just described within the cell are filled

*Nov. Act. Phys. Med. 1836, p. 301.

with a transparant colorless fluid. When the Hydra brings its arms in contact with its prey, the projecting ends of those nettling cells which touch it appear to adhere to the captured animal, and in the struggles of the latter, a delicate thread from the nettling cell is observed to be attached to the prey which is lengthened in the movements of the latter, entangling its limbs; and if the struggling continues or the prisoner escapes, it will be found to have several of the nettling cells, torn from the Hydra, adhering by the long delicate threads. In the detachment of the nettling cells, after considerable elongation of the thread, the whole of the interior mechanism is first withdrawn from the cell and adheres to its projecting end, as a cylindrical mass, faintly outlined, with a pyramidal summit from which proceeds the thread, and from the upper third of its sides, rise outwardly like springs, nearly at right angles to it, the four spinous processes before mentioned.* The nettling cell itself, appears darkly outlined from the thickness of its wall, and is much narrower than in the ordinary condition from the loss of a considerable part of its contents, and within is nothing else but a clear fluid. The traction continuing, the whole cell and appurtenances become detached from the Hydra. The thread which originated in the interior of the cell appears to be of a viscid character, for if any of these cells of the arms of the Hydra come in contact with its own body, they adhere with such tenacity, that the former can only be detached, at the expense of the loss of several of the nettling cells. From the detached cells often being found attached to the Hydra itself by the long threads, some observers, as Ehrenberg,* have considered that they were organs, which the animal threw out from itself like anchors.

The second form of nettling organs, are found arranged in more or less regular circles around the first or largest form, usually nine to fourteen in a circle. They are transparent, pyriform, about 1-3400th in. in length by 1-5666th in. in breadth, and have projecting from the prominent extremity a cilium about 1-875th in. in length. These cells are described by Corda as containing a thick walled sac, adhering to the outer cell at the base of the cilium. According to my observations, the appearance of an inner sac arises from a contained thread which forms a double spiral, one end of which forms the cilium projecting from the nettling cell.

The third form of nettling organs, are found in greatest abundance about the head of the animal, but also exist upon the arms, particularly at the lower part, and upon the surface of the body generally. This form appears never to have been before noticed. They are oblong, transparent cells, about 1-2125th in. long by 1-5666th in. broad, and contain within them a spiral thread, more delicate than in the second form of cells, and have a greater number of turns which take a direction transversely to the length of the cell. They resemble very much in their appearance one of the forms of nettling cells of Corynactis, figured by Allman in the 17th vol. of the Annals of Natural History, Pl. 11, fig. 4. I have never been able to see the threads prolonged externally, on account of their minuteness, in contact with the prey of the Hydra; but by pressure and the continued endosmosis of water I have detected them protruded in this as well as the second form described.

All the forms of nettling organs are placed within especial organic cells, adher-

*See Arch. für Naturgesch. 1842, p. 71.

ing by the more prominent extremity of the organ to that part of the interior parietes of the cell, corresponding to the free surface of the animal upon which they are placed. Their developement is special from the granular contents of the organic cells and not from the nucleus, for in the first or largest form of nettling organs, in their developement upon a bud of the Hydra, I have been able to detect one within an organic cell, and a nucleolated nucleus at its side.

The foregoing observations have been made in frequent efforts to detect some form of cell within the head of the Hydra which would be different from the general structure of the body, and probably characterize a nervous system, but although I have examined the animal in different menstrua under a variety of circumstances, I have never been able to discover anything which could be referred to a nervous structure.

December 17th.

Dr. MORTON, President, in the Chair.

A communication was read from the American Philosophical Society, dated Dec. 7th, 1850, acknowledging the reception of Part 1, Vol. 2, of the Journal of the Academy.

A communication was read from Dr. T. C. Henry, dated Albany, Dec. 2d, 1850, in reference to two fishes from Oswego Lake, lately presented by him to the Academy, and describing one of them as a new species under the name of *Centrarchus Oswego*. On motion, the communication was referred to a committee consisting of Mr. Cassin, Dr. Fisher and Dr. Leidy.

Dr. Leidy presented for the inspection of the members, fragments of fossil mammalian remains, from Missouri Territory, received from the Smithsonian Institution, through Prof. Baird, consisting of portions of crania, maxillæ and teeth, which he characterized under the names of Rhinoceros nebraskensis—a species not much larger than a common hog,—Palæotherium Bairdii, Merycoidodon Culbertsonii, and Agriochœrus antiquus.

1. RHINOCEROS NEBRASKENSIS.—A species founded upon a great portion of the face, containing all the superior molar teeth; an inferior maxilla with six molars; and three superior, apparently deciduous molars. It is about the same size as the R. minutus of Cuvier.

Length of line of seven superior molars, ...	4 7-10 inches.
" " six inferior "	4 2-10 "
Breadth of jaws from the first superior true molar teeth of one side to the other, ...	3 8-10 "

2. AGRIOCHŒRUS, *n. g.*—Founded upon a great portion of the face and inferior maxilla, containing six molar teeth on each side, and the posterior two molars of both sides superiorly of another individual. The posterior molars of this genus resemble in general form those of Merycopotamus, *Falk., & Caut.*, and are about one-third smaller, but the outer demicones are not separated to the base from each other like the former, but are combined by a rounded column as in Hyopotamus bovinus.

The fourth premolar has four demicones, but the internal posterior one is rudimentary. The third has two demicones; the external large, the internal small. The second form, but a single cusp. The inferior true molars in general form resemble those of Merycoidodon, but may at a glance be distinguished by the posterior edge of the postero-external demicone bifurcating before it terminates, sending one arm to join the internal angle of the posterior internal demicone; the other to join its posterior external face about the centre.

Length of range of superior six molars, ... 3 in. 1 line.
" " inferior posterior five molars, . . . 3 " 1 "
Breadth of face from one superior posterior molar to the other, 2 " 10 "

The species he called A. antiquus.

3. Paleotherium.—Remains of this genus have been previously discovered in this country. Dr. Prout in Silliman's Journal, Vol. 3, n. s., p. 248, describes a fragment of an inferior maxilla of a species larger than the P. magnum of Cuvier. The species, for distinction, may be named P. Proutii.

A second species was founded upon the cranium and a portion of the face containing the true molars; and the six superior and inferior molars of both sides of another individual. This species is about two-thirds the size of P. crassum. The arrangement of the superior molars is very like that of Paleotherium Hippoides.

Length of range of seven superior molars, ... 2 8-10 inches.
" " seven inferior " . . . . 3 "
Breadth of face on line with posterior superior molars, . 2¼ "

This second species Dr. L. named P. Bairdii, in honor of Prof. S. F. Baird, Curator of the Smithsonian Institution.

Dr. Morton commenced a series of remarks on the embalmed heads of Man, and the inferior animals from the Egyptian Catacombs; previously to which, he exhibited a drawing made from one of the former, which delineated with truthful precision the peculiar characteristics of the Egyptian conformation. The accompanying cut has been made from the drawing:

He called the attention of the Society to the fact, that the mummied body unwrapped by Mr. Gliddon, in Boston, during the past year, is unequivocally identified with the reign of Osorkon III, by finding the *cartouche* or oval of that King stamped in four different places on a leather cross, placed diagonally on the thorax in front.

Osorkon belongs to the XXII Dynasty, and his reign is placed between the years 895 and 905 B. C.; consequently the present individual, who was Theban, dates back about 2750 years. The physical characteristics are admirably in ac-

cordance with those of the pure Egyptian race, as seen in the somewhat receding forehead, the gently arched nose, slightly retracted chin, and general delicacy of form and proportion of the facial bones. The hair was destroyed by the bituminizing process, which has been performed in such excess as to efface the expression of the soft parts, and to render it impossible to measure the facial angle, or the internal capacity of the cranium.

There are one hundred and thirty embalmed Egyptian heads in the Collection of the Academy, but none of them can be even proximately dated; whence the great interest that attaches to the present example.

Two Egyptian heads were then unwrapped in the presence of the members. They were both from Thebes, where they were procured by A. C. Harris, Esq. of Alexandria, sent by him to Mr. Gliddon, and placed by the latter gentleman in the collection of Dr. Morton.

One of these heads, was of a man of 80 years, of Pelasgic or Græco-Egyptian form, with remarkably fine proportions and expression, and very fine hair, which the embalming process had changed, as it always does, from a black to a dark brown color.

The second head was that of a female, which was unfortunately so broken as to leave nothing but the cranial portion, and a profusion of the long, fine, curling hair, which was one of the characteristics of the *autocthones* of the Nile.

December 24th.

Dr. Morton, President, in the Chair.

A letter was read from Dr. John Evans, dated St. Louis, Mo., Dec. 9th, 1850, acknowledging the receipt of his notice of election, as a Correspondent.

Also one from the New York State Library, dated Albany, Dec. 20th, 1850, acknowledging the reception of Part 1, Vol. 2, New Series, of the Journal.

Also one of the same import from the Smithsonian Institution, dated Washington, Dec. 3d, 1850.

Mr. Cassin read a paper intended for publication in the Proceedings, entitled "Notice of an American species of Duck, hitherto regarded as identical with the Oidemia fusca, Linn." Referred to Drs. Zantzinger, Townsend, and Woodhouse.

Dr. Morton made some additional remarks on embalmed Egyptian heads.

December 31st.

Dr. Morton, President, in the Chair.

The committee to which was referred the following paper by Dr. Leidy, reported in favor of publication in the Proceedings.

Description of new genera of Vermes.

By Joseph Leidy, M. D.

1. Peloscolex. n.g. Setæ in two rows, 6 to 10 in each fasciculus; podal hooks in two rows, in twos or threes, bifurcated at the free extremity; each annulation furnished with a circle of prominent tubercles, with numerous smaller ones. Upper lip hardly projecting. Girdle not prominent. Blood red.

1. Peloscolex Variegatus.—Body cylindrical, posteriorly obtuse, anteriorly sub-acute. Setæ simple, usually 10 in each fasciculus anterior to the girdle, absent in the posterior 22 annulations. Podal hooks anteriorly in threes, divergent, strong, sigmoid, bifurcated at the extremity; posteriorly in twos, one rudimentary. Each annulation furnished with a circlet of elevated, rounded tubercles, 1.800th in. in heighth, and numerous smaller ones, also arranged in transverse circles. Anterior, 3 or 4 annulations reddish; after these 25 are deep black, except the tenth or girdle, which is broad and brownish; posterior annulations red or brown. Upper lip so little projecting that the mouth appears almost terminal, furnished with short, stiff hairs. Whole number of annulations 50.

Length 4 lines; length of setæ, 1-133d in. to 1-80th in.; length of podal hooks 1-400th in. to 1-178th in.

Habitation.—Found in the spring of the year in the ferruginous mud at the bottom of springs impregnated with iron, near Philadelphia.

2. Chætogaster, Baër:

Baër, *Nova acta nat. Curios.* 1827, *p.* 614; Ehrenberg, *Symb. Phys.*, 1831.

Nais diaphina and Nais diastropha. Gruithuisen. *Nov. act. nat. cur.* 1828, *p.* 407.

Body cylindrical, elongate; mouth inferior, large, triangular; anus terminal. Podal spines in transverse fasciculi, inferior, simple; the first pair of fasciculi close to the mouth; the second distant. Intestine straight, capacious. Eyes none. Blood white. Increasing by division. *Leidy.*

2. Chætogaster gulosus.—Body whitish, translucent; posteriorly obtuse, ciliated with long hairs; mouth infero-terminal, large, triangular, simple; upper lip digitiform, ciliated. Œsophagus short, narrow; first stomach long, cylindrical, transparent; 2nd stomach large, oblong; intestine straight, capacious. Podal spines in pairs of fasciculi of 5 or 6 each, simple, divergent, curved backward near the free end, retractile; first pair just posterior to each side of the mouth inferiorly; second pair removed far back. Usually found in the state of division; commonly 2 to 4 subdivisions.

First subdivision 1-24th in.; furnished with 6 pairs of fasciculi of podal spines, the second pair one half of the length of the subdivision from the first or oral pair. Second subdivision 1-100th in.; third, 1-66th in.; fourth 1-100th in. Each of these latter furnished with 4 fasciculi of podal spines.

Whole length, 1 line; will contract to half a line; breadth, 1-140th in.; mouth, when open, 1-250th in.; length of podal spines, 1-133d in.

Habitation and Remarks.—Found abundantly with Hydra fusca, etc., in the water of marshes in the vicinity of Philadelphia. This worm is very active in its movements and very rapacious. Creeping upon bodies in the water, it rapidly elongates the anterior part of its body in various directions, and swallows great numbers of the smaller infusoria. In turn, it is much preyed upon by the

from an alternation of contraction and dilatation, corresponding usually to ten segments, into which the animal may subdivide, but more or less disappearing in elongation of the body, becoming more apparent by wrinkling in shortening of the body; anteriorly semi-ovate, sub-acute; posteriorly elongated, cylindroid, obtusely rounded. Apparent segments panduriform, furnished each posteriorly with a clear globular nucleolated nucleus. Intestine variable in capacity, usually dilated in the anterior dilatation of each apparent segment, and much contracted in the intervals.

Length from 1-2 to 2 lines, shortening to 1 or 1-4 a line; breadth, when elongated, from 1-400th to 1-300th in.; when shortened from 1-300th in. to 1-2 of a line.

Habitation and Remarks.—Found in the same situation as the preceding, creeping planaria-like upon different substances, or most frequently holding a vertical position in the water, apparently without movement, but retaining their position by means of the actively moving vibrillæ, which are comparatively larger than in the preceding worms. They appear to feed upon vegetable particles brought to the mouth by means of the currents produced by vibrillæ. The intestine is usually empty, except at the dilated portions, where it is yellowish or greenish, from granular matters contained within. The whole structure of the animal is exceedingly simple, composed of nucleolated, granular corpuscles, those forming the exterior of the body being furnished with vibrillæ. Under slight pressure, these corpuscles undergo separation from one another, and become globular by endosmosis; in this state they measure from the 1-7000th in. to the 1-2800th in. The nucleoli are globular, shining, and measure the 1-900th in. in diameter. The exterior vibrillated corpuscles, after separation from the body, often move about for some seconds. The vibrillæ measure about 1-3500th in. long. Each segment of the animal's body, at its posterior part, contains a globular, transparent nucleus, measuring the 1-2333d in. in diameter, with a globular, refractile nucleolus the 1-7000th in. in diameter. This latter body, with the form of the apparent segments, makes the animal resemble a row of gregarinæ attached together.

The Committee on the following paper by Mr. Cassin, read Dec. 24th, 1850, reported in favor of publication in the Proceedings.

Notice of an American species of Duck, hitherto regarded as identical with the Oidemia fusca, (Linn.)

By John Cassin.

Oidemia velvetina, nobis. Audubon, Birds of Am. pl. 247.

Form.— ♂ Generally similar to that of O. fusca, but is rather larger, bill longer and more slender, with the protuberance at the base of the upper mandible more prominent and more extended. Space between the nostril and the edge of the upper mandible much narrower in the present species.

Upon the protuberance at the base of the bill in this species, the velvet like plumage of the front terminates in a well defined point, as represented in the figure of the female in Aud. pl. 247, while in O. fusca this termination is abruptly sub-rounded as in both figures in Selby, Ill. pl. 67, though I have never seen a specimen in which this rounded character is so distinctly marked as there represented.

also in entire accordance with the views of the earlier members of the Society, among them Mr. Maclure, who was decidedly in favor "of making the Library a Reading Room, with all possible facilities for those persons who wish to consult the books." I quote from the excellent report of the Library committee presented in 1836. These facilities are now certainly all that can be desired, and we may even hope that the restriction will be extended by an act of the Society, to *all the books* contained in the Library, no exceptions being made as at present.

Among the many valuable additions this year, may be mentioned the following:—D'Orbigny's Palæontologie Française, nearly complete, from Dr. Morton; Blainville's Ostéographie as far as published; Demidoff's Voyage dans la Russie Meridionale; Paxton's Magazine of Botany, Vols. 1 to 17: Memoirs of the Royal Society of Lille, 26 vols.; Commentationes Soc. Reg. Sci. Gottingensis, 32 vols.; Comptes Rendus, vols. 1 to 23, (completing the series in the Library;) Annales des Sciences Nat., 3d series, 20 vols.; Miscellanea curiosa, Ephemerides, Acta Physico-medica, and Nova Acta Acad. Cæsar, Leopold-Carolinæ Nat. Curiosorum, about 80 vols.; Commercium Litterarium, 15 vols.; Transactions of several Berlin Societies, 39 vols.; Annales Acad. Rheno-Trajectinæ, 25 vols.; Memoires, Annales, Nouv. Annales, et Archives du Museum d'Hist. Nat. de Paris, 21 vols. (completing the Academy's series;) Commentarii de Rebus, 44 vols.; Dictionnaire des Sci. Nat. 75 vols.; Trans. of Royal Irish Academy, vols. 1 to 13; of the Royal Asiatic Society, vols. 1 to 10; Journal of the Royal Geographical Society, vols. 1 to 19; Brewster's Edinburgh Journal of Science, and Brande's do. 32 vols.; Dict. classique d'Hist. nat. 17 vols.; Shaw's General Zoology, 14 vols.; for all of which we are indebted to the untiring liberality of Dr. Wilson.

Mr. Edward Wilson, of Pembrokeshire, Wales, the brother of our esteemed fellow-member, has been a large contributor to the Library during the present year. He has also been instrumental in creating an interest in the Library with other friends of our institution abroad, and among them a number of naturalists and men of science, from whom we have already derived numerous highly acceptable contributions.

Through exchanges with Societies, we continue to receive considerable accessions to the Journal department. To the "Ecole des Mines," of Paris, we are particularly indebted this year, for eighteen volumes of the Journal and Annales des Mines. Our series of that valuable periodical is now complete, with the exception of three or four volumes. The exchange list, however, is not yet as desirable as we hope it will be, when our relations with foreign scientific bodies are more extended, and placed upon a better and more permanent footing than at present.

The extraordinary rapidity with which the Library of our favored institution has advanced of late years, has astonished and gratified all connected with it. In the last annual report it was stated that, in consequence of its great increase, it had become necessary to extend the accommodations for books into the adjoining room, and that arrangements were then being made for that purpose. The alterations were soon afterwards completed, and the apartment has been fitted up in a tasteful and commodious manner. The cases on the floor contain the various Transactions, Journals, and similar works, and those on the gallery are entirely occupied with the Dictionaries of Arts and Sciences, and the valuable collection of works on Antiquities and the Fine Arts.

All objects of the museum of a destructible character are in a good state of preservation, and appear to be well protected from the attacks of Dermestes and Ptinus by the vapor of ether, which has been lately introduced into use for this purpose by Dr. Wilson.

The increase in the cabinet during this year, will be briefly noticed under the head of each respective department.

Mammalia.—In this class the Academy has been greatly enriched by the addition of the collection of Dr. J. K. Townsend, made by himself in the Rocky Mountains and Oregon, consisting of 37 species, 56 specimens, in skin, in a good state of preservation. These were liberally presented to the Society by Dr. Townsend: Most of them are the specimens from which the species were originally described, and many of them are exceedingly rare in natural history collections, and a few are unique.* Among them are two specimens of the gigantic wolf of America, *Lupus gigas*, lately described by Dr. Townsend in the Journal of the Academy.

We have also received skins of twenty species of mammalia,† of Europe, Asia, Africa, and Australia, from W. E. Strickland, Esq., of England, through Dr. Wilson.

Another addition of great value was made by Dr. T. B. Wilson, consisting of one hundred specimens from the collection of the Prince of Canino, C. L. Bonaparte, being the originals of those species figured and described in the Fauna Italica.

We are also indebted to Capt. W. McMichael for 7 species, 8 specimens, of animals from Van Dieman's Land.

Besides the above there were presented to the Society ten species from various sources.

Aves.—We have received during the year 71 bird skins, of which 51 are from Van Dieman's Land, presented by Capt. W. McMichael; 10 from China, presented by Capt. John Land; the remainder from various localities, presented by Dr. E. J. Lewis, and others.

The valuable Des Murs collection of Bird's eggs, containing 1261 species, mentioned in the last report of the Curators as a deposit, has since been presented to the Academy by Dr. Wilson.

To Mr. Samuel Ashmead we are also indebted for the donation of 38 species, 48 specimens of American bird's eggs.

There were also presented by various individuals, principally members of the Society, 15 species of nests, and 23 of eggs, from different localities.

Reptilia.— Of reptiles there have been received 65 species, 80 specimens, besides numerous American duplicates, principally from Dr. McCartee, of Ningpo, China; Capt. John Land; Mr. Sandwith Drinker, of Hong Kong, China; and Mr. Ashmead.

Pisces.—In ichthyology the cabinet has received, rather unexpectedly, a large and very valuable collection, presented by Dr. T.B. Wilson, consisting of 767 bottles containing fishes in alcohol, and 177 dried specimens of the latter, formerly belonging to Prince C. L. Bonaparte, and being the originals of the descriptions and illustrations of the Fauna Italica.

---

* For list, see Proceedings for January and February, 1850, p. 13.
† Ib. March and April, 1850, p. 37.

Another collection of great interest, presented to the Academy by Dr. Joel Y. Schelly, of Hereford, Berks county, Pennsylvania, consists of 58 fragments of enaliosaurian bones in a matrix of hard conglomerate, probably belonging to the newer red sandstone formation, found in upper Milford, Lehigh co., Penna.

We have also received 255 species, over 300 specimens, of fossil shells of different formations, of France, from Mr. Ed. Verreaux, of Paris, through Dr. Wilson.

Besides the foregoing, a number of other fossils were presented, chiefly by Mr. Joseph Culbertson, of Carlisle, Mr. Ogden, of New Jersey, Mr. Moss, and Dr. Budd.

Mineralogy.—137 specimens of minerals have been presented, among which may be particularly mentioned, a fine series of specimens of native gold from California, presented by Dr. Heerman, and some fine specimens of gold ores from Georgia and Virginia, and cinnabar from California, presented by Dr. J. B. McClellan. The others were presented by Mr. Moss, Hough, of Somerville, N. Y., and others.

Two fine deposites of minerals consist of a specimen of Fluor Spar weighing 23 lbs., from Jefferson county, N. Y., from Mr. Vaux, and a beautiful specimen of native Silver, of Peru, from Dr. Elwyn.

All of which is respectfully submitted by

JOSEPH LEIDY,
Chairman of Curators.

The Society then proceeded to an election for officers for the ensuing year, when the following were chosen :—

President, ...	SAMUEL GEORGE MORTON, M. D.
Vice Presidents, . . .	J Price Wetherill, Robert Bridges, M. D.
Corresponding Secretary, .	John Cassin,
Recording Secretary, . .	Samuel Powel,
Treasurer, ...	George W. Carpenter,
Librarian, ...	Wm. S. Zantzinger, M. D.
Curators, ...	Joseph Leidy, M. D. Wm. S. Vaux, Samuel Ashmead. John Cassin,
Auditors, ...	Wm. S. Vaux, Robert Pearsall, Samuel Ashmead,
Publication Committee. .	Wm. S. Vaux, S. G. Morton, Thomas B. Wilson, Robert Bridges, Samuel Powel.

DONATIONS TO LIBRARY

In November and December, 1850.

November 5th.

Supplementary observations on the structure of the Belemnite and Belemnoteuthis. By G. A. Mantell. From the author.

On the Pelorosaurus, an undescribed gigantic reptile from the strata of Tilgate Forest, in Sussex, and on a dorsal spine of the Hylæosaurus, from the same. By G. A. Mantell. From the author.

Indicis generum Malacozoorum primordia. Conscripsit A. N. Herrmannsen. No. 11. From Mrs. L. W. Say.

Brasilien. Nachträge, Berichtgungen und Busäke zu der Beschreibung meiner Reise im östlichen Brasilien von Max. Prinz zu Wied. From the author.

Dr. Wilson presented the following on the usual condition:—

Faune méridionale, ou description de tous les animaux vertébrés qui se rencontrent toute l'année, ou qui ne sont que de passage dans la plus grande partie du midi de la France. Par J. Crespon. 2 vols. 8vo.

The London Athenæum for August, 1850.

Almanach du Chasseur de Papillons et de tous les Insectes.

Procédés Gannal mis a la portée de toute le mond. Embaument appliqué à la conservation des Oiseaux, quadrupeds, &c.

Catalogus Avium et Mammalium quæ habitant in regionibus Europæ positis inter gradum 46° 57½ lat. Septent. et 35—55 long. a Ferro. (C. Tyzenhauz.)

Observations sur les Conferves en general et sur plusieurs infusoires. Par M. Paul Laurent.

Journal of the Franklin Institute. Vol. 20. 3d series. No. 4.

Preis verzeichness Ausländischer Konchylien welche einzeln verkauft werden bei dem "Zoologischen Museum der Univer. Heidelberg." No. 4.

Sur l'ancienne abondance des baleines, des phoques et des dauphins dans la Mediterranée et dans la Mer Rouge.

Observations critiques sur un memoire de M. Alcide D'Orbigny intitulé. "Considerations sur la station normale comparative des animaux mollusques bivalves." Par G. P. Deshayes.

Méthodes épouvées avec lesquelles on parvient facilement et sans maitre a connaitre les caractéres propres a chaque famille naturelle indigéne. Par F. J. Montandon.

Revue et Magasin de Zoologie. No. 6, 1850.

Archiv für Naturgeschichte. No. 3. 1848.

Om Faglarnes geographiska utbredning Och Th. Munck af Rosenschold 19 Junii 1830.

Directions for collecting and preserving animals; by the Board of Curators of the Museum of the Royal College of Surgeons.

Ovarium Britannicum. By George Graves. 8vo.

British Ornithology. By George Graves. 3 vols. 8vo.

Ueber die sogenannten Seemäuse. Von W. G. Tilesius. 4to.

Comptes rendus. Tome 31. Nos. 2, 3, 4, 5. 4to.

November 12th.

Geschichtliche Betrachtungen über die Pferderacen. From Dr. Leidy.

Zur Kenntniss der Balanophoren insbesonders der Gattung Rhopalocnemus Jungh. Von Dr. H. R. Göppert. From Dr. Morton.

Beiträge zur Anatomie des Elephanten und der Ubrigen Pachydermen. Von Dr. C. Mayer. From the same.

Knospenbilder, ein beitrag zur kenntniss der Laubknospen und der Verzweigungsart der Pflanzen. Von A. Henry, M. d. Part. 1. Dicotyledonen. From the same.

Madras Journal of Literature and Science. Nos. 26, 27.

The genera of Diurnal Lepidoptera. By E. Doubleday, continued by J. O. Westwood. Parts 35, 36.

Catalogue of the Mammalia in the Collection of the British Museum, part 1, Cetacea; of British animals in do., part 3, Birds, part 4, Crustacea; of Mollusca in do., part 2, Pteropoda; of the bivalve Mollusca in do., part 1, Placentadæ and Anomiadæ; nomenclature of Molluscous animals and shells in do., part 1, Cyclophoridæ.

Figures of Molluscous animals selected from various authors. By Maria Emma Gray. Vols. 2, 3, 4. 8vo.

Memoirs of the Wernerian Society. Vol. 8, part 1. 8vo.

Journal of the Royal Agricultural Society of England. Vol. 11, part. 1. 8vo.

Palæontographical Society—Monograph of the Entomostraca of the Cretaceous formation of England, by T. R. Jones, Esq.; Monograph of the Permian fossils of England, by William King; Monograph of the Fossil Reptilia of the London Clay, part 2, by Prof. Owen; Monograph of the British Fossil Corals, by H. Milne Edwards and Jules Haime, part 1.

Bibliographia Zoologiæ. By Prof. L. Agassiz and H. E. Strickland. Vol. 2. 8vo.

December 10th.

Catalogue of Shells in the collection of John C. Jay, M. D. 4th edition. 4to. From the author.

Memoir on the explosiveness of Nitre. By Robert Hare, M. D. From the author.

Contributions to the Natural History of the Acalephæ of North America. By L. Agassiz. Part 1. 4to. From the author.

A voyage round the world in H. M. S. Resolution, Capt. Cook, in 1772—'75. By George Forster. 2 vols. 4to. From Dr. Wilson, on the usual condition.

Francisci Hernandi Opera. De Historia Plantarum Novæ Hispaniæ. 3 vols. 4to. From the same.

Zoological Researches. By J. V. Thomson. No. 4. From the same.

Proceedings of the Royal Irish Academy. Vols. 1, 3, 4. 8vo. From Mr. Ball, of Dublin.

Address to the Geological Society of Dublin, Feb. 2, 1850. By T. Oldham. From the same.

Notice of the Remains of the Dinornis and other Birds, and of Fossils, &c., recently collected by Walter Mantell, Esq., in New Zealand. By G. H. Mantell, Esq. From the author.

Essai sur l'histoire naturelle. Par C. G. Chesnon. 8vo. From M. des Murs, of Paris.

Histoire des progres de l'esprit humaine dans les sciences et dans les arts qui en dependant. Par M. Saverien. 8vo. From the same.

Traité économique et physique des Oiseaux de Basse-Cour. 8vo. From the same.

Zasaday Ornitologii albo Nauki O Ptakach. Przez H. K. Tyzenhauza. 8vo. From the same.

Tableau methodique des Oiseaux dans le département de la Vienne. Par M. Manduyt. From the same,

Bulletin de la Société d'histoire naturelle du département de la Moselle. Nos. 1—5. 8vo. From M. Malherbe, of Metz.

Séance publique de l'Academie Nationale de Metz du 19 Mai 1850. Discours de M. A. Malherbe, President. From the same.

Nouvelle classification des Picinées ou Pics. Par M. Malherbe. From the same.

Remarks on the paucity of Libraries freely open to the public in the British Empire. By Edward Edwards, Esq. 2d edition. From the author.

A statistical view of the principal public libraries of Europe and America. By E. Edwards. 3d edition. From the author.

Dissertatio sur l'utilité de la soye des Araignées. Par Mr. Bon. 8vo.

L'art d'elever des Vers á soie. Par M. L. D. Pillot. 12mo.

Jacobi Vanierii Apes. 12mo.

Apus pisciformis. Insecti aquatici species noviter detecta, brevibusque descripta a J. C. Schæffers. Ed. 2d.

Ueber den unmittelbaren Nutzen der Insekten. Von dem Kœnig. Gerichtsamtmann Keferstein in Erfurt.

Nova Dipterorum genera. Auctore Dr. C. R. G. Wiedemann.

Die Südafrikanischen Crustaceen. Von Dr. Ferdinand Kreuss.

Mémoire Aptérologique. Par Jean Fred. Hermann, M. D. Folio.

Memoires sur divers sujets de l'histoire naturelle des Insectes. Par M. Latreille. 8vo.

Memoria del Dott. Carlo Passerini sopra due specie d'Insetti nocivi, &c.

Observations entomologiques traduites et extraites d'un ouvrage inédit de M. le Dr. J. N. Vallott.

Sur la découverte du rapport constant entre l'apparition ou la disparition travail, ou le non travail, le plus ou le moins d'attendüe des toiles ou des files d'attache des Araignées des diff. espéces. Par M. Quatremere Disjoinval.

Traité complet de l'insecte Kermés. Par M. de Truchet, d'Arles. 2d ed.

Essai sur l'Entomologie du Département du Puy-de-Douie. Monographie des Carabiques. Par M. Baudet Lafarge.

La Flore des Insectophiles. Par Jacques Brez. 8vo.

De Coleopteris novis ac rariobus minusve cognitis Provinciæ Novocomi. Auctore Antonio Comolli.

Mémoire pour servir á l'histoire de quelques Insectes connus sous les noms de Termés, ou Fourmis blanches. Par M. H. Smeathman. Redige en Francois par M. Rigaud.

Meletemata Entomologica, Auctore Dr. F. A. Kolenati. 2 fascic. 8vo.

Traité complet sur les Abeilles. Par M. l'Abbe Della Rocca. 3 vols. 8vo.

The English Lepidoptera, or the Aurelian's Pocket Companion. By Moses Harris. 8vo.

Novæ species Insectorum. Auctore J. R. Fostero. 8vo.

Caroli lib. Bar. de Geer genera et species Insectorum e generosissimi auctoris scriptis extraxit, digessit, &c. A. J. Retzius. 8vo.

Gustavi Paykull Fauna Suecica. Insecta. 3 vols in one. 8vo.

Abbildungen zu Karl Illiger's Uebersetzung von Olivier's Entomologie. Von J. Sturm. 2 vols. 4to.

Histoire des Monocles qui se trouvent aux environs de Genéve. Par Louis Jurine. 4to.

Horæ Entomologicæ. Auctore Toussaint de Charpentier. 4to.

Mémoire sur l'education des Abeilles. Par Marie-Therese Beaujeu, veuve Barras.

Traite de l'education des Abeilles et de leur conservation. Par P. C. G. Beville.

Lepidoptera Pedemontana illustrata a Leonardo de Prunner. 8vo.

De l'Araneologie. Par Quatremere Disjoinval.

Mémoire sur les Abeilles. Par M. l'Abbe Bienaymé.

Études pour servir á l'histoire des Myriapodes. Par Paul Gervais.

Entomologia von Illiger. Par M. Olivier. 4to.

Fauna Insectorum Germaniæ. Auctore G. W. F. Panzer. 36 vols. 12mo. and one case.

January 7th, 1851.

Dr. MORTON, President, in the Chair.

A letter was read from the Minister of Public Works of France, dated Paris, Sept. 4, 1851, accompanying No. 3, 4th series, of the Annales des Mines.

Also a letter from Mr. George R. Gliddon, dated Philadelphia, Jan. 3, 1851, requesting the loan, for a short time, of the Egyptian Mummy deposited in the Museum of the Academy by Mr. J. L. Hodge. Referred to the Curators.

Dr. Woodhouse read a communication intended for publication, entitled "Description of the N. American Jackall, *Canis frustror*." Referred to a Committee consisting of Dr. J. C. Fisher, Dr. Townsend, and Dr. Leidy.

Dr. Leidy read a communication from Mr. Richard C. Taylor, intended for publication in the Journal, entitled "Substance of Notes made during a Geological reconnoisance in the Auriferous Porphyry region next the Caribbean Sea, in the Province of Veraguas and Isthmus of Panama;" which was referred to the following Committee, viz:—Dr. Elwyn, Dr. Morton, and Mr. Ashmead.

The Secretary read an extract from a letter addressed to Dr. Morton by Dr. John Evans, dated St. Louis, Dec. 19, 1850, in relation to an intended Expedition to Missouri and Oregon.

The Chairman called attention to the enormous development in the size of the specimen of the common domestic cat presented by him this evening, as the result of emasculation. The following are the dimensions, weight, &c.:

Length from tip to tip 3 feet; circumference at middle 19½ inches; weight 42 pounds; color black mixed with white.

The following Resolution, offered by Dr. Fisher, was adopted:—*Resolved*, That the President, Vice President, Secretaries and Librarian, be a Committee to address the Commissioner of the Land Office at Washington, and solicit an appropriation sufficient to carry out the views of Dr. John Evans of Missouri, as expressed in his letter read this evening.

January 14th.

Vice President BRIDGES in the Chair.

Dr. Morton referred to some communications which he had recently made to the Society, on the races of Dogs, showing their origin from various species of dogs and wolves. He had endeavored to obtain information from persons whose frontier position as officers of the army, &c., afforded them suitable opportunities for this purpose, and read a letter from the Hon. H. H. Sibley, M. C., from Minesota of which the following is the substance.

The Indian Dog differs much in size and appearance among differ-

ent tribes. Among the Sioux, it is large and grey, resembling the Buffalo Wolf. He supposes that the Indian dog is crossed with that Wolf. All Indian dogs have small, sharp, erect ears. They cross with our domestic dogs. He does not believe that the dog crosses with the small Wolf (C. frustror?) or the Fox. The Indian dog is most analogous to the grey wolf, and breeds freely with the European dog.

Dr. Morton also read extracts from a letter from Dr. Cooper, of the U. S. Army, dated Fort Duncan, Texas, Dec. 4, 1850. "The Giant Wolf or Lobo, [Lupus gigas] is found in this region. Its color is dark grey, nearly black. It is very fearless of man. I have seen several in the interior of Mexico. It is always solitary in its habits. The small wolf or *Coyote*, [C. frustror] is found in great numbers here. It is never more than eighteen inches or two feet long, nor more than fifteen inches high."

It resembles somewhat a grey fox-hound, and is always in packs of from ten to two or three hundred. It is the most gregarious animal of the dog kind on this continent. Its voice is not like that of the wolf. It feeds on the carcases of dead animals, and is very meagre. It became necessary to destroy one in camp to prevent its crossing with the dogs. Every rancho has a dog resembling the *Coyote*, and a bitch to which no dog had had access, produced whelps, evidently a cross with the *Coyote*.

In further remarks on this subject, Dr. Morton adverted to the fact that where a race is the result of a cross between two different species of animals, the characteristics of one or the other race will occasionally be exhibited with peculiar force in generations more or less remote from the origin.

Dr. Leidy called the attention of the Society to three fossil bones from Big Bone Lick, Kentucky, belonging to the collection of organic remains of the American Philosophical Society, and now deposited with the Academy, which he stated were the vertebra dentata, left os calcis, and the first phalanx of the left hind foot of the Equus Americanus, described by him in the Proceedings several years since. These bones are about the size of the corresponding bones of the largest sized English dray horse.

Dr. Elwyn asked permission, which was granted, to introduce a letter which he had received from Prof. Sheppard, of Charleston, S. C., requesting Dr. Elwyn to procure for him a portion of the Meteorolite, found in New Jersey some years since, and presented to the Academy by Dr. McEuen. Prof. Sheppard was desirous of making an analysis of this specimen and a comparison with other meteorolites in his possession, and offered in return a fragment from one of the latter specimens.

On motion the subject was referred to the Curators, with instructions to comply with the request of Prof. Sheppard.

January 21st.

Dr. MORTON, President, in the Chair.

The Corresponding Secretary read a letter from J. G. H. Kinberg, dated Malmo and Gronby, 16th December, 1850, announcing that he had forwarded additional objects of Natural History for the Academy, and desiring certain exchanges.

A communication was read from Joseph P. Hazard, Esq., dated Seaside, near Point Judith, Rhode Island, noticing the arrival of the Rocky Mountain Swallow in that neighborhood, with some observations on its habits.

"They first made their appearance here in the Spring of 1844, when fourteen pairs of them built on the east and west sides of an outhouse of my residence, and such strangers were they, that I was unable to learn the name of the specics for some time. They have since confined themselves almost exclusively to the same premises, two or three pair only having in a few cases selected other localities in the neighborhood.

"In the autumn of the same year, (1844) I built a barn about half a mile distant, on the north side of which I provided for my new friends, in case they should visit me again, a convenient projection of nearly fifty feet in length, suitably protected. In the Spring ensuing, (1845) forty nests were built on the crib which was their first choice above alluded to, and as if for experiment, six nests only were built on the new barn, but in the Spring of 1846, sixty five nests were built on the barn, and the crib entirely deserted. In 1847, one hundred and thirty pairs built upon the barn and almost completely occupied the space prepared for them. At this time a few pairs which were crowded out took up quarters in the martin and blue-bird holes on the south side of the same building, ousting the rightful tenants which had previously arrived and taken possession.

As the location at the barn is much more protected than that on the crib, the nests are there constructed with much less reference to the probability of injury from the weather than formerly upon the latter, a circumstance which evinces a degree of *elasticity*, I believe not generally accorded to instinct.

These swallows make their first appearance here from the 10th to the 15th of May, and commence clearing out the old nests (in which many of the dead of the brood of the previous year are left) about the 1st of June. The material of which the nests are made, is a very fine sand with a small admixture of blue clay; when dry it is very friable and the nests suffer considerable dilapidation during winter. They generally make their appearance in a mass, but this season four birds only came on the 5th of May, which number received almost daily accessions until the 28th of the same month. Their arrival is earlier, and their departure also, than that of the barn swallow, none remaining, I believe, later than about the 1st of September.

"One circumstance in the habits of these birds, has struck me as peculiar: they are either all of them in the vicinity of their nests or all absent, not one to be seen on the premises, and although my observations have not been sufficient-

ly particular to enable me to speak with certainty on this point, I am inclined to believe these intervals of absence are at regular hours of the day. I have seen them two miles distant, in pursuit of insects, which their now large numbers have probably rendered scarce in this more immediate vicinity."

Dr. B. H. Coates read a notice of the antiquity of the use of Tin, mentioning its importation from Britain by the Phœnicians, and inferring from passages cited from Homer that it was regarded at a very early period as a precious metal. The communication was referred to Mr. Thomas Fisher, Mr. Phillips, and Dr. Elwyn.

Dr. Leidy read a paper intended for publication in the Proceedings, describing some new entozoa. Referred to Dr. Hallowell, Dr. Morton, and Mr. H. C. Lea.

January 28th.

Vice President BRIDGES in the Chair.

The Committee on Mr. Richard C. Taylor's paper, read Jan. 7th, reported in favor of Publication in the Journal.

The Recording Secretary read the following Report for the year 1850.

REPORT

OF THE RECORDING SECRETARY

For 1850.

It is customary for the Recording Secretary to submit his report at the last meeting of the year, but unavoidable absence from home rendered it impossible for me to offer it before this time.

Nine members and eight correspondents have been elected, and four members have died, to wit:—the venerable and esteemed Alexander Maclure; Dr. William Gambel, who was not less remarkable for the goodness of his heart than for the cultivation of his mind; our lamented Vice President, Dr. Robert Eglesfeld Griffith, whose amiability and generosity not less than his great acquirements, have rendered his loss severe; and the first elected President of the Institution, Dr. Gerard Troost, who has passed away after a long life devoted to the pursuit of science.

By comparing the list of the Society published October 1, 1848, with subsequent changes, there appear to have been elected up to this time 250 members and 513 correspondents, amounting in all to 793.

It does not appear that the institution was ever so prosperous. The average attendance at the meetings has been large, and many objects have been zealously pursued. Many communications of great interest have been made, as the publication of the Proceedings and the Journal will establish.

scribing a new species of American wolf, Lupus gigas, Townsend, of North America, published in Journal.

It may not be improper while enumerating the communications, to direct attention to a letter from Dr. Joel Y. Shelly, accompanying fossil remains of a supposed saurian found in Upper Milford, Lehigh county, Pennsylvania. Although not personally acquainted with this locality, it is believed to belong to a formation anterior to the coal, and it may be coeval with the period of the fossil footprints in red sandstone described by Dr. A. T. King in Proceedings for December 1844, and December, 1845. If this supposition be correct these are probably very old and interesting remains of vertebrate animals and are therefore deserving of attention.

It seems improper to close a notice of the records, without briefly adverting to the very large portion of them occupied by mere lists of the munificent donations received throughout the year. The constant liberality with which so many of the wants of the Academy are supplied, must be a rich source of gratitude in the hearts of all its friends, and while an exquisite and high toned delicacy on the part of a distinguished benefactor forbids me to breathe his name, his generous gifts are appreciated among our richest treasures. All which is respectfully submitted by

SAMUEL POWEL,
Recording Secretary.

Philadelphia, January 28th, 1851.

ELECTION OF MEMBERS.

John Jordan, Jr., Esq., and B. Howard Rand, M. D., of Philadelphia, were elected *Members* of the Academy.

Election of Standing Committees for 1851.

The following committees on the various departments of Science, &c., were elected to serve for the year 1851.

Ethnology, S. G. Morton, J. S. Phillips, J. C. Fisher; *Comparative Anatomy and General Zoology*, Joseph Leidy, E. Hallowell, B. H. Coates; *Mammalogy*, S. G. Morton, J. W. Woodhouse, R. Kilvington; *Ornithology*, E. Harris, John Cassin, J. K. Townsend; *Herpetology and Ichthyology*, E. Hallowell, John Cassin, W. Keller; *Conchology*, T. A. Conrad, T. B. Wilson, H. C. Lea; *Entomology and Crustacea*, S. S. Haldeman, R. Bridges, W. S. Zantzinger; *Botany*, R. Bridges, W. S. Zantzinger, Gavin Watson; *Palæontology*. T. A. Conrad, T. B. Wilson, Joseph Leidy; *Geology*, R. C. Taylor, T. F. Moss, Samuel Powel; *Mineralogy*, J. Price Wetherill, S. Ashmead, W. S. Vaux; *Physics*, J. S. Phillips, J. C. Fisher, Thos. Fisher; *Library*, R. Bridges, T. B. Wilson, J. Lambert; *Proceedings*, S. G. Morton, W. S. Zantzinger, Joseph Leidy.

February 4th.

Dr. MORTON, President, in the Chair.

A letter was read from Prof. C. U. Sheppard, dated Charleston, S. C., January 20, 1851, presenting his thanks for the fragment of the

New Jersey Meteorolite, and enclosing in return a portion of the Cabarras Meteorolite; and also stating his intention to make further donations of other meteorolites at an early period. From an examination of the specimen sent him, he had thus far obtained the following results. Sp. gr. 3.25: it also abounds with nickeliferous iron, together with magnetic iron pyrites, while the greyish-white earthy matter appears to be Howardite. ($\dot{Fe}\,\ddot{Si} + \dot{Mg}\,\ddot{Si}$.)

A letter was read from the Scandinavian Scientific Association (without date,) accompanying the donation of a copy of its Proceedings during the last meeting at Copenhagen.

A letter was read from H. B. Dewey, Esq., dated Para, Brazil, Dec. 28, 1850, tendering his thanks for his election as a Corresponding member of the Academy, and expressing his desire to still further promote the objects of the Institution.

A communication addressed by Peter A. Browne, Esq., to Dr. Morton was read, briefly enumerating the discoveries he had made by means of the microscope, micrometer, and trichometer,* in regard to *pile*, by which term he meant to include both hair and wool, as follows:

1st. I have found the hair of the head of man of three principal shapes, viz.: 1. The cylindrical; 2. The oval; and 3. The eccentrically elliptical.

Of the 1st I have noticed the ancient hairs from Peru, Mexico, Brazil, &c., those of our present Indians and the Chinese. Of the second, the hairs of the English, French, Hungarians, Germans and Americans, &c., &c. And of the third the wool of the Bushman and African negro.

2d. The pile of the 1st and 2d class comes out of the epidermis at an acute angle, that of the third at a right angle.

3rd. The pile of the 1st class is straight and lank, that of the 2d is flowing or curling, and that of the 3rd is crisp or frizzled, and sometimes spirally curled.

4th. The pile of the 2d class has its coloring matter in a central canal, but I have never been able to detect any central canal in either of the other classes; their coloring matter appears to me to be disseminated in the cortex and intermediate fibres.

5th. The cortex of the pile of all three classes is squamose; but the scales on the 1st and 2d classes are less numerous, are rounded at the anterior extremity, and adhere closely to the shaft; but those of the 3rd class are more numerous, pointed, and not so closely set to the shaft.

6th. That there are two distinct species of sheep, as determined by their pile, viz.—the hairy sheep, and the woolly sheep. The pile of the hairy sheep will not felt nor full; the wool of the woolly sheep will do both.

7th. Upon the heads of hybrids formed by the crossing of any two of the species of man above mentioned, are found separate filaments belonging to their two classes respectively; and upon the head of a double hybrid,† which I examined, I found filaments belonging respectively to all three classes.

---

* An instrument invented by Mr. Brown for determining the ductility, elasticity, and tenacity of filaments.

† One who had the blood of all three classes.

9th. All hair is not polaric.

10th. There are various degrees of the felting property in wool, which may be determined by the aid of the microscope, as they depend upon the number, shape and adherence of the scales.

11th. The *softness* of any woolly fabric, is in exact proportion to the *ductility and elasticity* of the filaments of which it is composed; and the ductility and elasticity of the fibre can be accurately determined by the trichometer.

12th. The method in common use of determining the diameter of any filament that is not cylindrical is inaccurate, for every filament that is not cylindrical has *two* diameters, which cannot be accurately determined, except by using *transverse* sections.

13th. That in all cases of doubt or difficulty, whether a filament is or is not a true hair, it can be determined with the trichometer.

14th. The *button* of the pile of the head of man changes its shape and color in diseases of the hair, and in diseases of the skin that affect the hair.

15th. The *buttons* of the pile of the head of lunatics differ from those of the sane.

16th. There is no difference between the wool found upon the head of a pure negro, and that found upon the back of a woolly sheep, except in the *degree* of the felting power possessed by them.

Dr. Morton in remarking upon the cranium of the Dijak deposited by him this evening, referred to the great difficulty in obtaining these crania, and stated that Mr. Wm. Gliddon, from whom he had derived the present specimen, had been unable, during many years residence in Borneo, to induce the natives to part with any of their trophy skulls upon any consideration. This had been carried off by a Dutch officer on a warlike expedition.

Dr. Morton announced the decease of Mr. John J. Audubon, a member of this Society; and after some appropriate observations upon the life and character of this distinguished zoologist, moved the following Resolutions, which were unanimously adopted:—

Resolved, That this Society has heard with profound regret of the death of their esteemed and venerable colleague, John James Audubon, at his residence near the city of New York, on the 27th ultimo.

Resolved, That by the demise of this truly great man, Science has lost one of her most zealous and gifted disciples, and the Arts, a master in the branch which he cultivated.

Resolved. That we recognise in Mr. Audubon a man who has happily lived to fulfil his destiny as an explorer of the great field of American Zoology, while the splendid volumes which are the fruit of his labors, will diffuse the knowledge and the love of science to the latest generations.

Resolved, That a copy of these Resolutions, signed by the officers, together with the sympathy of the members of this Society, be respectfully tendered to the family of Mr. Audubon.

On leave granted, the Committee, to whom was referred the paper

of Dr. Woodhouse, read January 7th, 1851, describing a new species of Jackal, presented a report, recommending the same for publication in the Proceedings and Journal, with some additional remarks on the subject by the Chairman, Dr. J. C. Fisher, which was adopted.

The North American Jackal—CANIS FRUSTROR.

By S. W. WOODHOUSE, M. D.

Char. Essent. Hair cinereous grey, varied with black above. Longer on the vertebral line, legs fulvous.

Dimensions.—Total length from the tip of the nose including the tail, with the exception of the hair at the tip, two feet seven inches; trunk of the tail eight and three-tenths inches; total length of ears four and three-tenths inches; length of fore leg nine inches: from the anterior canthus of the eye to the tip of the nose two and seven-tenths inches; from anterior angle of ear to posterior canthus of the eye two and four-tenths inches; between the anterior angles of the ears two and five-tenths inches.

Description.—Hair at base fulvous and woolly, middle of its length white and tipped with black; ears erect, pointed at tip, cinnamon color behind and at the base; inside dirty white, sides paler than the back, belly brownish white, breast brown, chin white, legs cinnamon color; the nose from the eyes to the tip cinnamon color. Cheeks grey; space between the ears reddish brown; tail fulvous below, dark grey above, black at tip, slightly bushy; iris light brown, lips white tipped with black; it has three series of setæ on the upper lip, above the eyes, and on the sides of the cheeks.

The most remarkable difference exists in the skull of this animal, which more closely resembles the Jackal of the Old World than any known species of wolf. But as Dr. Morton is now engaged on a memoir in which the cranial characteristics of the American wolves will be compared with those of the *Canis lupus* of Europe, I leave this part of the subject in his hands.

Habits.—This animal I first saw at Fort Gibson, on the Neosho river. They frequent this place at night in numbers, making their way to a ditch where the offals of the garrison are thrown. Their bark is sharp like that of a terrier, followed in quick succession, then a prolonged cry much like that of the hound.

Four or five of them make as much noise as twice their number of terrier dogs, so that a stranger on hearing them is apt to be deceived as to their number. I have seen them on all parts of the prairie, but they appear to be more abundant near the settlements.

They prowled frequently about our camp at night, keeping up an incessant barking.

I procured a male and female; these I regret to say have not lost their milk teeth, but they have attained their full growth, as I have seen numbers of them.

On showing them to Dr. Townsend, he recognised them immediately, and said that he had seen them frequently on the plains of the Missouri, but never beyond the mountains.

This animal has hitherto been confounded with the *Canis latrans* of Say.

Observations by the Committee.

The Committee are much gratified with this paper, as it assists in throwing

light upon a point in the Natural History of the wolves of North America, which has heretofore been involved in obscurity. Before the description of the Lupus Gigas of North America, by Dr. Townsend, all the varieties of wolves in this country were referred by naturalists to two species, the Lupus occidentalis or common wolf, and the Lupus latrans, or prairie wolf. Sir John Richardson was the first who unequivocally described the wolves of North America, as distinct from the European or Pyrenean wolf. The great majority of naturalists who have noticed the wolves of this continent, including Grey, Agassiz, De Kay, &c., agree with him in considering them as entirely distinct species from the wolves of the Eastern Continent.* With the exception of the "large brown wolf," of Lewis and Clarke, they all refer the American wolves of every variety to the two species named Lupus occidentalis, and Lupus latrans. It was scarcely possible to reconcile the various descriptions of the different wolves classed under the last of these, Lupus latrans, as belonging to the same animal. The Lupus latrans of Say, found on the *Upper* Missouri and the Saskechawan, is classed by Richardson† with the Californian *Ochropus*, and the Mexican *nigriostis*, (known also as the Coyote.) He has given a figure of the Lupus latrans, which agrees exactly with a specimen in the possession of the Academy.

The figure given by Audubon in his Quadrupeds of North America, Plate 71st, does *not* agree with Richardson's, or with the specimen above referred to, but *does* agree very closely with the Canis frustror, in color, shape, &c. It is an excellent drawing of the last mentioned animal. The Coyote of Mexico and California, has been, we believe, uniformly referred by naturalists to the Lupus latrans, and the drawing of Audubon appears to have been made from it, considered as an undoubted Prairie wolf. The figure of the Hare Indian dog of Richardson, the Canis familiaris lagopus, bears a very striking resemblance to the Lupus latrans of Audubon, and the Canis frustror of Woodhouse. We are inclined from the figure, measurements and description of the voice, to consider this dog as the analogue among our domestic animals of the Canis frustror or Coyote, if it be not the same animal merely domesticated. From the Canis frustror hunting so uniformly in packs of considerable numbers, as well as its size, it is more nearly allied to the Jackal than the wolf. It is decidedly gregarious in its habits. We hope that the Academy will soon possess good specimens of all the wolves of this continent, so that a more strict comparison may be made, and this question of species be definitely settled. At present we may consider the following species as clearly established, viz: Lupus gigas, Lupus occidentalis, Lupus latrans, and Canis frustror.

On leave granted Mr. Vaux, as Treasurer of the Publication Committee, presented the Annual Report, which was adopted.

February 11th.

Dr. Morton, President, in the Chair.

A letter was read from Dr. N. S. Jarvis, addressed to Dr. Morton, dated Fort Brown, Texas, Jan. 10, 1851, in answer to some enquiries by

* Report of the British Association for 1836.
† Fauna Boreali Americana.

Dr. Morton on the subject of the Lobos, Coyote, and Indian dogs. This letter was received by Dr. Morton on the 5th inst., and enclosed another in the French language from Dr. Louis Berlandier to Dr. Jarvis, dated Matamoras, Jan. 5th, 1851, with accompanying descriptions of several species of Canis indigenous to Mexico. Dr. Berlandier's knowledge and means of information on this subject had been very extensive, and his descriptions were well worthy the notice of the Society. His letter and descriptions were on motion referred to the Committee who had had charge of Dr. Woodhouse's paper, viz., Dr. J. C. Fisher, Dr. Leidy, and Dr. Morton.

Mr. Cassin stated on behalf of the committee having in charge Dr. T. C. Henry's paper describing a new species of Fish from Oswego Lake, N. Y., that a more extended communication had been received from the author by the Committee.

Mr. Cassin read a paper intended for publication in the Proceedings entitled, "Sketch of the Birds composing the genera Vireo Vieill. and Vireosylvia, Bonap." &c. Referred to Dr. Wilson, Dr. Bridges, and Mr. E. Harris.

February 18th.

Vice President Bridges in the Chair.

Mr. Cassin read a paper describing new species of the genera Bucco and Galbula, Briss. Referred to the committee on the paper by Mr. Cassin read at last meeting.

A letter was read from the Secretary of the Asiatic Society of Bengal, dated Aug 5, 1850, acknowledging the receipt of Part 3, Vol. 1, New Series of the Journal.

February 25th.

Dr. Morton, President, in the Chair.

The Committee on Mr. Cassin's papers, read 11th and 18th insts., reported in favor of publication in the Proceedings.

Sketch of the Birds composing the genera Vireo, Vieillot, and Vireosylvia, Bonaparte, with a List of the previously known and descriptions of three new species.

By John Cassin.

I. *Genus* Vireo, Vieillot. Hist. Nat. des Ois. de l'Am. Sept. i, p. 83. (Folio, Paris, 1807.)

1. *Vireo flavifrons*, Vieill. Ois. d'Am. Sept. i, p. 85, pl. 54. Aud. B. of Am. pl. 119.

Musicicapa sylvicola, Wilson. Am. Orn. i, p. 217, pl. 7, fig. 3.

Hab.—Eastern side of North America.

Obs.—The name given by Wilson, as above, of this handsome species,

appears to have been taken from Bartram's Travels, p. 290, though not being expressly so stated by him, it may have been applied by Bartram to another bird.

2. *Vireo solitarius*, (Wils.) Aud B. of Am. pl. 28.
Muscicapa solitaria, Wilson. Am. Orn. ii., p. 143, pl. 17, fig. 3.
Hab.—The whole of North America.

3. *Vireo noveboracensis*, (Gm.) Aud. B. of Am., pl. 63.
Muscicapa noveboracencis, Gmelin. Syst. Nat. ii., p. 947, (1788.).
Vireo musicus, Vieill. Ois. d'Am. Sept. i, p. 83, pl. 52.
"Muscicapa cantatrix, Bartram." Wilson Am. Orn. ii., p. 166, pl. 18, fig. 6.
Hab.—The whole of North America.

Obs.—It appears upon the authority of Wilson that this is the Muscicapa cantatrix, Bartram That name, even if it had priority, is not entitled to adoption, not being accompanied by any description whatever. The name alluded to is given with many others, in "Travels through North and South Carolina, Georgia, East and West Florida," &c., by William Bartram, Philadelphia, 1791, (octavo, 1 vol.,) p, 291. According to my views the authority for M. cantatrix should be Wilson, he having first defined the species, though very probably upon the designation of the celebrated Bartram himself. I do not mean to say, however, that none of the names of the latter ought to be adopted, for there a few of the species named by him, to which are attached sufficient descriptions, and which I hope to designate in an early paper.

4. *Vireo Bellii*. Aud. B. of Am. Octavo edition, vii, p. 333, pl. 485, (1844.)
Dimensions.— ♂ Total length of skin from tip of bill to end of tail 4 6-10ths inches, wing 2 3-10ths, tail 2 inches.
Colors.— ♂ Under mandible, viewed from below, yellowish white, superior mandible light brown. Shafts of the quills on the inferior surface of the wing, white. Entire plumage above light olive tinged with greyish brown on the head, wings and tail brown, the feathers of both of which are edged externally with pale yellowish green, quills with their inner webs narrowly edged with yellowish white. Greater and lesser wing coverts conspicuously tinged with the same color. Plumage of the entire under parts of the body pale yellowish white, running into pure yellow on the sides and inferior tail coverts. Nares and ring around the eye yellowish white. Tarsi and feet dark.
♀. Slightly smaller, colors paler, head inclining to cinereous, under parts nearly white.
Hab.—Western side of North America.
Obs.—The smallest of the birds of this genus. It was discovered by Mr. Audubon on the Upper Missouri river, during the last expedition accomplished by him, and has since been found in California by Mr. John G. Bell, after whom it is named. The descriptions above are from the specimens of the latter gentleman and from the originals of Mr. Audubon, which were presented to the Academy by his friend and associate Mr. Edward Harris.

5. *Vireo Huttoni*, nobis.
Form.—Robust and rather broad, generally similar to that of V. noveboracensis.

1 Vireo Huttoni Cassin

2 Vireosylvia philadelphica Cassin

species are those of Swainson, as cited, and of Audubon in Ornith. Biog. v., p. 296. I am not without suspicion that this is the bird figured by Wilson, as above.

3. *Vireosylvia altiloqua*, (Vieill.) Vieill, Ois. d'Am. Sept. i., pl. 38.
Muscicapa altiloqua. Vieillot, Ois. d'Am. Sept. i., p. 67.
Vireo longirostris, Swainson. Fauna Bor. Am. ii., p. 237.
" Vireosylvia olivacea, (Linn.)" Gosse, B. of Jamaica, p. 194?
" Turdus hispaniolensis. Gm." Lath. Gen. Hist. v. p. 149.
Phyllomanes mystacalis. Cabanis, Erichson Archiv, 1837, p. 348?
Hab.—Florida, West Indies, and South America.

Obs.—A species also considerably resembling *V. olivacea*, but larger and with the bill distinctly longer. It is easily distinguished by the narrow black lines running downwards from the corners of the lower mandible.

This is the largest of all the species yet discovered, and was first obtained within the present limits of the United States, by Dr. A. L. Heermann, in Florida. It is probably the bird alluded to by Mr. Gosse, in his delightful volume on the Birds of Jamaica, though I can only judge by the measurements given by him which are too large for *V. olivaceus*. Mr. Gosse appears though to have had access to the plate of Audubon and possibly that of Wilson. He gives no detailed description. Nuttall, in Manuel i., p. 360, (1840,) says "the *V. olivaceus* has never yet been found in those islands," (the West Indies,) but it does not appear to me to be impossible at all that it may be, as Audubon met with it in Florida and Louisiana. (Orn. Biog. II., p. 258.)

4. *Vireosylvia flavoviridis*, nobis. Buff. Pl. Enl. 558, fig 2?

Form.—Generally resembling that of *V. altiloqua*, but is rather smaller, the wings and legs are shorter, and the latter much less robust, the bill is also slightly more slender.

Dimensions. Total length of skin from tip of bill to end of tail 5¼ inches, wing 3 and 2-10ths, tail 2 and 2-10th inches.

Colors. Head above pale cinereous, superciliary stripes pale ashy-white, not so distinctly defined as in *V. altiloqua*. Entire plumage of the body above fine yellowish olive, wings and tail brown with their feathers widely margined externally with the same yellowish olive and internally with yellowish white. Sides of the neck and of the body beneath, inferior wing and inferior tail coverts fine greenish yellow, middle of the body beneath from the base of the bill to the abdomen pure white. Upper mandible lead color, lower white. No black lines from the base of the lower mandible, and general color of the body above much more vivid than in *V. altiloqua*. Irides red.

♀ Rather smaller and colors paler.

Hab. Panama, where it was obtained by Mr. John G. Bell, and San Juan de Nicaragua, from whence it was sent to this Academy by Mr. A. de Barruel.

Obs. This is a very handsome species, much more brightly colored, and without the black lines on the front of the neck which characterize the *V. altiloqua*. Four specimens are in the collection of the Academy.

Mr. Bell represents this bird as having been rather common near Panama in May, 1849, and that in habits and song it much resembled the red-eye, (*V. olivacea.*)

2. *Vireo Vigorsii*, (Aud.) Richardson, Report on N. A. Zoology to Brit. Assoc. for the Adv. of Science, (in Sixth Rep. Brit. Assoc. 1837, p. 172.)

Sylvia Vigorsii. Aud. Orn. Biog. 1 p. 153, pl. 30.

Obs. Audubon's figure has a Vireo-like look, and ought to be remembered. In his Synopsis, p. 55, he places this name as a synonyme for Sylvicola pinus, (Lath.)

3. *Vireosylva* is the orthography of M. Bonaparte in Geog. and Comp. List. p. 26, but in Conspectus Avium, p. 329, he makes it *Vireosylvia*, the former being apparently a typographical error. It is a very natural and easily defined genus, and was first pointed out by this deservedly celebrated naturalist in the edition of the work cited which was published in 1838. In Erichson's Archiv, xiii. p. 321, (1847,) Mr. Cabanis necessarily proposes the name *Phyllomanes* as a substitute.

Descriptions of new species of birds of the genera Galbula and Bucco, Briss., specimens of which are in the collection of the Academy of Natural Sciences of Philadelphia.

By John Cassin.

1. *Galbula cyanicollis*, nobis.

Form. Not essentially different from that of other short-tailed species. Rather stout, space from the bill around the eye bare and conspicuous, middle tail feathers but slightly longest.

Dimensions. Total length of skin from top of bill to end of tail 7½ inches, wing 3 and 1-10th, tail 3 inches.

Colours. Head above blue with golden olive reflections, the same color, blue, extends from the base of the bill upon the neck beneath the bare space around the eye, bordering (upon the neck only) the deep reddish brown of the entire under surface of the body. Entire plumage above and two middle tail feathers golden-green, very brilliant, and inclining to red in some lights. Outer tail feathers reddish brown, slightly edged externally with golden-green, quills black, primaries narrowly and secondaries broadly edged on their inner webs with brown, rather paler than that of the body beneath. A trace of a green collar on the neck in front.

Tip of upper mandible black, basal portion of upper, whole of under mandible (space around the eye and feet ?) yellow.

Hab. Para, Brazil.

Obs. This species is related to G. chalcocephala, Deville, and G. albirostris, Lath. I am acquainted with no other species in which the head and neck are blue as above described. Several specimens are in the collection, all of which are from Para.

2. *Bucco Ordii*, nobis.

Form. Generally short and robust, feathers of the head but little elongated, wings and tail short. A strict congener of B. macrorhynchus and pectoralis.

Dimensions. Total length of skin from tip of bill to end of tail 7¾ inches, wing 3 and 3-10ths, tail 2 and 8-10th inches.

Colors. Tail with a central transverse white bar. Breast with a narrow band of black, immediately succeeded by another much wider of dark chesnut-brown,

Bucco Cordi cassin

J. Stephens del

Lith. of Sarony & Co. 1 Old Compton Street



1,2 PALUDICELLA ELONGATA *Leidy*.

3-5. URNATELLA GRACILIS. „

number of elevated, longitudinal, moderately tortuous, papillated, linear ridges. Mouth small, round. Œsophagus long, cylindrical. Intestine simple, tortuous. Anus small, oval, situated about half the length of the alary expansion, from the posterior end.

Length 11 lines; breadth 3-5ths of a line. Transverse striæ of integument 1-650th in. wide. Œsophagus 2½ lines long; 1-5th of a line broad.

Habitation.—The description is taken from two males found within the stomach of Didelphis virginiana.

4. Spiroptera *Scalopis canadensis.*—Body whitish, cylindrical; anteriorly attenuated; posteriorly re-curved, furnished at the extremity with a lateral dilated alary expansion, containing four minute respiratory tubes, diverging from the position of the anus. Mouth small. Œsophagus cylindrical; Intestine moderately tortuous. Anus about half the length of the alary expansion from the posterior end.

Length 6 lines; breadth ½ of a line. Œsophagus ½ of a line long.

Habitation.—Description from a single male found in the stomach of Scalops canadensis.

5. Echinorynchus socialis.—Body white, cylindrical, with a dilatation of the anterior fifth; narrowed posteriorly, with a white spiral band passing around the whole length, and giving the appearance of transverse annulations. Proboscis moderately long, cylindrical, with twenty-six transverse rows of simple re-curved hooklets, sixteen in each row.

Male furnished with a posterior vesicular appendage.

Length from ½ an in. to 2 in. 4 lines; breadth of larger individuals anteriorly, ½ of a line; posteriorly 2-5ths of a line.

Habitation.—Found frequently in considerable numbers in the intestine of Platessa plana.

The Committee, to whom the paper of Dr. Berlandier, read to the Academy Feb. 11th, 1851, describing two species of Mexican wolves, was referred, reported:

That after a careful examination, they are satisfied that the first, the Canis Mexicanus of Desmarest, No. 297, and the Lupus Mexicanus of Col. Hamilton Smith, Vol. 9th, Mammalia Nat. Lib., though heretofore considered by Richardson and others as a variety of the common wolf, Lupus occidentalis, is yet, from its peculiarly marked form, entitled to be considered a distinct species. As this wolf has been described and figured in the work referred to, it would only be unnecessarily multiplying its synonyms to publish a new name for it, unless stronger reasons be given than exist in the present case. The second is unquestionably the one described by Dr. Woodhouse, under the name of Canis frustror, in a paper read to the Academy, Jan. 7th, 1851, and directed to be published in the Proceedings and in the Journal of the Academy. The same objection, the unnecessary multiplication of synonyms, also applies to the publication of the name given by Dr. Berlandier to this wolf. Although Dr. Woodhouse is entitled by priority of publication to the right of giving the specific name, yet the Committee feel unwilling to report against the publication of this part of the paper, especially as it strongly corroborates the views expressed by them in the remarks made on the Canis frustror. Considering the description of the first also as im-

Cr. Stone by Wm E. Hitchcock

T. Stephens del.

Lith. Printed & Col.d by J. T. Bowen Phila.

1 *Hirundo scapularis* Cassin

2 *Atticora hamigera* Cassin

Four very fine specimens of a fossil Ostrea from California. Deposited by Prof. Frazer.

Cranium of a Dijak woman of Borneo, received from Mr. W. A. Gliddon by Dr. Morton, and deposited by the latter.

February 11th.

Six fragments, and three casts of Dipleura pomàlonotus, six specimens of Pleurotomaria, three of Loxonema, and three Silurian fossil shells, from the Hamilton Group, Cazenovia, N. Y.; Goniatites, Onondaga Co., N. Y.; three specimens of Atrypa prisca and three of A. culioides, from Madison Co., N. Y. Presented by Mr. Ledyard Linklaen.

Phalæna odora, Lin. from the vicinity of Philadelphia, (a rare species in this locality). From Mr. John McIlvaine, of Blockley.

Shark's tooth from the Marl of New Jersey. From Mr. Powel.

February 18th.

Very fine specimen of Exogyra costata. From Mr. Harback, through Dr. Spackman.

Skins of Albatross, giant Petrel, Cape Pigeons, Owl; and seeds of Cherimoya and Mango. Presented by Dr. G. R. B. Horner, U. S. N.

Antlers of Cervus virginianus. From Mr. T. Fisher.

Spongia ———; from the Atlantic Ocean. From Mr. Wood.

Calcareous Tufa, from Mr. Teublin, of Illinois.

Siliceous oxide of Zinc, from Lehigh Co., Pennsylvania. From Mr. John Cooke.

Naucrates Echireis, in spirits. From Dr. T. C. Dunn, of Newport, R. I. through Dr. Morton.

DONATIONS TO LIBRARY

In January and February, 1851.

January 7th.

Proceedings of the American Philosophical Society, vol. 5, No. 45, April to December, 1850. From the Society.

Catalogue of the Marginellidæ in the collection of John H. Redfield, January 1, 1851. From the author.

Contributions to Helminthology. By Joseph Leidy, M. D. From the author.

Letter to the Rev. Dr. Bachman, on the question of Hybridity in animals, considered in reference to the question of the Unity of the Human Race. By S. G. Morton, M. D. From the author.

Additional observations on hybridity in animals, and on some collateral subjects: being a reply to the objections of the Rev. John Bachman, D. D. By S. G. Morton, M. D. From the author.

Notes on Hybridity, designed as a supplement to the Memoir on that subject. By S. G. Morton, M. D. From the author.

Annales des Mines. 4me. serie, tome 17, liv. 3 de 1850. From l'Ecole des Mines.

Bibliotheca Botanica, sive catalogus auctorum et librorum omnium qui de re botanica, de re rustica, &c. &c., tractant. A Joanne F. Seguierio Nemansense digessus. 4to. 1740. From Mr. George Ord.

Fourth Annual Report of the Regents of the Smithsonian Institution. From the Institution.

The following were presented by Mr. Edward Wilson, of Pembrokeshire, Wales, on the usual condition:

Outlines of Human Osteology. By F. O. Ward. 16mo.

Jocko: episode détaché des lettres inédites sur l'instinct des animaux. Par Charles Pougens. 3d ed. 12mo.

Tableau des Champignons observés dans les environs de Metz. Par MM. Fournel et Haro. 1me. memoire.

Gnaphalium neglectum, nouvelle espéce du groupe des Filaginées, &c. Par H. F. Soyer-Willemet.

Revue des Treflés de la Section Chronosemium. Par MM. Soyer Willemet et Godron.

Observationes sur quelques Plantes Lorraines. Par D. A. Godron.

De l'origine des Cordons placentaires dans la famille des Légumineuses. Par M. Godron.

Essai sur les Renoncules á fruits ridés transversalement. Par. M. Godron.

Monagraphie des Rubus qui croissent naturellement aux environs de Nancy. Par M. Godron.

A series of letters on Agricultural improvement. By John J. Mechi.

Die Heliceen, nach natürlichen verwandtschaft systematisch geordnet von J. Christ. Albers. 8vo.

Die Conchylien in Cabinette des Hernn Erbprinzen von Schwarzburg Rudolstadt. 8vo.

Riley's index to the British Land and Fresh water shells.

Atlas des Mollusques. 12mo.

La Cochliopérie: recueil d'expériences tres curieuses sur les helices terrestres vulgairement nommés Escargots. Par George Tarenne.

The Conchologist's Companion. By the author of Select Female Biography, &c. 12mo.

Traité sur la culture des Muriers blancs, la maniére d'elever les vers-a-soie, et l'usage qu'on doit faire des cocons. Par. M. Pomier. 8vo.

Godofredi Sellii historia naturalis Teredinis seu Xylophagi marini, tubulo-conchoidis speciatim Belgici. 4to.

Histoire d'un insecte qui devore les grains de l'Angoumois. Par MM. Duhamel du Monceau et Tillet. 12mo.

F. Chr. Lesser's Testaceo-Theologia. 8vo.

The Gardener's Pocket Journal. By J. Abercrombie. 8th ed. 8vo.

Gardening for Ladies. By William Loudon. 4th edition.

Elémens de l'art vétérinaire. Traité de la conformation extérieure du cheval. Par Cl. Bourgelat. 7me. ed.

The Suburban Gardener and Villa Companion. By J. C. Loudon. 8vo.

The English Gardener. By W. Cobbett. 8vo.

An account of a new Zoophyte from Greenland, in a letter to Dr. Haller, by C. Mylius. Translated into English. 8vo.

British Husbandry. 3 vols. 8vo.

Jnnuary 21st.

Journal of the Franklin Institute, for December, 1850. From Dr. Wilson.

Boston Journal of Natural History. Vol 6, No. 2. From Boston Soc. of Nat. Hist.

Rapport sur l'empoissonnement des Riviérés. Par M. Milne Edwards. From Dr. Leidy.

Contributions to Conchology. No. 8. By C. B. Adams. From the author.

The Song of the Sea-Shell, and other poems. By Thomas Fisher. 8vo. From the author.

The following were presented by Mr. Edward Wilson on the usual condition:

The History of the Dog. By W. L. C. Martin. 12mo.

The History of the Horse. By. W. L. C. Martin. 12mo.

The elephant, principally viewed in relation to man. New edition. By W. C. Martin. 12mo.

Die jezt lebenden Entomologen kerffreunde und kerfsammler Europàs und der übrigen Continente. Von J. Gistl. 12mo.

Leçons élementaires d'histoire naturelle, á l'usage des enfans. Par. M. Cotte. 2d edition. 12 mo.

An essay upon the Silkworm. By Henry Barham, Esq. 8vo.

Cours abrége d'histoire naturelle. Par M. Wandelaincourt. 12mo.

Traité de l'education des animaux domestiques. 2 vols. 12mo.

Index testaceologicus. By W. Wood. 8vo.

An essay on the Mines of England. By George Abbott, Jr. 8vo.

De l'accroissement continu des incisives chez les Rongeurs et de leur reproduction, considerée sous le rapport de leur application á l'etude de l'anatomie comparative des Dents. Par J. E. Oudet.

Melanges d'histoire naturelle de physique et de chimie. Par M. Th***. 8vo. 3 vols.

Zootomia democritæa: opus Marci Aurelii Severini. 4to.

Dissertationes de admirandis mundi cataractis supra et sub-terraneis, &c. Auctore M. J. Herbinio. 4to.

Histoire naturelle de l'Eperlan de la Seine inférieure. Par S. B. J. Noel. 8vo.

Le Porte-Feuille des Enfans. Rédige par une Société d'amateurs. 4to.

Notice historique sur une importation de six cents merinos extraits d'Espagne en 1808. Par M. Poyféré de Cére. 8vo.

Traité succinct sur les Abeilles. Par M. Cagniard. 8vo.

Naumannia. Archiv fur die Ornithologie vorzugsweise Europás. Von Eduard Baldanus. Nos. 1 and 2. 8vo.

Linnæa Entomologica: Von demEntomologischen Vereine in Stettin. Vols. 1—4.

Essai sur la Géographie physique, la climat et l'histoire naturelle du Département du Doubs. Par Girod Chantrans. 2 vols. 8vo.

Voyage Mineralogique fait en Hongrie et en Transilvanie. Par M. de Born; traduit de l'Allemand. 12mo.

Dissertatio hydrologica de Fontibus et Fluminibus. Auctore P. Alexio M. Planch. 12mo.

De origine des Fontaines. 12mo.

Histoire du Mont Vésuve. Par M. Duperron de Castera. 12mo.

An introduction to the study of Birds, or the elements of Ornithology on scientific principles. 12mo.

Continuation de la Lithogéognosie pyrotechnique. Par J. H. Pott. 12mo.

The Ornithological Guide. By Charles T. Wood. 8vo.

Notionaire ou memorial raisonné de ce qu'il y a d'utilité, et d'interessant dans les connoissances acquises depuis la création du Monde jusqu, à present. Par M. de Garsault. 8vo. 1761.

Elementa Metallurgiæ speciatim chemicæ conscripta à J. G. Wallerio. 8vo.

Mémoires sur l'education des Vers-a-Soie. Par M. l'Abbe Boissier de Sauvages. 8vo.

Tableau historique de la Péche de la Baleine. Par S. B. J. Noel. 8vo.

Voyage souterrain, ou description du Plateau de St Pierre de Maestricht et de ses vastes cryptes. Par le Col. Bory de St. Vincent. 8vo.

Allgemeine Naturgeschichte der Schildkröten nebst einem systematischen Verzeichnisse der einzelnen Arten mit zwei Kupfern. Von J. G. Schneider. 8vo.

Verzeichniss der Käfer Preussens. Entworfen von J. G. Kugelann. Ausgearbeitet von J. K. W. Illiger. 8vo.

Tableau des Pyrénées Francaises. Par M. Arbanére. 2 vols. 8vo.

Voyage fait en 1787 et 1788 dans la ci-devant Haute et Basse Auvergne. Par M. Legrand. 3 vols. 8vo.

Librorum impressorum qui in Museo Britannico adservantur catalogus. 7 vols. in 8. 8vo.

Lettres minéralogiques et géologiques sur les Volcans de l'Auvergne. Par La Coste. 8vo.

Geschichte der Schöpfung. Von Hermann Burmeister. 8vo.

Nouveau traité sur la laine et sur les moutons. Par MM. Le Conte Perrault de Jotems et F. Girod. 8vo.

Della Pietre antiche libri quattro di Faustini Corsi Romano. 8vo.

Histoire naturelle abrégée du ciel, de l'air et de la terre, ou notions de physique générale. Par Philibert. 8vo.

Georgii Martinii, M. D., de similibus animalibus et animalium calore libri duo. 8vo.

February 4th.

Annales des Mines. 4me. serie, tome 17, liv. 4me. de 1850. From l'Ecole des Mines.

Forhandlinger ved de Skandinaviska Naturforskeres femte mode der holdtes i Kiobenhavn fra den 12 til den 17 Julie 1847. 8vo. From the Association.

Floræ Capensis Medicæ Prodromus. By L. Rappe, M. D. From Dr. J. Dawson.

Report of the Horticultural exhibition held in Salem Massachusetts, under the direction of the Essex Institute. Sept. 25 and 26, 1850. From the Institute.

The American Journal of Science and Arts. Vol. 50. General index to 49 vols. 8vo. From the Editors.

Histoire physique, &c., de l'Ile de Cuba. Par M. Ramon de la Sagra. Livs. 55 et 56. From Messrs. Vaux, Elwyn, Clay, Wetherill and Carpenter.

The following were presented by Mr. Edward Wilson on the usual condition:

Lettre sur le Valais. Par M. Echasseriaux.

Voyage aux Iles de Lipari fait en 1781.

Introduction au rapport fait a l'Academie Royale des Sciences sur le voyage a l'Isle Julia en 1831 et 1832. Par M. Constant Prevost.

De l'incubation artificielle. Par un ancien administrateur.

Brevi e succinte notizie di storia naturale e civile dell'Isola d'Ischia del Dott. D. Francesco de Siano.

Nouvelle description de ce qu'il y a de remarquable a la Menagerie et au cabinet d'histoire naturelle du Jardin du Roi.

Discours œconomique non moins utile que recreatif, &c. Par M. Prudent de Choyselat, 1612.

Observationes sur l'art de faire eclore et d'elever la volaille sans le secours des Poules. Par M. Bonnemain.

Relation des événemens mémorables arrivés dans l'exploitation de Houille de Beaujonc, pres de Liege, le 28 Feb., 1812, &c.

Essai d'une explication géologique de la station apparente du soleil et de la lune a l'ordre de Josué. Par W. Van den Hull.

De sinu rhomboidali in medulla spinali avium. Auctore Edvinus A. Hay.

Geognostische Bemerkungen über Karlsbad von K. E. A. von Hoff.

Observations sur la formation des Montagnes, &c. Par P. S. Pallas.

A catalogue of extraneous fossils animal and vegetable, minerals, &c., in the possession of the Rev. Peter Hawker.

Elements of Zoology. By Wm. Rhind. 8vo.

M. T. Brunnichii Ornithologia Borealis. 8vo.

Descrizione dell'ultima eruzione del Monte Vesuvio de 19 Ottobre, 1767. 8vo.

Traité curieux sur les cataclysmes ou deluges, les revolutions du globe, le principe sexuel, et la generatione des mineraux. A M. Ferd. Mazzanti.

Notice sur les Chévres Asiatiques a Duvet de Cachemire. Par M. Polonceau.

Mineralogical nomenclature. By Thos. Allan. 8vo.

Recherches sur le mouvement des ondes. Par M. N. Th. Bremontier. 8vo.

L'Homme rival de la nature; ou l'art de donner l'existence aux oiseaux et principallement a la volaille par le moyen d'une chaleur artificielle. 8vo.

Nouvelle construction de Ruches de bois, avec la façon d'y gouverner les abeilles, inventée par M. Patteau. Par M. ***. 12mo.

Traité de l'education économique des Abeilles. Par M. Ducarne de Blangy. 12mo.

Memoire sur la Vallée de Lacs de Natron et celle du fleuve sans eau d'apres la reconnaissance faite par le Gen. Andréossi. 4to.

Traité des Tourbes combustibles. Par Ch. Patin. 4to.

Onomasticon du systéme d'Oryctognosie. Par le Prof. Gott. Fischer. 4to.

Francisci Bousseti de natura Aquatilium carmen. 4to. 1558.

De Thermis Carolinis commentatio. Auctore J. G. Bergero. 4to.

A catalogue of the Library of the Royal Institution of Great Britain. 2d edition. 8vo.

Essais sur divers sujets de physique, de Botanique, et de Mineralogie. Par Charles Pougens.

Essays on the Microscope. By the late George Adams. 2d. ed. 4to.

The following were presented by Mr. Edward Wilson, on the usual condition:

Dissertatio academica in qua Aves Paradisiacas. Auctore N. Bonenberg Luneburgensis.

The English Apiary: or the complete Bee-master. By John Gedde, Esquire. 12mo.

Sketches of Tenby and its neighborhood. By Fanny Price Gwynne. 12mo.

Le Monde Naissant, ou la creation du monde, démonstrée par des principes tres simples et tres conformes a l'histoire de Moyse. 12mo.

Memoire sur la cause des tremblemens de terre. Par M. Thomas.

Traité de la verité des causes et effects des divers cours, mouvements, flux et reflux, et saleure de la Mer Oceane, &c. Par M. Claude Duret. 12mo.

Traité du flux et reflux de la Mer. Par le R. P. D. Jacques Alexandre. 12mo.

Synopsis of the contents of the British Museum. 56th ed. 12mo.

Le XII Pietre Pretiose, le quali per ordine di Dio nella santa legge, adornauano i vestimenti del sommo Sacerdote, &c. &c. Di Andrea Bacci. 4to.

Mémoire sur les fourmis des Cannes a sucre. Par M. de Barry.

De Renum Succenturiatorum in Mammalibus structura penitiore. Auctore Mauritius Nagel.

Histoire de la Laponie. Traduite du Latin de M. Scheffer par L. P. A. L. 4to.

T. Cornelii Consentini Progymnasmata physica. 4to.

De la reproduction considerée dans l'animal et le végétal. Par Etienne Maniéres.

Mémoire sur l'interieur de l'Afrique. Par Jérome Lalande.

An account of the Pearl fisheries of Ceylon. By James Steuart. 4to.

D. Christoph Gottwaldts physikalisch-anatomische Bemerkungen uber den Fiber.

Vorstellung einiger merkwurdigen Versteinerungen mit kurzen Anmerkungen versehen von D. Cas. Cristoph Schmeidel.

Mémoire sur les questions proposés par la Soc. d'Ag., &c. de Bologne sur mer concernant les recherches enterprises á differentes epoques dans le Department du Pas de Calais pour y decouvrir de nouvelles mines de Houille. Par M. F. Garnier.

A voyage to the Cape of Good Hope, &c., from the year 1772 to 1776. By Andrew Sparman, M. D. 2 vols. in one. 4to.

Des derniers révolutions du globe. Par M. L. Castilhon. 8vo.

Mémoire et journal d'observations et d'experiences sur les moyens de guaranter les Olives de la piquers des insectes. Par M. Sieuve de Marseille. 8vo.

An attempt to establish a pure scientific system of mineralogy by the application of the electro-chemical theory and the chemical proportions. By J. J. Berzelius, M. D. Translated from the Swedish by John Black. 8vo.

Hydrogéologie. Par J. B. Lamarck. 8vo.

Mémoire sur les Trappes et les Roches Volcaniques. Par M. Barral.

The Art of Taxidermy. By Peter Boswell.

Dr. Wilson presented the following, on the usual condition:

Journal of the Franklin Institute. 3d series, Vol. 21, No. 1.

Revue et Magasin de Zoologie. No. 9, 1850.

London Athenæum for Oct., Nov. and Dec., 1850.

Comptes rendus. Nos. 11—19, tome 31, et index du tome 30.

Archiv für Naturgeschichte. Von F. A. Wiegmann. Herausgeg. von Dr. Troschel. No. 5, 1849, No. 1. 1850.

February 18th.

Annales des Mines. 4me. serie. Liv. v. de 1850. From L'Ecole des Mines.

Medical topography of Brazil and Uraguay. By G. R. B. Horner, M. D. 8vo. From the Author.

Journal of the Franklin Institute, Feb. 1851. From Dr. Wilson.

The following were presented by Mr. Edward Wilson, on the usual condition:

A treatise on the production of early swarms of Bees by artificial means. By E. Scudamore, M. D. 12mo.

Ragionamenti sopra la varieta de i flussi et reflussi del Mare Oceano Occidentale. Por Nicolo Sagri. 4to.

Descrizione dell'èruzione del Vèsuvio 25 e 26 Dec. dell'anno 1812.

Observations sur les volcans de l'Auvergne. Par Lacoste. 8vo.

Historiske efterretninger om Hestekiödes Brug til Menneskeföde i Norden aldre og Nyere tider. Ved E. C. Werlauff.

Historia et meteorologia Incendii Ætnæi anni 1668 J. Alphoni Borelli. 4to.

Recherches sur le corps de Wolf chez les Mammifères et les oiseaux. Par M. Coste.

Rapport de M. Brunet de la Grange 1841, sur l'industrie sericicole dans les Departments de Seine et Oise, des Deux Sevres, &c. &c.

Ornithologia Powszechna. Przez Hr. K. Tyzenhauza. 3 vols. 8vo.

Lettres sur l'histoire naturelle du Hareng. Par M. Noel.

Twelve unpublished Geological plates; and portraits of George Ransome, Lewenhoeck, Sir Ashton Lever, and Linnæus.

receive from the Executors of the late Mrs. Stott the amount of her legacy to this Institution, and to execute the necessary bonds on payment of the same.

April 1st.

Vice President BRIDGES in the Chair.

Dr. Morton read a letter addressed to him, from Dr. Alfred T. King, dated Greensburg, Pa., March 17, 1851, on the subject of the anatomy and functions of the brain in the inferior animals.

Dr. Morton, referring to the crania deposited by him this evening, stated that the cranium of the mummy recently dissected by Mr. Gliddon was that of a female, and an Egyptian in every respect. An attempt had been made to preserve all the bones, but upon some of them having been wetted, they were entirely converted into a clay-like mass; the cranium had, however, escaped. One of the Tapajos Indian crania was curiously embalmed, in a manner peculiar to these people, who place several together in jars: the eyes are singularly represented, and the skull presents the peculiar roundness of the posterior portion which is common to this race. The cranium of the Guayacuru (a young female) was interesting from the great rarity of these crania.

The following, offered by Dr. Elwyn, was adopted :—

Whereas, Mr. George Ord has kindly consented, at the request of members of the Academy, to place at its disposal a portrait of himself now in his possession:

Resolved, That the Recording Secretary be directed to correspond with Mr. Ord on the subject, and to signify to him the gratification it would afford the Society to receive the portrait.

April 8th.

Vice President BRIDGES in the Chair.

Dr. Leidy exhibited three fragments of the inferior maxilla of a gigantic species of Palæotherium, to which in the last number of the Proceedings he had given the name P. Proutii, in honor of Dr. Hiram A. Prout, of St. Louis. By the latter gentleman they had been obligingly lent to him through Prof. Baird of the Smithsonian Institute. One of them had been described by Dr. Prout in Silliman's Journal, the others had been since obtained. Two of the fragments apparently belonged to the same individual, viz.: that described by Dr. Prout, being a portion of the left ramus, containing the seventh molar tooth nearly entire and the preceding teeth much mutilated; and a part of the right ramus extending back to the angle containing three posterior molars mutilated. They correspond closely in appearance, age, and size. The third fragment is a much mutilated posterior molar of the right side, rather larger than the corresponding tooth of the above specimens. The posterior

molar measures antero-posteriorly 4½ inches, the sixth molar 3½, and the fifth molar has been about 3¼ inches. The angle of the jaw is eight inches behind the posterior molar. The lower jaw has been full two and a half feet long, and belonged to an animal three times the size of the Palæotherium magnum of Cuvier.

Prof. Baird has also sent three fossil Tortoises from the same locality, one of which Dr. Leidy believed to be a new genus.

Mr. Lea stated that he had examined the fossil bones of a *reptilian quadruped*, which Dr. J. Y. Shelley had sent to the Academy in Nov., 1847, from Upper Milford, Lehigh Co., Pa., on Hassac's Creek, a tributary to the Perkiomen. The notice of Dr. Shelley's donation, published in No. 7, Vol. 5, of the Proceedings, as part of the Annual Report of the Recording Secretary, had not met Mr. Lea's view until within a few days, it being there remarked, that these remains were from a formation probably anterior to the coal.

The great interest which attaches to all these sauroid remains, induced Mr. Lea to examine the specimens in the Cabinet of the Academy, when he was perfectly satisfied by the lithological characters of the matrix, and by the geographical position of the locality, that the epoch of the existence of this reptilian quadruped had been misapprehended. The matrix was found to be *carbonate of lime*, in the form of a conglomerate, and the locality near to the range of the trappean hills, known as the "Conewago Hills" in Pennsylvania, and as the Blue Mountains in Virginia. On the south of these intruded rocks, lies the formation known by the geologists of the United States, generally, as the *New Red Sandstone*, although Elie de Boumont, and Dr. Jackson, of Boston, are not of the opinion that it is the equivalent of the Trias or upper new red sandstone, or the Permian or lower new red sandstone of Europe. Certain it is, however, that this red sandstone formation, which stretches in a long and narrow band, from South Carolina to the Connecticut river, and exists probably at Truro in Nova Scotia, sometimes with considerable interruptions, has been found to contain the *foot prints* of numerous genera and species of birds, and of reptiles, as well as a large number of fishes. These have been chiefly observed on the Connecticut river. But until now there had not been found in this formation in the United States, so far as he knew, any *bones* of the animals which then inhabited its shores. It is well ascertained, that this calcareous conglomerate forms the upper portion of the so-called new red sandstone formation, and lies on its northern border, appearing at various points: in the N. E. part of New Jersey at Pompton, westwardly at Germantown in the same State, and it is found crossing the Delaware at Spring Mills about 15 miles below Easton. It is recognised at the locality, where these bones were found, in the S. E. corner of Lehigh county, and in the same line south-westward, below Reading, about one mile, where it exists in very large masses, the line of the Philadelphia and Reading railroad making a deep cut through it. It there exhibits its structure as a very coarse calcareous conglomerate of various colors. In the same direction it is found on the Potomac river, and is known there as the Potomac marble, of which the columns of the Halls of Congress are made.

Mr. Lea remarked that it was greatly to be regretted, that all the bones of this specimen had not been obtained, but it was due to Dr. Shelley to say that he

arrested from destruction and handed over to scientific investigation, with a promptness that does him credit, what remained to be obtained. The rocks had been taken out for the purpose of making the bed of a turnpike road, and the bones now in possession of the Academy consist of several vertebræ, parts of ribs and two imperfect teeth, which certainly place this animal among the *Saurians*.

To these remains, so fortunately preserved, Mr. Lea proposes to give a mature examination, and the curators have placed them under his charge for that purpose. When prepared, a description and figures of the important portions of these bones will be submitted by him for publication in the Journal of the Academy.

Mr. Lea thought it better to adopt a specific name without delay, but deemed it advisable to postpone a generic one, until a further examination shall prove the diagnosis, and then apply a descriptive one. He proposes *Pennsylvanicus* as the specific name.

On leave granted, a memorial to the Legislature of Pennsylvania, praying for the passage of an act authorising the completion and publication of the final report of the Geological Survey of the State, was presented and read. On motion, the same was adopted, and a copy signed by the officers of the Academy was ordered to be transmitted to the Legislature now in session.

April 15th.

Vice President BRIDGES in the Chair.

A letter was read from the Royal Leopoldine Carolinian Academy of Naturalists, dated Breslau, Jan. 21st, 1851, acknowledging the receipt of late Nos. of the Proceedings.

A letter was read from J. S. Gossler, Esq., dated Harrisburg, April 11th, 1851, acknowledging the receipt of the memorial addressed to the Legislature by the Academy on the subject of the State Geological Survey; also another from the same, dated April 12th, 1851, announcing the passage of the law by both Houses authorising the publication of the Report.

Dr. Leidy presented for the inspection of the members a fossil Tortoise from Nebraska Territory, received through Prof. Baird of the Smithsonian Institution. The specimen consisted of four-fifths of the carapace and plastron, the former considerably crushed. In general form it is like the genus Emys. It has been about 7 inches in length, and about 5¾ in breadth; its heighth is about 2¾ inches. An interval of one-eighth of an inch between the costal and marginal plates has been filled with cartilage. The union in the middle line of the sternum from behind to the ento-sternal bone has also been cartilaginous. The outer extremities of the costal plates are alternately broad and narrow as in Testudo. The most remarkable peculiarity of the animal has been the possession of four accessory bones, which do not exist in other genera. These bones give additional support to the carapace. Two are placed anterior to the attachment of the sternum to the marginal plates, and two posterior. The anterior are nearly straight

and quadrilateral, and pass, one upon each side, from the antero-external angle of the hyo-sternal bone obliquely upwards and inwards to a depression about the middle of the outer margin of the first costal plate. The posterior columns of support have nearly the same form as the anterior, and pass from the postero-external angle of the hypo-sternal bone upwards, backwards and a little inwards to a depression formed at the junction of the fifth and sixth costal plates. Dr. L. gave to this fossil the generic and specific name of Stylemys* nebrascensis.

April 22d.

Vice President BRIDGES in the Chair.

A letter was read from Mr. John Hooper, Secretary of the Brooklyn Institute, dated New York, Feb. 17th, 1851, accompanying a beautiful collection of native Algæ, (42 species,) presented by him to the Academy, and offering to contribute further if desirable.

Mr. Cassin read a paper intended for publication in the Proceedings, entitled "Notes of an Examination of the Birds composing the family Caprimulgidæ in the collection of the Acad. Nat. Sciences;" which was referred to Dr. Wilson, Dr. Watson and Dr. Ruschenberger.

Dr. Leidy called the attention of the members to two fossil Tortoises from Nebraska Territory, received through Professor Baird.

One of them consists of a great portion of the carapace and sternum broken into two fragments. It belongs to the genus Testudo. Its length has been about 2 feet, the breadth is 20 inches, and the height 9 inches. The bones are thick and strong. The species Dr. L named Testudo lata.

The second specimen consists of four-fifths of the sternum and about one-third of the carapax. In its perfect state it has been about 9½ inches in length, 7½ in breadth, and about 5½ high. The carapace is very convex. The costal plates are alternately narrow and broad at their outer extremity, and have been united to the marginal plates by cartilage. The latter rise at first a little convex from the sternum, but are afterwards vertical. The species Dr. L. named Emys hemispherica.

Mr. Isaac Lea, referring to his late communication to the Academy on the subject of fossil bones in the collection from the new red sandstone, stated that since then he had received the Proceedings of the Boston Natural History Society, which contained a paper by Mr. Welles, read in December last, noticing the fact that fossil bones of large vertebrate animals had been found in two instances in the red sandstone of Connecticut valley. Mr. Lea said that this was the first notice he had met with of the discovery of bones of this character in this formation.

Dr. Morton offered some remarks on the infrequency of mixed offspring between the European and Australian races.

The singular paucity of half-caste or mulatto children in New Holland, has been remarked ever since that country was first colonized by Europeans. Of

---

* στυλος; εμυς.

the fact there can no longer be a question; it has even led to official inquiries on the part of the Colonial Government, and is yet regarded as a physiological paradox.

Among many other questions which the Legislative Council of Sydney has addressed to the colonial magistrates, was the following one: "Are there any, and how many, half-castes in your district?" The official replies of thirty-one of these magistrates are published in detail in the "Minutes of Evidence" issued by the Legislature at Sydney, in October, 1845.* From these Reports I have drawn up the following TABLE, in which is given the name of each colony or settlement, the whole number of aborigines inhabiting its precincts, the number of half-breeds living with the natives, and the number also of half-breeds who remain with the white population.

Settlement.	No. of Natives.	Half breeds living with the natives.	Half breeds living with the whites
Darling Downs,	1000		3 or 4
Moreton Bay,	4000	Very few.	
McLeay River,	429	Not many.	
Port Macquarie,	370	20 to 30	
Raymond Terrace,	53	3	3
Dungóg,	63	3	1
Scone,	70 or 80	†Majority of children.	
New Castle,	38	Very few.	Very few.
Wollombi,	73	None.	None.
Brisbane Water,	47	2	2
Windsor,	63		3
Bathurst,	150		A few
Picton,	56		11
Berrima,	40		2 or 3
Bungonia,	Uncertain,		Several.
Goulburn,	20 or 30		A few.
Queanbeyan,	60		1
Mudgee,	50		1-5‡
New England,	500 to 600	But few.	
Broulee,	250		12
Murrumbidgee,	2000		A few.
Maneroo,	687		12
County of Grant,	200	None.	None.
Murray,	210	None.	None.§
Western Port,	1000		2‖
Portland Bay,	3000	None.	None.
Gipp's Land,	1000		2
Melbourne,	5000	20 or 30	
Campaspe,	1522		6
Yarra,	165	1	
Western Establishment,	2000	2	

* For these very interesting documents I am indebted to the kindness of Dr. Charles Nicholson, a highly intelligent Member of the Legislative Council.

† The magistrate testifies that there are "very few children" in his District, and that the majority of them are half-caste.

‡ This number, "one fifth," evidently alludes to the children, though it is vaguely expressed.

§ "Several have been born, but I know of none living."

‖ "Very few. I have only seen two."

Now we have here the extraordinary fact, that while the native population in the thirty-one districts is represented to be nearly 15,000, the whole number of half-castes or mulattoes does not exceed 200.

The *causes* of this singular disparity have been variously surmised. *Infanticide* at birth is one of them; but this can have but a partial effect, for we find that fully one-half of the mixed race is living with the natives. *Syphilis* is also adduced, but its influence is manifestly very restricted. *Promiscuous intercourse* is certainly a check upon fecundity; but why should its influence be more manifest in Australia than elsewhere? and as to *repugnance* between the races, this has been set aside by local circumstances. These and various other considerations have been cited in explanation, but without satisfying the inquirer; and we may therefore ask, is not the real cause the *difference of race*, the disparity of primordial organization?

Perhaps no two human races are more remote from each other than the European and Australian; and where such extremes are blended, reason and analogy lead us to expect only a limited fertility. In connection with, and explanatory of, this phenomenon, Count Strzelecki, a distinguished Polish traveller, has stated the following proposition, which I give nearly in his own terms:—Whenever a female of an aboriginal or barbarous tribe, has conceived by a European, she loses the power of conception on a renewal of intercourse with a male of her own race, retaining that only of procreating with a white man. "Hundreds of instances of this extraordinary fact," observes Count Strzelecki, "are on record in the writer's memoranda, to prove that the sterility of the female being relative only to one, and not to another male, is not accidental, but follows laws as cogent, though as mysterious, as the rest of those connected with generation."—*New South Wales and Van Diemen's Land*, p. 346.

My object on the present occasion is merely to state the apparent facts of the case, in order to draw the attention of physiologists, and observers in general, to a more careful and extended notice of these remarkable phenomena.

April 29th.

Dr. MORTON, President, in the Chair.

The Committee to which was referred Mr. Cassin's paper read at last meeting, reported in favor of publication in the Proceedings.

Notes of an examination of the Birds composing the family Caprimulgida, in the collection of the Academy of Natural Sciences of Philadelphia.

BY JOHN CASSIN.

1. *Caprimulgidæ.*

No family of birds presents an aspect more uninviting, nor perhaps greater real difficulties in its investigation, nor has any one been more generally neglected, than this. The great fathers of modern Zoology have been but rarely consulted respecting their knowledge of Caprimulgus.

The notes I am now about to offer, I have only to say, are the results of much labor and of as careful research as I am capable of making, with the assistance and

confirmation too, of gentlemen of this Academy in whose judgment and accuracy I have the most entire confidence. It is true, however, that they have been written, and the material accumulated during my but limited leisure, or at such fragments of time as I can spare from a business requiring constant attention, (and between which and myself I find it difficult always to maintain the *intents cordiale*,) from which fact, I am fully aware, there may have arisen oversights or misapprehensions from want of more extended or more systematic study. I hope, however, that few such will be found, and at all events I shall have the gratification of being one of the first to invite attention to a hitherto much neglected field for investigation, and perhaps to induce others to enter upon the general examination of the many species of birds, the names of which alone are known, and the descriptions of which continue to be copied by succeeding authors from their predecessors.

2. *Caprimulgus*, Linn.

This genus appears to be restricted to the old world. I have never seen a true Caprimulgus from any part of America or the American islands. I propose to notice in the course of this paper all the American genera, of which I will give a list of such species as I have seen.

3. *Hydropsalis*. Wagler, Isis, xxv. p. 1222. (1832.)

Original description. "Character universalis Caprimulgi; cauda profunde furcata, rectrice utrinque extima elongatissima."

Added by me. Bill rather long, (longer than typical Caprimulgus) slender, and compressed toward the tip, with about 8 or 10 pairs of bristles, which are longer than the bill and curved at the ends, gape moderate, nostrils medial, somewhat elevated.

Wings long, first and second primaries generally longest, second and third strongly sinuated on their outer webs, three first primaries serrated on their outer edges, shafts of primaries very strong.

Tail usually with the two external feathers much longer than the others, sometimes graduated with the two middle feathers shortest, sometimes with the two middle feathers lengthened and next in length to the external.

Tarsi covered with scales and slightly feathered below the joint. Wings without the white bar on the primaries which is found in typical Caprimulgus, tail more or less marked *longitudinally* with white.

Obs.—A very natural genus, first described by Wagler as above in 1832, and afterwards called Psalurus by Swainson in Cab. Cy. Birds, ii. p. 339 (1837.) It appears to be exclusively American.

The species of this genus which I have seen are:

1. *Hydropsalis torquatus*, (Gm.) *Caprimulgus furcifer*, Vieill. *C. psalurus*, Temm.
2. *Hydropsalis limbatus*, Cassin (Oct. 1849.) *H. creagra*, Bonap. (1850.)
3. *Hydropsalis segmentatus*, Cassin (Oct. 1849.)
4. *Hydropsalis lyra*, Bonap. (1850.)

4. *Hydropsalis torquatus*, (Gm.)

1. *Caprimulgus torquatus*, Gm. Syst. Nat. ii. p. 1032, (1788,) a name given by Gmelin on the faith of the "Gold-collared Goatsucker" of Latham, Gen.

Syn. ii., pt. 2, p. 601, (1783,) who copies from Briss. Orn. ii, p. 481, (1760,) the latter giving the name of *Caprimulgus Brasiliensis* on the faith of, and copying the description of the Guira querea Basiliensibus of Marcgrave and Piso in Historia Naturalis Brasiliæ, p. 202, (Amsterdam 1648.)

2. *Caprimulgus furcifer*, Vieill. Nouv. Dict., x. p. 242, (1817,) a name given by Vieillot on the faith of "Del cola de tixera" of Azara, Apunt. Hist. Nat. del Paraguay, ii. p. 536, (Madrid 1805.)

3. In copying Azara's description of the tail of this bird, Vieillot makes an important mistake in substituting the French "plus" for the Spanish "ménos."

4. *Caprimulgus psalurus*, Temm. Pl. col. ii. p., pl. 157, 158, (27 liv.)

5. The above names are probably synonymes.

6. *Caprimulgus manurus*, Vieill. Nouv. Dict. x. p. 239, (1817)?

The name, *Caprimulgus brasiliensis*, was given by Brisson to the bird described by Marcgrave and Piso, as above, and he copies their description with some alteration. He says of the tail "Rectrices autem binæ intermediæ lateralibus multo sunt longioribus."

The expression used by Marcgrave and Piso is, "Cauda octo digitos longa, constans *in extremitate* duabus pennis longioribus reliquis."

In the tail of the common species known as *Caprimulgus psalurus, Temm.*, the two outer feathers are much the longest of all, and the two *middle* feathers are next in length, presenting a very unusual form.

Gmelin in his description (or rather definition) of *C. torquatus*, cites *C. brasiliensis Briss.* as a synonyme, also "Guira querea, Ray and Willoughby" and "Gold-collared Goatsucker, Lath." and copies Brisson's description of the tail of this bird, which Latham had also done, but having seen the original description the latter adds, "The two middle tail feathers are eight inches in length."

The entire description by Marcgrave and Piso is copied almost verbatim by Willoughby, Ornithologia p. 71, (Folio, 1676). That of the tail is exactly the same word for word, "Cauda octo digitos longa constans *in extremitate* duabus pennis longioribus reliquis."

In Ray's edition, in English, of "the Ornithology of Francis Willoughby," p. 108, (Folio, 1678,) he translates the Latin of Marcgrave and Willoughby thus: 'Tail eight inches long, having *in the outsides* two feathers longer than the rest."

The term used by Marcgrave "in extremitate" is so equivocal, it is not surprising that Brisson was perplexed, and to have fully justified Ray's English, it would have looked better in the plural. Ray's translation is, however, quite as warrantable as any other, and with the description otherwise answers sufficiently well for the Caprimulgus psalurus, Temm. Pl. col. 157. I am acquainted with no other American species to which can be applied the following from Marcgrave: "circum *totum* collum autem pone caput annulum habet, obscure aureum." The size given by Marcgrave is not very definite: "Alaudæ magnitudine est, sed quia longas alas et caudam habet multo longiorem, videtur major." This phrase is copied by the subsequent writers above mentioned, in the course of the observations of whom nothing occurs from which I can infer that either of them had seen the species.

Upon comparing a specimen of *C. psalurus* with either *Alauda arvensis* or *cristata* it will be found that the comparison made use of by Marcgrave may be

applied to this bird without such an extended exercise of the imagination as might at first appear necessary, throwing out of the case too his "videtur major." His only other dimensions are "digiti fere longitudine," applied to the bristles, "rostri superioris ad latera," and "Alas longas habet nimirum semipedem," both of which answer quite well for the bird we now suppose them to have been applied to, and so does his description in all other respects.

I beg to remind the reader, however, that I have no disposition whatever to attempt to make out a case, *ex parte*, and therefore suggest the possibility of Marcgrave and perhaps Brisson having had in view an African species, the Caprimulgus climacurus, Vieill. Gal. des Ois. i. pl. 122, which will suit their descriptions to some extent. Probably at the time Marcgrave wrote (1648) and certainly in the time of Brisson, (1760) bird skins from Africa were often taken to Brazil by vessels engaged in the slave trade, and errors respecting locality might have occurred readily.

The tail of this bird has been particularly unfortunate. In the description by Azara, in "Apuntamientos para la historia natural de los Paxaros del Paraguay," ii. p. 537, (octavo, Madrid, 1805,) he gives the dimensions of the tail of his "Del cola de tixera" thus: "cola 10 plumas: la de afuera ó primera 24 lineas mas larga que la segunda: esta 5 mas que la tercera: y esta 2 mas que la quarta, y 11 *ménos* que la central."

In the French edition of Azara, (Walckenaer's) iv. p. 115, (octavo, Paris, 1809) these dimensions are given correctly: "Des 10 (pennes) de la queue, l'exterieure a 24 lignes de plus que la deuxieme, celle-ci 5 de plus que la troisieme, et cette derniere 2 de plus que la quatrieme, et 11 de *moins* que les 2 du milieu."

But Vieillot in Nouv. Dict. x. p. 242, in his description of *Caprimulgus furcifer*, which is copied from Azara almost verbatim, alters one most important word in the dimensions as given above; he says, "Cette queue a la penne exterieure de vingt-quatre lignes plus longue que la deuxieme, celle-ci en a cinq de plus que la troisieme, et cette derniere deux de plus que la quatrieme, et onze de *plus* que les deux du milieu."

This error has, of course, caused some confusion, and Vieillot's description containing it appears to have been relied on by some authors, (including Bonaparte in Consp. Av.)

This tail was a standing riddle to Vieillot. In Ency. Meth. ii. p. 543, (quarto, Paris, 1823) although he continues to copy the description of Azara, he further alters, thus: "Cette queue a sa penne exterieure plus longue de vingt-quatre lignes que la deuxieme; celle-ci en a cinq de plus que la troisieme, qui en a deux de plus que la quatrieme, *qui surpasse les deux du milieu de pres d'un pouce.*"

All the dimensions of Azara answer very well for the Caprimulgus psalurus, Temm., in young plumage or perhaps in the plumage of winter, which was the season when the observations of Azara were made, "He visto," he says, "algunos siempre solos, y en lo mas crudo del *invierno* nunca en verano ni primavera."

The synonymes of this species given by Hartlaub, in Systematischer Index zu Don Felix de Azara's Apuntamientos, &c., p. 19, (quarto pamphlet, Bremen, 1847,) are entirely correct as far as they go.

The fact that a specimen in the British Museum is named *Caprimulgus manurus*

Vieill., and inserted in the catalogue (p. 10) as distinct, only prevents me from giving that name also, as a synonyme for the present species. I do not see how the species can be made out from Vieillot's description in either Nouv. Dict. x, p. 239, (1817) or Ency. Meth. ii. p. 540, (1823) which both contain important errors. In the original description (Nouv. Dict.) he says, "Nous verrons par la suite un engoulevent dont la *troisième* penne de la queue est la *plus longue de toutes*; singularité qui ne se rencontre chez aucun autre oiseau. Celle du Manure se présente sous une forme plus extraordinaire; la première penne caudale de chaque côté est très longue et dépasse les deux intermédiares d'environ cinq pouces; les *troisième* et quatrième sont *très courte*, et la cinquième, qui a plus de longeur qui celles-ci, est plus courtes que les deux du milieu qui ont plusieurs pouces de moins que les deux premières."

The third feather of the tail is twice mentioned and contradictorily represented, the second feather is not described at all, and the fifth is said to be shorter than the two in the middle, which must be considered as making twelve tail feathers, when really Hydropsalis and other American Caprimulgi have not more than ten. In *Ency. Meth.* the observation "*Nous verrons*," &c., is omitted. He proceeds, however, with exactly the same description, which even without the introductory representation that the third feather is longest of all is not intelligible, because the fifth is still represented as "plus courte que celles du milieu." There are mistakes here, now difficult to correct, but as the descriptions in both books are otherwise quite like the species now before us, I have little doubt that it is the bird meant by this distinguished and learned naturalist.

5. *Genus Stenopsis*, nobis, *nov. gen.*

Bill longer than typical Caprimulgus, tapering and depressed; upper mandible with about six or seven pairs of bristles, which are very rigid at their bases, but very slender and curved at their tips; gape very moderate, nostrils medial; aperture somewhat elevated.

Wings moderate, second and third primaries longest (usually the second) and sinuated on their outer webs. Tail ample, *fan-shaped*, truncate or slightly emarginate. Tarsi slightly feathered below the joint, shorter than the middle toe and claw, and covered with scales.

Wings with a conspicuous white bar in males, and probably in females; neck with a broad and uninterrupted collar, white in front, and fulvous behind; tail usually with a large portion of white on the external feathers; characters of the bill resembling Hydropsalis, Wagler.

Obs.—Another exclusively American genus, the bill in which very considerably resembles that of Hydropsalis. The species which I have seen are:

1. *Stenopsis cayennensis*, (Gm.) Pl. Enl. 760. Jard. and Sel., Ill. pl. 87.
2. *Stenopsis longirostris*, (Bonap.) Jour. Acad., Philada., iv. p. 384.
3. *Stenopsis parvulus*, (Gould.) Proc. Zool. Soc., London, 1837, p. 22.

Which have several synonymes.

6. *Genus Nyctidromus*. Gould, Icones Avium, part ii. (August 1838.)

The species which I have seen of this genus are:

1. *Nyctidromus americanus*, (Linn.) *Caprimulgus albicollis*, Gm. *Nyctidromus Derbyanus*, Gould.
2. *Nyctidromus guianensis*, (Gm.)
3. *Nyctidromus grallarius*, Bonap.

7. *Nyctidromus americanus*, Linn.

1. *Caprimulgus americanus*, Linn. Syst. Nat., i. p. 346, (1766,) a name given by Linnæus on the faith of *Caprimulgus seu Noctua sylvatica Jamaycensis minor*, described by Ray, Syn. Av. et Pis. Appendix, p. 180, (1713,) who copies his description from the manuscripts of Sir Hans Sloane, which were afterwards published in Nat. Hist. Jamaica ii. p. 296, (1725,) with a figure, pl. 255. fig. 1.

2. *Caprimulgus albicollis*, Gm. Syst. Nat. ii. p. 1030, (1788) a name given by Gmelin on the faith of the White-throated Goatsucker of Latham, Gen. Syn. ii pt. 2 p. 596.

3. *Nyctidromus Derbyanus*, Gould Icon. Av. part ii. p. pl. (August 1838.)

4. These names are probably synonymes, and the original describers from specimens are Sloane for C. americanus, Latham for C. albicollis and Gould for N. Derbyanus,—to which Azara may be added, (Del Ybiyau, Apunt. ii. p. 538, 1805.)

The Caprimulgus americanus of Linnæus appears to have been founded on the faith principally of Ray's description, and on Sloane's description and figure. Linnæus enumerates two species only of Caprimulgus; the first of which (*C. europæus*,) he briefly characterizes as "C. narium tubis obsoletis," and the second (*C. americanus*,) as "C. narium tubulis eminentibus." He cites as synonymes the description and figure of Sloane, and the description by Ray, as above, also "Caprimulgus jamaicensis, Briss. Av. ii. p. 480," and "Hirundo major subfusca miscella, macula alba sphærica in utraque alba. Brown, Jam. p. 467."

In Brown's Jamaica p. 467, (Civil and Natural History of Jamaica by Patrick Brown, M. D. London 1756,) there is a short and entirely inconclusive description the most important feature in which is, that the bird is "about the size of a Sparrow Hawk, and of a darkish, mottled and striped colour." He gives as synonymes "Catesby i. pl. 8" and "The lesser Goatsucker of Edwards, pl. 63," both of which are *Caprimulgus vociferus*, Wilson.

Brisson in Orn. ii. p. 480, (1760) under the head of *Caprimulgus Jamaicensis*, copies Sloane's description above referred to, and gives several names as synonymes, among them one from Brown different from that given by Linnæus, that is to say, "Strix capite levi, plumis griseo albidus labiorum pilosus, Brown, Hist. of Jam. p. 473." Upon turning to this I find a bird described as "The screech Owl," with the Latin phrase just quoted, which comprises the entire description.

The synonymes then, to the point we have now attained are, for much the greater part, unsatisfactory, nor are Brown's descriptions of any account whatever, so for as relates to actually determining the species.

Gmelin in his edition of the Syst. Nat. of Linn. ii. p. 1032 (1788,) gives as additional synonymes "Engoulevent a lunettes ou Haleur, Buff. hist. nat. des ois, vi. p. 543," and "American Goatsucker, Lath. syn. ii. 2 p. 600, n. 14," both of which are avowedly founded on Sloane's description and figure.

Geo. R. Gray, in Genera of Birds gives this as a *Chordeiles*, citing Sloane's figure. It is by no possibility a Chordeiles, in which there is no such character as "along the upper mandible were several bristly hairs in line," as stated by Sloane and represented in his plate.

Gosse in Birds of Jamaica p. 51, thinks it may be his *Nyctibius pallidus*, which

is also impossible for the reason just stated, and others which are obvious upon examination of Sloane's description and figure.

Bonaparte, in Conspectus Avium p. 63, places Caprimulgus americanus, Linn. as a *Chordeiles*.

It does not appear that either of the authors cited, from Ray to the present time, ever saw a bird which he understood to be the Caprimulgus americanus, Linn., for which Sloane is the sole authority. In fact, the exact expressions used by him are repeated by nearly all writers;—for instance, the term "Feuille mort" which he applies to the colour of his bird, is copied exactly by Brisson, Buffon, Vieillot and Latham, while Gmelin latinizes it into "folii marcidi."

For the purpose then of ascertaining or rendering probable what bird is entitled to the name of *Caprimulgus americanus, Linn.*, there is nothing left but to revert to the description and figure of Sloane, and to the description in the catalogue of Sloane's birds, by Ray, who describes "ex ejusdem Schedis manuscriptis," in Syn. Av. App. p. 180.

A difficulty occurs at once, which has perplexed authors. It is, that although Sloane describes his bird as "seven inches from the end of the bill to that of the tail," he gives a figure about eleven inches long, respecting which Buffon justly enough observes, "qu'il est fort rare que l'on donne de pareilles figures grossies." Ray says, "parva admodum avis est,—septem non plus digitis longa," having seen the manuscript only. Gmelin, Vieillot, G. R. Gray and Bonaparte appear to rely on the text exclusive of the figure. Brisson says eleven inches long without comment, relying on the latter. Buffon (Hist. Nat. des Ois. vi. p. 544, 1779) attempts to elucidate, and suggests that the measure given by Sloane may have been taken to the base of the tail only, which he says with the tail (4 inches) would coincide with the length of the figure. Latham, perhaps taking the idea from Buffon, offers a similar supposition. But Sloane says very distinctly, "from the end of the bill to that of the tail," and it is clear enough and easily ascertained that all the other birds described and figured by him were so measured.

It is sufficiently evident to me that Sloane's measurements are simply wrong; he says, "This was seven inches long from the end of the bill to that of the tail, and *ten* from the *end* of wing to wing expanded,—the tail was four inches long." It would be difficult to find a bird with such relative dimensions, especially a Caprimulgus. It is simply a mistake made by Sloane himself, as it evidently was so written in his manuscript, according to Ray. Nor are the dimensions given by him ever entirely to be relied on, for the good and sufficient reason that he measured with his *thumb*, "which," he says, "with a *little allowance* I reckoned an inch." (Preface to Vol. i. p. 2.) I am disposed to reject his dimensions entirely as given in the description of the species now under consideration, but to place full dependence on those of the figure, because, as he says expressly, his figures were made "on the place." "I employed," says he, "the Reverend Mr. Moore, one of the best designers I could meet with there, to take the figures of them, (fruits,) also of the Fishes, Birds, Insects, &c., in crayons, and carried him with me into several places of the country, that he might take them on the place." The Reverend Mr. Moore no doubt came generally pretty near the right size, but otherwise did not acquit himself very handsomely in birds, judging from the engravings. In plants, however, he did much better.

Rejecting then the measurements in the description, it is otherwise, with the plate, sufficient to determine the genus and perhaps the species.

The bird belongs to the genus Nyctidromus, Gould, Icon. Av. part ii, and the species is probably N. Derbyanus, Gould, upon which the genus is founded. It is stated in Sloane's description that "it had a quarter of an inch long crooked black bill, with two tubuli about one-eighth part of an inch long for nostrils; along the upper mandible were several bristly hairs in a line—the legs and feet were an inch and a half long, covered with brown scales; the toes four, three before, that in the middle three-quarters of an inch long, and one behind." "The head and back," he says, "were covered with feathers of a mixt color of *feuille mort*, grey and black, the wings and tail were of the same color, only lighter, under the chaps breast and belly, were also of the same.

All these characters, except the colors, are represented in the plate.

They are all, including the colors, to be found in the genus Nyctidromus, and there only. Tubular or elevated nares,—"Nares sub-basales elevatæ" (Gould) are characteristic. It is the only American genus with legs entirely bare, except one species of Podager, and there is no species of any American genus at all, to the color of which the term "feuille mort" can be applied with as great propriety as to those of this.

The entire description, so far as relates to color, applies to all the species of the genus Nyctidromus, of which there are three. They are so much alike that they can scarcely be said to differ in any other respect than size. The largest of these species which is about the size of Sloane's figure, I am disposed to conclude is the Caprimulgus americanus, Linn., and that it is the same as the Nyctidromus Derbyanus, Gould, a common South American bird.

It is important that it should be mentioned, however, that this bird has not been observed in Jamaica by Mr. Gosse, or by any other writer so far as my knowledge extends. Should future investigations elicit the fact that it does inhabit that island I shall consider the matter settled beyond a doubt. That a species of Nyctidromus does inhabit Jamaica, and which is not mentioned by Mr. Gosse, Sloane's figure and description clearly demonstrate.

Caprimulgus albicollis, Gm., is the white throated Goatsucker of Latham described by him from a specimen "in the collection of Major Davies, supposed to have come from Cayenne." The description is accurate, except that the size is rather small, "length ten inches and a quarter," but of course taken from a skin. In Gen. Hist. vii. p. 359, he (Latham) gives the length twelve inches, and an excellent description under the same name, and justly cites "L'Ibiyan, Voyage d'Azara iv. No. 310" as a synonyme. This citation is of the French edition of Azara, with notes by Cuvier and Sonnini, Paris, 1809. (Walckenaer's edition.) The description by Azara is the best extant. Gould's figure in Icon. Av. is incomparable.

The bird now under consideration is the Caprimulgus albicollis, Gm., of the greater number of the European authors; occasionally, however, this name is applied to the bird which is properly Caprimulgus guianensis, Gm., as by De Wied, Beitr. iii., p. 318.

It also appears to be the *Caprimulgus laticaudus*. Drapiez. Dict. Class. d'Hist. Nat. vi. p. 169. (Paris, 1824, octavo.)

A specimen in the Rivoli collection appears to be this bird. Though much resembling *A. carolinensis*, in colors and general appearance, it is smaller, the wings are shorter and the bristles along the bill are simple, not ciliated as in that species, and are, as Buffon says, "tres roides." I may observe, by the way, that although this author expressly describes his bird as having the bill bordered by nine or ten pairs of very stiff "moustaches," he omits them in his plate. (Pl. Enl. 735.)

The specimen alluded to does not accurately agree with Buffon's figure; the bill is longer, and the lateral tail feathers are largely tipped with white, the neck has, moreover, a whitish collar. I suspect that the *A. rufus* is a South American species nearly allied to *A. carolinensis*.

13. *Antrostomus macromystax*. (Wagler.) Isis 1831, p. 533.

I have attached this name to two specimens from California which are very nearly related to *A. vociferus*, (Wilson.) They seem to be the bird meant in the description or rather notice by Wagler, as above.

14. *Genus Nyctibius*. Vieillot, Analyse, p. 38.

Obs.—This genus is one of the most easily recognized in the circle of the Caprimulgidæ, and is another which is exclusively American. I have seen the following species:

1. *Nyctibius grandis*. (Gm.) Gray's Gen. pl. 16.
2. *Nyctibius æthereus*. (De Wied.) Reise, Bras. i, p. 236.
3. *Nyctibius longicaudatus*. (Spix.) Av. Bras. ii, pl. 1.
4. *Nyctibius jamaicencis*. (Gm.) Goase, Ill. B. of Jam. pl. 6.
5. *Nyctibius leucopterus*. (De Wied.) Des Murs, Icon. Orn. pl. 49, 50.
6. *Nyctibius bracteatus*. Gould. Proc. Zool. Soc. Lond. 1846, p. 1.

15. *Nyctibius grandis*. (Gm.)

The Wood Owle of Sloane (Nat. Hist. Jamaica ii. p. 295) and the Guira querea of Buffon (Hist. Nat. des Ois. vi. p. 570, Quarto, 1783) appear to be this species. I am not acquainted with any other American species which has the jaws three inches in width, as stated by both the authors cited, nor to which their descriptions in other respects can be more properly applied.

Latham (Gen. Syn. ii. pt. 2, p. 591) gives both those names as synonymes for his "Jamaica Goatsucker," of which he gives a description and figure,—upon transferring which to his edition of the Systema Naturæ, Gmelin gives the name *Caprimulgus jamaicensis*, (Syst. Nat. ii. p. 1029,) and also erroneously cites as synonymes the same names as Latham. The figure given by Latham (Gen. Syn. ii. pt. 2, pl. 57) represents the N. jamaicensis, which is a well known species, and that plate seems to have saved Gmelin's name from being a synonyme of the N. grandis, there being little in the description which may not be applied to the latter, except the size.

16. *Nyctibius æthereus*, (De Wied.)

1. *Caprimulgus æthereus* described by De Wied in Reise nach Brasilien i. p. 236, (1820.)
2. *Caprimulgus longicaudatus* described by Spix in Av. Bras. ii. p. 1, (1825.)

No one of six specimens, all of which I consider the *N. jamaicensis* as described by Mr. Gosse in his delightful and valuable volume on the Birds of Jamaica, p. 41, appears to have been so large as indicated by his measurements. There is, however, no reliance whatever to be placed on the measurements of skins, so far as relates to the total lengths, and those of other parts are also liable to error, both from the distortion of the skin in the course of preparation, and from various modes of measuring by naturalists.

The measurements given by the authors cited above, vary considerably, but their descriptions are, I think, sufficiently similar. One specimen in the Rivoli collection (labelled *C. Gouldii*) is certainly Mr. Gould's *N. pectoralis*, though it is rather too large for his description, but not large enough for his figure in Icones Avium; the wing, for instance, measuring about 10¼ inches, instead of 9¾ as in the description, or 10¾ as in the figure. It appears to me to be the bird described by Mr. Gosse, whom I consider the best authority for the species, and, so far as I can see, quite justified in quoting N. pectoralis, Gould, as a synonyme. Gosse's and Gmelin's descriptions are sufficiently similar,—that of the latter is, however, copied from Latham.

To this bird in very nearly the same plumage as figured by Mr. Gould, the observations by La Fresnaye on *N. urutau* seem to apply, which avowedly professes to be the same as *C. cornutus, Vieill.* or the *urutau* of Azara. The description by Vieillot is copied from that of Azara, and corresponds remarkably well with that in Walckenaer's French edition of Azara, iv. p. 112, (Paris 1809.)

The description by Buffon of the *Engoulevent gris*. which is *C. griseus, Gm.*, applies very well so far as it goes to the young bird of this species. There is a specimen in the collection of the Academy not fully grown which is nearly white. This description by Buffon is the sole foundation for the Caprimulgus griseus Gm., a name which has maintained a place in all systems and compilations to the present time, no bird having ever been found to suit it, to my knowledge.

18. *Scotornis longicaudus*. (Drapiez.)

This is the African bird described by Vieillot as *Caprimulgus climacurus* and figured in Gal. des Ois. pl. 122, 1825. It appears to have been first described by Drapiez in Dictionnaire Classique D'Histoire Naturelle vi. p. 169, (Paris 1824, Octavo) next by Vieillot, in 1825, and in the same year (1825) again named Caprimulgus longicaudis, by Stephens, Gen. Zool. xiii. p. 89 on the faith of a description and figure by Latham in Gen. Hist. vii. p. 335 pl. 114. The latter calls it "the long tailed Goatsucker."

19. *Genus Chordeiles*. Swainson, Faun. Bor. Am. Birds p. 466.

Obs.—Of this genus I have seen the following species, the first three of which have several synonymes:

1. *Chordeiles virginianus*. (Briss.) Aud. B. of Am. pl. 147.
2. *Chordeiles brasilianus*. (Gm.)
3. *Chordeiles acutus*. (Gm.) Buff. Pl. Enl. 732.
4. *Chordeiles rupestris*. (Spix.) Av. Bras. ii. pl. 2.
5. *Chordeiles sapiti*. Bonap. Consp. Av. p. 63.

There is also in the collection of this Academy a bird which I suppose to be *Chordeiles minutus*, Bonap. Cons. Av. p. 63. It suits the short description but

the upper parts of the body. Neither the white spots near the ends of the tail feathers, nor the white collar in front of the neck are mentioned, which I cannot account for, as the latter is not absent in any American Goatsucker. The bird described may have been young, or a female. The expression "caudam elegantem" alludes probably more to the form than the color.

Caprimulgus noitibo, Vieill., is avowedly a substitute for the name given by Gmelin. Vieillot's description is copied from Buffon, (Hist. Nat. des Ois. vi. p. 539, 1789,) who, however, copies from Marcgrave. *Caprimulgus variegatus*, Vieill., appears to be the same bird.

The term "Jaspeado" applied to his bird by Azara, appears to mean simply "*marbled*" (Connelly and Higgins' Dictionary of the Spanish and English languages ii. p. 232, Quarto, Madrid, 1798,) its latinization into "jaspideus," which appears to have been done by Merrem, is of very doubtful correctness, and calculated to convey to ears accustomed to the English language, the erroneous idea that the bird is the color of the stone known as jasper, which would be taken to mean in the generality of cases a reddish brown or liver color; or worse, according to the classic meaning of the word jaspis or jasper, (hence jaspideus,) "a stone of a green color," (vide Latin dictionaries.)

21. *Chordeiles acutus*, (Gm.)

Caprimulgus acutus, Gmelin, Syst. Nat. ii. p. 1031. Buff. Pl. Enl. 732.

Caprimulgus pruinosus, Tschudi, Av. Consp. p. 8. Fau. Peru. Aves pl. 6.

Caprimulgus exilis, Lesson, Rev. Zool. 1839, p. 44. Comp. de Buff. xx. p. 258.

Chordeiles labeculatus, Jardine, Ann. and Mag. Nat. Hist. 1846, p. 118.

All these names are synonymes. The acumination at the tips of the shafts of the tail feathers, from which the specific name of this bird is derived, affords a character by which it is easily recoguized, when present. But this is by no means constantly the case, though when not observable the ends of the shafts of the feathers are frequently abruptly terminated, and appear as if broken off. This fact, and the very indifferent character of Buffon's figure, (Pl. Enl. 732,) are sufficient reasons that this bird has not been readily recognized, and that it has been several times described under different names by very able and learned authors.

Caprimulgus pruinosus, Tschudi, is this bird. In Fauna Peruana, Cabanis erroneously refers that species to *Caprimulgus semitorquatus*, Gm., having been influenced probably by the Prince de Wied's description of the bird, which he supposed to be the latter, (Beitrage iii. p. 330.) This description applies, however, to Caprimulgus brasilianus, Gm., and not to C. semitorquatus, which belongs to another genus.

22. *Genus Podager*, Wagler, Isis xxv. p. 277, (1832.)

Proithera, Swainson, Cab. Cy. Birds ii. p. 339, (1837.)

Orig. descr. Wagler. "Wesentlichstes äuszeres Merkmal der Sippe: pollex interno-transversalis, non versatilis. Andere Kenzeichen liegen in der Gestalt der Flügel, des Schwanzes, in der Farbe des Gefieders, u. s. w.

Hierher als Species: Caprimulgus diurnus, Wied, (Nacunda, Azar.) Fliegt gesellschaftlich bey Tage."

Orig. descr. Swains. "Rictus almost smooth. Wings very long, equal to the tail, which is short and even. Tarsus very naked. America. P. diurnus. Pl. Col. 182."

(very bad.) Buffon's name, "Engoulevent tachete," is quite appropriate for this species.

Temminck seems therefore to have been correct (Pl. col. vi. p. 78) in applying the name *C. semitorquatus* to Buff. Pl. Enl. 734.

25. *Lurocalis Nattereri*. (Temm.) Pl. col. 107.

This bird is larger than the preceding, and may be distinguished from it not only by its size, but by the greater extent of the rufous color of the lower parts of the body.

In the present species, not only the ventral region and abdomen are of this color, but it extends upwards almost to the breast. This difference may be seen by comparing Pl. col. 107 and Pl. Enl. 734. In other respects the two birds present considerable similarity, and may be sexes of the same species.

26. *Genus Steatornis*. Humboldt, Obs. de Zool. ii. p. 141.

I mention the curious bird which constitutes this genus for the purpose of completing the notices inserted in this paper of all the American genera of Caprimulgidæ, and list of all the American species which I have seen. The only known species of this genus, several specimens of which are in the collection of this Academy, is,

1. *Steatornis caripensis*. Humb. Nouv. Ann. du Mus. Paris, 1834, p. 321, pl. 15.

The Chairman presented a statement from the Treasurer, George W. Carpenter, Esq., announcing that he had received from the executors of the late Mrs. Elizabeth Stott of this city, the amount of the legacy bequeathed by her to the Academy, and that the same had been invested by him for the benefit of the Publication fund of the Journal of the Academy, as directed in the will.

A new Portuguese Grammar. 2d edition. By Anthony Vieyra Transtagano. 8vo. From Mr. R. Pearsall.

A Dictionary of the Portuguese and English Languages. By A. Vieyra Transtagano. 2 vols. 4to. From the same.

Catalogue of the Knowsley collections belonging to the Earl of Derby. By L. Fraser. From the Author.

American Journal of Science and Arts for March, 1851. From the Editors.

Contributions to Ornithology. By Sir Wm. Jardine. Parts 5 and 6. 1850. From H. S. Strickland, Esq.

Journal of the Indian Archipelago and Eastern Asia. Vol. 4, Nos. 9 and 10. From the Editor.

The following were presented by Dr. Wilson on the usual condition:—

Histoire naturelle generale et particulier des Mollusques terrestres et fluviatiles. Par M. de Ferussac, continue par M. Deshayes. 38 et 39 Livs. folio.

Études sur les Echinides fossiles du Departement de L'Yonne. Par M. Gustave Cotteau. 5e et 6e Liv.

History of British fossil Reptiles. By Richard Owen. Part 3. 4to.

Palæontographica. Beytrage zur Naturgeschichte der Vorwelt. Heraus. von W. Dunker und H. Von Meyer. Vol. 3. No. 1.

N. Godofredi Leske additamenta ad J. T. Klein naturalem dispositionem Echinodermatum, &c. 4to.

Annals and Magazine of Natural History. Nos. 35 and 36.

History of British Mollusca and their Shells. By Prof. Forbes and S. Hanley. Nos. 33 and 34.

Phycologia Britannica. By H. Harvey, M. D. Nos. 52 and 53.

Conchologia iconica. By Lovell Reeve. Nos. 91 and 92.

Genera of Diurnal Lepidoptera. By E. Doubleday: continued by A. O. Westwood. Nos. 37 and 38.

Monograph of the Odontophorinæ. By John Gould. Part 3. folio.

The fresh-water Fishes of Great Britain. By Mrs. T. E. Bowdich. Part 4. (completing Acad. copy.)

March 11*th*.

A Dictionary of English, German and French. By Mr. Christian Ludwig. 3d ed. 4to. From Mr. R. Pearsall.

A Dictionary of the English and Italian Languages. By Joseph Baretti. 2 vols. 4to. From the same.

Christian Ludwig's Teutsch-Englisches Lexicon. 4to. From the same.

A new Spanish and English Dictionary. By Capt. John Stevens. Folio. From the same.

Lichenes Americæ Septentrionalis exsiccati. Fascic. 1 et 2. Curante E. Tuckerman. 4to. From the Author.

Bibliotheca Botanica seu Herbaristarum scriptorum promota Synodia J. Antonio Bumaldo Bonan. collect. 4to. From Dr. L. Turnbull, of Philadelphia.

Charts of Cat and Ship Islands: of Hyannis Harbor: and of Pasquotank River. From U. S. Treasury Department, through Prof. Bache, U. S. Coast Survey.

The following were presented by Mr. Edward Wilson on the usual condition:—

Lettre sur le Rhinoceros (M. l'Advocat.)

Nouvelle notice sur le Giraffe envoyee au roi de France par le Pacha d'Egypt. Par M. L. D. Ferlus.

Histoire des Éléphans de la Ménagerie Nationale et relation de leur voyage á Paris.

Aviarium, seu de educandis avibus carmen. Autore Joanne Raze.

A complete Illustration of the British Fresh-water Fishes. By W. Wood. Nos. 1, 2 and 3. 8vo.

Analyse d'une nouvelle Ornithologie élémentaire. Par L. P. Vieillot.

Tratado de la cria de Palomos.

Considerations sur les Poissons, et particuliérement sur les Anguilles. Par M. le Baron de Riviéra.

March 18th.

Memoirs of the American Academy of Arts and Sciences. New series. Vol. 4, pt. 2; and Proceedings of the same, Vol. 2, pp. 161. From the Academy.

Dr. Wilson presented the following on the usual condition:—

London Athenæum, for January, 1851.

Recherches anatomiques et Zoologiques faites pendant un voyage sur les Cotes de la Sicile et sur divers points du littoral de la France. Par MM. Milne Edwards, A. D. Quatrefages et Emile Blanchard. Pts. 1, 2, 3. 4to.

Recherches anatomiques et physiologiques sur le dévelopement du Fœtus, et du particulier sur l'évolution embryonnaire des Oiseaux et des Batrachiens. Par MM. Baudrimont et Martin St. Ange. 4to.

The following were presented by Mr. Edward Wilson on the usual condition:

L'ami de la Nature. Par G. Toscan. 8vo.

Histoire des Singes et autres animaux curieux. 8vo.

Traité sur le maniére d'empailler et conserver les animaux. Par M. l'Abbé Manesse. 8vo.

The Journal of a Naturalist. 3me. ed.

Caroli Linnæi Fauna Suecica. 8vo.

The Note-book of a Naturalist. By E. P. Thompson. 8vo.

Quelques mémoirs sur différens sujets. 2d ed. (Dupont.) 8vo.

Utkast till Elefantens natural historia. Af C. Quesnel. 8vo.

The history of Cheltenham and its environs, &c. 8vo.

Interesting facts connected with the animal Kingdom, with some remarks on the unity of our species. By J. C. Hall, M. D. 8vo.

Œuvres sur divers sujets d'histoire naturellé. Par J. Draparnand. 8vo.

Traité élémentaire d'histoire naturelle. Par A. M. Constant Dumeril. 8vo.

Observations de Lamoignon-Malsherbes sur l'histoire naturelle de Buffon et Daubenton. 2 vols. 8vo.

Essai Zoologique, ou histoire naturelle des animaux sauvages, quadrupedes et oiseaux indigénes. Par A. Delarbre. 8vo.

Tratado de Simplici, Pietre, et Pesci Marini che nascono nel lito di Venetia Di Antonio Donati. 4to.

Beytrage zur Naturgeschichte, von F. von Paula Schrank. J. C. D. Schreberi novæ species Insectorum. F. A. Ant. Meyer Tentamen Monographiæ generis Aloes. MSS. 4to.

Miscellaneous tracts and collections relating to Natural History. By W. Falconer, M. D. 4to.

Zoographie des diverses régions tant de l'ancien que du nouveau continent. Par L. F. Jauffret. 4to.

Faune du Department de la Moselle. Par J. Hollandre. 2 vols. 12mo.

Histoire naturelle, &c., du Tonquin. Par M. l'Abbé Richard. 2 vols. 8vo.

Le voyageur naturaliste. Par M. Lettsom. 8vo.

Histoire naturelle de la Hollande Equinoxiale. Par Philippi Fermin, M. D. 8vo.

Beskrifning pa Svenska Djur. Mammalia. Af Carl P. Thunberg. 8vo.

Memoire sur l'histoire naturelle de l'ile de Corse. Par M. Barral. 8vo.

L'art de preparer, monter et conserver les Oiseaux, &c. Par P. Evans.

Vue générale des progres de plusieurs branches des Sciences naturelles. Par M. Lacépéde. 8vo.

Directions for collecting and preserving specimens of natural history in tropical climates. By Samuel Stevens.

Catalogue du cabinet d'histoire naturelle delaissé par feu Joan Raye.

Tracts relating to Natural History. By J. E. Smith, M. D. 8vo.

Synopsis of the contents of the British Museum. 24th ed. 8vo.

Abhandlungen über verscheidene Gegenstände der Naturgeschichte. Von J. S. Schrœter. 2 vols. 8vo.

Miscellanea curiosa. 3 vols. 8vo.

Cours d'histoire naturelle, conforme au nouveau programme de l'Universite. Par D. H. L. Fournel. Zoologie. 8vo.

Memoria en que se trata del insecto grana ó Cochinella. Por Dr. Josef Anton de Alzate.

Ancient Liverpool. By J. A. Picton.

Hieronymi Cardani Mediolanensis medici de Subtilitate libri 21. 8vo.

Observations on the arts, &c., by Thos. Winstanley. New edition. 8vo.

A practical treatise on the law of mines and minerals. By W. Bainbridge. 8vo.

Notice des tableaux du Musée Royal a la Haye.

Description des tableaux déposés au Musée Royal des Pays-Bas.

Notice des tableaux exposés au Musée d'Anvers, 1829.

Beitrag zur Insecten-fauna von Angola. Von Dr. W. F. Erichson.

Dissertation physique sur le flux et reflux de la Mer et sur d'autres sujets. Par M. Roubaix de Turcoin. 12mo.

Essai sur la Marne. Par M. A. Puvis. 8vo,

Cours gratuits de Sciences industrielles faits a l'hotel de Ville de Metz. 8vo.

Dissertation sur le tænia ou Ver-plat. Par Charles Dionis. 12 mo.

Lettres philosophiques sur la formation des sels et des crysteaux, &c. Par M. Bourguet.

Itineraires en France, pour l'etude de l'histoire naturelle et de la geologie. Par M. Néree Boubée. 12mo.

Essai sur le climat de Montpellier. Par Jacques Poiteven.

April 8th.

Special anatomy of the terrestrial Gasteropoda of the United States. By Joseph Leidy, M. D. From the author.

Journal of the Indian Archipelago and Eastern Asia. Vol. 4, Nos. 11, 12. From the Editor.

Thirtieth Annual Report of the Board of Direction of the Mercantile Library Association of New York, January, 1851. From the Association.

Quarterly Journal of the Geological Society. Vol. 6, No. 21. From the Society.

Transactions of the Zoological Society of London. Vol. 4, Part 1. 4to. From the Society.

Enumeration des Insectes qui consumment les tabacs. Par M. Guerin-Meneville. 8vo. From the author.

Proceedings of the American Association for the advancement of Science. 3d meeting, held at Charleston, S. S., March, 1850. From the Association.

Conspectus Generum Avium. (C. L. Bonaparte.) pp. 433—464. 8vo.

Notes on Hybridity, designed as a supplement to a memoir on that subject in the Charleston Med. Journal: and second letter on same subject to the editors of same. By S. G. Morton, M. D. From the author.

Oration by Hon. R. C. Winthrop, July 4th, 1848, on the occasion of laying the corner stone of the Washington Monument. From Mr. Varden, of Washington.

Oration by Hon. H. S. Foote, July 4th, 1850, at Monument Place. From the same.

Constitution and By-Laws of the National Institute. From the Institute.

Contributions to Ornithology. By Sir William Jardine. Part 7, 1850. From H. E. Strickland, Esq.

Catalogue of the Knowsley collection, pp. 25—40. From the Earl of Derby.

Microscopical examination of Soundings made by the U. S. Coast Survey. By Prof. J. W. Bailey. From the author.

On Mosasaurus and the allied new genera. By R. W. Gibbes, M. D. From the author.

Philyra. Auctor D. H. F. Delius. From Mr. Balliere.

Verhandlungen der Gesell. Naturforsch. Freunde in Berlin. Vol. 1, pt. 6. 4to. From the same.

Dr. Wilson presented the following on the usual condition:

Conchologia iconica. By Lovell Reeve. Parts 93, 94.

Traité élémentaire de Conchyliologie. Par G. P. Deshayes. Liv. 12.

Annals and Magazine of Nat. History. Vol. 7, 2d series. Nos. 37, 38.

A discourse on the studies of the University of Cambridge. By Adam Sedgwick. 6th ed. 8vo.

The British Coleoptera delineated. W. E. Schuckard, editor. 8vo.

Popular treatises on Science, written during the middle ages, in Anglo-Saxon, Anglo-Norman and English. By T. Wright. 8vo.

An essay on Electricity. By the late George Adams. 5th ed. 8vo.

Treatise on Falconry. By J. C. Belany. 8vo.

Description of the Feroe islands. By the Rev. J. Landt. Translated from the Danish. 8vo.

S. G. Gmelin's Reise durch Rusland zur Untersuchung der drey Natur-Reich. 4 vols. 4to.

Sketches of Vesuvius. By John Auldjo, Esq. 8vo.

Monographie des Cétoines et genres voisins. Par MM. Gory et Percheron. 8vo.

The British Desmidieæ. By J. Ralfs; the drawings by Edward Jenner. 8vo.

Travels into the interior of Brazil in 1836—'41. By George Gardner, M. D. 2d ed. 8vo.

De Noordsche Weereld, door S. De Vries. 4to.

Minus cognitarum Stirpium ac etiam rariorum ἐκφρασις. Fabio Columna autore. 4to.

Meteorological observations and essays. By J. F. Daniell. 2d ed. 8vo.

Natural history of the Lepidopterous insects of New South Wales. By J. W. Lewin. 4to.

History of the Royal Society of London, from its first rise. By Thomas Birch, M. D. 4 vols. 4to.

Getrue Abbildungen und naturhistorischer Beschreibung des Thierreichs aus den nördlichen Provinzen Russlands, vorzeiglich Liefland, Ehstland, und Kurland betreffend. Von Ernst W. Drümpelmann und W. C. Friebe. 2 vols. Folio.

The Geology and fossils of the Tertiary and Cretaceous formations of Sussex. By Frederick Dixon. 4to.

An introduction to Zoology. By P. H. Gosse. 2 vols. 8vo.

April 22d.

The studies of the medical man; an introductory address at the opening of the session, 1850, '51, at St. George's Hospital. By E. Lankaster, M. D. From the author.

Addresses delivered in the Ipswich Museum, March 9th, 1848. By Rev. J. S. Henslow. From Geo. Ransome, Esq.

Observations on the Fauna of Norfolk, and more particularly on the district of the Broads. By the Rev. Richard Lubbock. 8vo. From the same.

Six lectures on Astronomy at the Temperance Hall, Ipswich, March, 1848. By Geo. B. Airy. 8vo. From the same.

Notice of a species of Seal apparently new to the British Shores. By W. B. Clarke, M. D. From the same.

Proceedings of the Royal Irish Academy. Vol. 2. From Mr. Bell, of Dublin.

A new Dictionary of the English Language. By Charles Richardson. 2 vols. 4to. Deposited by Mr. Samuel Powel.

A general dictionary, historical and critical, in which a new and accurate translation of that of the celebrated Mr. Bayle, with corrections and observations, is included. 3 vols. folio, 1734. From Dr. J. C. Fisher.

Annals of the Minesota Historical Society. 2d ed. 1850. From the same.

Verhandlungen der Schweizerischen Naturforschenden Gesellschaft, 1847, '48, '49, '50, '51. From the Society.

Mittheilungen der Naturforschenden Gesellschaft in Bern aus dem Jahre, 1846. From the same.

Annals of the Lyceum of Nat. Hist. of New York. Vol. 5, No. 2. From the Lyceum.

Journal of the Franklin Institute, April, 1851. From Dr. Wilson.

Mr. Edward Wilson presented the following, on the usual condition:

Specchio delle Scienze o Giornale Encyclopedico di Sicilia. Nos. 1—11.

Provisional report on the Meteorological observations made at Calabra, Bombay, in 1844. By George Buist, LL. D.

Conchology, or the natural history of Shells. (Da Costa and Humphreys.) Folio.

A description of the principal picturesque beauties, antiquities, and geological phenomena of the Isle of Wight. By Sir Henry C. Englefield. Folio.

Report of the general meeting of members of Ipswich Museum, and six reports of lectures delivered at the same.

as well as in some others. The plant which produces the Siamese gamboge, for instance, is confessedly unknown. In the southern parts of these Provinces, near the Siamese boundary, there is a tree which produces a species of gamboge that cannot be distinguished from the gamboge that is brought from Siam; and in an article which was read before the Asiatic Society of Bengal, three or four years ago, I showed that that tree was *Garcinia elliptica*, a species named and described as a species imperfectly known by Dr. Wight; who was not at all aware that it produced gamboge. There can, I think, be little doubt, but that this is the tree which produces the Siamese gamboge. This was so clear to the members of the Asiatic Society, that the Secretary wrote me, 'Our best botanists here, consider that you have hit on the true tree at last.' Again, gum-kino was exported several years ago in considerable quantities from Maulmain, brought overland from the Shan States, and is produced so far as I can ascertain, from *Sterocarpus Wallichii;* yet this tree has no place in our Medical Floras.

I suspect that a large part of the crude camphor exported from China, and which is always referred to *Camphora officinarum*, is the product of one of the commonest weeds in Eastern India and China. In the early years of my residence at Yavoy, the Burmese pointed out to me a weed with leaves like mullen, which when bruised emits a strong odour of camphor. From it they told me they had been in the habit of distilling, from time immemorial, as good camphor, except that it was not so pure, as that which they saw in my medicine chest. Some of the Chinese settlers also say that the same plant abounds in China, and that camphor is made from it there. Mr. O'Riley, a sugar manufacturer at Amerst, made more than a hundred pounds of camphor from this weed, a few years ago, and sent a part of it to Calcutta for examination; and the official authorities reported on his specimens. 'In its refined form, it is identical in all its properties, with Chinese camphor.' Mr. O'Riley sent flowering specimens of the plant to Calcutta, and they were forwarded from thence to Dr. Voigt of Serampore, and the report added: 'Dr. Voigt states that it belongs to De Candolle's genus Blumea, and is, so far as he can see, a new species.' Not having books to enable me to determine the question of its being a new species or not, I left it in abeyance until I procured De Candolle's Prodromus, three or four years ago, and I was soon satisfied then, that it is the same plant as that which appeared in Wallich's catalogue, as *Conyza grandis*, and which De Candolle has described as *Blumea grandis*. Wallich's specimens were from Yavoy, without flowers, and De Candolle describes the leaf* as nine inches long with the petiole, by three wide, serrated, and bearing on the petiole five or six remote linear acute lobes; which corresponds precisely to some specimens of our camphor plant; but it does not correspond to any other species of Blumea in the Provinces. This plant probably covers more of the surface of the Tenasserim Provinces than any other weed. Wherever the trees are cut down to clear the land, it springs up so thick that scarcely any thing else can live with it; so that an old clearing looks in the distance like a field under cultivation."

A letter was read from the Royal Society of London, dated Feb.

* "Cum petiolo 9 poll. longa, 3 poll. lata—serratis, petiolo lobulos, 5—6 distantes lineares acutos gerentibus."

20th, 1851, acknowledging the receipt of the Proceedings Nos. 3 to 5, Vol. 5.

Also a letter from the Asiatic Society of Bengal, dated Feb. 21st, 1851, acknowledging the receipt of the Journal Vols. 1 to 8, old series, Part 1, Vol. 1, new series, and Proceedings, Vols. 1, 2, 3, and Nos. 1—5, of Vol. 4.

On motion of Dr. Zantzinger, the thanks of the Society were presented to Mr. George Ord for the portrait received this evening.

May 16th.

Vice-President WETHERILL in the Chair.

Upon taking the chair, Mr. Wetherill announced the decease of the President of the Society, Dr. Samuel George Morton, which took place at his residence in Arch Street yesterday morning, after an illness of only four days. The present meeting had been convened for the purpose of expressing the feelings of the members on this melancholy occasion.

Dr. Bridges in some very appropriate remarks on the character of the deceased, adverted to his long connexion with the institution, almost from its origin; his close adherence to its interests under the varied and trying circumstances through which it had passed; having successively filled its different offices, he had become the ornament of its prosperity, and died at last its President.

Dr. Charles D. Meigs expressed his deep and sincere regret for the loss of Dr. Morton, and bore testimony to his great private worth, his eminent scientific and professional abilities, and offered the following Preamble and Resolutions.

The Academy of Natural Sciences of Philadelphia being called upon to deplore the loss of its late respected and beloved President, Dr. Samuel George Morton, and considering that event as of deep interest to the whole Republic of Letters; feeling that the eminent attainments of their late Chief in the various departments of Literature and Science, entitled him to the respect and admiration of all the friends of learning; that his consistent course of virtue, his liberality and urbanity, adorned and illustrated the Academy over which he presided, and reflected honor upon its name, are deeply impressed by the irreparable loss they, in common with all the friends of the Natural Sciences, have sustained by his death: Therefore,

Resolved, That this Academy esteem the life of their late President to be for all men a shining example of earnest and successful zeal in the pursuit and promotion of learning, in the cultivation of wisdom and virtue, and the practice of the highest liberality and benevolence.

Resolved, That the Academy do cherish and revere the memory of their deceased illustrious President, and that in order to commemorate

his name, a marble tablet with a suitable inscription be placed in the Hall of the Academy.

Resolved, That with heartfelt sympathy we present to his bereaved family, this expression of our admiration of him whose death deprives both them and our common country and the world, of one of the most meritorious of men.

The Preamble and Resolutions were unanimously adopted.

Dr. J. C. Fisher offered the following, which was also unanimously adopted.

Resolved, That a Committee be appointed to select a member to prepare a biographical memoir of our late President, Dr. Morton, and that the kindred societies in this city, of which he was a member, be invited to be present when it is read.

The Committee under this resolution was then appointed as follows; Dr. Jas. C. Fisher, Dr. R. Bridges, Dr. J. K. Mitchell, and Dr. Leidy.

On motion of Dr. Bridges, the Resolutions were ordered to be published in four daily papers of this city.

Dr. Horner offered the following, which was adopted.

Resolved, That when we adjourn, it shall be to meet in this Hall on Sunday afternoon next, 18th inst., at 3 o'clock, to attend, as a body, the funeral of our late lamented President.

Dr. Mitchell moved that the Chairman and Secretaries and three other members, be a committee to wait upon the family of Dr. Morton and testify the sympathy of the Society; which was adopted, and the following members appointed, Dr. Mitchell, Mr. Peterson, and Dr. Horner.

May 20th.

Vice-President WETHERILL in the Chair.

Dr. Leidy remarked that in a recent visit to Dr. Wilson, near Newark, Delaware, while rambling in a neighboring wood, upon turning over a log, he discovered a mole cricket, (*Grillo-talpa Americana*,) standing very quietly at the mouth of a hole. Upon taking it up, the animal exhibited no signs of movement, though perfectly fresh and life-like in appearance. He took it home and next morning examined it, and found it still presenting no signs of life. Every part of the insect was perfect, not even the antennæ being broken. Upon feeling it, it was very hard and resistant, and on making an incision through the thorax, it exhaled a fungoid odor. The insect had been invaded with a parasitic fungus, which every where filled the animal, occupying the position of all the soft tissues, even into the tarsal joints. It formed a yellowish or cream-colored compact mass, and in the abdomen enclosed in its centre the stomachal teeth of the insect.

Examined microscopically, the fungus matter was found to consist of a mycelium of filaments for the most part simple, but occasionally branched, and elliptical or globular sporular bodies, averaging the 1-2333rd in. in diameter.

Mr. Isaac Lea stated that he had visited within a few days, the locality whence Dr. J. Y. Schelley had procured the reptilian fossil. It was a calcareous conglomerate, the rock being in place and forming a wall on the side of the road, and was not a boulder as had been supposed. No further traces of bones had since been discovered. Mr. Lea exhibited a specimen of the rock, and stated that he had now determined to name the fossil *Clepsysaurus pennsylvanicus*, from the peculiar form of the vertebra, which resembled an hour glass in shape.

On leave granted, Mr. Vaux moved that Mr. Pearsall be added to the Committee appointed to select a member to prepare a biographical memoir of the late Dr. Morton. Adopted.

On motion of Mr. Vaux, it was also resolved that a committee of five be appointed to select a suitable design for a tablet to the memory of Dr. Morton, to be placed in the Hall, and to carry out the resolution relating to this subject, adopted at the meeting of the Society held on the 16th inst.—Committee, Mr. Vaux, Dr. Bridges, Mr. Wetherill, Dr. Meigs, Mr. Phillips. On motion of Dr. Leidy, the Curators were added to the Committee.

May 27th.

Vice-President WETHERILL in the Chair.

The Library Committee, to whom was referred the communication from the Historical Society of Pennsylvania, requesting the deposit with them of the Paris Moniteur belonging to the Academy, reported "that as said papers constitute part of a series in connection with the documentary History of the French Revolution, it would be inexpedient to separate them, and they would therefore respectfully decline complying with the request of the Historical Society." Adopted.

Dr. Fisher, from the Committee on the subject, reported that Dr. Charles D. Meigs had been unanimously chosen by the Committee to prepare a biographical memoir of Dr. Morton, and that Dr. Meigs had accepted the appointment.

The Committee to whom was referred the following paper by Dr. Leidy, reported in favor of publication in the Proceedings.

Contributions to Helminthology.

By JOSEPH LEIDY, M. D.

ASCARIS, *Linn.*

1. ASCARIS ALIENATA.—Rud. *Entoz. Syn.* p. 661; Dujardin *Hist. Nat. des Helminth.* p. 158.

Body nearly uniformly cylindrical, white; mouth prominent, with the three lips prominent and very distinct: no membranous or other appendages.

Female.—Body cylindrical to within four lines of the mouth, when it gradually becomes narrowed; posteriorly straight, abruptly narrowed into a very small ob-

tuse tail, 1-5th of a line long from the anus. Whole length 4 inches 3 lines; breadth 1 and 1-5th lines.

Male.—Cylindrical, attenuated towards the extremities; posterior extremity incurved, without appendages; tail short, curved. Length 2 inches; breadth ¾ths of a line.

Habitation.—A male and female found in the intestine of Mephitis americana. Received from Prof. S. F. Baird, Carlisle, Pennsylvania.

Remark.—It corresponds in every particular except in size, being twice as large, with the *Ascaris alienata* obtained from Nasua rufa, described by Rudolphi.

2. ASCARIS ENTOMELAS, *n. s.*—Body cylindroid, attenuated at each extremity, curved, whitish, with the black intestine visible through the translucent integument, without membranous appendages. Generative aperture posterior to the middle. Tail conical, pointed, 1-18th line long.

Length of female 1 to 1½ lines; breadth, ¼th of a line.

Ovum 1.333d in. long; 1-500th in. broad.

Habitation.—Lungs of Rana halecina.

Remarks.—Very distinct from Ascaris nigro-venosa, *Zeder*, which is three times as large, and possesses membranous appendages. The largest females, with the oviducts distended with eggs of Ascaris entomelas, do not measure over 1½ lines. It is also not to be confounded with Angiostoma entomelas, Duj., which, as a generic character, possesses a corneous capsule within the head.

DISTOMUM, *Retzius.*

3. DISTOMUM LONGUM, *n. s.*—Body whitish, with the blackish ovaries showing through the anterior two-thirds, sub-cylindrical, compressed; posteriorly sub-ligulate, or spatulate, obtusely rounded; neck cylindrical. Oral acetabulum obliquely terminal, urceolate, broader than the neck, 3-5ths of a line in diameter. Ventral acetabulum, a little smaller, and from 1½ to two lines behind the former, orbicular, projecting, ½ a line in diameter. Generative aperture just anterior to the middle of the neck, or nearer the oral acetabulum.

Length 15 lines to 3 inches; breadth, 2-5ths to ½ths of a line.

Habitation.—Six individuals found in the mouth of Esox estor, Cleveland, Ohio. Received from Prof. S. F. Baird.

Remarks.—This is a remarkable species of Distomum from the very great relative length to the breadth.

4. DISTOMUM TERETICOLLE, *Rud.* Entoz. Syn. p. 102; *Dujardin*, Hist. Nat. des Helm.; *Diesing*, Syst. Helm. p. 358.

Body subcylindric, light flesh color, posteriorly rounded. Ventral acetabulum ½ths of a line behind the oral, ½d line in diameter. Oral acetabulum, ½th of a line.

Length, 8 lines; breadth posteriorly, ½ line, anteriorly, ½d line.

Habitation.—Stomach of Esox reticulatus, *Lesueur.*

Remark.—The generative aperture is placed immediately in advance of the ventral acetabulum. When the animal contracts, the two acetabula are nearly brought into contact.

a line long, lateral, or subterminal, or transversely projected, furnished with 12 transverse rows of strong hooklets, 6 in each row, alternating; neck short. Male without copulatory appendage.

Body from 2 lines to 1 inch in length; breadth anteriorly from ½ to 3-5ths of a line; breadth posteriorly from 1-5th to 2-5ths of a line.

Hab.—Seventy-six individuals were found within the intestine, and according to Prof. Baird, from whom they were received, also attached to the integument upon the exterior of the body, of Salmo fontinalis.

Remark.—Closely allied to E. angustatus, *Rud.*

10. ECHINORHYNCHUS PROTEUS. *Westrumb*, De Helm. Acanth. p. 37; *Duj.* Hist. Nat. des Helminthes, p. 529.

Body orange color, fusiform; anteriorly slightly spherically dilated; posteriorly obtusely rounded. Proboscis cylindrical, with twelve to twenty transverse rows of hooklets, transversely projected, yellow. Neck long, posterior three-fourths filiform, anterior fourth dilated into a spherical vesicle.

Length of body 3 to 6 lines; neck 2 to 3 lines long, 1-6th line broad posteriorly.

Hab.—Found very frequently in the large intestine, often in great numbers, of Labrax lineatus.

THELASTOMA, *Leidy.*

11. THELASTOMA BREVICAUDATUM, *n. s.* Body white, cylindrical, anterior to commencement of ventriculus rapidly narrowed, conoidal; posteriorly abruptly rounded, with a very short spiculate tail. Generative aperture just posterior to middle. Anus just anterior to posterior rounded termination. Ventriculus broadly dilated at commencement, and moderately so at termination.

Length of body 1½ to 2 lines; anterior to ventriculus 1-50th inch; from anus to end of tail 1-200th in.; tail 1-285th in. long; breadth of body just above anus 1-133d in.; at middle 1-80th in.; at commencement of ventriculus 1-75th in.; cylindrical portion of œsophagus 1-66th in. long by 1-666th in. broad; pyriform portion 1-250th in. long by 1-285th in. broad. Ovum semi-oval, 1-285th in. long by 1.1000th in broad.

Hab.— Found in numbers from one to four in the intestine of larvæ of a large lamellicorn insect, found by my friend Mr. S. Powel in earth mould near Philadelphia.

GREGARINA, *Dufour.*

12. GREGARINA.—Body white, cylindro-fusiform. Superior division presenting four sides of a hexahedron, subacute. Nuclear body of inferior division transparent, globular or elliptical, containing several coarse granules.

Length from 1-66th in. to 1½ lines; head 1-400th in. to 1-133d in. long by 1-285th in. to 1-111th in. broad. Anterior portion of inferior division 1-200th in. to 1-86th in. broad; posterior portion 1-666th in. to 1-250th in. broad. Longitudinal lines of inferior division more distinct than those of the upper division, 1-8000th in. apart.

Hab.—Found in the same insect as the preceding.

Remark.—Since the discovery* of the beautiful, parallel, longitudinal lines of the inferior division of the body of Gregarina, after a careful examination I have come to the conclusion that they also exist upon the superior division.

---

*Proc. Acad. Nat. Sci., Vol. 4, p. 232.

June 3rd.

Vice-President BRIDGES in the Chair.

A letter was read from Edward Wilson, Esq., dated Lydstip House, Pembrokeshire, Wales, 15th April, 1851, giving information of a case containing books and specimens of Natural History, which he had forwarded for the Academy.

Also a letter from the President of the National Society of Agriculture, &c., of Lyons, dated 23rd December, 1850, accompanying the donation by that Society, of its Annals for 1849, and '50.

Mr. Cassin read a communication from Col. Geo. A. McCall, U. S. A., entitled "Some account of Birds found in Western Texas and New Mexico, with descriptions of new species;" which was intended for publication in the Proceedings, and referred to the following committee: Mr. Cassin, Dr. Watson and Mr. E. Harris.

Dr. J. K. Mitchell exhibited a specimen of a fungus growing upon a piece of decayed white-oak wood, which when recent is so luminous as to attract insects to it at night.

Dr. Leidy remarked, that it had occurred to him whilst examining the mole cricket, referred to at the meeting of May 20th, that if the fragments of the insect were placed under favorable conditions, the fungoid matter in the interior of the insect might develope itself into an external form of fungus. He accordingly placed them in a small glass case, with some moist sphagnum, and allowed them to remain until the present time. Dr. L. exhibited the glass case with the fragments, each having sprouting out of it one, two, or three, elongated, conical stipes of a cream color, from 3 lines to 1 inch long, and from ½ a line to 1½ lines in diameter. Dr. Leidy continued, in examining insects for entophyta and entozoa, he had found the hemiptera remarkably free from them, which he considers an important fact. Those insects which eat large quantities of vegetable solid food, especially such as eat decaying substances, are very much infected with parasites. The spontaneous generation of entophyta and entozoa finds but few advocates at the present day. Late researches lead us to suspect that many, if not all, entozoa, pass part of their life out of the animals in which they are known as parasites, under forms different from those when within the animals.

The entrance of the parasites into other animals is effected probably in two ways: with the food of the latter, or by boring from the exterior. The former method is probably the most frequent in aerial animals; and both methods are frequent in aquatic animals, because, in the latter case, the water affords a good vehicle for the approach of the parasites to any part of the body of the animals to be infected.

As hemipterous insects suck the juices only of plants or animals, through a delicate proboscis, they are placed under circumstances the most favorable of all animals to avoid taking in with their food, ova, spores, or developed animals and plants of a parasitic character; whilst insects like papulus, crickets, etc., or gulus amongst myriapoda, from their eating decaying substances, swallowing large morsels of such food, are very apt to take in parasites.

Frequently I have detected adhering to insects and annelida, while living, cryptogamic sporules, which under favorable circumstances, before or after the

death of the animal, undergo development into the perfect plant. House-flies, and especially earth-worms, are very liable to the growth of Achlya upon them, and sometimes I have even detected the growth of the latter upon the surface of earth worms still living.

Mr. Lea stated that during his recent visit to Reading, Penn., he had discovered there a new locality for Zircon, a specimen of which he exhibited, and also a specimen from another unrecorded locality, the Yellow Springs.

Dr. Burnett, of Boston, made a communication on the subject of his recent microscopic examination of the Cicada septendecim, especially of the alimentary canal and sexual organs, and of the apparatus in the male for producing sound.

The Librarian announced the donation to the Academy of a portrait of its late President, Dr. Samuel George Morton, which had been executed under the direction of a committee consisting of Dr. Zantzinger, Mr. J. Cooke, and Mr. J. Lambert, appointed at an informal meeting of the Society, held for that purpose in December 1850. The portrait was painted by Mr. Paul Weber, of Philadelphia County, and is a very faithful likeness. An earlier presentation of the portrait had been unavoidably prevented. The following members are the donors: William Hembel, George W. Carpenter, William S. Vaux, J. H. B. McClellan, George B. Wood, William S. Zantzinger, John Cooke, William Parker Foulke, Jr., Alexander Biddle, E. J. Lewis, Thomas Fisher, Thomas B. Wilson, John S. Phillips, Robert Pearsall, Robert Bridges, A. L. Elwyn, Samuel Ashmead, and J. Price Wetherill.

June 10th.

Vice-President Bridges in the Chair.

Letters were read:—

From the Librarian of the British Museum, dated 19th May, 1851, acknowledging the receipt of late Nos. of the Proceedings.

From the Librarian of the New York State Library, dated Albany, June 3rd, 1851, acknowledging the receipt of last No. of the Proceedings.

From Mr. John Hooper, dated New York, June 5th, 1851, accompanying an additional collection of American Algæ, and also referring to a species of Petrel supposed to be new, from the Florida coast; abdomen white, toes fastigiate, web extending nearly to the claws, claws very short and even in length, size much larger than the stormy Petrel.

From Edward Wilson, Esq., dated Lydstip House, Wales, May 14th, 1851, enclosing bill of lading and invoice of a case of books intended for the Academy.

Dr. Horner exhibited a portion of skin affected with the disease called Nigrities, taken from the cheek of a white man; a part originally white

which had become black, occasioned by the actual deposit of pigmentum nigrum in the rete mucosum.

June 17th.

Dr. Leidy read a continuation of his paper entitled "Contributions to Helminthology;" which was referred to Drs. Bridges, Ruschenberger and Fisher.

Dr. Leidy stated that he had examined microscopically, the specimen of *nigrities* which had been exhibited by Prof. Horner at the last meeting; and that it proved to be a true deposit of pigmentum nigrum in rete mucosum.

A letter was read from the Rec. Sec. of the Penna. State Med. Soc., dated Philadelphia, June 10th, 1851, transmitting a resolution of thanks from that Society for an invitation to visit the Museum of the Academy.

Dr. Leidy stated he had repeated the experiment of introducing cancerous matter beneath the integument of a frog, which was first announced to the Academy, May 6th.

The cancerous matter was a fragment of encephaloid, taken from a female after death, by Dr. Henry H. Smith. It was almost as soft as cerebral substance. Beneath the microscope it exhibited a structure of very delicate organic cells, containing numerous granules and one of two nuclei.

A portion ⅛ths of an inch long, by ⅛th of an inch broad, was inserted under the skin of the back of a frog, on May 8th, 34 hours after its removal from the body of the female. This frog, still living, Dr. L. exhibited to the members, and by an incision through the integument, presented to view the fragment of cancer which had been introduced, and which had not only formed a vascular attachment to the integument, but for one half itself was of a fine red color from the net-work of capillaries which had become developed within it. The fragment had not increased in size. A number of its structural cells remained unchanged, but others had broken down into granular masses.

Dr. L. observed, the experiment not only proved the independent vitality of tissues, which was generally admitted, but also rendered it exceedingly probable that cancer was inoculable, for, as in the experiments, the cancerous fragments continued to live when introduced into cold-blooded animals, they would probably not only continue to live when introduced into warm-blooded animals, but would grow or increase in size.

Dr. Zantzinger announced to the Society the decease of William Hembel, Esq., which occurred on the 12th inst., at his residence in this city, at the advanced age of 88 years. His long connection with the Institution, his liberality to it on many occasions, his position as its President for nine years, and his scientific and literary acquirements, eminently entitled him to honorable mention on the present occasion.

The following Preamble and Resolutions were then offered on the part of Mr. George Ord, and unanimously adopted.

The Academy deeply sensible of the death of their venerable member, are impelled by a sense of duty, to give formal expression of their sorrow at the loss of one, who, during the period of twenty-six years, was zealously active in his exertions to advance those branches of knowledge for the cultivation of which this Institution was created. It is, therefore,

Resolved, That the Academy, in mourning the departure of a friend whose long life was signalized by his devotion to scientific pursuits, derive consolation from the reflection that their steadfast benefactor was as conspicuous for his efficient benevolence, as for his integrity and social virtues.

Resolved, That a copy of the foregoing, be transmitted to the family of the deceased.

June 24th.

The Committee to which was referred the communication of Col. McCall on Birds of Mexico, reported in favor of publication in the Proceedings.

Some Remarks on the Habits, &c., of Birds met with in Western Texas, between San Antonio and the Rio Grande, and in New Mexico; with descriptions of several species believed to have been hitherto undescribed.

By Col. Geo. A. McCall, Inspector-General, U. S. Army.

Falco, *Linn.*

1. F. Peregrinus, *Linn.* Perigrine Falcon.

In passing and re-passing through this extensive range of country, during a period of twelve months, I met with this Falcon but once—at Santa Fé, in the month of June. Here, two were seen; one of which was killed. This proved to be a female, of immature age and plumage, answering to the following description:

Length, 17 3-10ths inches; alar stretch, 38 5-10ths inches; front, eyebrows, lores, chin, throat, and a crescent around the occiput, extending to the eyes, light brownish white; head, back, scapulars, greater and lesser wing coverts and tail coverts dark dusky, each feather margined with light brown, giving a mottled appearance; primaries, secondaries, tertials dark dusky, broadly and closely barred with pale brown; tail dusky brown, tipped with paler brown, and all, except the two middle feathers, thickly barred on the inner vanes with pale brown; all the lower parts brownish white, striped with dark brown; under wing coverts dark dusky, each feather with two to four spots of dull white, and edged with the same; cere greenish yellow; feet lighter; iris hazle; middle toe and nail 2 7-10ths in.

CIRCUS, *Lacep.*

2. C. CYANEUS, *Linn.* Marsh Hawk.

The Harrier I found in *very* great numbers on the plains stretching from the Pecos river to the Apache mountains, in February; whereas in October following but few were seen in the same region; stragglers were, however, met with in the lower plains, everywhere.

ATHENE, *Boie.*

3. A. HYPUGÆA, *Bonap*, [S. CUNICULARIA, *Gmel.*] Burrowing Owl.

This singular little owl I found, occasionally, along the Rio Grande, from Val Verde to Santa Fé, and quite abundant in the Valley of Las Vegas. It was abroad at all hours of the day, and often amused me with its odd manners; taking wing at the near approach of my horse, and again alighting at the distance of a few yards, when it would face towards me and make, almost uniformly, three distinct and formal bows, with a mock solemnity that was irresistably ludicrous. Between sunset and dark, however, I always observed them to be most numerous; and at this hour they were, also, more shy and less ceremonious.

There is a general impression, that this owl habitually takes up its abode in the dominions of the "*Prairie Dog*," where, in company with the Rattlesnake, it feeds freely upon the young marmots. That it has been found, in some regions, in the *dog towns*, seems to be established on reliable authority; indeed I have conversed with more than one person who was a witness to the fact. Still, I am rather disposed to look upon the fact as an accidental occurrence, than as an instinctive or positive habit of the bird. My own experience, too, tends to anything but the corroboration of this testimony; for I have met with *Hypugæa* in various places, from Fort Gibson, in Arkansas, to the Rocky Mountains; and it has never, in one instance, been my fortune to find it in company with the Marmot.

On the high, dry plains between the Pecos river and the Apache mountains, I rode for days through the *dog towns*, as they are called, and did not see a single owl, although the whole land seemed vivacious with marmots. Again; both on the east and west of the Valley of Las Vegas, where, as already observed, this owl is found in great numbers, there are within a few miles of the edge of the valley, on the high dry plains, extensive settlements of the marmots; and yet I never saw an owl about their burrows, in repeatedly passing through them. Nor is the most usual food of this owl found on high sandy plains; but in low lands, near water courses; and here I have always found him most numerous. With a view to satisfy my own mind on this point, I studied these animals closely, on this expedition; in the northern parts of New Mexico, in the months of August and September; and in the Apache country in February and October.

It may not, perhaps, be amiss to remark here, with respect to the reported *hibernating* habits of the marmot, [ARCTOMYS LUDOVICIANA,] that on the high plains of the Limpia, and also on those among the Apache mountains, these frolicksome little fellows made their appearance above ground, in crowds, soon after sunrise, and remained abroad, frisking and barking, until about 2 o'clock, P. M., in the month of February, although the nights and mornings were cold—the thermometer sometimes indicating a temperature 10° or 12° below the freezing point, at sunrise. What may be their habits in higher latitudes, where the earth is for

long periods covered with deep snows, I have never had an opportunity to observe in winter.

CAPRIMULGUS, *Linn.*

4. C. CAROLINENSIS, *Briss.* Chuck-Wills-Widow.
A few were met with in New Mexico, in June and July.

CHORDEILES, *Swains.*

5. C. VIRGINIANUS, *Briss.* Night Hawk.
Numerous about Santa Fé, and generally throughout N. Mexico, during the summer months.

CHELIDON, *Boie.*

6. C. BICOLOR, *Vieill.* White Bellied Swallow.
Appeared at Santa Fé in May, and nested there, but was not numerous.

COTYLE, *Boie.*

7. C. RIPARIA, *Boie.* Bank Swallow.
Was more numerous than the last; nesting also near Santa Fé.

HIRUNDO, *Linn.*

8. H. RUFA, *Linn.* Barn Swallow.
This species was rather common at Santa Fé, nesting there.

SITTA, *Linn.*

9. S. CAROLINENSIS, *Briss.* Carolina or White Breasted Nuthatch.
A few were seen in the mountains west of Santa Fé; where they nested.

10. S. CANADENSIS, *Linn.* Canada, or Red Bellied Nuthatch,
Not more than three or four were seen in N. Mexico.

ANTHUS, *Briss.*

11. A. LUDOVICIANUS, *Licht.* Brown, or American Titlark.
This little wanderer I saw in N. Mexico, in small flocks, late in autumn.

SIALIA, *Swains.*

12. S. ARCTICA, *Swains.* Arctic Blue Bird.

Was first seen on the Rio Grande, about 60 miles below El Paso del Norte. Here they were abundant in the month of March, and were usually collected near the river bank, before sunset, in search of insects; when they proved themselves expert in the pursuit, darting from the tops of tall bushes to seize their prey upon the wing, and returning again, in the manner of true fly-catchers. In May, they made their appearance at Santa Fé—but were not numerous. Immediately on their arrival, they prepared their nests; one of these, built in the gravel bank of an *arroyo seco* or dry creek, I examined. It was composed entirely of dry grass; but it was well formed, having high walls of considerable thickness, and contained six eggs of a marine-blue color. The hole in which the nest was found, and which was in the side of a perpendicular bank, about five feet from the bottom, was four inches in diameter and ten in depth. Each brood, (generally seven or eight, including the old birds,) seemed to keep united during the summer. About the first of September, they began to move off.

MIMUS, *Briss.*

13. M. MONTANUS, *Bonap.* Mountain Mockingbird.

I found this gallant bird at times, though rarely, on the mountain sides in Northern New Mexico. I could not but admire his song, and his gay, dashing character, although I was constrained to admit the inferiority of his notes to those of his inimitable congener.

14. M. POLYGLOTTIS, *Bois.* The Mockingbird.

This bird was also rare in New Mexico, although it is abundant on the south western frontier of Texas.

CINCLUS, *Bechst.*

15. C. AMERICANUS, *Swains.* American Dipper.

One pair, only, of C. A. was seen. These were found on a very rocky and precipitous mountain stream, some twelve miles west of Santa Fé.

MILVULUS, *Swains.*

16. M. FORFICATUS, *Swains.* Swallow-tailed Fly-catcher.

This graceful bird was found in the south-western part of Texas, near Lavaca, in December.

TYRANNUS, *Vieill.*

17. T. VERTICALIS, *Say.* Arkansas Fly-catcher.

Was found in Northern New Mexico, in August and September, in small flocks.

TYRANNULA, *Swains.*

18. T. SAYA, *Swains.* Say's Fly-catcher.

Was met with occasionally in the mountains near Santa Fé.

CYANOCORAX, *Bois.*

20. C. STELLERI, *Gmel.* Steller's Jay.

Was rather common along the mountain sides, between Santa Fé and Las Vegas, in the months of August and September.

21. C. ULTRAMARINUS, *Bonap.* Ultramarine Jay.

This Jay, also, was seen in the same range with the preceding, during summer.

21. C. CASSINII, *Nobis.* Cassin's Jay.

Length 11 7-10ths inches; alar stretch 18 inches. Upper parts slate blue; front and crown darker, almost black; chin and throat greyish white; cheeks and sides of neck light blue; wings same as back, the quills dusky on the inner vanes; below slate color, lighter than above; iris dark brown; bill and feet black.

This Jay first made its appearance, about Santa Fé, in April, and remained there, in considerable numbers, during the summer. It nested and passed the midday in the highest mountains, coming down their sides upon the hills to feed, morning and evening. At these times they moved in large, loose flocks, alternately alighting to pick up an insect or a lizard, and again passing to the front; keeping up, the while, a regular cry, in a rather low plaintive tone, very different from the *Blue Jay*. In this way they generally passed some time before sunset amongst the scrubby white cedars of the hills, and then returned to the mountains to roost. The bird from which the above description was taken, had, when killed, just swallowed, entire, a "*horned frog*," or lizard, [*Agama Cornuta*] 2¼ inches in length.

Leona and San Pedro rivers, (western Texas,) and was more or less common on the whole route from Lavaca to Santa Fé. The song, I think, is superior to that of S. LUDOVICIANA. The only place at which I heard it was at Santa Fé, in the spring months.

SCOLECOPHAGUS, *Swains.*

28. S. FERUGINEUS, *Swains.* Rusty Blackbird.

Was rather common along the Rio Grande to Santa Fé.

QUISCALUS, *Vieill.*

29. Q. MAJOR, *Vieill.* Boat-tailed Blackbird.

Was seen as far north as San Elizario, on the Rio Grande, lat 31 deg. 40 min. I am induced to think it a rare visitor even here. I saw them in great numbers, on a former occasion, near Matamoras, where they nested in large congregations.

MOLOTHRUS, *Swains.*

30. M. PECORIS, *Swains.* Cow Blackbird.

Seen in various parts of N. Mexico; not numerous.

AGELAIUS, *Vieill.*

31. A. XANTHOCEPHALUS, *Bonap.* Yellow-headed Blackbird.

32. A. PHŒNICEUS, *Vieill.* Red-winged Blackbird.

Were found only occasionally in N. Mexico; more common in Southern Texas.

CALAMOSPIZA, *Bonap.*

33. C. BICOLOR *Nutt.* Prairie Reedbird.

I first met with this bird on the Rio Grande, between Santa Fé and Cañada, in September, when several small flocks were seen. I again found them on the Rio Puerco, in October. Their note and flight reminded me at once of our *D. Oryzivora*; but I found their flesh very inferior in delicacy and flavor to the latter.

FRINGILLA, *Linn.*

34. F. OREGONA, *Towns.* Oregon Snow Bird.

Common near Santa Fé, in winter.

PIPILO, *Vieill.*

35. P. ARCTICUS, *Swains.* Arctic Ground Finch.

I found perhaps half a dozen individuals of this species about Santa Fé, in May.

CHONDESTES, *Swains.*

36. C. GRAMMACA, Say. Lark Finch.

Was found, in moderate numbers, on the plains near Santa Fé, in May and June, when its pleasing song and gay manners attracted attention.

OTOCORIS, *Bonap.*

37. O. ALPESTRIS, *Bonap.* Shore Lark.

Appeared about Santa Fé in April, and became quite numerous in that region in May. Was scarce in the autumn.

38. O. ?OCCIDENTALIS.* Probably the young of a species not heretofore described.

The bird from which the following description was taken, was shot near Santa Fé, in the month of July. It had, in some respects, the appearance of an adult bird, or at least a bird of the preceding year, although its general markings, to judge from analogy, would indicate a young bird. Yet, judging from the firmness of its bones, appearance of its bill, and a slight abrasion of the ends of the tail feathers, I did not, at the time, take it to be a young bird.

Its length (when killed) was 7 7-10ths inches; alar stretch 11 inches; wing, from flexure, 3 7-10ths; above, light brown, each feather being dark dusky near the tip, the extreme tip white—giving the appearance of a mixture of light and dark brown, thickly speckled with white; in this respect resembling the young of the *Shore Lark*; the greater and lesser wing coverts broadly edged with yellowish white, and tipped with pure white, forming two distinct bars, most apparent when the wing is extended; the second primary longest, the third shorter than the first, the outer vane of the latter white; remaining wing feathers edged with whitish, broadest on the tertials; tail of twelve feathers, even, the two middle ones light brown, edged with whitish, the remainder dark dusky, the two exterior ones being white on the outer vanes; all the underparts pale brownish white, most clear at the lower extreme; bill slender and slightly curved, of a horn color above, and lighter below; eyebrows, extending back of the eyes, whitish: irides dark hazel; legs and feet nearly black; hind nail longer than the toe.

The difference between this bird and the young of the Shore Lark, is in the different dimensions, and in the whole of the under parts being whitish; but more particularly in the length and shape of the bill, which is longer, more slender, and rather more curved above than that of the Shore Lark, either young or old.

It is believed to be of a species of the genus Otocoris, hitherto unknown to science.

Carpodacus, *Kaup.*

[Erythrospiza, *Bonap.*]

39. C. frontalis, *Say*. Crimson Fronted Finch.

I found this charming little finch abundant at Santa Fé, where they commenced nesting in March, although the weather was still wintry, and so continued, with frequent snow storms, for more than a month. Notwithstanding this, the song of the male failed not to cheer his mate, during incubation, with the liveliest melody. The notes often reminded me of the soft trill of the house wren, and as often of the clear warble of the canary. The males of the last year, though mated and apparently equally happy and quite as assiduous as their seniors, were not yet in full plumage, having little or nothing of the red colors that mark the adult birds.

The nests, which were stuck into every cranny about the eves and porticos of the houses throughout town, were variously composed, of dry grass, fine roots, horse-hair, long pieces of cotton twine, or strips of old calico; in fine, of countless odds and ends, that were picked up about the yards; these were curiously and firmly interwoven, so as to make a warm and comfortable abode for the new comers. Eggs, four or five, pale blue, slightly marked on the larger end. The young were able to fly by the middle or latter part of April. A second brood, and, in some cases, I believe, a third was raised during the summer; as not a few

of them continued to incubate until some time in the month of August. Before the latter part of September, however, nearly all of them had disappeared from about Santa Fé.

40. C. OBSCURUS, *Nobis*. Dusky Finch.

Length (when killed) 6 inches; wing 2 8-10ths inches; front, crown and back, dark brownish ash, striped with dark dusky brown; wings and tail dusky brown, each feather edged with brownish white; the greater and lesser wing coverts more broadly edged with the same, making two faint bars on the wing; all the under parts dull white, striped with dark dusky brown; tail slightly forked; bill slightly curved, upper mandible dusky, lower mandible paler, inclining to yellow; iris hazel; feet dark dusky. This was the female.

The male, though with lighter colors, did not appear to differ greatly from the female; nor could I, at a short distance, distinguish the usual tinge of red that marks this genus.

The song of the male consists of a few pleasing notes, without the volume or compass of voice of the preceding species. I was much disappointed in not being able to secure the male. I saw but one pair; and after following them for some time and observing their habits; having them in line, I shot the female, from my horse, with a pistol, whereupon the male took wing, and eluded all further search. The same ground was repeatedly hunted afterwards, but without success. This was near Santa Fé.

COLAPTES, *Swains.*

41. C. COLLARIS, *Vig.* Red-shafted Woodpecker.

Appeared in N. Mexico in September.

GEOCOCCYX, *Wagl.*

42. G. VIATICUS, *Wagler.* Paisano.

I met with this bird, occasionally, throughout western Texas and New Mexico.

ECTOPISTES, *Swains.*

43. E. CAROLINENSIS, *Linn.* Turtle Dove.

This species is the only one of the family that I met with on this expedition. It was very common in N. Mexico during the summer. On the Rio Grande further South, I found on a former occasion, between Matamoras and Camargo, five species, viz: Z. *Amabilis*, Z. *Leucoptera*, C. *Passerina*, E. *Carolinensis*, and C. *Solitaria*. Most of them seem to confine themselves to the warmer latitudes.

ORTYX, *Steph.*

44. O. VIRGINIANA, *Linn.* Common Quail, or American Partridge.

Of four species of *Odontophorinæ* found in Western Texas, the *habitat* of each of which is confined to an almost distinct locality or region, this was the first met with on this occasion. It was extremely numerous about San Antonio; and thence, beyond the settlements to the San Pedro, or Devil's river, (a distance of 170 miles, westwardly, by the route travelled to the Rio Grande,) it was more or less common. This region, it is worthy of note, is by far the best on the whole route to El Paso; (a distance by the trail of 673 m.) That is to say, it is a better watered country, has a richer soil, and produces spontaneously a greater variety

of grasses and other plants, whose seeds afford abundant and nutritious food to all kinds of game. I discovered no difference in the appearance or habits of this bird, here, from those of the common quail of the Atlantic States.

CYRTONYX, *Gould.*

45. C. MASSENA, *Gould.* Massena Quail, or Partridge.

This species was not seen before crossing the San Pedro: but it was not long until it made its appearance in the waste and rocky region into which we then entered. And from that time until we reached the Rio Pecos, a distance of 140 m., (westwardly by the route travelled,) it was frequently seen, though I should not say it was very common. This region is a desert of great length from North to South, our trail crossing it nearly at right angles. The general face of the country is level, and consists of either a crumbling argillaceous limestone, or a coarse grey sand, producing nothing but a sparse growth of sandplants. Water is found only at long intervals; and except at these points there is but little cover for game, and apparently less food,—the principal growth being *Cacti*—of which the most common is *C. arborescens;* yet here, amongst projecting rocks, or on the borders of dry gullies, or in loose scrub, I found C. Massena in all the beauty of his rich and varied plumage.

The habits of this species are different from those of any other species of Partridge that I have met with. They were in covies of from 8 to 12, and appeared to be extremely simple, and affectionate in disposition. In feeding, they separated but little, keeping up a social *cluck* all the time. They were so gentle as to evince little or no alarm on the approach of man; scarcely moving out of his way as he passed; and only running off or flying a few yards when perhaps half their numbers were laid low by a shot. This inclined me to think they might with little difficulty be domesticated, although I found them, *here*, in a boundless barren waste, and *nowhere* near the habitation of man. This trait of gentleness is the very opposite of those strikingly manifested by the *scaly partridge*, which I always observed to be, though found perchance in grounds as little frequented as these, remarkably vigilant, shy, and difficult to approach. The call or signal note of this species is peculiar. I never saw them after crossing the Pecos river.

LOPHORTYX, *Bonap.*

46. L. GAMBELII, *Nutt.* Gambel's Quail, or Partridge.

After losing sight of the last species, I did not fall in with this until we reached the Limpia river, about 100 m. west of the Pecos. This beautiful bird, whose habits in some respects bear more resemblance to the common partridge, like that, seems to prefer a more genial and hospitable region. In this part of the country, the Mesquite tree (*A. glandulosa*) is more or less common; and the Mesquite grass, and other plants bearing nutritious seeds, are abundant. Here, this partridge increases rapidly in numbers, and becomes very fat. And, as I afterwards ascertained, is much disposed to seek the farms, if any be within reach, and to cultivate the acquaintance of man. About the rancho of Mr. White, near El Paso, I found them very numerous; and here in gangs of 50, or 100, they resort, morning and evening, to the barn-yard, and feed around the grain stacks in company with the poultry, where they receive their portion, as it is scattered among them by the hand of the owner.

I found them distributed through the country from the Limpia to the Rio

Grande, a range from east to west exceeding 100 m., and along the Rio Grande from Eagle Spring Pass to Don Ana, a distance of 120 m. North of this, I did not see them. I was not among them during the season of incubation.

CALLIPEPLA, *Wagler.*

47. C. SQUAMMATA, *Wagler.* Scaly Quail, or Partridge.

This species I have met with, at different times, throughout a more extended region than either of the last two, viz: from Camargo, on the lower Rio Grande, to Santa Fé. On the present occasion, they were more numerous between the latter point and Don Ana than elsewhere. They seem to prefer the vicinity of the greater water courses to interior tracts. They are much more wild than either of the preceding, and being extremely watchful and swift of foot, they elude pursuit with surprising skill, scarcely resorting to flight, even in comparatively open, sandy ground. They do not approach the settlements as much as the last. For the table, all these species, however, possess in a high degree the requisites of plump muscle and delicate flavour. Massena is perhaps the best.

TETRAO, *Linn.*

48. T. CUPIDO, (*L.*) *Wils.* Pinnated Grouse.

Were found in Texas, between Lavaca, Victoria, and Goliad.

49. T. OBSCURUS, *Bonap.* Dusky Grouse.

A few flocks were seen in the mountains from Santa Fé to Taos. In September they were feeding on the berries of the White Cedar.

[I should mention that the Wild Turkey (*M. G.*) was found on almost every stream margined with timber, throughout the whole of the country traversed. On the Nueces, Leona, and Turkey Creek, they were in great numbers.]

CHARADRIUS, *Linn.*

50. C. VOCIFERUS, *Linn.* Kildeer plover.

This bird I found occasionally on the whole route.

HIMANTOPUS, *Brisa.*

51. H. NIGRICOLLIS, *Vieill.* Black-necked Stilt.

Occasional flocks were seen on the Rio Grande, as high up as San Elizario.

TRINGA, *Linn.*

52. T. HIMANTOPUS, *Bonap.* Long legged Sand piper.

I found a few birds of this species near San Elizario, in October. Their favorite range, however, does not extend far from the Gulf. On reference to my notes, I find they were abundant about Corpus Christi, from September to March, 1845-6; at the termination of which period I left them still there. They were exceedingly numerous about Matamoras, during the following winter, and were served at the tables of the Hotels and Restaurants very prodigally, as well as the *Chiac-chia-lacca.* The Sandpiper was at this season very fat, and was considered, by many, little inferior to the Snipe, (S. Wilsonii) for which it often passed.

[I might remark, in passing, that the *Chiac-chia-lacca,* as it is called by the Mexicans—a name doubtlessly derived from its peculiar cry, which strikingly resembles a repetition of those syllables—is also a capital bird for the table. It is the *Penelope Poliocephala* of *Wagler;* and since the extension of our domain to the Rio Grande, is now a bird of the United States. It is very numerous on the

lower river, where the forests are made to echo with its shrill cry—not unlike that of the Guinea fowl. It is often domesticated by the Mexicans, and goes at large about the grounds.]

GRUS, *Linn.*

53. G. AMERICANA, *Temm.* Whooping Crane.

On the whole route I met with but one pair of this large crane. This was at the *Arroyo Hondo*, in Texas, above San Antonio, in the month of November. I find in my notes taken at Corpus Christi in 1845, that they were seen there occasionally in pairs, or in parties of 3 or 4, but never in large flocks, nor in company with *G. Canadensis*, although the latter were innumerable. Here, this bird was generally observed feeding at the water's edge; mostly on the river banks or around ponds of fresh water, but also quite frequently on the sandy points that extended into the salt water of the Bay. Whereas, the Brown Crane frequented mostly the low prairies at some distance from the Bay or River.

54. G. CANADENSIS, *Temm.* Brown Crane.

This Crane I found on the Rio Grande from Santa Fé to El Paso, in October; but more particularly between Albuquerque and Sorocco, where, for 50 miles, the land appeared to be covered with them. They filled the cornfields and alighted close to the houses, never being disturbed by the gun.

SCOLOPAX, *Linn.*

55. S. WILSONII, *Temm.* Common Snipe.

This bird I found almost every where from the Gulf to Santa Fé, where a patch of wet ground was encountered, but nowhere were they numerous. In 1845, numbers nested and raised their broods near Corpus Christi.

NUMENIUS, *Briss.*

56. N. BOREALIS, *Lath.* Esquimaux Curlew.

A few were seen on the plains east of the Rio Grande.

57. N. LONGIROSTRIS, *Wilson.* Long billed Curlew.

These were seen much more frequently than the last, and were common on the plains near the Apache mountains.

CYGNOPSIS, Brandt.

58. C. CANADENSIS, Brandt. Canada Goose.

I did not meet the Canada Goose until I reached the Rio Grande, which was at a point 60 miles below El Paso; thence I found them tolerably numerous until I left the river near Santa Fé.

CHEN, *Boie.*

59. C. HYPERBOREA, Boie. Snow Goose.

Small flocks of this Goose were found occasionally in company with the last.

BERNICLA, *Steph.*

60. B. BRENTA, *Steph.* Brant or Brent Goose.

A few only were seen on the Rio Grande.

ANSER, *Briss.*

61. A. ERYTHROPUS, *Linn.* White fronted Goose.

This Goose was more common than the last; they were, as I have generally

found them elsewhere, less shy than those of any other species. They seek out little pools or mud puddles near the river, to which they resort to feed more habitually than their congeners; and here they are without difficulty approached and shot.

CYGNUS, *Linn.*

62. C. BUCCINATOR, *Rich.* Trumpeter Swan.

In Texas, I at times saw flocks of this swan at great heights, and heard their wild, melancholy note, as they leisurely yet swiftly winged their way through the upper air.

ANAS, *Linn.*

The following species I found every where that water was found, in the plains or among mountains, between San Antonio and the Rio Grande—a distance, as the crow flies, of over 400 miles. In the midst of extensive plains, I scarcely ever approached a "*water-hole*" (or rain water pond) in which I did not find small flocks of one or more species.

63. A. BOSCHAS, *Linn.* Mallard Duck.
64. A. STREPERA, *Linn.* Gadwell Duck.
65. A. AMERICANA, *Gmel.* Widgeon or Baldpate.
66. A. CAROLINENSIS, *Steph.* Green winged Teal.
67. A. DISCORS, *Linn.* Blue winged Teal.
68. A. CLYPEATA, *Linn.* Shoveller Duck.

The last, however, I saw only at San Elizario; where also, and generally along the Rio Grande and Rio Puerco, and their mountain branches, nearly to the foot of the *Sierra de los Mimbres*, I found most of the others—which shows their extensive range.

The Committee on Dr. Leidy's "Additional Contributions to Helminthology," reported in favor of publication in the Proceedings.

Helminthological Contributions.—No. 2.

By JOSEPH LEIDY, M. D.

ASPIDAGASTER, *Baer.*

ASPIDAGASTER CONCHICOLA. *Baer*, Act. Acad. Nat. Cur., T. 13, p. 527; *Dujardin*, Hist. Nat. des Helm., p. 324; *Diesing*, Syst. Helm., Vol. 1, p. 414.

Body oval, posteriorly obtusely rounded; color yellowish white. Neck translucent, cylindric; mouth terminal, large, surrounded by a thick, contractile lip. Lateral margin of ventral disk crenate.

Measurements at rest.—Length ½ to 4-5ths of a line by ¼ to ⅓ of a line broad. Neck ⅓ length of body, by 1-9th line in breadth. Œsophageal bulb longitudinally oval, 1-166th in. long by 1-285th in. broad. Ovum oval, 1-333d to 1-285th in. long, by 1-666th to 1-500th in. broad.

Measurements in action.—Length 1 to 1½ lines by 1-5th to ¼ line broad. Neck

may elongate to one-half length of body, by 1-200th in breadth. Lip may expand into a circular disk, or be elongated into a triangular rostrum.

Hab.—Found in the pericardial cavity of Unio purpureus, U. nasutus, U. radiatus, U. carinosus and Anadonta marginata.

PLANARIA, *Müller.*

2. PLANARIA MACULATA. *Leidy*, Proc. Acad. Nat. Sci., Vol. 3, p. 251; *Diesing*, Syst. Helm., Vol. 1, p. 205.

Length from 2½ to 6 lines; breadth ½ to 1 line.

Hab.—Everywhere in ditches near Philadelphia. (Found in great abundance between the outer decaying petioles and inner living ones of the leaves of the Arum virginicum, growing in profusion in ditches below the city.)

3. PLANARIA TRUNCATA, *n. s.* Body sublinear; posteriorly obtusely rounded; anteriorly truncated, with the angles slightly prominent laterally. Blackish white, translucent at margin, with a blackish streak down the back. Eyes two, reniform, 1-400th in. long by 1-500th in. broad; 1-200th in. apart. Œsophagus simple, cylindrical, ½ line long.

Length 3 to 5 lines; breadth ½ to ¾ of a line.

Hab.—Found in a running rivulet in the vicinity of Newark, Delaware.

4. PLANARIA (TYPHLOLEPTA ? *Oersted,*) FULIGINOSUS, *n. s.* Body oval, dilated; inferiorly flat; superiorly moderately convex, fuliginous. Eyes none: in their ordinary position a slightly greater accumulation of black pigment upon the upper surface. Mouth inferior, a little posterior to the centre; œsophagus simple, cylindrical, white, 1 line long by ½ line broad.

Length 5 lines, breadth 4 lines.

Hab.—Rancocas Creek, near Pemberton, New Jersey.

ANGUILLULA, *Oken.*

5. ANGUILLULA LONGA, *n. s.* Body cylindrical, translucent, colorless. Mouth round, buccal capsule inverted campanulate; œsophagus and intestine cylindrical, equal in diameter, the former 1-25th in. long.

Female, 2 to 3 lines long; anteriorly 1-333d in. broad; middle 1-285th in. Tail narrow, acute, 1-111th to 1-75th in. long from anus.

Male, 1½ to 2 lines long; posteriorly dilated, obtusely rounded, curved, with three slight tubercular thickenings of the integument ventrally; 1-285th in. broad: at middle 1-370th in. broad. Penis a curved spiculum, 1-280th in. long.

Hab.—Found in very great abundance, wriggling above the surface of soft mud, in stagnant ditches in the neighborhood of Philadelphia.

6. ANGUILLULA LONGICAUDA, *n. s.* ♀ Body cylindrical, colorless, hyaline; anteriorly obtusely rounded; posteriorly attenuated, with a long, delicate, flexible, subulate tail. Mouth without cirri; œsophagus cylindrical, often with the appearance of a globular bulb at its lower end; intestine cylindrical; anus indistinct. Generative apparatus ?

Length of largest 1-40th in.; breadth 1-1000th in.; length of tail 1-200th in. Smallest: length 1-160th in.; breadth 1-2000th in.; length of tail 1-800th in. In an individual 1-100th long, the œsophagus measured 1-570th in. long.

Hab.—Found with Lyngbya muralis and other confervæ about gutters and water spouts in the city of Philadelphia. This species is very active in its

movements, and appears to have the power of fixing itself by the end of the tail to surrounding objects.

7. ANGUILLULA FOSSULARIS. ♀ Body cylindrical, anteriorly narrowed, truncated. Mouth round, surrounded by a prominent circular lip; buccal apparatus none; pharynx short; œsophagus long, clavate, or fusiform, slightly tortuous; intestine cylindrical, brown in color; rectum distinct, cylindrical, colorless. Tail acute. Ovary double. Generative aperture anterior to the middle.

Length 2 to 2½ lines; breadth 1-250th in. Tail 1-50th in. long from anus. Œsophagus 1-28th in. long; 1-1333d in. broad at commencement; 1-400th in. at termination. Intestine 1-475th in. broad. Rectum 1-75th in. long.

Hab.—Stagnant ponds and rain-puddles in the suburbs of Philadelphia.

ACESTUS, *Leidy*.

Body vermiform. Podal spines in 4 rows; anteriorly 3 to 5 in each fasciculus, posteriorly in pairs; long sigmoid, bifurcated at extremity. Upper lip conoidal, inarticulate. Annuli under 100. Blood red. Eyes, girdle and muscular stomach none.

8. ACESTUS SPIRALIS, *n. s.* Body cylindrical, posteriorly attenuated, obtusely terminated; color reddish; integument thick. Annuli 80; anterior five with 5 podal spines in each fasciculus, afterwards 3 in each, and posteriorly in pairs; furnished with a shoulder, and a bifurcate unguiform extremity. Œsophagus passing the sixth annulus. Intestine simple, cylindrical, capacious. Blood vessels large, tortuous, without distinct cœca, filled with red blood.

Length 1 inch; breadth anteriorly 1-12th line; at middle 1-10th line; posteriorly 1-16th line. Lip 1-280th in. long from mouth. Podal spines 1-400th in. long.

Hab.—In the soft mud at the bottom of stagnant ditches and ponds in the neighborhood of Philadelphia.

Remark.—When drawn out of its concealment in the mud, it rolls the posterior ⅓ of the body into a spiral.

9. ACESTUS HYALINUS, *n. s.* Body cylindrical, posteriorly obtuse, hyaline. Annuli 24 to 34. Podal spines anteriorly 3 to 4 in each fasciculus, posteriorly in pairs, swollen slightly one-third their length from the extremity, which is unguiform and bifurcated. Blood faintly red.

Length 1½ to 3 lines; breadth anteriorly 1-333d in.; middle 1-280th in.; posteriorly 1-400th in. Lip 1-500th in. long. Podal spines 1-550th in. long.

Hab.—Found with the preceding, its anterior half buried in the mud and the tail rapidly vibrating like Sænuris or Strephuris.

DERO, *Oken*.

Body vermiform. Podal spines in two rows. Lateral setæ. Caudal appendages. Blood reddish. Proboscis and eyes none.

10. DERO LIMOSA, *n. s.* Body cylindroid, faintly reddish, translucent. 8, 16, 26 to 34 setigerous annulations when the body is in from 1 to 4 divisions. Five anterior annuli without setæ. Two rows of podal spines; 5 to 6 in each fasciculus anteriorly; 3 to 4 posteriorly; long sigmoid, bifurcate at extremity. Setæ single, in one row upon each side. Caudal annulation, expanded, truncated,

furnished upon each side of the anal aperture with four unequal, compressed, oval, curved, contractile, vibrillated appendages. Upper lip triangular. Œsophagus passing to sixth annulation.

Length 2 to 6 lines; breadth anteriorly 1-10th line; middle 1-8th line; caudal annulation expanded 1-5th line. Lip 1-250th in. long. Setæ 1-666th in. to 1-133d in. long.

Hab.—Living in tubes of mud or decayed vegetable particles, upon the bottom of stagnant ponds and ditches, in the neighborhood of Philadelphia.

It is usually observed with the posterior half or two-thirds of its body projecting nearly vertically from its tube, with the caudal, contractile appendages expanded. Upon any disturbance it rapidly retreats within its tube. A sessile species of vorticella is frequently found attached to the posterior part of the body.

At first sight there appears to be only three appendages each side of the anus, but closer examination proves the existence of a fourth, small and not so distinct.

Dr. Leidy, on behalf of the Curators, stated that he desired to correct an error which he had noticed in a report of some remarks by Mr. Squier at a meeting of the American Ethnographical Society, in which Mr. S. stated that Dr. Morton's collection of Crania had been presented to the Academy. Dr. Leidy had ascertained from Dr. Morton's Executors, that the collection had not been presented to this Institution.

ELECTION OF MEMBERS.

Caspar Wistar, M. D., and Mr. Charles E. Smith, of Philadelphia, were elected *Members* of the Academy.

June 17th.

Twenty-two species of marine Algæ. Presented by Mr. John Hooper, of Brooklyn, L. I.

Laminated Peroxide of Iron, from the red sandstone of Connecticut. From Dr. R. Bridges and S. Powel.

A Microscope by Oberhaueser. Deposited by Dr. J. K. Mitchell, on the usual condition.

DONATIONS TO LIBRARY

IN MAY AND JUNE, 1851.

May 6th.

Human Physiology. By Robley Dunglison, M. D. 7th ed. 2 vols. 8vo. From the Author.

Novorum Actorum Acad. Cæsar. Leopold-Carolinæ Nat. Curiosorum, Vol. 22, pars altera. 4to. From the Academy.

American Journal of Science and Arts, May, 1851. From the Editors.

A proposal to establish and maintain one uniform system of Weights, Measures and Coins. By P. A. Browne. From the Author.

Archiv für Naturgeschichte. Herausg. von Dr. F. H. Troschel. Nos. 2, 3. 1850. From Dr. Wilson.

The London Athenæum for March, 1851. From the same.

The following were presented by Mr. Edward Wilson on the usual condition:—

Des Races Humaines. Par P. P. Bosc. 4to.

Nuove osservazione intorno alle Cocciniglie ed ai Loro Pretesi Maschi. Del Dott. F. G. Costa.

J. F. Blumenbachii decas collectionis suæ Craniorum diversarum gentium illustrata. 4to.

Dissert. med. inaug. de Tænia. Auctore G. Andreæ.

Dissert. physico-med. inaug. de Vermibus intestinalibus hominum. Auctore G. Van Doeveren.

Mittheilungen aus den Verhandlungen des Gesell. naturforsch. Freunde zu Berlin 1836, '37, '38.

Bericht über die Verhandlungen der Naturforsch. Gesell. in Basel 1835, '36, '38.

Mittheilungen der Naturforsch. Gesell. in Bern 1843, '44, '45, '46, '47.

De l'education des Vers à soie, d'apres la methode du Comte Dandolo. Par M. Bonafous.

Description des Oursins fossiles du Department de l'Isere. Par M. Albin Gras.

Principes fondamentaux de Semeiologie. Par C. F. Rafinesque-Schmaltz.

Catalogus de livres comprenant la Bibliotheque de feu Mr. A. Goldfuss.

Synopsis of the contents of the British Museum. 57th ed. 12mo.

Cuvier. Histoire de ses travaux. Par P. Flourens. 2d ed. 12mo.

Observationes quædam Helminthologicæ. Auctore J. H. Eber.

Entwicklung des Hummereies von dem ersten Veränderungen im Dotter an bis zur Reife des Embryo. Von Dr. M. P. Erdl.

Useful Knowledge: or a familiar account of the various productions of Nature. By Rev. W. Bingley. 3 vols. 8vo. 4th ed.

Memoire sur les Polypiers de mer Par J. E. Roques de Maumont. 8vo.

Recherches interessantes sur l'origin de la formation, &c., de Vers a Tuyan qui infestant des Vaisseaux. Par P. Massuet, M. D. 12mo.

Traité d'Insectologie. Par M. Charles Bonnet. 2 vols. 12mo.

Catalogue synonymique des Coleopteres d'Europe et d'Algerie. Par J. Gaubel. 8vo.

Du Tænia, ou ver solitaire, &c. &c. Par M. Mérat. 8vo.

Species des Mammiferes bimanes et quadrumanes suivi d'un memoire sur les Orycteropes. Par M. R-P. Lesson. 8vo.

Traite pratique du Microscope. Par le Dr. L. Maudl. 8vo.

De la generation des Vers dans le corps de l'homme. 3me. ed. Par M. Andry. 2 vols. 8vo.

Journal für die Liebhaber des Steinruchs und der Konchyliologie. Von J. S. Schræter. 6 vols. 8vo.

Neue Litteratur und Beytrage zur kenntniss der Naturgeschichte, vorzuglich der Conchylien und Fossilien. Von J. S. Schræter. 4 vols. 8vo.

Statuten der Basler Naturforschenden Gesellschaft.

Schwedisches Museum. Herausgeg. von F. B. und E. H. Gronig. 2 vols. 8vo.

Nachtrag zu der Conchylien im Fürstlichen Cabinette zu Rudolstadt (C. L. Kammerer.) 8vo.

The Homologies of the Human Skeleton. By Holmes Coote. 8vo.

Species des Coléoptéres trimères securipalpes. Par M. E. Mulsant. Parts 1 and 2.

Die Dendrolithen, in Beziehung auf ihren innern Bau. Von B. Cotta. 4to.

Dissert. med. inaug. de Hirudinis historia naturali et usu medico. Auctore Albertus Van Calcar. 4to.

Description de quelques poissons fossiles du Mont Liban. Par F. J. Pictet. 4to.

Tableau synoptique des Lépidoptéres d'Europe. Par MM. de Villiers et Guenée. 4to.

Études sur les Scincoides. Par J. T. Cocteau.

Collection de Mammiferes du Museum d'histoire naturelle. Par Huet fils et J. B. Huet jeune. 4to.

D. Carl Gustav Carus von den Aussern Lebensbedingungen der Weiss-und Kaltblütigen Thiere. 4to.

Choix de memoires sur divers objets d'histoire naturelle. Par MM. Lamarck, Brugiere, Olivier, Hauy et Pelletier. 4to.

Des Hernn Dezallier von Argenville Conchyliologie. Folio.

Vermium terrestrium et fluviatilium seu animalium infusoriorum, helminthicorum et testaceorum non marinorum succincta historia. Auctore O. F. Müller. 4to.

Historia natural y medica de il principado de Asturias. Obra posthuma que escribio el Doct. D. Gaspar Casal. 4to.

An attempt to develope the law of Storms, &c. &c. 3d ed. By Lieut. Col. W. Reid. 8vo.

The progress of the development of the law of Storms and of the variable Winds, &c. By Col. Reid. 8vo.

Die Forst Insecten oder Abbildung und Beschreibung der in den Waldern Preussens und der Nachbarstaaten als schädlich oder nützlich bekannt gewordenen Insecten. Heraus. von J. T. C. Ratzeburg. 4 pts. 4to.

Die Ichneumonen der Forstinsecten in forstlicher und Entomologischer Beziehung ein Anhang zur Abbil. und Beschr. der Forstinsecten. Von J. T. C. Ratzeburg. 2 pts. 4to.

Description des fossiles des Terraines Miocene de l'Italie Septentrionale. Par G. Michelotti. 4to.

Histoire naturelle des plus rares curiositez de la Mer des Indes. Folio.

Museum Richterianum continens fossilia, animalia, vegetabilia Mar. Folio.

May 13th.

Proceedings of the Boston Natural History Society. Vol. 3, pp. 337—396. From the Society.

Introductory delivered at the Middlesex Hospital at the opening of the Session 1850—'51. By S. J. Goodfellow, M. D. From the Author.

The London Philosophical Journal. Vol. 1. Nos. 1—5. From the Editors.

Quarterly Journal of the Geological Society of London. No. 25. From the Society.

Gleanings from the Menagerie and Aviary at Knowsley Hall. Vol. 2. Folio. From the Editor, John Edward Gray.

Dr. Wilson presented the following on the usual conditions:—

Journal of the Franklin Institute for May, 1851.

Journal de Conchyliologie. An. 1850. No. 4.

Phycologia Britannica. By W. H. Harvey, M. D. No. 56.

History of British Mollusca and their Shells. By Prof. Forbes and S. Hanley. No. 36.

Annals and Magazine of Natural History. Vol. 7, new series. No. 39.

Conchologia Iconica. By Lovell Reeve. Part 95.

Illustrations of British Mycology. By Mrs. T. J. Hussey. 2d series, pt. 3.

The Genera of Diurnal Lepidoptera. By E. Doubleday: continued by J. O. Westwood. Part 41.

Philosophical Transactions of the Royal Society of London, Part 2. 1850. 4to.

Fauna Japonica. Aves No. 12; Pisces No. 16; Crustacea Nos. 6 and 7.

Journal of the Asiatic Society of Bengal. Vols. 1—5, and No. 79.

Actes de la Société Linnéene de Bordeaux. Tomes 5—15, et livs. 1—5, tome 16.

Voyage en Abyssinie: par une Commission Scientifique. Atlas, livs. 32; texte, Zoologie, Vol. 6. 8vo.

Voyage en Abyssinie. Par MM. Ferrett et Galinier. Planches livs. 17—20; texte, tome 2, pp. 401—540, tome 3, pp. 145—536.

Avium systema naturale.

Zoologia Danica. Auctore O. F. Müller. Vol. 4.

Testacea Utriusque Siciliæ, &c. &c. A J. X. Poli. Vol. 3. Folio.

Voyage en Crimee au Caucase, en Armenie, &c. Par Frederick Dubois. Atlas folio.

Proceedings of the Boston Society of Natural History. Vol. 3, pp. 337—396.

May 20th.

The London Athenæum for April, 1851. From Dr. Wilson.

The Charleston Medical and Surgical Journal, May, 1851. From the Editors.

Elements of Latin pronunciation for the use of Students in Languages, Law, &c. &c. By S. S. Haldeman 8vo. From the Author.

June 3d.

Proceedings of the American Association for the Advancement of Science. Fourth meeting, Aug., 1850. 8vo. From the Association.

Monography of the family Unionidæ of North America. By T. A. Conrad. No. 12. From Mrs. L. W. Say.

Rural Sports. By the Rev. W. B. Daniel. 3 vols. 8vo. Supplement to the same. 1 vol. 8vo. From Mr. George Ord.

Annales de la Société Nationale d'Agriculture, &c., de Lyon. 2e. serie, tomes 1 et 2. 8vo. From the Society.

Uranus. Synchronistisch geordnete Ephemeride aller Himmelserscheinungen des Jahres 1850, 2, 3, 4 Quartate, und des Jahres 1851, erstes semestre. Herausgeg. von der k. Univ. Sternwarte zu Breslau durch deren Director Dr. Boguslawski. From the Director.

June 10th.

Contributions to Conchology. By C. B. Adams. No. 9. From the Author.

Catalogue of the Land Shells which inhabit Jamaica. By C. B. Adams. From the Author.

Historical and Statistical information respecting the history, condition and prospects of the Indian Tribes of the United States. By H. S. Schoolcraft, LL. D. Part 1. 4to. From the United States Bureau of Indian Affairs.

The following were presented by Mr. Edward Wilson on the usual condition:—

Elementi di fisiologia e notomia comparativa di Guiseppi Jacopi. 3 vols. 8vo.

L'Homme. Essai Zoologique sur le genre humain. 3e. ed. Par Bory de St. Vincent. 2 vols. 12mo.

Essay on Instinct and its physical and moral relations. By Thomas Hancock, M. D. 8vo.

Handbuch der Entwickelungs geschichte des Menschen mit vergleichender Rücksicht der Entwickelung der Säugethiere und Vögel. Von Dr. G. Valentin. 8vo.

Gleanings in Natural History. By Edward Jesse, Esq. 3d edition. 8vo.

Game Birds and Wild Fowl; their friends and foes. By A. E. Knox. 8vo.

G. B. Schmeidlein's Einleitung in die nahere Kenntniss der Insektenlehre nach dem Linneischen system. 8vo.

A history of the British Fresh-water Algæ. By Arthur Hill Hassall. 2 vols. 8vo.

The Cabinet; or a Natural History of Quadrupeds, Birds, Fishes and Insects. 2 vols. 8vo.

Orthoptera Suecica. Disposita et descripta a J. W. Zetterstedt. 8vo.

Dei Fortpflanzung der Vögel, von F. Berge. Nos. 1—12.

The British Museum, historical and descriptive. 8vo.

Nomenclature of Coleopterous Insects in the collection of the British Museum. Parts 1—4; list of Hymenopterous do. in do. Parts 1 and 2.

Bijdragen tot de Natuurkundige Wetenschappen verzamed door H. C. Van Hall, W. Vrolik in G. J. Mulder. 7 vols. 8vo.

A system of Geography, popular and scientific. By James Bell. 6 vols. 8vo.

A treatise on a section of Strata from Newcastle-upon-Tyne to the Mountains of Cross Fell in Cumberland. By W. Forster. 2d edition.

C. N. Langii Historia lapidum figuratorum Helvetiæ ejusque vicinitæ. 4to.

Livre de Poste pour l'an 1845. 2e. tirage. 8vo.

Memoire sur les Iles Ponces, &c. Par M. Deodat de Dolomieu. 8vo.

General view of the Agriculture and Minerals of Derbyshire. By John Farey, Sr. 3 vols. 8vo.

The Gem of the Peak: or Matlock Bath and its vicinity, &c. By W. Adam. 8vo.

Historia Rivallensis. By the Rev. Wm. Eastwood. 8vo.

A general treatise on Cattle; the Ox, the Sheep and the Swine. By John Lawrence. 2d ed. 8vo.

The Orchard and Fruit Garden. By Charles McIntosh. 8vo.

The Flower Garden. By C. McIntosh. 8vo.

The Green House, Hot House and Stove. By C. McIntosh. 8vo.

Paseo por el Gabinete de Historia natural de Madrid. Par Don Juan Mieg. 8vo.

June 19th.

Fourth Annual Report of the Regents of the University of New York on the condition of the State Cabinet of Natural History. Jan. 11, 1851.

Sixty-fourth Annual Report of the Regents of the University of the State of New York. March 1, 1851.

The following were presented by Mr. Edward Wilson on the usual condition:—

Buffon's Natural History of the Globe and of Man; corrected and enlarged by John Wright. 4 vols. 12mo.

On the Economy of Machinery and Manufactures. By Charles Babbage, Esq. 3d ed. 12mo.

Johannis Lathami Systema Ornithologiæ sive index ornithologicus: editio nova ab E. Johanneau. 12mo.

The Steam-Engine familiarly explained and illustrated. By the Rev. Dionysius Lardner, LL. D. 5th ed. 8vo.

Journal of an Excursion to Antwerp during the siege of the citadel in Dec., 1832. By Capt. the Hon. C. S. W. 8vo.

A Commercial Dictionary of the names of the Coins, Weights and Measures in the world. By Joseph Palethorpe. 8vo.

The Animal World Displayed. By Frederick Watson. 8vo.

An Essay towards a natural history of the Herring. By Jas. S. Dodd. 8vo.

A new system of Geology. By William Cockburn, D. D. 8vo.

Memoires pour servir à l'hist. nat. et principalement á l'oryctographie de l'Italie et des pays adjacens. Par Albert Fortis. 2 vols. in one. 8vo.

Westminster Review. No. 69.

Nuove Recherche Zootomische sopra alcune specie di Conchiglie bivalvi del Cit. G. Mangili. 8vo.

Doutes ou observations de Mr. Klein. Traduit du Latin. 8vo.

Die lebenden Schnecken und Muscheln der umgegend Berlins beschrieben von J. P. E. Fr. Stein.

Recherches sur l'origine des peuples du Nord et de l'Occident de l'Europe. Par M. Darttey.

Proceedings of the Royal Society, No. 75, and index and title to Vol. 3.

Transactions of the Tyneside Naturalists' Field Club. Vol. 1. No. 5. 1850.

Sketch of the relation which exists between the three Kingdoms of Nature. By T. Williams.

Analysis of the Anthracite Coal from Bonville's Court Collieries, Pembrokeshire. By E. Frankland, Ph. D.

Insecta Saundersiana. Diptera part 1. By Francis Walker, Esq.

Description of a new species of Mole. (Talpa leucura, Blythe.) By E. Blythe, Esq.

Museum Septilianum. Pauli Mariæ Terzagi descriptum. 4to.

Statistics of the British Empire. By James McQueen, Esq. 8vo.

Storia naturale della Sicilia. Dell Ab. Francesco Ferrara. 4to.

A history of British Birds. By the Rev. F. O. Morris. Nos. 1—11. 8vo.

A history of the Fishes of Madeira. By Richard T. Lowe. Nos. 1—4. 8vo.

Transactions of the Microscopical Society of London. Vol. 2, and part 1, Vol. 3.

The Edinburgh Philosophical Journal, conducted by Dr. Brewster and Prof. Jamieson. Vols. 1—14. 8vo.

Traité de Geognosie de M. D'Aubuisson de Voisins. Par Amedée Burat. 3 vols. 8vo.

De la Houille. Par M. A. Burat. 8vo.

Memoires pour servir à l'histoire naturelle des Abeilles solitaires qui composent le genre Hariete. Par C. A. Walckenaer. 8vo.

Catalogue of the contents of Stowe House. 4to.

Di Corpi Marini che su, Monti si trovano: Let. critiche di Antonio Vallisneri. 4to.

Reisen in Britisch-Guiana in den Jahren 1840—1844. Von Richard Schomburgk. 3 vols. 8vo.

July 1*st*, 1851.

Vice-President BRIDGES in the Chair.

A letter was read from Thos. E. Yeateman, Esq., addressed to Geo. W. Carpenter, dated St. Louis, June 16, 1851, in reference to a portrait of the late Dr. Gerard Troost, which he was about transmitting to the Academy, as a donation from himself.

Also, a letter from Mr. William Haidinger, dated Vienna, 6th June, 1851, acknowledging the receipt of his notice of election as a Correspondent, and advising of the shipment of a present of books to the Academy from himself and M. Hauer, and also the Year-book, sent by the Royal Imperial Geological Institution of the Austrian Empire.

Dr. Leidy stated that the Cicada septendecim, was subject to a fungous disease. The posterior part of the abdomen he observed in several instances to be filled with a mass of oval spore-like bodies, embossed upon their surface, but becoming smooth from endosmosis when placed in water.

He also stated he had just received the dead larva of a lamellicorn insect, which was filled with the same fungus which sometimes attacks the mole cricket.

July 8*th*.

Vice-President BRIDGES in the Chair.

Letters were read from the Linnean Society of London, dated Nov. 7, 1850, and from Dr. F. H. Troschel, dated Bonn, 23d Jan., 1851, severally acknowledging the receipt of Nos. of the Proceedings of the Academy.

July 15*th*.

Vice-President BRIDGES in the Chair.

Mr. Vaux presented a paper, entitled "Descriptions of seventeen new species of Crinoidea, from the Subcarboniferous Limestone of Iowa and Illinois; by D. D. Owen, M. D., and B. F. Shumard, M.D., with a plate;" which, being intended for publication in the Journal, was referred to a committee, consisting of Dr. Leidy, Mr. I. Lea, and Dr. Ruschenberger.

A communication was read from the Imperial Society of Naturalists of Moscow, advising of the transmission of recent Nos. of the Bulletin of that Society.

July 29*th*.

Vice President BRIDGES in the Chair.

The Committee to which was referred the paper of Drs. D. D. Owen and B. F. Shumard, describing new species of Crinoidea from Iowa and Illinois, reported in favor of publication in the Journal.

On motion of Mr. Cassin, the privilege of endorsing tickets of admission to the Museum of the Academy, on Tuesdays and Fridays, and of issuing orders for the same purpose, was conferred on Mrs.

Mary E. Griffith, widow of Dr. R. E. Griffith, late Vice-President of the Academy; Mrs. Charlotte H. Townsend, widow of Dr. J. K. Townsend; Mrs. Catharine M. Gambel, widow of Dr. Wm. Gambel; and Mrs. Rebecca P. Morton, widow of Dr. Samuel George Morton, late President of the Academy; and the same were also privileged and invited to visit, at all times, the Museum and Library.

ELECTION.

M. Ambrose Tardieu, Prof. agregé a la faculte de Médecine de Paris, was elected a *Correspondent;* and Mr. Francis Lennig, of Philadelphia, was elected a *Member* of the Institution.

August 5th.

Vice President BRIDGES in the Chair.

Communications were read—

From the Librarian of the Smithsonian Institute, dated July 9th, 1851, addressed to the Librarian of the Academy, transmitting a copy of "Notices of public Libraries in the United States," published by the Institute.

From the Librarian of the British Museum, dated 18th July, 1851, acknowledging the receipt of late Nos. of the Proceedings.

From Dr. Joseph Hyrtl, dated Vienna, July 13th, 1851, acknowledging the receipt of his notice of election as a Corresponding Member.

Mr. Cassin asked attention of the members to the specimens of owls on the table.

These specimens comprise parent male and female, and three young birds, fully grown, which were reared in the woods at Powelton, the residence of John Hare Powel, Esq., at whose hospitable mansion the members of this Academy have been always made welcome.

The adult male exhibits the plumage of the mottled owl, or *Ephialtes nævia*, (*Gm.*), the adult female that of the red owl, or *E. asio*, (*Gm.*), and the young birds, sufficiently feathered to be able to fly readily, and which were ascertained, by dissection, to be two males and one female, are assuming the red plumage of their parent female, but having evidently been previously of a grayish white color, the entire plumage of the head and body above and below, with every feather marked with transverse lines of dark reddish gray, very distinct, and not seen in either of the adults.

The present specimens must, of course, be regarded as fully demonstrating the identity of the red and the mottled owl, and the only point now to be determined is, whether the female ever becomes mottled. This, however, Mr. C. regarded as very probably the case, as it is well established that rapacious birds of several species breed before they assume mature plumage.

Mr. Phillips made some remarks on a brilliant meteor, which he had observed in this city on the evening of the 3d inst., taking a direc-

tion apparently from West to East. The meteor was remarkable for its bright green color.

August 12*th.*

Vice-President WETHERILL in the Chair.

Dr. Leidy read a paper, entitled "Contributions to Helminthology, No. 3," which was referred to Drs. Bridges, Watson, and Hallowell.

Dr. Fisher, in adverting to a suggestion made at a late meeting of the Academy, that it was probable that many of the insects which are destructive to various trees of this country, were periodical in their recurrence, resembling, in this respect, the Cicada septendecim, remarked that six or seven years since the black caterpiller, or canker worm, had been very destructive to the Elm trees at New Haven, but that since then they were comparatively rare. On a visit to New Haven this summer he found them again very numerous, and doing great injury.

August 19*th.*

Vice President BRIDGES in the Chair.

Dr. Leidy presented a paper entitled "Conspectus Crustaceorum quæ in Orbis Terrarum circumnavigatione Carolo Wilkes e Classe Reipublicæ Fœderatæ duce lexit et descripsit J. D. Dana;" which, on motion was referred to the following Committee, Dr. Leidy, Dr. Bridges, and Dr. J. C. Fisher.

A letter was read from the "Akademie der Wissenschaften zu Wien," dated April 30th, 1851, in reference to the publications of that institution, announced this evening.

Dr. Fisher read a paper describing a new species of Cicada, named by him *C. Cassinii*, which being intended for publication in the Proceedings, was referred to Dr. Ruschenberger, Mr. C. E. Smith, and Dr. Zantzinger.

Mr. Cassin read a paper intended for publication in the Proceedings, "Notes on the Cicada Cassinii, and on C. septendecim. Referred to the above Committee.

Mr. Cassin read a paper entitled "Descriptions of Laniadæ," intended for publication in the Proceedings. Referred to Col. G. A. McCall, Mr. Harris, and Dr. Watson.

Dr. Leidy called the attention of the members, to several fragments of fossil ruminant ungulates, from Nebraska Territory.

One of these is the greater portion of a cranium, which, in its perfect condition, had been about 7 inches in length. For the examination of this he expressed his indebtedness to Dr. Hiram A. Prout, of St. Louis, who first pointed out the remains of a gigantic species of Palæotherium, from the same region in which the present fossil was obtained.

The teeth in the specimen are in a very much mutilated condition, but with

the aid of several fragments of upper maxillæ containing perfect teeth, from several other individuals of the same animal, received from the Smithsonian Institution, through Prof. Baird, the dentition in a great measure can be made out.

The teeth form nearly a continuous row, as in Anoplotherium, the only interval, being one of ¼ of an inch between the canine and the first premolar.

The canine is broken away, but judging from the fragment of the root, which is 4 lines in diameter antero-posteriorly, it was well developed. The anterior 3 premolars are too much broken to obtain any knowledge of their form. The fourth is like one-half of the true molars, and resembles closely, the corresponding tooth of Cervus.

The 3 true molars have exactly the same form, and very nearly the size as the 2 posterior superior molars, described in the Proceedings of this Academy, Vol. iv. p. 47, as characterizing a genus under the name of Merycoidodon. From the latter fact it might be readily supposed, that the fossil before us belonged to Merycoidodon, but a fragment of a face of a smaller animal now exhibited, received from Prof. Baird, contains the first and second true molars, mutilated, which have the same form as the corresponding teeth of the preceding fossil, but the fourth premolar has three cusps instead of two, like the former, indicating that we may have animals of different genera, with true molars identical in form.

Neither of these fossils Dr. L. suspected belonged to Merycoidodon, for in it the enamel of the teeth is rougher than in the former.

For the first he proposed the name of Oreodon.

The face of Oreodon has a remarkably cat-like expression, being depressed, and as broad between the malar bones, as it is long. The orbits are closed posteriorly as in the ruminants, by the junction of the post-orbital process of the os frontis with that of the malar bone, and present outward, forward, and upward, less in the latter two directions than in the cats, but more so than in the ruminants.

Just anterior to the orbit, is a remarkably large lachrymal depression or *lacunar*, relatively several times larger than that of Cervus virginianus.

The glenoid cavity is a broad, extensive, nearly flat surface, as in the ruminants.

The posterior portion of the head, relative to the face, is very narrow, and resembles in its form the fragment of a cranium described in Vol. v., of the Proceedings, p. 90, as characteristic of a genus under the name of Eucrotaphus.

The temporal fossæ are as large as in the carnivora, and lead to the impression, with other characters given of the head, that flesh probably formed part of the food of the animal.

The species Dr. L. named Oreodon priscum.

Measurements.

Length of line of 3 true molars,	19½	lines
" " 4 premolars,	20	"
Breadth of middle true molar,	8½	"
Diameter of orbit,	13	"
Breadth of face between malar bones, below the orbits,	48	"
Length from same point to root of canine tooth,	43	"
Breadth of cranium just anterior to the meat. aud. ext.,	26	"

Several fragments were then exhibited of a much smaller animal than the last, consisting of the greater part of the inferior and superior maxillæ, the latter containing the 4th premolar and the true molars perfect, having the same form as those of Oreodon priscum. To this species, the name of Oreodon gracile was given.

The posterior two inferior molars have the same form as the corresponding ones of Merycoidodon.

Measurements of O. gracile.

Line of inferior molars to root of canine, . . .	25½ lines.
Greatest breadth of inferior maxilla, below the posterior molar tooth, ...	16½ "
Line of superior molars, ...	26 "
" " true molars, ...	14 "
Greatest breadth of the middle superior true molar, .	5½ "

The fragment of a face before alluded to having the same form of the superior true molars as Oreodon, but differing from it in having 3 cusps to the fourth premolar, belonged to an animal very closely allied to the latter genus. It possesses the remarkably large lachrymal depression, which in this fossil appears to have been more hemispherical than in Oreodon. The depression being of such a striking character in Oreodon and in this genus, the name Cotylops was proposed for the latter. The only entire tooth preserved in the fragment of Cotylops is the third premolar, the crown of which is antero-posteriorly oblong, constricted in the middle so as to give in outline the form of 8. It has a single cusp, and presents an oval fossa about two lines long, postero-internally; and a heel or short tubercle antero-internally.

The species was named Cotylops speciosa.

Measurements.

Length of line of 1st and 2d superior true molars, . .	10 lines.
" " 2d, 3d, and 4th premolars, . . .	13 "
Antero-posterior diameter of 3rd premolar, . . .	4½ "
Greatest breadth of " "	2½ "
Diameter of lachrymal depression, ...	6½ "
Depth " " "	2½ "

The fragment of cranium for which was proposed the name Enerotaphus,* from its great resemblance to that of Oreodon, and its proportions, with the close alliance of Oreodon to Merycoidodon, Dr. L. suspected belonged to the latter genus.

August 26th.

Vice-President WETHERILL in the Chair.

The Committee on the following, by Dr. Leidy, reported in favor of its publication.

Helminthological Contributions.—No. 3.

BY JOSEPH LEIDY, M. D.

Gen. Nov. SYNPLECTA.†

Body nematoid, cylindroid, distinctly and coarsely annulated. Head composed of two trilobed portions, between which is the mouth. Œsophagus long, simple.

*Proc. Acad. Nat. Sci., Vol. v. p. 90. † σὺν together; πλέκω I twine.

Intestine narrow, simple. *Male*, attenuated at the extremities; posteriorly rolled into a spiral, and furnished ventrally with numerous tegumentary tubercles. Penis short, corneous, composed of two lateral portions. *Female* anteriorly attenuated; posteriorly terminating in a strong, thick, muscular acetabulum, with a posterior conoidal depression containing a single strong, recurved hook. Anus and generative apertures close together, just anterior to the muscular acetabulum. Ovum elliptical, elongated at the poles.

The female of this curious genus of nematoid entozoa attaches herself, by means of the posterior hook, to the mucous membrane of the intestinal canal of the animal it infests, while the male clings to the female by winding the posterior part of its body spirally around the posterior part of the latter, retaining itself in that position through the aid of the numerous tubercles upon its ventral surface, which closely apply themselves to the part of contact in the female.

1. SYNPLECTA PENDULA, *n. s.*

Body faintly reddish-white, cylindroid. Annulations with from 12 to 18 transverse muscular striæ. Lobes of the head nearly equal. Œsophagus very long, cylindroid, slightly dilated inferiorly. Intestine narrow, cylindrical.

Male. Length 4 to 5 lines; breadth 1-6th of a line. Posterior fourth of body forming three turns of a spiral, furnished ventrally with about 20 longitudinal rows of tegumentary tubercles, or small quadrilateral plates 1-1600th in. long, by 1-2666th in. broad, extending as far back as the anus. Tail curved, conoidal, 1-60th in. long from the anus, furnished ventrally with 7 or 8 pairs of minute conical tubercles. Œsophagus 1-5th line long, 1-333d in. broad; intestine 1-400th in. broad. Penis 1-200th in. long, conoidal, obtuse, bent at free extremity, composed of two lateral halves.

Female. 6 to 11 lines long, 1-5th to 1-4th line broad. Posterior extremity bent, dilated, terminating in a thick, oval, strongly muscular receptacle or acetabulum, truncated posteriorly and excavated into a deep conical cavity, containing a strong hook, with the point directed forward, 1-200th in. long, with a base 1-400th in. broad. Œsophagus, in an individual 8½ lines long, 1 line long by 1-666th in. broad at commencement, 1-333d in. at termination. Intestine 1-450th in. broad. Ovum 1-570th in. long, 1-3333d in. broad.

Habitation. Stomach and commencement of the small intestine of Emys guttata.

Remarks.—The female hangs suspended by its posterior hook from the mucous membrane of the stomach of the Emys, in which it is parasitic, while the male clings closely to the female by means of its spiral folds, retaining its position readily from the roughness of surface produced by its numerous ventral tubercles, and also those upon the tail. I found this entozoon three times, in 15 individuals of Emys guttata. In one instance it was a large female; in the second two, average size females, and one male; in the third instance the stomach was distended with the worms, of which about one in five or six was male, and usually clung to the largest of the females.

CUCULANUS, *Müller*.

2. CUCULANUS TRISPINOSUS, *n. s.*

Body reddish, narrow, cylindrical, finely striated, attenuated at the extremities. Mouth large, sustained by a red or brown corneous capsule, presenting 8 radiating ribs or lines upon each side of a middle line. Œsophagus of two por-

tions; the first, elongated pyriform; the second cylindroid, a little dilated at its lower end. Intestine simple, cylindrical, a little narrower than the œsophagus.

Male.—3 lines long, 1-200th to 1-160th in. broad at middle. Posterior extremity curved, acute, furnished on each side ventrally, with an expansion of the integument, of nearly uniform breadth, 1-800th in., to its termination, commencing 1-50th in. above the end of the tail, and perforated by 6 nearly equidistant respiratory canals. Tail 1-300th in. long from anus. Anal and generative apertures indicated by a prominent lip, and separated by a small conical papilla. Penis consisting of two corneous, curved spiculæ; one 1-56th in. long, the other 1-200th in. long.

Female.—Viviparous, 6 lines long, 1-100th to 1-90th in. broad. Tail straight, long conoidal, 1-111th long from anus, obtuse, terminated by 3 minute points 1-4000th in. long. Generative aperture surrounded by a very prominent lip, a little posterior to the middle. First portion of œsophagus 1-66th in. long; 1-200th in. at broadest part; second portion, 1-56th in. long.

Habitation.—Small intestine of Emys guttata.

TÆNIA, *Linn.*

3. TÆNIA PULCHELLA, *n. s.*

White, without any admixture of any other color, variable, usually broadest anteriorly. Head quadrilateral, sub-clavate, obtusely rounded, broader than the neck. Acetabula circular, cup-shaped, lateral and opposite, sessile, protractile. Neck very long, cylindroid. Articuli containing several colorless globules; anteriorly subglobular or transversely oval; posteriorly moniliform, longitudinally oval, or cylindroid and centrally incrassate.

Measurements.—*Longest* 9 in. Articuli commencing to be distinctly separate 4 in. from the head. Breadth anteriorly ½ line; posteriorly 1-6th line. Anterior articuli 1-6th line long; posterior ½ line. Acetabula, 1-166th in. diameter.

Smallest 2 in. Head, 1-75th in. broad. Articuli commencing distinctly separate ½ in. from the head. Broadest part of neck, 1-90th in.; short distance posterior to the head, 1-125th in. Anterior articuli 1-100th in. diameter; posterior 1-44th in. long; 1-200th broad at extremities, 1-133d in. broad at middle. Acetabula, 1-200th in. diameter.

Habitation.—Small intestine of Bufo americanus.

Remarks.—Closely resembles the Tænia dispar, *Goeze*, found in the Bufo viridis, etc., but it is relatively longer and narrower, and is never colored.

PLANARIA, *Müller.*

4. PLANARIA SYLVATICA, *n. s.*

Body elongato-fusiform, thick, becoming narrowed forward, smooth, shining; superiorly convex, grayish with a fuliginous stripe down each side of the dorsal line, and a transverse spot of the same color, at, or just posterior to the centre: inferiorly compressed, whitish; anteriorly attenuated, proboscidiform; tip recurved, fuliginous, obtuse; posteriorly broadest, terminating acutely. Eyes two, black, globular, lateral, slightly prominent.

Length 2 to 5 lines; breadth at the anterior fourth, ½th of a line; at posterior fourth, ¼th of a line.

Habitation.—Beneath stones, flower-pots, and boxes, in gardens in Philadelphia, and under fragments of wood, bark, old logs, etc., in forests in the neighborhood of Philadelphia.

Remarks.—This is the first terrestrial planaria which has been detected in North America. I accidentally discovered it first beneath several flower boxes, and pots in the small garden attached to my residence in this city, since which, I sought for and found it in the hilly woods bordering the Wissahicon Creek and Schuylkill River. In its movements it resembles a slug (Limax,) and like this leaves behind it a mucous trail. When in motion, the anterior portion of the body is much elongated, and very narrow, and the portion anterior to the eyes is recurved. Frequently it raises the anterior third of the body from the ground, moving it from side to side as if in search of something. The recurved portion inferiorly, is flat, with the edges often inflected.

When at rest, the body is contracted into an oblong form, and the head lies doubled upon the back. The longest will contract to 2½ lines in length by ½ a line in breadth, and ⅓rd line thick posteriorly, and ¼th line wide anteriorly.

The coloring matter upon the back is arranged in faint transverse annuli, accumulating upon each side of the middle into a longitudinal line, and a transverse spot about the centre.

The eyes are globular, apparently composed of a vitreous humor, two-thirds enveloped with a black pigment. They are situated laterally, the 1-100th to the 1-48th of an inch posterior to the extremity of the head, and measure about the 1-500th in. in diameter.

The mouth is inferior and a little posterior to the centre. Œsophagus keg-shaped, about 1-50th in. long. From the acute tail end is secreted a delicate mucous thread.

The planaria appears not to like the water, for although it will live for some hours beneath the surface, when prevented from rising, yet it always seeks to leave it and remains out when it has escaped.

In the same forest localities with the planaria, is found an insect larva, possessing similar habits, which upon careless inspection might be mistaken for it. The movements of the larva are more rapid and vermicular.

PLANARIA, *Müller.*

Sub-genus nov. BDELLOURA.*

Characters same as Planaria, without tentaculæ, and the posterior extremity of the body separated by a constriction serving as a disk of attachment.

5. BDELLOURA PARASITICA, *n. s.*

Body milk white, with a faintly yellowish intestine showing through the translucent integument, smooth, thin, lanceolate, or spatulate; anteriorly narrowed, obtuse; lateral margins, thin, undulating; constricted portion posteriorly truncated, nearly as broad as the middle of the body. Eyes two, reniform. Œsophagus simple, cylindrical, campanulate when protruded.

Length from 3 to 10 lines; breadth 2-5ths to 2½th lines. The longest may contract to 6 lines by 3½ lines.

Habitation.—Parasitic upon the King Crab, Polyphemus occidentalis, *Lam.*

*βδέλλα, a leech; ὀυρα, tail; because the animal adheres by the tail like a leech.

Found often in great numbers, adhering with considerable tenacity by means of the posterior constricted extremity of the body, to the under surface of the branchial covers, the branchial laminæ, and to the extremities, especially in the vicinity of the joints.

Remarks.—When the king crab is removed from the water, its planaroid parasite retires to the deepest recesses between the limbs and other external organs to avoid evaporation. The parasite moves with a gliding motion like the species of Planaria, and also by fixing the posterior extremity and extending the anterior part of the body to its greatest length, and then abruptly detaching and drawing forward the former, like the leeches. At other times it fixes itself posteriorly, and waves the anterior portion of the body to and fro through the water.

Attached to the branchial laminæ of the king-crab, are frequently observed ochreous or brownish, oval, compressed cysts, from ¼th to 2 lines long, and 1-6th to 1 line broad, attached by a short pedicle at one extremity, and unusually closely applied to the surfaces between the branchial laminæ, which are receptacles or ova? of the Bdelloura parasitica. Occasionally the margin of the cysts is provided with a fringe of short, irregular, blackish filaments. Sometimes these cysts exist in such numbers as to have the appearance of flaxseed sprinkled between the branchial laminæ.

6. BDELLOURA RUSTICA, *n. s.*

Body brownish or blackish, translucent, lanceolate; anteriorly narrowed, obtuse; lateral margins thin, undulating; constricted portion truncated posteriorly, with parallel margins. Eyes two, reniform. Œsophagus simple, cylindrical.

Length 2 to 3 lines; breadth 2-5ths to 4-5ths of a line.

Habitation.—Egg Harbor bay, New Jersey, upon Ulva latissama, *Linn.*

Remarks.—Movements same as in the preceding species. When free in water it moves with great rapidity, and rises to the surface in the manner of the leech, or the larva of the gnat.

Gen. nov. MYZOBDELLA.*

Body elongated, compressed fusiform, smooth. Head continuous with the body, subindibuliform, obliquely ventrally terminal. Mouth central, unarmed. Acetabulum ventrally obliquely terminal, concave, not corneous.

7. MYZOBDELLA LUGUBRIS, *n. s.*

Body cylindro-fusiform, in transverse section, elliptical, black olivaceous green; anteriorly narrowed, cylindroid; posteriorly incrassate. From 15 to 18 annulations. Integument translucent, permitting the sacculated intestine of a black green hue, to be visible. Acetabulum circular, concave, a little larger than the oral disk.

When elongated 10 lines, by ½ line in breadth posteriorly, 1-5th of a line anteriorly. Will contract to 4 lines by 4-5ths line in breadth.

Habitation.—Parasitic upon the common edible crab, Lupa dicantha, *M. Edw.*; usually found attached about the base of the limbs.

MECKELIA, *Leuckart.*

8. MECKELIA LACTEA, *n. s.*

Body very soft, milk white, in transverse section lenticular, convex above and below; when extended, very much compressed, more especially posteriorly, in-

*μυζω, I suck; βδελλα, a leech.

crassate rounded just posterior to the head; lateral margins, thin, undulating; posterior extremity thin, sub-acute. Head compressed, conical or hastate, anteriorly obtuse, breadth at base 1 line; lateral cleft 1½ lines long. Generative aperture longitudinally oval.

Greatest length 6 inches: ordinarily 5 inches, by 3 lines in breadth, and 1 line in thickness: may contract to 1 inch in length, by 2 lines in breadth, and 1½ lines in thickness.

Habitation.—In mud and sand under stones, dead shells, etc., in positions uncovered at low tide, upon the coast of Great Egg Harbor, New Jersey.

Remarks.—The more it is extended the broader and thinner it becomes, especially posteriorly. When free in water, it swims like the eels, and in such cases, the broad surfaces of the body are more or less vertical.

9. MECKELIA ROSEA, *n. s.*

Body bright flesh-colored with fainter lateral margins, and a central darker line inferiorly; in transverse section oblong, convex superiorly, flattened inferiorly; when elongated, becomes cylindroid; posteriorly, obtuse. Head compressed, conical or hastate, whitish. Generative aperture distinct, round.

Length from 2 to 6 inches; ordinarily about 5 inches.

Habitation.—With the preceding species.

Remarks.—As it elongates it approaches more the cylindrical form, becoming thicker and narrower.

The Committee on Mr. Cassin's descriptions of new species of Laniadæ, reported in favor of its publication in the Proceedings.

Descriptions of new species of birds of the family Laniadæ, specimens of which are in the collection of the Academy of Natural Sciences of Philadelphia.

BY JOHN CASSIN.

1. *Lanius pallidirostris*, nobis.

Form.—Bill rather long and compressed, wings rather short with the third quill distinctly longest, general form robust, and that of typical Lanius. About the size of *L. septentrionalis*, Gm.

Dimensions.—Total length of skin from tip of bill to end of tail, about 8½ inches, wing 4½, tail 4½ inches.

Colors.—Adult. Bill pale horn color. Upper surface of the head, with the back and rump pale cinereous, scapulars white and conspicuous, wings with a large patch of white on the primaries, and with the secondaries broadly tipped with white.

A stripe of black through the eye, very narrow on the nares, but wider behind the eye. Entire under-surface white, with a delicate, pale rosy tinge, most observable on the breast. Tail, with the two external feathers on each side, white, each with a narrow longitudinal line of black on the shaft, slightly widening into both webs, other tail feathers black, tipped with white, except the two in the centre, which are pure black. Tarsi and claws pale brown.

Hab.—Eastern Africa.

Obs.—This fine species, of which there is one specimen only in the Rivoli collection, may be distinguished readily from all others known to me by its very

pale horn-colored bill, and the pale rose-red tinge of the under parts of the body. The cinereous plumage above, is paler than that of *L. excubitor*, and it is without the white patch on the middle of the *secondaries*, which is so obvious in that species. It is more nearly related to *L. meridionalis*, but is smaller and much lighter colored.

2. *Lanius pallens*, nobis.

Form.—Bill rather weak, wings and tail rather long, but with the general form of typical Lanius. About the size of *L. minor*, Gm.

Dimensions.—Total length of skin from tip of bill to end of tail about 8 inches, wing 4, tail 4¼ inches.

Colors.—(Specimen not in mature plumage.) Rump and entire under surface pure white. Head above and back cinerous, wings black, with a large patch of white on the middle of the primaries, and with the secondaries edged and broadly tipped with white, tail, with the two external feathers on each side white, with the shafts black, others black with white tips, very narrow on the four central feathers.

A black stripe through the eye, above which is a stripe of white.

Bill and tarsi dark horn-color.

Hab.—Fazogloa, Eastern Africa.

Obs.—This species considerably resembles the preceding, but differs in having the rump white, and appears to be, so far as preserved specimens can be relied on, a smaller and more slender bird; the bill is not so long nor powerful. Two specimens are in the Rivoli collection, neither of which are fully adult.

3. *Laniarius quadricolor*, nobis.

Form.—Much resembling that of *L. gutturalis* (*Daud.*) but is smaller, and the tail more rounded. Wings short, rounded, fourth, fifth and sixth primaries longest and nearly equal.

Dimensions.—Total length of skin from tip of bill to end of tail, about 7¼ inches, wing 3¼, tail 3¼ inches.

Colors.— ♂ Adult. Generally resembling those of *L. gutturalis* (*Daud.*) but with the abdomen and ventral region yellow and the basal portion of the tail olive green. Entire superior surface of the head, body, and wings olive green, which is also the color of a basal third of the external, and of three-fourths of the central tail feathers. Throat fine scarlet, stripe through the eye and wide pectoral band, black; beneath the latter a badly defined band of yellowish scarlet, fading into the rich greenish yellow of the abdomen, under tail coverts yellowish scarlet. Bill black, paler at the base, tarsi and feet pale brown.

♂ young.—Resembling the adult, but with the tail entirely green, and the throat, under parts of the body and inferior tail coverts pale greenish yellow; a trace of black lines on the feathers of the breast, and of scarlet on those of the throat.

Hab.—Port Natal, Eastern Africa.

Obs.—Of this beautiful bird two adult males and several young birds are in the collection of this Academy. They are from the collection of Mr. Verreaux of Paris, and were acompanied by this significant memorandum, "considerée comme differente de la *gutturalis*." I have invariably found that M. Verreaux's opinion of species is of the greatest value, in fact almost infallible.

This bird may readily be distinguished from the larger *L. gutturalis*, of which we have specimens also, by the characters above indicated, and especially by its yellow abdomen.

4. *Dryoscopus sublacteus*, nobis.

Form.—Bill and legs rather long, wings rounded with the fourth to the eighth quills nearly equal and longest, plumage of the rump downy and profusely developed. Somewhat larger than *D. Gambensis* (Licht.)

Dimensions.—Total length of skin from tip of bill to end of tail, about 7¼ inches, wing 3½, tail 3¼ inches.

Colors.—Adult. Entire plumage of the head and body above, wings and tail glossy black; downy plumage of the rump grayish white at base and tipped with black, (as in D. rufiventris (Swainson) Le Vaill. Ois. d'Af. pl. 68, and D. ethiopicus, (Gm.) Rupp. Uebersicht, pl. 23.)

Under plumage entirely very pale ochraceous white or cream color, deepest on the flanks, (same color as in D. ethiopicus.) No white markings on the wings nor other part of the plumage.

Bill black, tarsi paler.

Hab.—Eastern Africa?

Obs.—A general resemblance exists between the bird now described and several other species of Dryoscopus, but it is peculiar in having the fine cream-colored under surface of the body, and no white marks whatever on the wings.

5. *Dryoscopus atrialatus*, nobis.

Form.—Bill long, wings with the fourth quill longest, tail rather long and ample. Generally similar to *D. affinis* (G. R. Gray,) but is larger, being about the size of *D. Gambensis* (Licht.)

Comparative Dimensions.

	D. atrialatus.	D. affinis.
Total length of skin from tip of bill to end of tail, about	7¼	6¼ inches.
wing,	4	3¼
tail,	3¼	2¾

Colors.—Adult. Very similar to those of *D. affinis* (G. R. Gray) and generally to these of *Chaunonotus Sabinei* (J. E. Gray.)

Entire upper surface, except the rump, deep black; under parts and rump white. Wings clear black, with no white edgings or tips to either quills or coverts, tail black, shafts of the feathers white at base beneath, bill black, tarsi brown.

Inferior wing coverts black, (white in *D. affinis.*)

Hab.—Eastern Africa?

Obs.—One specimen only of this bird is in the Rivoli collection. It was labelled "*L. Sabinii*," having evidently been mistaken for *Chaunonotus Sabinei* above alluded to, which has recently been added to the collection of the Academy, but from which the bird now described is generically distinct. It is very similar to D. affinis, but may readily be distinguished by its larger size and black inferior wing coverts.

The Committee to which was referred Mr. Dana's communication, reported in favor of its publication in the Proceedings.

Conspectus Crustaceorum quæ in Orbis Terrarum circumnavigatione, Carolo Wilkes e Classe Reipublicæ Foederatæ Duce, lexit et descripsit J. D. Dana.

Descriptio Familiarum Subfamiliarum Generorumque Crustaceorum Grapsoideorum in Ephemeride Scientiarum Americana Sillimani, vol. xii, p. 283, anno 1851, auctore edita. Synopsis brevis Familiarum et Subfamiliarum sequens :—

CRUSTACEA GRAPSOIDEA, (Cyclometopa, Edwardsii.)

1. Articulus Maxillipedis Externi 4tus angulo 3tii interno articulatus.

Fam. I. Gonoplacidæ, vel Grapsoidea Cancridica. Gen. *Eucrate* De Haan, *Curtonotus* De H. (*Pseudorhombila*, Edw.), *Gonoplax* Leach.

2. Articulus Maxillipedis externi 4tus angulo 3tii interno non articulatus.

Fam. II. Macrophthalmidæ.

Sub-fam. 1. Macrophthalminæ.—Gen. *Cleistostoma*, De H., *Macrophthalmus*, Latr.

Subfam. 2. Ocypodinæ.—Gen. *Gelasimus*, Latr., *Helacius*, Dana (*Gelasimum cordiformem* amplectens), *Ocypoda*, Fabr., *Scopimera*, De H.

Subfam. 3. Dotinæ.—Gen. *Doto*, De H.

Fam. III. Grapsidæ.

Subfam. 1. Grapsinæ.—Gen. *Pseudograpsus*, Edw., *Eriocheir*, De H. (*Utica*, White), *Platynotus*, De H., *Brachynotus*, De H., *Trichopus*, De H. (*Varuna*, Edw.), quorum maxillipedibus externis vix hiantibus ; *Grapsus*, Lamk., *Goniograpsus*, Dana (*Graps. cruentatum, messor*, etc., amplectens), *Planes* Leach (*Nautilograpsus*, Edw.), *Hemigrapsus*, Dana (*Cyclograpsus* partim, Edw.), *Cyrtograpsus, Dana*,—maxillipedibus externis rhomboidicé hiantibus.

Subfam. 2. Sesarminæ.—Gen., *Sesarma*, Say (*Pachysoma*, De H.), *Sarmatium*, Dana,—quorum, articulo maxillipedis externi 3tio apicem rotundato ; *Cyclograpsus*, Edw. (*Gnathochasmus*, M'Leay), *Chasmagnathus*, De H., *Helice*, De H.,—quorum articulo maxillipedis externi 3tio apicem truncato et sæpe excavato.

Subfam. 3. Plagusinæ.—Gen. *Acanthopus*, De H. (*Plagusiam clavimanam* amplect), Plagusia, *Latr.*

Fam. IV. Gecarcinidæ.

Subfam. 1. Ucainæ.—Gen. *Uca*, Leach, *Gecarcinucus*, Edw., *Cardisoma*, Latr. *Gecarcoidea*, Edw.

Subfam. 2. Gecarcininæ.—Gen. *Gecarcinus*.

Fam. V. Pinnotheridæ.

Subfam. 1. Pinnotherinæ.—Gen. *Pinnotheres*, Latr., *Fabia*, Dana, *Xenophthalmus*, White, *Xanthasia*, White, *Pinnixa*, White, *Pinnotherelia*, Lucas.

Subfam. 2. Hymenicinæ.—Gen. *Hymenosoma*, Leach, *Halicarcinus*, White, *Hymenicus*, Dana, *Elamena*, Edw.

Fam. VI. Myctiridæ.—Genus *Myctiris*.

Specierum Grapsoidearum adhuc ineditarum Descriptiones.

FAM. I. GONOPLACIDÆ, vel GRAPSOIDEA CANCRIDICA.

GENUS EUCRATE, *De Haan.*

EUCRATE CRASSIMANUS.—Carapax nudus, bene areolatus, margine anterolaterali 4-dentato, dentibus tribus posticis prominenter triangulatis; fronte fere recto, medium emarginato. Pedes antici crassi, subæqui, nudi, læves, inermes, manu infra compressâ, carpo intus breviter acuminato, brachio in margine postico prope apicem unidentato. Pedes 8 postici sat graciles, marginibus ciliati, tarso recto, infra hirsuto.

Long. carapacis 10‴; lat. 13‴. *Hab.* in portu "Rio Janeiro?"

FAM. II. MACROPHTHALMIDÆ.

SUBFAM. I. MACROPHTHALMINÆ.

GENUS MACROPHTHALMUS.

MACROPHTHALMUS PACIFICUS.—Carapax valde transversus, nudus et lævis, margine laterali arcuato, anterius 2-emarginato, emarginatione anteriore profundâ, posteriore obsolescente, fronte latiusculo et lateribus non excavato. Oculi graciles, sat breves, tertiam latitudinis carapacis partem longitudine æquantes. Pedes maris antici parvuli, læves, manu extus nudâ, subtiliter punctatâ et non costatâ, digito inferiore non deflexo. Pedes postici marginibus pubescentes, articulo pedis 4ti 3tio duplo latiore quam 5tus, apice cum dente acuto armato.

Long. carapacis 4‴, lat. 5½‴. *Hab.* insulâ "Upolu."

SUBFAM. II. OCYPODINÆ.

GENUS GELASIMUS, *Latreille.*

GELASIMUS NITIDUS.—*G. Duperreyi* similis. Carapax nitidus, antice paulo arcuatus, fronte angustissimo, paulo constricto. Pedes *maris* antici valde inæqui, manu majore multo compressâ et latâ, extus valde granulatâ, intus cristis duobus obliquis ornatâ, digito superiore laminato, fere duplo latiore quam inferior, inferiore juxta basin uni-dentigero. Pedes 8 postici fere nudi, articulo 3tio pedis 5ti perangusto.

Long. carapacis 6½‴. *Hab.* archipelagine "Viti."

GENUS HELŒCIUS, Dana.

HELŒCIUS INORNATUS.—Carapax convexus, nudus, angulis anticis fronte posterioribus. Pedes antici sat breves; carpo non duplo longiore quam latiore, margine interno angulato; manu latâ, parte palmari paulo oblongâ. Segmentum abdominis ultimum breviter transversum, penultimo subito angustius. Articulus pedum 3tius supra tomentosus.

Long. carapacis 6‴; lat. 8½‴. *Hab.* ad oras australes Novi-Hollandiæ. *Helœii cordiformis* (*Gelasimi cordiformis* auctorum) manus carpusque multo longiores quam in *inornato*; segmenta abdominis breviora, ultimo non subito angustiore quam penultimum.

FAM. III. GRAPSIDÆ.

SUBFAM. I. GRAPSINÆ.

GENUS PSEUDOGRAPSUS, *Edwards.*

PSEUDOGRAPSUS OREGONENSIS.—Carapax parce areolatus, regione mediană leviter circumscriptâ, cum lineâ transversâ antice levissimè notatâ et margine hujus

regionis antice abrupto; fronte sinuoso; margine antero-laterali bi-emarginato, dentibus acutis. Pedes antici læves, manu extus nudâ, infra obsolete uni-costatâ, intus partim lanosâ, carpo lævi, digitis *maris* hiantibus. Pedes postici margines paulo hirsuti, præcipue articulorum 4ti et 5ti.

Long. carapacis 10‴; lat. 11½‴. *Hab.* in Oregoniæ freto "Puget."

Pseudograpsus nudus.—Carapax obsolete areolatus, regione medianâ vix circumscriptâ, cum lineâ elevatâ non intersectâ, areolâ intramedianâ (3 M) non circumscriptâ; fronte paulo arcuato; margine antero-laterali leviter bi-emarginato. Pedes toti nudi; antici æqui, manu extus nudâ, lævi, infra levissimè costatâ, intus partim lanosâ, carpo lævi; 8 postici paulo lati, tarso sulcato.

Long. carapacis 10½‴; lat. 12½‴. *Hab.* in Oregoniæ freto "Puget."

GENUS GRAPSUS.

1. Grapsus planifrons.—*G. variegato* similis, fronte fere horizontali, sat lato. Articulus maxillipedis externi 3tius vix oblongus. Margo carapacis lateralis bene arcuatus, antero-lateralis bi-emarginatus. Epistoma brevissimum. Pedes antici sat crassi, manu supra pustulatâ, extus infraque lævi; brachio apicem anticum 5—6-denticulato. Pedes 8 postici valde compressi, articulo 3tio pedis postici ad apicem inferiorem integro, penultimo supra scabro.

Long. carapacis 17½‴; lat. 19‴. *Hab.* ad oras juxta urbem "Valparaiso."

2. Grapsus longitarsis.—Carapax nudus, regione medianâ granulatus; fronte abrupto, perangusto; lateribus parce arcuatis, margine antero-laterali 1-emarginato. Articulus maxillipedis externi 3tius vix oblongus. Epistoma breve, utrinque acutè cristatum. Pedes antici sat parvi, manu carpoque supra parce granulatis, manu extus fere lævi, infra leviter costatâ. Pedes postici nudi, tarso elongato, spinulis dorsi multo brevioribus.

Long. carapacis 9½‴; lat. 10½‴. *Hab.* in archipelagine "Paumotu."

Grapsus crinipes.—*G. livido* affinis. Carapax nudus, sublævis, fere quadratus, fronte sat abrupto, margine antero-laterali 1-emarginato. Pedes antici fere æqui, carpo manu digitoque mobili superne granulatis, manu extus fere lævi, nec costatâ; brachio ad apicem anticum 5—7-denticulato. Pedes postici sparsim criniti, articulo tertio lato, tarso perangusto, lineari, paulo curvato. Margo epistomatis posticus valde arcuatus.

Long. carapacis 9½‴; lat. 11½‴. *Hab.* ad insulas "Sandwich."

GENUS GONIOGRAPSUS, *Dana.*

Goniograpsus simplex.—*G. vario* similis. Carapax fere quadratus, lateribus postice vix convergentibus, fronte paulo declivi, parce sinuoso, margine antero-laterali 1-emarginato. Carpus supra minutè rugatus; manus extus lævis, supra paulo rugata. Articuli pedum 8 posticorum 4tus 5tusque sparsim hirsuti; 3tius pedis postici apice inferiore truncatus, integer, pedis 4ti 3tiive 2—3-dentatus.

Long. carapacis 4‴; lat 4½‴. *Hab.* in portu "Rio Janeiro." ?

Goniograpsus innotatus.—Carapax fere quadratus, lateribus postice convergentibus, fronte sat declivi, margine antero-laterali 1-emarginato, lineis transversis carapacis subtilissime crenulatis. Carpus supra lævis; manus supra extusque lævis; brachium apice 2—3-dentatum. Articulus pedis postici 3tius apice inferiore 3-dentatus.

Long. carapacis 7‴; lat. 9‴: long. frontis 5½‴. *Hab.* ad oras Americæ Australis ?

GENUS PLANES, *Leach.*

PLANES CYANEUS.—Pedes octo postici valde compressi, articulis tribus ultimis extus dense villoso-ciliatis. Abdomen maris angusto-triangulatum, duplo longius quam latius, 7-articulatum, articulo 3tio latiore, breviore quam 4tus, ultimo triangulato.

Long. 6‴—8‴. *Hab.* in mari Pacifico, lat. bor. 28°, long. orient. 174°.

GENUS HEMIGRAPSUS, *Dana.*

HEMIGRAPSUS CRASSIMANUS.—Carapax subtiliter granulatus, margine antero-laterali leviter 2-emarginato, dentibus brevissimis, rotundatis, etiam emarginatione 3tiâ obsoletâ. Pedes *maris* antici crassi, nudi, carpo supra indentato. Pedes sequentes tenues, articulo 3tio supra fere nudo, infra lanoso, reliquis margines plerumque pubescentibus, 5to supra sulcato, tarso gracili. Abdomen maris perangustum, articulo ultimo anguste elongato.

Long. carapacis 6½‴; lat. 6½‴; long. frontis 2½‴. *Hab.* ad insulas "Sandwich."

HEMIGRAPSUS AFFINIS.—*H. crassimano* fermè affinis. Manus *maris* crassæ, minus tumida, antice paulo compressa, digitis hiantibus. Articulus pedis 2di, 3tii, 4tive 3tius infra villosus, supra partim pubescens. Pes 5tus articulis 4to 5to 6toque infra supraque pubescens. Margo carapacis antero-lateralis 3-emarginatus, emarginationibus duabus posticis parvulis.

Long. carapacis 7‴. *Hab.* portu "Rio Negro" Patagoniæ.

GENUS CYRTOGRAPSUS, *Dana.*

CYRTOGRAPSUS ANGULATUS.—Carapax angulato-gibbosus, granulosus, nudus, margine antero-laterali fere recto, 4-dentato, margine postero-laterali leviter uni-dentato. Pedes *maris* antici crassi, granulati, manu supra paulo truncatâ, carpo intus truncato. Pedes 8 postici fere nudi, articulo 5to supra sulcato, tarso sulcato.

Long. carapacis 17½‴; lat. 21‴, long. frontis 6‴. *Hab.* portu "Rio Negro," Patagoniæ.

SUBFAMILY II. SESARMINÆ.

GENUS SESARMA, *Say.*

SESARMA OBTUSIFRONS.—Carapax quadratus, sat transversus, postice paulo angustior, omnino bene granulatus, granulis sparsis, lateraliter nec lineolatus, margine antero-laterali integro, fronte perpendiculari, supra rotundato, margine frontali arcuato. Epistoma granulatum. Pedes antici mediocres, carpo manuque supra granulatis, manu extus lævi, digitis nudis. Pedes postici granulati, articulo 5to brevissime sparsim hirsuto, 4to fere nudo.

Long. carapacis 4‴; lat. ant. 5½‴, post. 4½‴. *Hab.* ad insulas "Sandwich."

SESARMA OBESUM.—Carapax crassus, quadratus, parce areolatus, postice vix angustior, punctatus, non nitidus, lateribus fere arcuatis, nulla parte acutis, margine antero-laterali integro; fronte perpendiculari, supra fere recto, infra bene arcuato. Epistoma granulatum. Pedes antici breves, manu brevi, non granulatâ, superne integrâ et brevi. Pedes 8 postici angusti, articulo 4to non hirsuto, 5to sparsim breviter hirsuto, tarso breviter hirsuto.

Long. carapacis 6‴: lat. 6½‴. *Hab.* freto "Balabac."

GENUS SARMATIUM, *Dana*.

Sarmatium crassum.—Carapax crassus, supra lævis, lateribus valde arcuatus, fronte fere recto, margine antero-laterali leviter 2-emarginato, dentibus rotundatis. Pedes antici *maris* breves, manu supra transversim 4—5-plicatâ, extus fere lævi, digito supra breviter 4-subspinoso, carpo plerumque lævi, supra paulo seriatim granulato.

Long. carapacis 6¼‴; lat. 7‴; alt. thoracis 4¼‴; long. frontis 3‴. *Hab.* ad insulam Samoensem "Upolu."

GENUS CYCLOGRAPSUS, *Edwards*.

1. Cyclograpsus cinereus.—Carapax parce transversus, non areolatus, paulo nitidus, non granulatus. Orbita infra plerumque circumscripta. Articulus maxillipedis externi 3tius valde oblongus, 2do non brevior, pubescens, cristâ fere ad angulum 2di externo-posteriorem productâ. Digiti intus denticulati. Articulus pedis 2di 5tus apice non tomentosus, tarso non spinuloso, lineis angustis tomentosis supra ornato. Abdomen maris fere rectangulatum, postice parce angustius lateribus subparallelis, rectis, segmento postico elongate triangulato, triplo angustiore quam penultimum. Sternum pone aream buccalem pubescens.

Long. carapacis 6‴, lat. 7¼‴: long. frontis 3‴. *Hab.* ad oras Chilenses; quoque ad insulas "Sandwich."

2. Cyclograpsus granulatus.—Carapax non areolatus, antice paulo granulatus. Orbita infra incompleta. Articulus maxillipedis externi 3tius vix oblongus, 2do multo brevior, nudus, cristâ tenui, pilosâ, angulum 2di externo-anteriorem intersecante tantum, 2dus nudus. Articulus pedis 2di 5tus apice non tomentosus, tarso lineis tomentosis paulo laxis ornato, non spinuloso. Manus glabra, nitida, digitis *maris* intus non denticulatis. Abdomen *maris* eo *C. cinereo* fere simile, lateribus vix excavatis, segmento postico parce oblongo, apice late rotundato. Sternum pone aream buccalem nudum.

Long. carapacis 3.7‴; lat. 4.6‴. *Hab.* ad oras insulæ "Maui" Hawaiensis.

GENUS CHASMAGNATHUS, *De Haan*.

1. Chasmagnathus subquadratus.—Carapax convexus, lævis, postice paulo punctatus, paulo areolatus, fronte margineque antero-laterali uti in *C. granulato*, lateribus parce arcuatis, areolâ præmedianâ antice vix notatâ. Maxillipedes externi sternique pars proxima brevissime hirsuti. Pedes antici posticique plerumque uti in *C. lævi*, manu non granulatâ, minute punctatâ. Regio pterygostomiana breviter reticulata. Articulus pedis 2di 5tus infra non tomentosus, supra anticeque tomentosus. Abdomen lateribus excavatum, basi latius, longius ciliatum.

Long. carapacis 8‴; lat. 9¼‴; long. frontis inter oculos 4‴. *Hab.* ad oras Novi-Zealandiæ? Novi-Hollandiæ orientalis?

2. Chasmagnathus granulatus.—Carapax valde convexus, sat areolatus, fronte sinuato, medio depresso et juxta marginem medianum minute apiculato; margine antero-laterali tenui, 2-inciso, dentibus triangulatis, acutis. Margo epistomatis inferior fronte prominentior. Pedes antici *maris* crassi, subæqui, granulati, carpo intus acuto, manu supra tenui et paulo obtusâ. Pedes postici valde compressi, articulis 4to 5to dorso paulo tomentosis, 5to pedis 2di infra non

tomentoso, tarso tenui, tenuiter sulcato et sulcis hirsuto. Abdomen *maris* lateribus fere rectum.

Long. carapacis 15‴; lat. 17½‴; long. frontis inter oculos 7‴. *Hab.* palude juxta lacum "Peteninga" urbi "Rio Janeiro" vicinum.

3. CHASMAGNATHUS LÆVIS.—Carapax convexus, lævis, vix granulatus, paulo areolatus, fronte margineque antero-laterali plerumque uti in *C. granulato*, fronte juxta marginem medianum non apiculato, areolâ præmedianâ antice præruptâ. Epistoma fronte non prominentius. Pedes antici *maris* æqui, manu leviter granulatâ, supra non tenui. Pedes postici angustiores, articulus pedis 2di 5tus infra antice supraque tomentosus. Abdomen lateribus fere rectum vel obsolete excavatum.

Long. carapacis 11½‴; lat. 14‴; long. frontis inter oculos 6‴. *Hab.* in portu "Sydney" Novi-Hollandiæ Orientalis.

GENUS HELICE, *De Haan.*

HELICE CRASSA.—Carapax subquadratus, margine laterali antice bi-emarginato, fronte dimidii latitudinis carapacis longitudine. Manus brevis et lata, superne subcarinata, extus fere lævis, minute granulata. Articulus pedum sequentium 3tius supra subacutus. Regio pterygostomiana granulata, leviter pubescens.

Long. carapacis 5½‴; lat. 6½‴. *Hab.* ad oras "Illawarræ" Novi-Hollandiæ Orientalis.

SUBFAM. III. PLAGUSINÆ.

GENUS ACANTHOPUS, *De Haan.*

ACANTHOPUS ABBREVIATUS.—Carapax subquadratus, non oblongus, supra omnino tomentosus lineis nudis nullis; fronte uti in *planissimo* sed latiore; margine antero-laterali 4-dentato, dente 2do inconspicuo. Pedes *maris* antici æqui, manu vix inflatâ, supra sulcatâ. Abdomen *maris* angustius, lateribus excavatum.

Long. carapacis *maris* 6‴. *Hab.* ad oras insulæ "Tahiti."

GENUS PLAGUSIA.

1. PLAGUSIA SPECIOSA.—*P. squamosæ* affinis. Margo antero-lateralis 3-dentatus.

Long. carapacis 14‴: lat. 15‴. *Hab.* archipelaginis "Paumotu" insulâ "Waterland."

2. PLAGUSIA GLABRA.—Carapax lævis, glaber, margine antero-laterali 4-dentato, fronte superne oblique subcristato, non spinigero. Pedes *maris* antici perbreves, parte manus palmari breviore quam altiore, supra granulatâ, extus lævi et non costatâ, carpo fere lævi. Articulus pedum 8 posticorum 3tius lævis, non multispinosus. Articulus maxillipedis externi 3tius quadratus, parce oblongus.

Long. carapacis maris 9‴; lat., dentibus exclusis, 9‴, dentibus inclusis 9½‴. *Hab.* ad oras Novi-Hollandiæ Orientalis.

FAM. IV. GECARCININÆ.

SUBFAM. I. UCAINÆ.

GENUS CARDISOMA.

CARDISOMA OBESUM.—Carapax obesus, undique convexus, lateribus antero-lateralibus valde tumidis, linea angulove marginis omnino carentibus. Articulus

antennæ externæ 1mus transversus, apice utrinque productus et subacutus, superficie granulatus, processu orbitam antennamque sejungente subtriangulato, trihedrico, non truncato.

Long. carapacis 3″; lat. 3‖″; long. frontis inter oculos 12‴; lat. areæ buccalis antice 9‴. *Hab.* archipelagine "Paumotu."

CARDISOMA HIRTIPES.—Carapax longitudinaliter convexus, margine laterali antice notatus, prope dentem post-orbitalem minute apiculato, areolâ præmedianâ antice juxta frontem paulo abruptâ, regione pterygostomianâ pilosâ. Processus præorbitalis orbitam antennamque externam sejungens triangulatus, trihedricus. Articulus antennæ externæ 1mus rectangulatus apice recte truncatus. Pedes *maris* antici crassi, subæqui, sat breves, manu punctatâ, digitis late hiantibus. Pedes postici hirti.

Long. carapacis *maris* 22‖‴; lat. 28‴; long. frontis 7‖‴; lat. areæ buccalis antice 5‖‴, postice 8‖‴. *Hab.* insulis "Viti."

FAM. V. PINNOTHERIDÆ.

SUBFAM. I. PINNOTHERINÆ.

GENUS PINNOTHERA, *Latreille.*

PINNOTHERA FABA.—Carapax late transversus, nudus, paulo nitidus. Maxillipedes externi nudi, vix obliqui. Oculi parvuli. Pedes antici *feminæ* breves, manu supra rotundata, digitis subtiliter pubescentibus. Pedes postici perbreves, crassiusculi, articulo 3tio pedis 4ti triplo breviore quam carapacis latitudo, tarso brevi, basi crasso, subconico, apice uncinato.

Long. carapacis *feminæ* 5‖‴; lat. 8‴. *Hab.* in freto "Puget" Oregoniæ.

GENUS FABIA, *Dana.*

FABIA SUBQUADRATA.—Carapax (feminæ) subquadratus, antice rotundatus, parce latior quam longior, nudus, nitidus. Maxillipedes externi nudi, valde obliqui. Oculi minimi. Suturæ post-frontales fere parallelæ. Pedes antici (feminæ) sat tenues, manu elongatâ, infra 2 lineis pubescentibus (lineâ unâ usque ad digiti extremitatem productâ) ornatâ. Pedes 8 postici sat graciles, articulo 3tio supra partim pubescente, 5to infra pubescente, tarso brevi, dimidii articuli 5ti longitudine, uncinato.

Long. carapacis 5‖‴; lat. 6‖‴; lat. inter suturas post-frontales 2‖‴. *Hab.* in freto "Puget" Oregoniæ.

SUBFAM. II. HYMENICINÆ.

GENUS HALICARCINUS, *White.*

HALICARCINUS PUBESCENS.—Carapax ovato-orbicularis pone medium latior. Pedes longitudine mediocres, 8 postici laxe pubescentes. Abdomen *maris* angustum, fere lineare, apice triangulatum.

Long. 1‖‴. *Hab.* in mari, juxta Patagoniam orientalem, altitudine 50 brachiorum.

GENUS HYMENICUS, *Dana.*

1. HYMENICUS VARIUS.—Carapax lævis, nudus, planus, ovato-orbiculatus, vix transversus, fronte expansus et trilobatus, lobis rotundatis, margine antero-laterali dentibus duobus obsoletis remote armato. Abdomen *maris* angustum, subtriangulatum, segmento basali latiore et utrinque triangulato, penultimo angustiore

quam precedens, ultimo paulo oblongo, apice rotundato. Pedes antici mediocres 8 sequentes tenuissimi, nudi aut nudiusculi.

Long. 2‴—3‴. *Hab.* ad oras portus "Bay of Islands" Novi-Zealandiæ.

2. HYMENICUS NOVI-ZEALANDIÆ.—Carapacem, frontem, pedesque *H. varii* similis. Abdomen *maris* lineare, segmentis penultimo precedentibusque duobus latitudine æquis, ultimo triangulato, non oblongo, obtuso. An varietas *varii*?

Hab. ad oras portus "Bay of Islands."

3. HYMENICUS PUBESCENS.—Carapax pubescens, fermè orbiculatus aut vix ovato-orbiculatus, postice arcuatus, rostro parvulo simplicissimo, rotundato et marginem pubescente, margine carapacis omnino integro, inermi. Abdomen *maris* angustum, lineari-subtriangulatum, segmentis penultimo precedentibusque duobus fere æquis, postice parce angustantibus, ultimo subtriangulato, paulo oblongo, obtuso. Pedes breviter pubescentes; antici mediocres; sequentes tenues.

Long. 1¼‴—2‴. *Hab.* in portu "Bay of Islands."

ELECTION.

Robert Swift, Esq., of St. Thomas, West Indies, was elected a *Correspondent*, and Mr. William H. Allen, President of Girard College, was elected a *Member* of the Academy.

DONATIONS TO MUSEUM

In July and August, 1851.

July 1st.

Crustacea of the genera Aletecyclus, Grapsus, Chlorodius and Lissa, Portunus, from the Mediterranean, and Cypridina, from the British Seas; Mollusca, of the genera Crenella, Modiola, Galleonoma, Pupa, Helix, Cardita, Lucina, Spiralis, Arca, Buccinum, Astarte, Chiton, Pinguicula, Leda, Pecten, Nacra, Emarginula, Terebratula, Kellia, from the South of Europe, North of Africa, &c. Presented by Mr. McAndrew.

Very fine specimen in skin of Rupicola peruviana, from near Quito. Presented by M. Bourcier.

Crustacea from Pembrokeshire, Wales, of the genera Hyas, Amphithœ, Hippolyte, Talitrus, Crangon, Palæmon, Ebalia, Portunus, Porcellana, Carcinus. From E. & C. Wilson, of Pembrokeshire.

Palinurus Burgerii, Doclea muricata, Matuta Peronii, from Borneo; Pagurus, Carcinus, Portunus, Porcellana, Stenorhynchus, Cancer, Crangon, from Pembrokeshire; Asterias, Solaster, Heuricra, Palmipes, Ophiophis, Ophiothrix, Astropecten, Echinus, Amphidotus, Brisiopsis, from the British Seas; also, Pecten niveus, Serpula serrulata. Presented by Edward Wilson, Esq.

July 8th.

Crustacea of the genera Palæmon, Portunus, Crangon, Ebalia, Eurynome, Ligia, Galathea, Cancer, Hyas, Inachus, Pinnotheres, Idotea, Pagurus, Armadillo, Carcinus, Stenorhynchus, Anonyx, Ophiolepus, Pilumnus and Xantho, from the British Seas; Echinodermata, &c., of the genera Echinus, Palmipes, Ophiura, Spatangus, Solaster, Asterias, Ophiothrix, Echinocardium, Pavonaria, Brissus, Turbinola, Caryophillia, from the British Seas; also portions of rock, with attached Terebratula, Crania and Serpula from the British Seas. From Mr. Edward Wilson.

Fine specimens of Panopœa and Venus mercenaria, from St. Mary's County, Maryland. Presented by Mr. J. Gilliams.

Unio favidens, U. marginatus, 6 ages, Paludina ceranicoponæa, P. Bengalensis, Linnæa chalmys, Planorbis compressus, P. indicus, Pupa pullus, P. bicolor, Bulimus pretiosus, B. gracilis, Succinea crassiuscula. From Theodore Cantor, M. D., of the Bengal Medical Staff.

Three specimens of Erinaceus europæus, four of Talpa vulgaris, from Scotland. From Dr. Gavin Watson.

July 15th.

Numerous specimens of Silurian fossils, from the vicinity of Orwigsburg, Pa., and fragments of rock, with organic remains, from near Smyrna, Del. From W. Parker Foulke, Esq.

Fine specimen of a Silurian fossil, from near Orwigsburg, Pa. From Thomas Bannan, Esq.

Four Silurian fossils, from Keokuk, Mississippi, and one do. from the Falls of St. Anthony; Asphaltum, from Arkansas; Agate pebbles, from Lake Pepin. Presented by Mr. M. Maslin.

Seven specimens of Minerals, from near the Yellow Springs, and Reading, Pa. Presented by Mr. Isaac Lea.

July 22d.

Marsupium of Didelphis virginiana, containing four embryos of about six days old, three of them adherent to the nipple. Prepared by Dr. Goddard and preserved in Goadby's Solution. Presented by Dr. C. D. Meigs.

August 5th.

Five specimens of Ephialtes asio, male, female and three young. From Mr. Samuel Powel.

Seven specimens of Phosphate of Lime, from Huntsville, Morris Co., N. J. From Dr. J. C. Fisher.

August 12th.

Mounted specimens of Tamias Lysterii, Mustela erminea, (white pelage,) Philadelphia Co., and the same in brown pelage, from England. Presented by Mr. William Wood.

Fossil Spatangus, from the Marl, Salem Co., N. J. From Dr. Zantzinger.

Alumina, with peroxide of iron, used as a mineral paint, from the new red sandstone near Norristown, Pa. Presented by Aubrey H. Smith, Esq.

August 19th.

Head of the Walrus, Trichecus rosmarus, from the Arctic Ocean. Presented by Sandwith Drinker, Esq., of Hong Kong, China.

Hirundo rustica, and Emberiza rustica?, from Japan. From Lieut. Edward Brinley, U. S. N.

Three specimens of Fucoides Alleghaniensis, from the Juniata river, near Lewistown, Pa. Presented by Dr. Joseph Ard.

DONATIONS TO LIBRARY

IN JULY AND AUGUST, 1851.

July 8th.

Annales des mines. 4me. serie. 6me liv. de 1850, 1me. liv. de 1851. From the Ecole des Mines.

Catalogue of Malayan Fishes. By Theodore Cantor, M. D. 8vo. From the author.

The Pennsylvania Farm Journal. S. S. Haldeman, editor. Nos. 1—4. From the editor.

On the geographical distribution of the Bulimi. By Lovell Reeve. From the author.

Leeds Philosophical and Literary Society. Annual report for 1849, '50. From the Society.

Proceedings of the Geological and Polytechnic Society of the West Riding of Yorkshire, 1850. From the Society.

Journal of the Indian Archipelago and Eastern Asia. Vol. 5, Nos. 1 and 2. From the editor.

Archiv für Naturgeschichte. Herausgeg. von Dr. F. H. Troschel. Nos. 3, 4, 5, 1849, No. 1, 1850. From the editor.

Contributions to Ornithology. By Sir Wm. Jardine. Pts. 1 and 2, 1851. From H. E. Strickland, Esq.

Proceedings of the Linnean Society of London. Nos. 35—43. From the Society.

List of the Linnean Society of London, for 1850. From the same.

Dr. Wilson presented the following, on the usual condition:—

Systematische Beschreibung der bekannten europäischen zweiflügeligen Insekten. Von J. W. Meigen. 2 vols. 8vo.

History of the expedition, under Capts. Lewis and Clark, to the sources of the Missouri, &c. American edition, by Paul Allen. 2 vols. 8vo.

The Natural History of Ireland. Vol. 3. Birds. By W. Thompson, Esq. 8vo.

The Birds of Australia. By John Gould. Supplement. Part 1.

Annales de la Société Entomologique de France. 2e serie. Nos. 1—4, 1850. No. 1, 1851.

Annals and Magazine of Natural History. 2d. series. Nos. 40, 41.

Thesaurus Conchyliorum. By. G. B. Sowerly, Jr. Part 12.

Etudes sur les Echinides fossiles. Par M. Cotteau. Nos. 7 and 8.

Phycologia Britannica. By Wm. H. Harvey, M. D. Nos. 57 and 58.

History of British Mollusca and their shells. By Prof. Forbes and S. Hanley. Parts 37 and 38.

Journal of the Franklin Institute for June, 1851.

Zeitschrift für Malakozoologie. Von R. T. Menke, M. D. und Dr. L. Pfeiffer. Nos. 8, 9, 10, 1850.

Revue et Magasin de Zoologie. Par M. Guerin-Méneville. No. 10, 1850. Nos. 3 and 4, 1851.

Proceedings of the Zoological Society of London. 1850. pp. 81—192.

Illustrations of British Mycology. By Mrs. T. J. Hussey. 2d series. pts. 4 and 5.

Abbildungen und Beschreibungen neuer oder wenig gekannter Conchylien. Von Dr. R. A. Phillippi. No. 5. Vol 3.

Conchologia iconica. By Lovell Reeve. Parts 96 and 97.

The London Athenæum for May, 1851.

The Genera of Diurnal Lepidoptera. By E. Doubleday. Continued by J. O. Westwood. Part 42.

Histoire naturelle des Mollusques. Par M. de Ferussac: continue par M. Deshayes. No. 41.

July 15th.

Memoires sur la Digitaline: par MM. Homolle et Quevenne.

Proceedings of the American Philosophical Society. January to July, 1851. From the Society.

Bulletin de la Société Imperiale des Naturalistes de Moscou. An. 1849, No. 4. An. 1850, Nos. 1 et 2. From the Society.

The Charleston Medical and Surgical Journal and Review. July, 1851. From the editor.

Experimental researches on the unity and diffusion of nervous action. By Bennett Dowler, M. D. From the author.

Contributions to the natural history of the Acalephæ of North America. By L. Agassiz. Part 2. From the author.

Reports of reconnoissances of routes from San Antonio to El Paso; report of Capt. Marcy's route from Fort Smith to Santa Fé; and report of Col. Simpson of an expedition into the Navajo country. 8vo. From Col. Abert, U. S. Topog. Engineers.

Smithsonian contributions to Knowledge. Vol. 2. 4to. From the Smithsonian Institute.

July 22d.

The London Athenæum for June, 1851. From Dr. Wilson.

The Franklin Institute Journal for July, 1851. From the same.

August 5th.

Historical Discourse before the Graduates of Yale College, Aug. 14, 1850. By T. D. Woolsey. From Mr. E. C. Herrick.

Catalogus Collegii Yalensis, 1850. From the same.

On the coloring matter of red sandstone and of greyish and white beds associated with them. By J. W. Dawson, Esq. From the Author.

Smithsonian Reports. Notices of Public Libraries in the United States. By C. C. Jewett, Librarian of Smithsonian Institute. From the Institution.

The following were presented by Mr. Edward Wilson on the usual condition:—

Memoire sur les ossemens fossiles d'Elephans trouvés en Belgique. Par M. Chas. Morren.

Ordonnance concernant les enfans trouves et abandonnes.

La caisse d'Epargne et les Oursins. Par le Baron Charles Dupin.

Observations et questions concernant les moyens d'ameliorer la situation des ouvriers agriculteurs. Par M. de Rainneville.

Extrait des proces verbaux des Seances de la Soc. des Jeunes Liberes du Department de la Seine.

Catalogue des coquilles recueillies dans le Department du Puy de Dome, et determinees d'apres les ouvrages de MM. Draparnaud et Michaud. Par M. J. B. Bouillet.

Sur la theorie de la population. Par M. de Morel-Vinde.

The Income Tax Act. By William Nicholson.

Société Philantropique. Prix proposes en faveur des Memoires qui auront le mieux établi les bases et les conditions d'association applicables aux Sociétés de Savans mutuel et de Prevoyance.

Compte rendu des travaux de la Société des jeunes libérés.

Musei Indici index.

De Pteropodum ordine et novo ipsius genere. Ab. J. F. G. Kósse.

J. F. Blumenbachii specimen Historiæ naturalis ex auctoribus classicis.

De Pleurobranchæa novo Molluscorum genere. Ab. S. F. Leue.

Ittiologia Adriatica. Di F. Luigi Naccari.

Parergon ad L. H. Bojani anatomen Testudinis, &c.

Rapports et comptes rendus de la Caisse d'Epargne de Paris pendant l'annee 1837.

Über die fossile Reptilien welche im Wurtemburg aufgefunden worden sind. Von Geo. F. Jaeger, M. D.

Prodrome d'une monograph des Radiaires ou Echinodermes. Par Louis Agassiz.

Memoire sur le Delphinorhynque microptére. Par B. C. Dumortier.

Cosmus C. Cuno observationes Microscopia.

Remarques zoologiques et anatomiques sur l'Hyperodon. Par M. Deslongchamps.

H. Livii Van Altena commentatio ad questionem systematica enumerentur species indiginee reptilium ex ordine Batrachiorum.

Dalmatiæ nova Serpentium genera. Auctore F. L. Fleischman.

Ueber die Polypen im Allgemeinen und die Actinien insbesondere. Von W. Rapp.

Dissertation sur les Poissons qui se rapprochant le plus des animaux sans vertebres. Par A. M. Constant Dumeril.

Considerations sur les Montagnes Volcaniques. Par M. Collini.

Compte rendu de la Société de Charité maternelle de Paris, Annees 1835—1840.

Mémoire descriptif et Ostéographic de la Baleine. Par L. Companyo.

Horæ Tergestinæ: oder Beschriebung und Anatomie der im Herbste 1843 bei Triest beobachteten Akalephen. Von J. G. F. Will.

De Ranis nonnullis observationes anatomicæ. Auctore G. A. Steffen.

Sulla Scoperta dello Scheletro di un Quadrupede colossale fra Strati marini fatta in colle del Placenten dal Cav. Cortesi.

Des alten Grönlands neue perlustration, oder naturell-histoire und Beschreibung der Situation, Beschaffenheit, Lufft und des Temperaments dieses Landes. Von Hans Egede. 4to.

Promptuarium Rerum Naturalium et Artificialium Vratislaviense præcipue quas collegit D. J. Chr. Kundmann. 4to.

Genera et species Plantarum Fossilium. Auctore F. Unger. 8vo.

Pseudodoxia Epidemica: or enquiries into very many received tenets and commonly presumed truths. By Dr. Thomas Browne. Folio.

Memorie per servire alla storia di Polypi Marini di Filippo Carolini. 4to.

Ueber die grosse Seeblase (Physalia arethusa) und die Gattung der Seeblasen im Allgemeinen. Von J. Fr. M. v. Olfers.

Memoire sur la Conformité Organique dans l'Echelle animale. Par Ant. Duges.

Orthoptera descripta et depicta a F. de Charpentier. Fascic. 1—10. 4to.

De corporibus marinis Lapidescentibus. Auctore Aug. Scilla. 4to.

Illustrations of the recent Conchology of Great Britain and Ireland. By Capt. Thos. Brown. 2d edition. 4to.

Sammlung meistens Deutscher Vögel. Von D. Ben. Chr. Vogel. Folio.

Honneurs funébres a la memoire de M. de Montyon.

Descrizione dei Pesci e dei Crostacei fossile nel Piemonte dell Dott. Eugenio Sismonda. 4to.

Aparato para la historia Natural Espanola. Tomo primo. Auctore el Rmo. P. Jos. Torrubia. Folio.

Beiträge zur Entwickelungsgeschichte des Hühnchens im Eye Von Dr. Pander. Folio.

Recherches anatomiques sur les Reptiles regardes comme douteux par les naturalistes. Par F. G. Cuvier.

Description des coquilles fossiles de la famille des Rudistes. Par Oscar Rolland du Roquan. 4to.

Entomologie Française. Rhyncotes. Par C. J. B. Amyot. 8vo.

August 12th.

Historia naturalis Curculionum Sueciæ. Auctore G. Bonsdorff. 2 pts. 4to.

Note por una Bibliografia Malacologica serio al 1840 inclus. (Porro.)

Observations upon a report of the Select Committee on Salmon Fisheries, Scotland. By Robert Knox.

Memoire sur quelques coquilles fossiles nouvelles du Bassin Sous-Pyreneen. Par M. J–B–Noulet.

Revue critique des Poissons fossiles figurés dans Littiolitologia Veronese. Par L. Agassiz.

Catalogue des Mollusques marins sur les cotes des Boulonnais. Par M. Bouchard-Chantereux.

An essay on Scientific nomenclature. By the Rev. F. O. Morris.

Observations sur l'emploi de l'Escargot ingéré vivant. Par L. Legrand.

Discours sur la Zoologie fossile. Par M. le Dr. Grateloup.

Summary of the Progress of the Zoological Society of London for 1850. By D. W. Mitchell.

Zoological Society of London. Account current for 1850.

Descriptive catalogue of Shells. (Gray.)

Organisation de la Société Philomatique et réglément de ses travaux.

Proceedings of the Berwickshire Naturalists' Club. No. 18 and No. 1, Vol. 3.

Amtlicher Bericht über die Versammlung deutscher Naturforscher und Ärzte zu Breslau im Sept. 1833. Von J. Wendt und A. W. Otto.

Transactions of the Entomological Society of London. 1st series, 5 vols. 2d series, pts. 1, 2 and 3; and Journal of Proceedings of same, Nos. 1—10.

Taxidermy made easy, &c. By John Tyrer. 12mo.

A treatise on the form of Animals, by the late Henry Cline, Esq. By J. P. C. 12mo.

Bibliographie entomologique. Par Charles Nodier. 12mo.

Chambers' Educational Course. Rudiments of Zoology. 8vo.

Essai sur les cavernes á ossements et sur les causes qui les y'ont accumules. Par Maneul de Serres. 3me. ed. 8vo.

The Harleian Diary System. By William Harley. 8vo.

A diary of the wreck of H. M. S. Challenger on the Western Coast of South America in May, 1835. 8vo.

Botanique cryptogamique. Par J. Payer. 8vo.

Die Cetaceen Zoologisch-anatomisch dargestellt. Von W. Rapp. 8vo.

Musæum Plossionum zoologicum. 8vo.

Notions élémentaires de Statisque. Par J. J. O. D'Halloy. 8vo.

The complete Horseman and expert Farrier. By Thomas De Grey, Esq. 2d edition. 4to.

De Diergaarde en het Museum van het genootschap Natura artis magistra te Amsterdam. Door E. Schlegel. 8vo.

Descrizione di una nuova famiglia e di un nuovo generi di Testacei di Catania. Da Guiseppe Gioni. 8vo.

Tabular view of the principal fossiliferous deposits of the British Isles. By John Morris.

Encyclopédie d' Histoire Naturelle. Mammiferes, series 4 et 5.

Histoire naturelle des Crinoides vivans et fossiles. Par Alcide D'Orbigny. Nos. 1 et 2.

Recent Conchology of Great Britain and Ireland.



September 2d, 1851.

Vice President BRIDGES in the Chair.

A letter was read from the Trustees of the New York State Library, dated Albany, August 11th, 1851, acknowledging the receipt of late numbers of the Proceedings.

Also a letter from Mrs. Charlotte H. Townsend, dated Philadelphia, 1851, returning her acknowledgments for certain resolutions recently adopted by the Academy.

Mr. Lea remarked that he had observed in a recent number of the Proceedings of the Boston Society of Natural History, a communication on the subject of the "Wave Theory," in regard to the dynamics of earthquakes. He observed that this "wave theory" was by no means of as recent a date as was generally imagined, and stated that Dr. Franklin, while in France in 1782, distinctly suggested this wave motion, produced by a central force reaching to an immense distance. Mr. L. read part of Dr. Franklin's letter to the Abbé Soulavie, (Trans. Am. Phil. Soc., Vol. 3, p. 1, old series,) dated at Passey, September 22d, 1782, in which he says, "But we are still subject to the accidents on the surface, which are occasioned by a wave in the internal ponderous fluid: and such a wave is producible by the sudden violent explosion you mention, happening from the junction of fire and water under the earth, which not only lifts the incumbent earth which is over the explosion, but impressing with the same force the fluid under it, creates a wave that may run a thousand leagues, lifting thereby successively all the countries under which it passes."

September 9th.

Vice President BRIDGES in the Chair.

A communication was read from Aug. A. Gould, M.D., and D. Humphreys Storer, M.D., Executors of the late Amos Binney, M.D., of Boston, dated Boston, July, 1851, presenting, in accordance with his will, a copy of Vols. 1 and 2 of his work on the Terrestrial Mollusks of the United States.

Dr. Leidy called the attention of members to a fragment of rock a few inches square, covered upon one surface with numerous root-like fibres, which he stated belonged to a species of branching, fresh water, ciliated polyps of the genus Plumatella. The piece had been broken from a slab 18 inches square, which was entirely covered upon its under surface in the same manner. The species he characterized as follows:

PLUMATELLA, *Bosc.*

PLUMATELLA DIFFUSA, *n. s.*

Polypidom diverging from a centre over large surfaces, consisting of a series of simple curved branches, from one to two lines long, rising from one another upon the convex side, and attached throughout their length except at the extremities for 1-4th to 2-5ths of a line, which are erect, keg-shaped, or a little dilated at the middle and contracted at the orifices. Border of the orifices deeply emar-

ginate and continuous with a fissure down the inner or concave side of the branches, upon the summit of a slight ridge. Color dirty olivaceous brown, with the erect extremities of the branches yellowish or translucent whitish.

Polyp with 42 divergent, sigmoid tentaculæ, arranged at their summits in the outline of a reniform disk. Length of the tentaculæ about 3-5ths line. Color of the stomach greenish yellow.

Ovum with its marginal sheath semi-oval, 1-68th in. long, 1-333d in. broad. Sheath whitish, translucent, smooth, cellular; with the aperture upon its convex side 1-142d in. in diameter; that upon the flat side 1-133d in. Ovum lenticular, reddish brown.

Habitation.—Upon the under surface of stones which do not come in contact entirely with the ground, in running brooks and creeks emptying into the Schuylkill and Delaware rivers, and also in the latter.

Remarks.—This species of Plumatella appears to prefer for its residence stones of large size. It is not common to find it on such as are under 3 or 4 inches square, but is frequently seen covering surfaces closely from one to several feet square, upon which I have counted from 150 to 300 polyps to the square inch. It also flourishes best in the course of currents of moderate strength.

The object of its occupying the under surface of stones appears to be not so much to escape from the light, as it is to favor the removal of the abundant excrement, which is voided in the form of oblong, greenish or clay colored pellets.

The interior structure of Plumatella corresponds pretty closely with those of Alcyonella.

The extruded ova are frequently found attached to rocks, generally by the flat side, but sometimes by the convex side.

The sheath of the ovum is composed of transparent colorless cells, about the 1-4000th in. in diameter.

Whilst observing this species of Plumatella under a lens, I noticed several small aquatic larvæ, probably of a species of Hydrophilus according to my friend Dr. Le Conte, which would advance the anterior part of the body, up the erect portion of the branches of the polypidom, with all the stealth of a spider, until upon a level with the margin of the orifices, when they would suddenly dart with great rapidity upon the body of the polyps: but in every instance for a quarter of an hour in which I observed them, the latter succeeded in escaping by contracting within the tubes, where the larvæ appeared not to be disposed to follow them.

—

Dr. Leidy observed that he had for some time past been collecting materials towards elucidating the natural history of the family of Gordiaceæ, *Siebold*, upon which he was now preparing a memoir for the Journal.

Our most common species has been confounded with the Gordius aquaticus, *L.*, of Europe, but a striking character at once proves it to be distinct. The caudal extremity of the female is trifurcated, while that of the European species is blunt.* The length is from 4 to 12 inches. Of this species there are several varieties from different localities, which may upon further comparison prove to be distinct species.

To this species the name Gordius varius was proposed. A second species of

* Siebold: Arch. f. Naturg. 1838, p. 303.

Gordius was obtained by Professor Baird from a spring in Essex county, New York. It is very much more delicate than the former, and from 5 to 7 inches long. The female caudal extremity is blunt The male caudal extremity is bifurcate and fringed with peculiar epidermoid appendages.

For this second species the name Gordius lineatus was proposed.

Dr. L. also had found several remarkable species of Mermis, *Dujardin*.

Eleven specimens of one species were procured by Dr. Budd from a ditch in New Jersey. These are yellowish white in color, and from 6 to 18 inches in length. To the species the name Mermis elongata was given.

A second species was found in a ditch near Philadelphia. It is pure white in color, 8 inches long, and has a peculiar tubercular thickening of the integument upon the caudal extremity. For this species the name Mermis crassicaudata was proposed.

Dr. L. further remarked that he had lately had an opportunity of repeating his former investigations* upon the embryology of Gordius varius.

The embryology of Gordius aquaticus, *L.*, had been studied and published by Gruby† before he had published his notes, but he did not know it at the time, which he considered important, as the observations conducted in two parts of the world, though differing in several specific points, were generally confirmatory of one another.

The perfect embryo of Gordius varius differs so much from the parent that it is impossible to recognise the latter in the former. This has two circles of protractile tentaculæ, each of six, and a protractile proboscis, not uncinate, however, as in the embryo of Gordius aquaticus‡, no trace of which exist in the parent. The body of the embryo consists of two portions, and is distinctly annulated, while the parent is simply hair-like in form, and has no trace of an annulated integument. Gruby remarks he never saw the Gordius, excepting the embryo, shorter than 3¼ inches,§ so that between the annulose, tentaculated embryo, in the Gordius varius the 1-466th of an inch in length, and the parent of at least 3¼ inches, nothing whatever is known of the history of the animal. Gordii have been stated upon numerous and the most reliable authorities to have been seen in the body of insects, so that from the embryo to the parent, there may probably be a series of forms in alternating generation, entozoic and ectozoic, as numerous and unlike as has been observed in the development of certain species of Distoma.

The Gordius varius is prolific in a very remarkable degree. A female 9 inches in length placed in a tumbler of water, September 25th, up to the present time has extruded a string of ova 49 inches in length and still actively continues the process.

September 16th.

Vice President BRIDGES in the Chair.

Dr. Le Conte, of New York, read a continuation of his paper, entitled "An attempt to classify the Longicorn Coleoptera of the part of America north of Mexico;" which being intended for publication in

---

* Proc. Acad. Nat. Sci., Vol. 5, p. 98.
† Archiv für Naturgesch. 1849, p. 358.
‡ Ibid, pl. 7, fig. 10.
§ Ib. p. 374.

the Journal, was referred to Dr. Zantzinger, Dr. Leidy, and Prof. Haldeman.

Dr. Leidy presented a paper entitled "Conspectus Crustaceorum quæ in Orbis Terrarum circumnavigatione, Carolo Wilkes e Classe Reipublicæ Fœderatæ duce, lexit et descripsit J. D. Dana," intended for publication in the Proceedings of the Academy. Referred to the committee on a former paper on the same subject by Mr. Dana.

A letter was read from the Imperial Society of Naturalists of Moscow, dated 6th and 18th May, 1851, presenting the numbers of the Bulletin of that Institution announced this evening.

Dr. LeConte exhibited a series of tertiary fossils from San Diego, California; they bore the closest resemblance to species now living on that coast: the formation is of great extent along the coast, although very narrow. In passing from San Diego to the Colorado river, he observed that these tertiary beds were soon succeeded by various kinds of porphyry, and these by sienitic metamorphic rocks; the upper beds of these exhibited a very curious arrrangement, being light coloured, with fusiform masses of darker sienite, all placed with their longitudinal axes parallel. The sections of these masses were 5—18 inches long, and 1¼ to 3 inches thick; these metamorphic rocks became more granitic, and in some places gneissoid in their character towards the central part of the Sierra. Near Valleido these micaceous strata were much contorted. The eastern range of the Sierra at this point consists entirely of a very coarse conglomerate, containing rounded masses from the above mentioned metamorphic rocks of immense size: the cement is granitic gravel, with a very small amount of calcareous matter. Dr. LeConte was inclined to consider this chain, which is near 5000 feet high, as belonging to the cretaceous epoch; it is flanked by a small deposit of unstratified drift, which becomes stratified a few miles distant from the base of the mountains. Underlying the drift is a tertiary formation containing small beds of sandstone and gypsum, precisely as at San Diego: only Ostrea were found in these beds. In a small hill north of Cariso Creek, he had found limestone beds composed almost entirely of Gnathodon, and farther in the desert the same shell was found in strata of clay, lying almost vertically. The desert has two levels, the lower being covered with alluvium, containing numerous Planorbis and Anodon, with smaller fresh water species now inhabiting the Colorado; the upper level is about 50 to 70 feet above this alluvium, and consists of stratified matter usually very sandy, and belongs to the drift epoch. The range of sand hills is formed from the lighter portions of this upper level near the edge. In the northern part of the desert is a salt lake, on the edge of which is a solfatara with boiling water and mud; some of the water issues in jets from small cones of inspissated mud, which form over the circular pools. The water deposited large quantities of sal ammoniac tinged with sulphur, and within a short distance from these pools are eight small volcanic mounds of lava and pumice; for many miles stranded pieces of pumice are found on the alluvial level.

Dr. LeConte also expressed his opinion that the Vancouver Island coal belonged, like that found in Oregon, to the tertiary epoch; it was very fragile and light, exhaled a peculiar odor which is characteristic of tertiary lignites.

It existed in a single stratum (as he learned from persons who had visited the

bed,) of 22 inches in thickness, horizontal, and but a short distance from the surface. The shafts sunk had not yet reached any other deposit.

No distinct vegetable impressions had been found, although Dr. L. had carefully examined a large quantity of the coal. He considered the existence of true carboniferous deposits in California highly improbable.

Dr. Leidy called the attention of the members to a pyriform mass, about three inches long by one and a half broad at the base, suspended in a vessel of water. This, he said, consisted of numerous Polypi within their Polypidom encrusting a dead branch of a tree, and was taken from a similar mass one yard long, with an additional lateral branch two feet long, found in a ditch below the city. The species he characterized as follows:

CRISTATELLA, *Cuv.*

CRISTATELLA MAGNIFICA, *n. s.*

Polypidom massive, fixed, encrusting bodies from a few inches to several feet in length, by a few lines to 2 inches in diameter, gelatinoid, consistent, hyaline, with numerous polypi upon the free surface arranged in close, irregular areolæ.

Polypi furnished with 2 lobes conjoined together in the form of U, enclosing the mouth at the base, and having diverging from the margins from 50 to 80 sigmoid tentaculæ arranged at the summit in the double outline of U, with the extremities of the arms of the latter inclining towards each other. Lip elevated, with the base of the tentacular lobe, and the lower fourth of the inner margin of the tentaculæ in the vicinity of the mouth, lake or dark rose-red colour; œsophagus colorless; stomach longitudinally folded, yellowish brown; rectum dilatable, hyaline, its extremity slightly projecting but retractile.

Length from the bottom of the stomach to the top of the extended tentaculæ 1½ lines. Long diameter of tentacular expanse ½ to 3-5th line. Length of tentaculæ 1-40th in.; breadth 1-1000th in.

Ovum lenticular, brown, enclosed at the margin by a brownish white, annular, cellular sheath, 1-200th in. deep upon one side, 1-166th in. upon the other side, furnished at its outer edge with 14 to 16 appendages 1-200th in. long, terminating in a double, rarely a triple hooklet. Ovum with its sheath, thin, discoidal, bent, 1-33d in. broad, with its appendages enveloped in a hyaline, albuminoid mass; when ripe floating.

Habitation.—Upon dead branches or twigs of trees, in ditches or sluggish streams in the neighbourhood of Philadelphia, in shaded situations.

Remarks.—The extent of this polyp appears to be determined by that of its basement of attachment. It is usually found surrounding twigs or dead branches of trees which have fallen into the water, and is permanently fixed to its position.

The surface of the polyp mass has the appearance of being covered with a dense mucor from the numerous tentaculæ projecting from it. Immediately beneath this is a layer having a faint roseate hue from the red colouring in the vicinity of the mouth of the polypi, then succeeds a layer of a dirty yellowish color, arising from the stomach of the animals, beneath which are numerous opaque, white, yellowish, and brown spots, which are ova in various stages of development, and finally the greater depth of the mass consists of a perfectly hyaline, consistent, gelatinoid substance.

After the death of the animals, and their bodies and tubes have macerated from the surface of the Polypidom, their bases upon the areolæ of attachment have a irregular stellate or lobate appearance, which penetrate in a convergent manne to the nuclear twig or branch. The decaying mass has a strong odor in a re markable degree like that of putrid fish.

The animal is not so irritable as Plumatella, but is like it capable of entirel retracting within its tube, in which state the stomach appears transversel wrinkled.

The ova as they are detached from the mass rise near, or to the surface of th water and float.

There is probably some confusion existing in the distinction of the gener Cristatella and Alcyonella, as characterized by Cuvier, Lamarck, Allma &c., but if correct then C. magnifica would belong to a new genus betwee Cristatella, *Cuv.*, and Alcyonella, *Lam.*, for while the polyp and its ovum co respond to the former, the polypidom corresponds to the latter. Should it prov distinct I propose for it the name *Pectinatella.*

Dr. Leidy further stated as follows:

The female Gordius which he had mentioned at the last evening, a having extruded from September 25th up to that time a cord of ova 4 inches in length, had continued the process until Sunday evening, October 7th, u to which time it had expelled in fragments from a few lines to one foot in lengt in all a cord 91 inches long, in which he estimated there were over 6,000,000 ov Dr. L. exhibited the cord of ova preserved in alcohol, which was long and whi and resembled a piece of cotton thread.

September 23d.

Vice President BRIDGES in the Chair.

A letter was read from the Linnean Society of London, dated Jun 5th, 1851, acknowledging the receipt of numbers 6 and 7, Vol. 5, c the Proceedings of the Academy.

Dr. McEuen exhibited a specimen of the fruit of Paullownia im perialis, from the garden of Mrs. J. B. Smith of this city.

September 30th.

Vice President BRIDGES in the Chair.

The committee to which was referred the continuation of Dr Le Conte's paper on the Longicorn Coleoptera of the United States r. ported in favor of publication in the Journal.

The Committee to which was referred Mr. J. D. Dana's paper, rea 16th inst., reported in favour of publication in the Proceedings.

Conspectus Crustaceorum quæ in Orbis Terrarum circumnavigatione, Carolo Wilkes e classe Reipublicæ Fœderatæ Duce, lexit et descripsit J. D. DANA.

PAGURIDEA.

The Paguridea include two groups, distinguished by peculiarities in the form of the inner antenna, outer maxillipeds, and some other characteristics;—the one *aquatic* in habit, and the other *subterrestrial*. They are as follows:

Fam. I. PAGURIDÆ.—Inner antennæ short, first joint very short. Palpus of maxillipeds with a multiarticulate flagellum. Aquatic or littoral.

Fam. II. CENOBITIDÆ.—Inner antennæ very long, the first joint of the base as long as the eyes or longer, and bent obliquely downward. Palpus of outer maxillipeds without a flagellum. Subterrestrial.

The Paguridæ have hitherto been divided into but two genera; *Pagurus*, with unsymmetrical abdomen, and *Cancellus*, (Edw.) with symmetrical. There are, however, important characteristics, which point to a division into other groups. These have been partly indicated by Milne Edwards, in the subdivisions of the genus Pagurus, laid down in his work on Crustacea,* and more distinctly in the Annales des Sciences Naturelles, for July, 1848.† In the latter article there are discrepancies in certain instances, between the character of the species and those mentioned for the subdivisions, which we find it difficult to reconcile; such as the placing of *P. tibicen*, and some related species, with his "Æquimanes," when, in fact, the left hand is very much larger than the right, and the *guttatus* and *granulatus* with the "Senestres," although, in the former, the hands are nearly equal, as in many of the "Æquimanes," and in the latter the right hand (as is observed in his "Crustacés") is actually the larger. Yet his sections are, in the main, natural groups, and some of them have more important points of distinction than he has mentioned.

The *Pagurus Bernhardus* is the type of one of these groups. Besides being "dextres," they are peculiar in having *acuminate fingers*, with the tips of those of the larger hand *calcareous*; and although the feet of the 4th pair are subcheliform, like most other Paguridæ, the scabrous area or rasp of the hand is confined nearly to the posterior edge. Moreover, the species belong mainly to colder waters, while the ordinary Paguri abound especially in the tropics. All the Paguri of England (or with but one uncertain exception, recently pointed out,) are of the *Bernhardus* type; those of the Northwest coast of America are the same. We naturally, therefore, distinguish this group as a genus under the name of BERNHARDUS.

Among the remaining Paguri, the larger part have the feet of the 4th pair subcheliform, the penult joint being broad, and the last (or tarsus) forming a finger placed on its anterior margin. Yet, a few have these feet vergiform, the tarsus being terminal; and these species are also peculiar, in having two pairs of slender appendages at the base of the abdomen, on account of which they are called the "Pagures appendicules" by Edwards. Besides, they have the flagellum of the outer antennæ more or less hairy, and often long ciliate along the under side, and, also, the inner antennæ have a longer base than usual, the 2d basal joint

* Crustacés, ii, 213, and Annales des Sci. Nat. [2], vi, 257.
† Ann. des Sci. Nat. [3], x, 59.

reaching nearly, or quite, to the extremity of the eyes. These species make a well characterized group, which we name *Paguristes*.

Another small group is singular in having a rostriform appendage to the ophthalmic joint; they are the "Pagures armés" of Edwards, including *P. miles* and *P. custos*, the former the *Cancer Diogenes* of Herbst. Besides this distinction, the fingers of the hands are acuminated, as in the Bernhardi, and have calcareous tips, although the species are not right-handed; also, the 2d joint of the outer antennæ is complete on the upper side, and there is no moveable appendage or acicle (a name we give to the so-called palpus, in allusion to its form). With these distinctions, the group is entitled to the rank of a genus, which may be named *Diogenes*.

The remaining species of Paguri are similar, in having the fingers of the hands more or less spoon-shaped;—with no rostriform appendage to the ophthalmic segment between the eyes;—the outer antennæ bearing a moveable acicle;—the flagellum of the outer antennæ naked; the 2d joint of the base of the inner antennæ not reaching to extremity of eyes;—the feet of the 4th pair subcheliform with the scabrous area on the hand, lateral and broad.

The great majority of these have the tips of all the fingers corneous. But a few have these tips in the larger hand calcareous, besides being peculiarly smooth and neat in the appearance of the limbs, and naked, or nearly so, with the shell more calcareous than usual. They have the left hand much the larger; yet unlike those species with *corneous* tips to the fingers that are strongly left-handed, the front margin has a small salient point at middle. Of the species with calcareous tips to the fingers, I make the genus *Calcinus*. This genus includes the old species *P. tibicen*, *Gaimardii*, *elegans*, &c.

The remaining species, still the larger part of the whole family, constitute the genus Pagurus. The following is a synopsis of the subdivisions proposed.

FAM. I. PAGURIDÆ.

Antennæ internæ mediocres, articulo primo brevissimo. Maxillipedis palpus externi flagello multiarticulato instructus. Species aquaticæ vel littorales.

Subfam. I. PAGURINÆ.—Abdomen asymmetricum.

I. Pedes 4ti subcheliformes. Abdomen ad basin duobus paribus appendicium infra non instructum. Antennarum externarum flagellum nudum vel nudiusculum.

1. *Annulum ophthalmicum non rostriferum. Antennæ internæ aciculo mobili instructæ.*

Gen. 1. BERNHARDUS, D.—Pedes antici depressi: digiti acuminati; manus dextra major, apicibus digitorum calcarea. Macula scabra manus 4tæ submarginalis, linearis.

Gen. 2. PAGURUS, *Fabr.*—Manus anticæ sive depressæ sive compressæ; digiti plus minusve instar cochlearis excavati, apicibus cornei; manus sinistra sæpius major. Macula scabra manus 4tæ lateralis, lata. Frons medio sive truncatus sive acutus.

Gen. 2. CALCINUS, D.—Manus compressæ, sinistra major, apicibus digitorum calcarea et instar cochlearis optime excavata. Frons medio acutus. Pedes læves, nudi vel nudiusculi.

2. *Annulum ophthalmicum rostriformem. Antennæ externæ aciculo mobili non instructæ.*

Gen. 4. DIOGENES, D.—Manus sinistra major. Digiti acuminati, apicibus calcarei.

II. Pedes 4ti vergiformes, tarso terminali. Abdomen ad basin 4 appendiculis infra instructum. Antennarum flagellum externarum plus minusve pilosum sæpe elongatè ciliatum.

Gen. 5. PAGURISTES, D. – Antennæ internæ elongatæ, apice articuli 2di extremitatem oculorum fere attingente.

Subfam. II. CANCELLINÆ.—Abdomen symmetricum. Gen. CANCELLUS, *Edw.*

FAM. II. CENOBITIDÆ.

Antennæ internæ basi longissimæ, articulo primo oculis sæpe longiore et valde deflexo. Maxillipedis palpus externi flagello non instructus. Species subterrestriales.

Gen. 1. CENOBITA, *Edw.*—Corpus angustum, carapace parce elongato, fronte non rostrato. Abdomen in cochleam retortum, superficie plerumque carnosum.

Gen. 2. BIRGUS, *Leach.*—Corpus latum, carapace parce oblongo, postice latissimo, fronte triangulato. Abdomen directum, inflexum, laminis crustaceis quoad dorsum plerumque tectum.

Specierum Paguridearum adhuc ineditarum Descriptiones.

GENUS BERNHARDUS.

BERNHARDUS NOVI-ZEALANDIÆ.—Oculorum pedunculi margine carapacis antico vix breviores, basi antennarum externarum longiores, aciculo hirsuto multo longiores; cornea non obliqua, perbrevis; squama basalis paulo angusta, apice inciso-denticulata. Pedes antici valde inæqui, fere nudi; carpo versus apicem paulo pubescens, granulato-spinuloso; manu grandi, oblongâ, parce longiore non latiore quam carpus, superficie externâ sex-seriatim tuberculatâ (marginibus inclusis) inter has series fere lævi, digito mobili carinato, crenulato, et superficie uniseriatim tuberculato, etiam tuberculis minoribus instructo. Pedes 4 sequentes marginibus dense hirsuti, vix spinulosi.

Long. 1½—2". *Hab.* in portu "Bay of Islands" Novi-Zelandiæ.

BERNHARDUS TENUIMANUS.—Frons medio subacutus. Carapax nudus. Oculorum pedunculi breves, basi antennarum externarum paulo breviores, aciculo subulato subnudo vix breviores; cornea non obliqua, brevis; squama basalis angusta, acuta. Pedes toti nudi, antici valde inæqui, granulati, granulis vix seriatis, carpi margine superiore denticulato, manu grandi tenuissimè compressâ, parce oblonga, multo latiore quam carpus, margine superiore tenuiter cristato et denticulato, inferiore tenui; manu minore carpoque angustissimè oblongis. Pedes 4 sequentes lateraliter læves, margine superno subspinulosi.

Long. 1—1½". *Hab.* in freto "Puget" Oregonensi.

BERNHARDUS ARMATUS.—Carapax subnudus. Oculorum pedunculi margini carapacis antico breviores, sive basi sive aciculo subulato subnudo antennarum externarum multo breviores; cornea obliqua, dimidii pedunculi longitudine; squama basalis subovata, apiculata. Frons marginatus, medio paulo saliens, obtusus. Pedes toti fere nudi (junioribus exceptis pubescentioribus); antici valde inæqui, usque ad digitorum extremitatem tenuiter dense spinosi, spinis partim subseriatis, manu grandi latâ, oblongâ, multo longiore et parce latiore quam carpus; 4 sequentes supra spinulosi, tarsis infra paulo lateraliter uniseriatim spinulosis.

Long. 1¼″. *Hab.* in freto "Puget" Oregonensi.

BERNHARDUS HIRSUTIUSCULUS.—Frons medio subacutus. Carapax brevis, sparsim pubescens, regione antico transverso. Oculorum pedunculi perbreves, basi antennarum externarum multo breviores, aciculo subnudo parce breviores; cornea vix obliqua; squama basalis ovata, non acuta. Pedes antici valde inæqui, angusti, carpo manuque pubescentes et granulato-scabri, margine superiore crassi, non spinulosi nec denticulati; manu oblongâ (duplo longiore quam latitudo) paulo breviore parce latiore quam carpus. Pedes 4 sequentes hirsutiusculi, non spinulosi, tarsis paulo compressis, infra subtiliter spinulosis.

Long. 1¼″. *Hab.* in freto "Puget" Oregonensi.

BERNHARDUS PUBESCENS.—*B. hirsutiusculo* affinis. Frons medio subacutus. Carapax longior, fere nudus, regione antico non transverso. Oculorum pedunculi longi, margine carapacis antico non breviores, basi antennarum externarum parce longiores, aciculo multo longiores; cornea non obliqua; squama basalis subovata; apice rotundata. Pedes antici valde inæqui, angusti, carpo manuque pubescentes; scabriculi, non sparsim granulosi, carpo ad marginem superiorem minute spinuloso manu oblongâ (duplo longiore quam latitudo) paulo breviore parce latiore quam carpus. Pedes 4 sequentes pubescentes, non spinulosi.

Long. 1″. Hab. ? Conchæ quas habitant oris Americæ septentrionalis invenientur.

GENUS PAGURUS.

1. *Frons medio truncatus. Squama oculorum basalis lata.*

PAGURUS FABIMANUS.—Frons medio fere rectus. Carapax plerumque nudus regione antico parce transverso. Oculi longiusculi, basi antennarum longiores; squama basalis lata, inverso-triangulata. Pedes antici valde inæqui, manu majore oblongâ, marginibus fere parallelis et subacutis, superiore spinuloso, inferiore crenulato aut subintegro, superficie externâ bene convexâ, tomentosâ, scabriculâ, digito mobili superne fere ad apicem minute spinuloso. Pedes 4 sequentes leviter hirsuti, tarsis prælongis, tarso pedis sinistri tertii subtriquetro, superficie hujus articuli præcedentisque externâ aut planâ aut subconcavâ, tomentosâ, margine superiore non spinuloso.

Long. 1¼″. *Hab.* ad oras insulæ "Mindanao" Indiæ orientalis.

PAGURUS SCABRIMANUS.—*P. fabimano* fermè affinis, formâ carapacis, manus squamæque oculorum basalis similis. Oculi parce breviores, basi antennarum externarum longiores, internarum non longiores. Manus major extus non tomentosa, nudiuscula, scabricula, supra spinulosa, infra denticulata aut crenulata, digito mobili supra vix spinuloso, carpo supra extusque prope apicem spinuloso. Pedes

PAGURISTES HIRTUS.—Rostrum brevissimum. Carapax plerumque hirtus Oculi graciles margine carapacis antico non breviores, basi vel aciculo antennarum externarum multo longiores, basi internarum breviores, squamâ basali valde elongatâ, angustâ, margine externo arcuato et tenuiter bene denticulato Flagellum antennarum externarum infra elongate ciliatum. Pedes 2di 3tii hirti crassiusculi.

Long. 2". *Hab.* in mari Sinensi.

GENUS CENOBITA.

CENOBITA CARNESCENS.—Regio carapacis antica plana, scabricula, lateribus quoque plana. Oculi fronte longiores, plus duplo longiores quam altitudo, valde compressi, squamâ basali triangulatâ, acutâ. Pedes antici inæqui, sinistro majore superficiem granuloso, carpo paulo breviore quam manus, brachio apicem obliquo plano-truncato. Pedes quatuor sequentes fere nudi, parce pubescentes, articulo ultimo scabriculo.

Long. 1¼—1½". *Hab.* in archipelago "Paumotu."

CENOBITA BRUNNEA.—Regio carapacis convexa, nuda. Oculi fronte paulo breviores. Pedes antici validi, paulo inæqui, manu carpoque hirsutis, manu spinulis minutis sparsis scabriculâ, brachio apicem rotundato. Pedes 4 sequentes hirsuti, articulo ultimo subterete, longiore quam penultimus.

Long. 3". *Hab.* ad insulam "Upolu" Samoensem. Abdomen nuce myristicæ sæpe tectum.

The Committee to which was referred Dr. J. C. Fisher's description of a new species of Cicada, with Mr. Cassin's Notes on the same and on C. septendecim, reported in favor of publication in the Proceedings.

On a new species of Cicada.

BY J. C. FISHER, M. D.

In the course of the observations made by the Committee of this Academy, to which was assigned the duty of investigating the habits and history of the seventeen year Locust, Cicada septendecim, which appeared during the present year (1851) in the neighborhood of Philadelphia, the attention of its members was directed by Mr. John Cassin to the fact, that two species had been confounded, and that the insect regarded as the smaller variety was in fact a distinct species, a conclusion at which he had arrived during their previous appearance in 1834. It is much smaller, is blacker in color, especially on the lower surface of the abdomen, where also the segments are bordered more narrowly with yellow, and has a note *entirely different* from that of the larger Cicada septendecim, Linn. Syst. Nat. i. pt. ii. p. 708, (1767.)

The two species did not associate together, but were found mostly on separate trees, the smaller being the less abundant.

I propose on these grounds to characterize the smaller species as follows:

Cicada Cassinii, nobis. ♂ total length of body 9-10ths of an inch, of the wings 1 2-10ths inches; ♀ frequently smaller.

Colors and general appearance much like those of Cicada septendecim, Linn.,

in some part of the country every year. Assuming all that part of North America in which it has ever been observed to be its zoological province, how are the sub-provinces and different times of appearance to be accounted for? Are all those sub-provinces to be regarded as the theatres of independent creations? Do the facts demonstrate that the same species may exist in provinces which may be presumed to have had different eras of origin?

It would be a curious fact, and one of important application, that exactly the same species can inhabit provinces having independent creations, and if, too, as in the case of this insect, it should be clearly impossible for it to have extended from one province to another.

Or, can it be possible that every distinct district in which the *Cicadæ* appear is really an entomological province, and that entomological provinces in this part of North America are quite restricted in extent, as has been observed by Dr. LeConte in California? (Communicated by that gentlemen to the American Association for the advancement of Science at its meeting in August, 1851.)

Those sub-provinces may have relations to geologic changes. Having the extraordinary characteristic necessity of remaining in the earth for seventeen years, as a fact in the history of this insect, may it be possible to infer that geologic changes have effected the difference in the times of its appearance, or that so short periods as fractions of seventeen years have been of geologic importance throughout the range of the Cicadæ?

The *Cicada septendecim* has appeared in the vicinity of Philadelphia, at intervals of seventeen years, certainly since 1715. There has been, it appears, no variation of temperature, nor causes accidental nor other since that date sufficient to affect its habits in any perceptible degree. It is stated in Clay's Swedish Annals, to have appeared in May, 1715, in this neighborhood, (which, so far as I know, is the earliest authentic record;) punctually in the same month, every seventeenth year, now certainly for nearly one hundred and fifty years, has this extraordinary insect been known to make its visit. No causes have affected it during that period, not even so far as relates to the month in which it appears.

Passing, I would observe that so far as relates to the neighborhood of Philadelphia, the *Cicada septendecim* clearly had not a fair start with the year 1,—anno mundi of the commonly received chronology. If it had had, the sum produced by 1851+4004—1 ought to divide by 17 without a remainder, which it will not do,—more insignificant facts than which have troubled schoolmen.

I have never seen any animals more entirely stupid than the seventeen year Locusts. They make no effort to escape, but allow themselves to be captured with perfect passiveness, thus reminding one of the tameness of animals in countries where they are not molested by enemies. All animals of as high grade of organization as these insects, acquire instincts from impressions made by the presence of danger and otherwise, which they transmit to their offspring. The young Fox of to-day is undoubtedly superior to his juvenile progenitor of a century since. The *cicadæ* have acquired no such instinct. Their short life of maturity above the surface of the earth, does not appear to be of sufficient duration for such to be formed and impressed on their posterity.

In short, it appears to me that the study of these insects, and the examination of their separate ranges, might result in conclusions of extraordinary importance, especially relative to modern views of the distribution of animals. No animal is

more easily traced. In other aspects, too, they present interesting points for study, perhaps of general interest in zoological science.

Dr. Zantzinger offered the following, which was adopted,

Resolved, That a member of the Society be appointed to prepare a new and extended "Notice of the Academy," to be read before the Society, and designed for publication.

The Chairman on motion being authorized to make the appointment, selected Dr. Ruschenberger, who accepted the same.

ELECTION.

The Rev. Lorenzo L. Longstreth, of Philadelphia, was elected a *Member* of the Academy.

October 7th.

Vice President BRIDGES in the Chair.

Dr. Leidy read a paper intended for publication in the Proceedings, entitled "Corrections and Additions to former papers on Helminthology published in the Proceedings of the Academy of Natural Sciences of Philadelphia," which was referred to Dr. Zantzinger, Dr. Fisher, and Dr. Watson.

A letter was read from the Secretary of the Geological Society of London, dated May 1st, 1851, acknowledging the receipt of recent numbers of the Proeeedings.

Dr. Leidy remarked, the members probably recollected that a few evenings since he had mentioned, that it had been asserted by numerous and good authorities, that Gordii had been observed within the body of insects. He now exhibited a specimen of a Gordius and a grasshopper, preserved in a bottle of alcohol, which had been sent to him by his friend Dr. Budd, of Pemberton, New Jersey. The Gordius, Dr. Budd stated, was seen to come out of the body of the grasshopper, and in a half an hour afterwards died. It is a different species from those described a short time since. It is a female, about six inches long, by half a line in length, rigid, strongly marked by transverse wrinkles, and annuli, with the caudal extremity somewhat compressed and obtuse. To the species he gave the name Gordius robustus.

He also exhibited a species of Mermis from Brazil, belonging to the collection of the Academy. It is fourteen and a half inches long, and of a reddish brown color. To it he gave the name Mermis ferruginea.

October 14th.

Vice President BRIDGES in the Chair.

Mr. Cassin read a paper entitled "Catalogue of the Caprimulgidæ in the collection of the Academy of Natural Sciences of Philadelphia,"

which was referred to Dr. Wilson, Col. G. A. McCall, and Dr Watson.

Mr. Charles Girard read a paper entitled "Historical Sketch of th Gordiaciæ," which, being intended for publication, was referred to Committeee consisting of Dr. Leidy, Dr. Hallowell, and Dr. Horner.

Dr. Fisher read a note from Dr. C. D. Meigs, announcing that h was now prepared to read before the Society his biographical Memoi of the late Dr. Morton.

Professor Horner narrated a case illustrating the extreme lethargy produced by the action of Carbonic acid gas on the human system. The individual, while engaged in burning lime, had fallen asleep during the night upon the edge of the kiln, and had been exposed to the action of this gas for many successive hours. A great part of the right fore arm, arm, scapula, and back had been severely burned, without the knowledge of the patient, until he was extricated by persons passing next morning.

Dr. Leidy presented for the inspection of the members a mutilated cranium of an extinct mammal, formerly characterized by him under the name of Oreodon robustum.* It was one of five specimens of crania of the same species lately received through Professor Baird from the Smithsonian Institute. When first obtained, one side was completely enveloped within a matrix, upon the removal of which the complete dentition of the animal was disclosed. The teeth form a continuous arch as in Anoplotherium. The formula is m. $\frac{3}{3}$, p. m. $\frac{4}{4}$, c. $\frac{1}{1}$, i. $\frac{3}{3}$ upon each side.

Dr. L. also exhibited three inferior molars of the Rhinoceros occidentalis,† of which the posterior measured seventeen lines antero-posteriorly, and ten lines transversely; the others about fourteen lines antero-posteriorly, and ten lines transversely.

—

Dr. Fisher offered the following, which was adopted.

Resolved, That an invitation be sent by the Secretary, through the Dean of each of the four Medical Colleges, of this city, to the students attending lectures at the respective institutions, to visit the Museum of the Academy on Tuesdays and Fridays, (public days,) and to inform them that they will be admitted upon exhibiting their matriculation tickets.

Mr. Vaux offered the following, which was also adopted.

Resolved, That the Committee appointed at a meeting of the Academy, held May 16th, 1851, to select a Biographer of the late Dr. Morton, be requested to obtain a suitable place for hearing the Memoir by Dr. Meigs, and to make such other arrangements as may be requisite.

---

* Proc. Ac. Nat. Sci., 5, 238. † Ibid, 119.

October 21st.

Vice-President BRIDGES in the Chair.

Mr. Lea read a paper on the genus *Acostæa* of D'Orbigny, a new fresh water mollusc of the order *Dimyaria*, from the river Guadua, New Granada.

Mr. Lea considers this shell as one of the most remarkable and interesting which has ever come under his notice. The fact that it is in its young state a free *bimusculose* shell, and in its mature state an affixed *unimusculose* shell, places it among the anomalies which zoologists find it difficult to understand, but which, in this case, points out its true position in a natural arrangement. Mr. Lea expressed his convictions that this shell, now so well described by M. D'Orbigny, belonged to the same genus which Ferussac described in 1823, in the Mem. of the Soc. Nat. Hist., Vol. 1, under the name of *Mulleria*, if it be not of the same species, a single specimen (adult) of which had then only been seen. Ferussac, considering the general resemblance of *Mulleria* to *Ostrea*, thought it ought to be put alongside of, if not in, the latter genus. Brongniart and Latreille thought it ought to go between *Spondylus* and *Arca*. Other authors had assigned it to various positions, while some doubted whether it was anything more than a malformation. The perfect specimen, in its junior and adult state, if it be *Mulleria*, now banish all difficulties. Mr. Lea thinks now, in placing *Mulleria* (Acostæa) in its true position, at the head of the order *Monomyaria*, where it makes the link with *Dimyaria*, it forms an easy transition from the first to the second order. Thus retaining the trace of one while it passes so curiously into the other. *Nihil per saltum.*

Mr. Lea, under the impression that D'Orbigny's *Acostæa Guaduasana* may prove to be a distinct species from the shell described by Ferussac, under the generic name of *Mulleria*, while it may belong to the same genus, proposes to give the name of that distinguished zoologist to it. That of *Guaduasana* should be retained of course for D'Orbigny's species. The genus would then represent *Mulleria Ferussacii*, and *Mulleria Guaduasana*.

The paper being intended for publication in the Journal, was referred to Dr. Leidy, Dr. Ruschenberger, and Dr. Wilson.

Dr. Fisher, on behalf of the Committee on the Memoir of Dr. Morton, reported that they had selected the Hall of the University of Pennsylvania, and had appointed the first Thursday in November as the time for hearing the Memoir read by Dr. Meigs, provided the consent of the Trustees of the University could be had, notice of which would be given.

On motion of Dr. Leidy, it was

Resolved, That persons, not members of the Academy, who may contribute to the Museum or Library specimens of Natural History or Books, deemed of sufficient value by the Curators or Librarian, be entitled to a ticket of admission to the Museum on public days, for a period of six months.

Dr. Leidy exhibited three broken teeth, consisting of the body of a canine and that of two posterior molars, which, he observed, were fossils from Nebraska Territory, and belonged to an animal closely allied to the genus Ursus. The tubercles upon the crown of the molars are more elevated and conoidal than in the recent bears, and the crown of the canine is relatively more robust. He proposed for the animal the name of Arctodon.

Dr. L. stated that he was preparing a memoir, in which would be described in detail all the fossil remains of Mammalia from Nebraska Territory, heretofore characterized by him in the Proceedings.

He next presented for examination a species of fresh-water sponge found growing in the Delaware and Schuylkill rivers, in the vicinity of Philadelphia, which he characterized as follows:

SPONGILLA FRAGILIS.—Discoidal, lichenoid, growing in patches, flat, oval or circular, lobate at the margin, translucent, yellowish-white or cream-colored. Areolæ distinct, subcircular. Reproductive bodies arranged in a single close layer at the base of attachment of the sponge, shining, whitish-yellow, elevated into a central papilla upon the upper surface.

Measurements.—From ½ to 2 inches in diameter by 1 to 1½ lines in thickness at the centre and gradually thinning off to the margin.

Habitation.—Grows upon the under side of stones below low water mark in the Rivers Delaware and Schuylkill.

Structure.—Composed of an intertexture of spiculæ about 1-400th of an inch long, having a minutely tuberculated surface, over which is reflected a granulo-cellular membrane.

Remarks.—After the death of the sponge, the areolated tissue macerates off, leaving the reproductive bodies in a close layer attached to the rock. The living sponge is never green, nor does it ever grow exposed to the light.

Dr. L. further stated that another species of fresh-water sponge is not uncommon in our rivers, which grows exposed to the light, and is green in color like the European Spongilla fluviatilis, but whether it is specifically distinct from the latter, he has not yet ascertained.

October 28th.

Vice-President WETHERILL in the Chair.

The Committee to which was referred Mr. Lea's paper on the genus Acostæa, of D'Orbigny, reported in favor of publication in the Journal

The Committee to which was referred Mr. Cassin's "Catalogue of the Caprimulgidæ in the Collection of the Academy of Natural Sciences of Philadelphia," reported in favour of publication. [☞ *For this paper see the end of the present number.*]

The Committee to which was referred the following paper of Mr. C. Girard, reported in favor of publication in the Proceedings.

Historical Sketch of Gordiaceæ.

By Charles Girard.

I.

There are groups, amongst the invertebrates of the animal kingdom, whose natural history has made but little progress, although known to science for more than half a century.

The animals of which they are composed being generally of a diminutive size, modest in form, modest in colors, have been looked at with indifference, thought unworthy of a careful investigation, and deemed of too small an importance in a general system of classification.

Every living being, however, is entitled to occupy a rank in the creation; every one has its place, its aim, and its design.

Yet some are called enigmatic, paradoxical, doubtful,—as if to the Creator's mind, any thing or any being could be either an enigma, a paradox, or a doubt. Such groups, we must acknowledge, present great difficulties to investigators: but let investigators be patient and laborious, and they will gradually sweep away the enigmas, the paradoxes, and the doubts.

When the researches on a group are slow, and embrace a long period, then it becomes necessary, for the safe and future advancement of its natural history, to recapitulate all the data in their chronology. These data will become a guide into the various desiderata for new observations.

Most diverse opinions are still entertained concerning Gordiaceæ, and important zoological questions are still waiting the results of further investigations.

Are Gordiaceæ indigenous in America, or introduced from abroad? If they are indigenous amongst us, are they identical with, or specifically different from, the European species?

Here commences a labor of comparison between the internal structure and external appearance of specimens from both countries. Besides, specimens from all the localities of one country should be compared, in order to ascertain the number of species. Their embryology and metamorphosis must be traced; their habits recorded, in order to enable us to assign a natural position to that family in the class of worms.

If they are introduced on this continent, how, where, and how long since, did that event take place? What is their geographical distribution and progressive migration to the places where they are now found?

Some facts, which we already possess, and which are related hereafter, rather enforce the belief of their aboriginal nature, than that of their introduction. Even in the case of an identity between the American and European Gordiaceæ, these worms still deserve special attention from American anatomists, as the latter might be successful in elucidating the controverted anatomical questions which divide the naturalists of the old world.

II.

The genus *Gordius* was established by O. F. Müller during the last century.* Under that name were included aquatic worms, others living in moist grounds,

* Vermium terrestrium et fluviatilium historia, 1773.

and still others, more numerous, found as parasites in the body of other animals Those which lead a permanent parasitical life, constitute now the genus *Filaria* of the same author,* which has been admitted by all subsequent naturalists, and more than forty species of these are described by Rudolphi.† But there has been a general belief, that the only difference between Gordius and Filaria consisted in their habits, no zoological characters having as yet been detected.

Lamarck‡ even says, that the species of Gordius were probably Filariæ; and if he has kept those two genera, it was merely in accordance with a prevailing practice.

Cuvier‖ places Gordii at the end of the annelids, thus made to follow the leeches, remarking, however, that they might perhaps come nearer the intestinal worms. He was unacquainted with the fact, since ascertained, that several species of true Gordius may be found, at a certain season of the year, within the body of other animals.

The genus Filaria is placed, by the same author, at the head of intestinal worms. Its characters are derived from the external appearance, which, however, he (Cuvier) acknowledges, resembles closely that of Gordius.

Should a generic difference hereafter be found between Gordius and Filaria, in their anatomical structure, and we think it very likely to be the case, besides the difference of embryonic development which already distinguishes them, we shall have that peculiarity in their habits which makes Filaria to occur in such cavities of the body of other animals having no communication with the exterior, whilst Gordii, when occasionally found within other animals, occur in the intestinal canal; that is to say, in a cavity which communicates directly with the surrounding medium. This fact is of no small importance.

The letter of Mr. Jacobson, to de Blainville,§ relates to Filaria, and not to Gordius, as its title would lead any one to believe.

Mr. Charvet,¶ in describing two species of true Gordius, thinks that these worms are indifferently external and internal, and that the distinction made between Filaria and Gordius becomes thus insignificant. But he is inclined to believe that, if it can be proved that Filariæ have a mouth provided with a sucking apparatus, the character would be generic. He was not prepared, by direct observations, to decide upon this fact.

Leon Dufour** alludes to Gordii, and rejects the idea of an identity between them and Filariæ, considering the first as true Annelids, and the second as true Entozoa; there existing, he says, a mere external resemblance, which can only be proved to depend on identity of structure by anatomical investigations.

---

* *O. F. Müller*, in Naturforscher. Vol. xxii., 1787.

† Entozoorum sive vermium intestinalium Historia Naturalis. (3 vol. 8vo., 1808—1811), Vol. ii. p. 55 et seq.

‡ Histoire naturelle des Animaux sans vertèbres. Vol. iii., 1809, p. 670.

‖ Le Règne Animal distribué d'après son organisation, vol. iv., 1817, and 2d ed. vol. iii., 1829.

§ Extrait d'une lettre adressée à Mr. de Blainville sur le dragonneau. Ann. Sc. Nat. 2de série i. 1834, p. 320.

¶ Nouvelles Annales du Muséum d'histoire naturelle. Vol. iii. 1834, p. 37.

** Annales des Sciences Naturelles, 2de série, vol. vii., 1837, p. 7.

Prof. Siebold* speaks of Filariæ of various kinds of insects, resembling Gordii, which lived for some time in clear water, in which they had been placed. He afterwards discovered the fact† that sexes of Gordii were individualised, and males more numerous than females; and, withdrawing Gordii from Entozoa, he places them actually among Annelids. Subsequently‡ he makes of Gordii a separate family, including also, the genus *Mermis* of Dujardin; the family he calls GORDIACEÆ, differing chiefly from that of *Nematoidea* in its embryonic development.

Entozoa have that peculiar mode of generation, in which several broods follow each other, without resembling each other; nor will they resemble their parent stock before the third, fourth, or fifth generation, according to the species.

The young Gordiaceæ resemble their parents as soon as hatched. There is, however, not yet a single species of that family whose eggs have been made the subject of a careful and complete study. Isolated facts only are known, and to these we shall devote a few lines further on.

There is a phenomenon, with which the naturalists of the old world are well acquainted, which takes place during the existence of Gordiaceæ, (in Mermis as well as in Gordius), it is the fact that they pass one part of their life within the body of other animals,—of Grasshoppers and Crickets, for example. They are found in the clear running waters of the meadows and fountains, early in the spring and summer; they enter the body of grasshoppers in the fall, where they deposit their eggs. These insects die, and their bodies afford to these eggs a convenient shelter during the winter, when the next spring they will hatch, and become free again.‖ Eggs, however, are sometimes found without any such nidus; whether naturally or accidentally, remains to be ascertained.

A. S. Œrsted§ agrees with Prof. Siebold in making of Gordiaceæ a separate group amongst Nematoidea, on the ground of their embryonic development.

Mr. Dujardin¶ is remarkably short, and adds nothing to our knowledge on these worms, which he still calls enigmatic.

The manner in which Mr. Emile Blanchard** has illustrated the anatomical structure of the other families of the intestinal worms, would lead us to expect from that observer, more precise facts respecting Gordiaceæ, than those we had before. But the author, at the outset, tells us that he was unable to fulfil the task he had undertaken, that is, a complete history of that family. The want of materials in such researches, added to the difficulty of experimenting, are the reasons advanced to account for the deficiency in this part of his investigations. The subject, therefore, stands precisely as it did before Mr. Blanchard undertook his anatomical researches on the class of worms.

---

* *Wiegman's* Archiv für Naturgeschichte, 1837, ii., p. 254.

† *Wiegman's* Archiv, &c., 1838, ii. p. 292, (*on the progress of Helminthology*); and 1838, i., p. 302, (*Helminthologische Beiträge*).

‡ In *Germar's* Entomologische Zeitung, 1842.

‖ *Wiegman's* Archiv, &c., 1843, ii., pp. 302 and 307.

§ Entwurf einer systematischen Eintheilung und speciellen Beschreibung der Plattwürmer, &c., 1844, pp. 28, 35.

¶ Histoire Naturelle des Helminthes ou vers Intestinaux. Paris, 1845, 8vo.

** Recherches sur l'organisation des vers. *Gordiacea*. Annales des Sciences Naturelles, 3d ser. Vol. xii., 1839, p. 5.

The last European writer on this subject is Mr. Ed. Grube,* who has m some observations on the development of the eggs of *Gordius aquaticus*, described a new species from Africa. His paper bears chiefly on minute p sitical nematoids. He also alludes to the great resemblance there is betw *Mermis albicans* and *Ascaris acuminata*.

III.

The anatomical structure of Gordiaceæ is also a matter of much controve amongst anatomists.

Prof Siebold,† in giving an account of the difference between intestinal wo and Gordii, again calls the latter enigmatic.

Berthold‡ describes a system of circulation, neither seen nor acknowledged the authors that came after him. He likewise mentions a nervous system; giving no further account of it, its characters and distribution in the body of th worms remain to be investigated.

Dujardin‖ is in a complete doubt.

Prof. Siebold,§ in resuming Berthold's and Dujardin's investigation, says t the organs which Berthold took for veins and arteries, are contracted fibres, that he has failed of seeing any organs which he could confidently call nervou vascular systems.

We do not know yet the digestive tube of any Gordiaceæ. One fact, howev is ascertained with regard to that organ: it atrophies in full grown in viduals. Even the structure of the skin, or external envelope of the bo deserves a more full comparative study.

Although Charvet and Berthold agree in saying that Gordiaceæ are androgyno it has been plainly ascertained since, that the sexes are distinct. But the str ture of the sexual organs is not known. Prof. Siebold found an external cha ter by which males differ from the females, the former, in *G. aquaticus*, hav a bifurcated tail.

IV.

Some observations on the development of the eggs of *Gordius aquaticus* h been made by Ed. Grube.¶ Dr. Joseph Leidy had made similar investigations 1846, and published only in 1850.** The eggs are laid in strings, nearly of t length, and sometimes the color, of the worm itself. Within those whitish stri or cords are found the eggs. The division of the yolk takes place, according the general law of division of that substance, previous to the formation of t embryo. The embryo itself is gradually formed out of the yolk's substance, i manner similar to that in Clepsinæ, and leeches in general. The young resemb their parents as soon as hatched.

---

* Uber einigen Anguilulen und die Entwicklungs. von *Gordius aquatic Trosch.* Archiv für Naturgeschichte 1849, vol. i. p. 358. Pl. vii.

† *Wiegman's* Archiv, 1838, vol. iv., i. p. 302.

‡ Ueber das Bau das Wasserkalbs, 1842, in 12.

‖ Annales des Sciences Naturelles. 2de serie, vol. xviii., 1842, p. 142.

§ *Wiegman's* Archiv, 1843, ii. pp. 302 and 307.

¶ *Troschel* für Naturgeschichte, 1849, i. p. 358. Pl. vii.

** Notes on the development of *Gordius aquaticus*. Proc. Acad. Nat. Sc Philad., 1850, p. 89.

Young Gordii possess two circles of filamentary appendages around the proboscis, which, at this early period, is alternately protruded and retracted. Whether the same motion, and the same appendages, are still present in the adult state, is yet to be examined. Many worms are known to be provided with a retractile proboscis, which they use in perforating the sand and mud in which they live. Gordii might require it to introduce themselves into the living bodies where they are sometimes found. As to the circles of tentacles, they very likely disappear in the adult, while the alimentary canal atrophies, their function being intimately connected with the functions of the latter organ.

V.

With regard to the species of Gordiaceæ to be admitted, naturalists do not any more agree.

The most common in Europe is *Gordius aquaticus*, L.* The *G. marinus* and *G. annulatus* of Montague,† are Nemerteæ.

Mr. Charvet‡ describes two others, from the vicinity of Grenoble, (France,) under two trivial names.

Mr. Dujardin‖ considers as distinct, from the above, a species from the vicinity of Toulouse, his *Gordius Tolosanus*, and describes another species, proposing for it the genus Mermis, calling the species *M. nigrescens*.

Prof. Siebold§ has made us acquainted with a second species of Mermis, his *M. albicans*.

Mr. Blanchard¶ has described one species from Chili, under the name of *G. Chilensis*.

Finally, Mr. Ed. Grube** describes another from Africa, which he calls *Gordius crassus*.

Before we identify the North American Gordii with any of the above mentioned ones, we must be prepared to account for many objections which can be made, respecting their having been created identical over such an extensive area, or else of their having migrated naturally, or having been accidentally transported.

VI.

We have in the United States one species, which seems quite common in fresh water, and referred by some to *G. aquaticus*. Rev. Z. Thompson, of Burlington, (Vt.), expresses himself in the following terms: "The little animal called the *Hair snake* also belongs to this order, (annulata,) and to the genus Gordius.

---

* Systema Naturæ ed. xii. 1767, p. 1075.

† Transactions of the Linnean Society of London, vii. 1804, p. 72 and 74.

‡ Observations sur deux espèces du genre dragoneau qui habitent dans quelques eaux courantes aux environs de Grenobles. Nouv. Ann. du Mus. d'hist. Nat. iii. 1836, p. 37. Ann. Sc. Nat. 2de ser. ii. 1834, p. 123. *Wiegm.* Archiv i., i. 1835, p. 341.

‖ Mémoire sur la structure anatomique des Gordius et d'une autre Helminthe qu'on a confondu avec lui. Ann. Sc. Nat. 2de ser. xviii., 1842, p. 129 and 146. Institut., 1842, p. 256. Archives gén. de Médec. xii., 1842, p. 488.

§ Entomologische Zeitung, 1843, p. 80.

¶ Historia fisica y politica de Chile, por Claudio Gay. Zoologia iii., 1848, p. 109.

** *Troschel* Archiv, &c., 1849, i., p. 370.

These are very common in the still waters, and mud, in all parts of the Sta They are usually about the size of a large horse hair, and are from one to six eight inches in length. In color they vary from pure white to nearly black, s hence we probably have several species. The vulgar notion that they origin from hairs which fall from horses and cattle, and become animated in the wat would seem to be too absurd for contradiction; and yet, absurd as it is, peo are to be found who believe it."*

The same popular opinion is prevailing in Europe. Gordii have been notic in the body of insects, also, by an American entomologist, Dr. Th. Wm. Harr who says: "I have taken three or four of these animals out of the body o single locust."† They have been found, by others, within the cricket, (*Ach abbreviata*).

We saw a specimen, six or seven inches in length, caught in the clear wat in the vicinity of Richmond, (Va.) Several others were detected by Dr. Lei in the neighborhood of Philadelphia.

Finally, we may mention several specimens of Gordii from Oregon, brou home by the U. S. Exploring Expedition.

Gordii, therefore, are spread all over the Western hemisphere.

The Committee on the following paper, by Dr. Leidy, reported favor of its publication in the Proceedings.

Corrections and Additions to former Papers on Helminthology published in t Proceedings of the Academy. By Joseph Leidy, M. D.

BODO, *Ehrenberg.*

1. Bodo Helicis, *Diesing:* Syst. Helm. i, 45.

Cryptobia Helicis, *Leidy:* Proc. A. N. S. iii, 101; An. and Mag. of N Hist. xix, 209.

Cryptoicus Helicis, *Leidy:* Journ. A. N. S., new series i, 67.

VERTEX, *Hemprich et Ehrenberg.*

1. Vertex marginatus, *Diesing:* Syst. Helm. i, 229.

Prostoma marginatum, *Leidy:* Proc. A. N. S. iii, 251. Rarely more th 3-5ths line long. Abundant in ditches below the city of Philadelphia.

AORURUS, *Leidy:* Pr. A. N. S. iv, 230.

Characteribus reformatis. Body cylindroid, broadly and strongly annulat Tail long, spiculate, and inflexible. Mouth simple, round, unarmed. Fema generative aperture posterior to the middle. Male with a single spiculate peni

1. *Sub-genus.* STREPTOSTOMA, *Leidy:* Pr. A. N. S. iv, 230.

Characteribus reformatis. Annuli very broad, distinct, and few in numbe Mouth large, circular; buccal organ (*asophagus*) and gizzard pyriform. T very long, and ensiform.

---

* Natural History of Vermont, 1842, 8vo., p. 170.

† Report on the Insects injurious to vegetation, 1842, p. 155.

1. STREPTOSTOMA AGILE, *Leidy:* Proc. A. N. S. iv, 230.

2. STREPTOSTOMA GRACILE, *Leidy:* Proc. A. N. S. v, 100.

Oxyuris Diesingii, *Hammerschmidt:* Isis von Oken, 1838, 354, Taf. iv, fig. vi.

Oxyuris Blattæ orientalis, *Hammerschmidt:* Naturwis. Abhandl. von Haidinger i, 284, Tab. x, Figs. 4, 7, 13—15.

2. *Sub-genus.* THELASTOMA, *Leidy.* Pr. A. N. S. iv, 231.

Characteribus reformatis. Annuli few in number, broad. Oral annulus papillaform. Mouth small, circular; buccal organ long, cylindrical; gizzard pyriform. Tail spiculate, moderately long.

1. THELASTOMA ATTENUATUM, *Leidy:* Proc. A. N. S., iv, 231.

2. THELASTOMA APPENDICULATUM, *Leidy:* Proc. A. N. S., v, 101.

Oxyuris Blattæ orientalis, *Hammerschmidt:* Naturw. Abhandl. von Haidinger i, 284, Tab. x, Figs. 10—12, (♂ 8, 9, 20 ?)

3. THELASTOMA LABIATUM, *Leidy:* Pr. A. N. S. v, 101.

4. THELASTOMA ROBUSTUM, *Leidy:* Ib. v, 101.

5. THELASTOMA BREVICAUDATUM, *Leidy:* Ib. v, 208.

The larva of a lamellicorn insect, from which this species was obtained, Dr. J. L. Le Conte informs me, belongs to Scarabeus relictus.

6. THELASTOMA GRACILE, *Leidy.*

Oxyuris gracilis, *Hammerschmidt:* Naturw. Abh. v. Haidinger i, 287, Tab. x, Figs. 21—25.

7. THELASTOMA DILATATUM, *Leidy.*

Oxyuris dilatata, *Hammerschmidt:* Ib. i, 287, Tab. x, 26, 27.

8. THELASTOMA LATICOLLE, *Leidy.*

Oxyuris laticollis, *Hammerschmidt:* Ib. i, 288, Tab. x, 28—34.

LUMBRICULUS, *Gruby.*

Acestus, *Leidy:* Pr. A. N. S. v, 226.

Characteribus reformatis. Body filiform, cylindroid, hyaline. Podal spines in 4 rows, in fasciculi of 2 to 5, furcate. Upper lip simple, conoidal. Girdle none. Eyes none. Blood bright red.

1. LUMBRICULUS SPIRALIS, *Leidy.*

Acestus spiralis, *Leidy:* Pr. A. N. S. v, 226. Description from the young; found in the spring of the year.

Adult.—Body very long and delicate, filiform, cylindrical; posteriorly obtusely rounded. Upper lip compressed, conoidal. Annuli over 200. Podal spines in 4 rows, 3 to 5 anteriorly 2 to 3 posteriorly in each fasciculus, long sigmoid, furcate. Intervals of the viscera distended with globular corpuscles, which, shining through the translucent integument, give the annuli a deep greenish or bluish white opalescent appearance.

Length from 1 to 3 inches; breadth from 1-8th to 1-5th line. One of three inches in length had 276 annuli.

Habitation.—In the mud about the roots of Pontederia cordata, Sagitaria s tifolia, and Arum virginicum, in ditches below Philadelphia. It is also o found coiled up in a remarkably close knot, among the outer decaying peti of the leaves of the plants just mentioned. Months of August and September

2. Lumbriculus hyalinus, *Leidy*.

Acestus hyalinus, *Leidy:* Proc. A. N. S. v, 226. Description from the yo in the Spring.

Adult. Body filiform, red in color, the posterior fifth yellowish, translu Upper lip sub-acute. Caudal annulus obtuse. Annuli from 120 to 180. P spines in fasciculi of from 3 to 8, furcate.

Whole length 2 inches, with usually 150 annuli; breadth anteriorly 1-5th l posteriorly 1-6th line. One of 1 inch is about 1-6th line anteriorly, 1-8th line posteriorly.

Habitation. Found in ditches with the preceding, the anterior two-third the body burried in the mud, with the tail rapidly vibrating like Saenuris Strephuris. Months of August and September.

CHÆTODEMUS, *Genus novum.*

Body cylindroid. Upper lip very large and broad. Podal spines in 4 ro fasciculate, aristate. Mouth large, inferior; pharynx capacious, œsopha cylindrical; intestine capacious. Eyes none. Blood colorless. Increasing segmentation.

1. Chætodemus panduratus, *Leidy*.

Body transparent, colorless. Upper lip panduriform, broader than the bo Podal spines in fasciculi of 4, long sigmoid, aristate, divergent, 1-666th in. l commencing with the oral segment. Pharynx oval; œsophagus narrow, cy drical; intestine large, narrowing posteriorly.

Whole length of an individual of three segments 1 line; breadth 1-570th i Breadth of upper lip 1-500th inch. First segment of the body with 7 ann second with 5; the third with 9.

Habitation. Found in stagnant ponds and ditches.

Remark. Allied closely to Æolosoma.

STYLARIA, *Lamarck.*

1. Stylaria paludosa, *Lamarck.*

Nais proboscidea, Linn. Syst. Nat. 13th ed. vol. i, pt. 6, p. 3121.

Body cylindroid, colorless, transparent. Without segmentation from 15 t annuli; one of two segments 40 annulations. Podal spines, 7 to 10 in fasciculus, long sigmoid, hooked and bifid at the free end. Setæ commen after the fifth annulus from the mouth, usually single, occasionally two, f 1-400th in. to 1-66th in. in length. Caudal annulus truncated, sinuous, fri with short stiff hairs. Upper lip broad, emarginate, with a cylindroid, flexi proboscidiform appendage from the 1-33d to the 1-25th in. long projecting f its notch, fringed with short, stiff hairs. Eyes two, transverse reniform, situ one on each side of the mouth. Mouth triangular; pharynx capacious, œsoph cylindrical, terminating in the intestine at the third setous annulus.

Whole length from 2 to 4 lines; breadth 1-6th line.

Habitation. In ditches and ponds in the neighborhood of Philadelphia.

2. STYLARIA FOSSULARIS, *Leidy.*

Body of two segments, composed of 24 annuli in the first, 22 to the last. Podal spines 5 to 7 in each fasciculus. Setæ commencing after the fifth annulus, usually double, to 1-66th in. long. Upper lip broad, demi-oval, compressed, not emarginate, with a cylindroid, flexible, proboscidiform appendage the 1-33d in. long projecting from its summit. Eyes two, transverse, one on each side of the mouth. Pharynx capacious, extending to the 4th annulus; œsophagus cylindroid, tortuous, extending to the 7th annulus.

Whole length 4¼ lines; breadth 1-6th line.

Habitation. Found with the preceding.

ANELCODISCUS, *Genus novum.*

Body cylindroid, smooth, posteriorly terminated by a cordiform, retractile acetabular disk. Mouth and anus terminal. Intestine simple, straight.

1. ANELCODISCUS PELLUCIDUS, *Leidy.*

Body cylindroid, colorless, transparent; anteriorly rounded, obtuse; posteriorly spreading into a cordiform disk for attachment. Disk retractile: when retracted, the body becoming dilated oval in the middle and the posterior part doubly intussuscepted.

Length 1-100th in.; breadth 1-1000th inch.

Habitation. Parasitic within the intestine of *Stylaria fossularis.*

Remarks. From the translucency of the last mentioned worm, its parasite may be seen within the intestine attached to the mucous membrane by means of its posterior cordiform disk. While attached it alternately retracts its body with a jerk, and then lengthens itself; in the former movement the posterior third of the body becoming doubly intussuscepted, so as to have the appearance of a double articulation. When detached the same movements take place, but in that of retraction the cordiform disk is entirely drawn within the animal's body. More details of this curious parasite I did not obtain, for, although I saw three, and removed them from the intestine of the Stylaria, yet their movements were so active I could not study them to advantage, and to quiet them I tried a minute portion of the vapour of chloroform, which instantly killed them, but at the same moment they underwent total destruction. Since then I have not been able to examine others.

GREGARINA, *Dufour.*

1. GREGARINA SCARABEI RELICTI, *Leidy.*

Gregarina, *Leidy:* Pr. A. N. S. v, 208. Found in the larva of Scarabeus relictus.

EMEA, *Leidy:* Pr. A. N. S. v, 125.

Characteribus reformatis. Body linear, compressed. Head continuous with the body, with two lenticular depressions upon each side. Mouth infero-terminal. Œsophagus styliferous. Eyes 4 to 6 anterior. Fresh water Nemertinea.

1. Emea rubra, *Leidy:* Pr. A. N. S. v, 125.

Body contracting irregularly, reddish or yellowish flesh colored. Anterior and posteriorly obtusely rounded. Eyes two or three black spots, placed in line behind one another, upon each side of the head: often irregular. First pa of lateral depressions opposite the interspace of the anterior two pairs of eye second pair just postero-lateral to the posterior pair of eyes. Œsophagus ve long and tortuous, villous, furnished at its bottom with a single spine or nail-li tooth, and four others upon each side in a rudimentary condition, enclosed in sac. Intestine becoming obliterated posteriorly.

Ordinary length from 1 to 6 lines; breadth from 1-8th to 1-5th line. Occasic ally 10 lines long by 1-3d broad.

Habitation. In marshes, ditches, and stagnant ponds in the vicinity of Phil delphia.

Variety a. White, 2 lines long; 1-6th line broad.

Habitation. On the under side of stones in the Schuylkill River.

Remark. I have sometimes met with the largest sized females without th appearance of a developed ovum, and at others, those of from 1 to 3 lines length, with from 3 to 18 large yellow eggs.

2. Emea Dugesii, *Leidy.*

Polia Dugesii, *Quatrefages:* Rech. Anatom. et Zoolog. ii, 211.

DENDROCŒLUM, *Oersted.*

Characters same as planaria, with the head furnished with a hemispheric cotyloid cavity, capable of eversion into the form of a pediculated discoid acetabulum.

1. Dendrocœlum superbum, *Girard:* Proc. Bost. Soc. Nat. Hist. iii, 26 Keller and Tiedemann, Nordamerik. Monatsb. ii, 2.

Body thin, plano-convex, translucent white, with the sides nearly paralle anteriorly truncated, with the lateral angles slightly projecting; posterior obtusely angular. Cotyloid cavity of the head prominent, opening at the anteri truncated margin, when everted presenting the form of a circular disk support upon a broad columnar contraction of the head. Eyes two, nearly globular, com posed of a transparent vitreous humour enclosed at the postero-internal half by black choroid. Œsophagus long, keg shaped; intestine delicately and minutely ramified, brown or blackish-brown in color.

Length 3 to 8 lines; breadth 2-5th to 4-5th of a line. The longest may con tract to 3 lines by 4-5th in breadth.

Habitation and Remarks. In ditches communicating with the Delaware an Schuylkill Rivers, below Philadelphia, creeping upon the submerged stems Arum virginicum, Pontederia cordata, Nelumbium luteum, and Zizan aquatica.

When seized or irritated it everts its acetabulum, by which it attaches itself surrounding bodies with the tenacity of a leech.

RHYNCHODEMUS, *Genus novum.*

Body cylindroid, ob-fusiform. Head continuous with the body, proboscidiform, recurvatile, without tentacular appendages. Eyes two, lateral. Interior structure planaroid. Terrestrial.

1. RHYNCHODEMUS SYLVATICUS, *Leidy:* Pr. A. N. S. v, 241.

2. RHYNCHODEMUS ? TERRESTRIS, *Leidy.*
Fasciola terrestris, *Müller.*
Planaria terrestris, *Gmelin:* Syst. Nat. 3092; *Duges:* An. Sc. Nat. 21, 82, Pl. 2, fig. 18; *Oersted:* Entw. d. Plattw.; *Diesing:* Syst. Helm. i, 206.

BDELLOURA, *Leidy:* Proc. A. N. S. v, 242.

Body dilated, plano-convex; posteriorly, dilated, constricted, truncated. Head continuous with the body; tentacular appendages none. Mouth inferior, subcentral; œsophagus protractile, cylindrical. Eyes two. Marine.

1. BDELLOURA PARASITICA, *Leidy:* ib.

2. BDELLOURA RUSTICA, *Leidy:* ib. 243.

3. BDELLOURA ? LONGICEPS, *Leidy.*
Planaria longiceps, *Duges:* An. Sc. Nat. 21, 83, Pl. 2, fig. 21; *Diesing:* Syst. Helm. i, 207.

PLANARIA, *Müller.*

1. PLANARIA MACULATA, *Leidy:* Pr. A. N. S. iii, 251; v, 225.
Dugesia maculata, *Girard:* Keller and Tiedemann, Nordam. Monatsb. ii, 23.
Body thin, spatulate, with sharp, nearly parallel, lateral margins; anteriorly thin trapezoidal, the lateral angles formed by an acute, angular, erectile tentacular appendage; posteriorly sub-acute; superiorly a little convex, irregularly maculated with black, in the young sometimes with brown; inferiorly translucent whitish. Eyes two, reniform, proximate, situated at the inner side of an oval translucent space.
Length from 2 to 8 lines.
Habitation. In ditches and ponds in the neighborhood of Philadelphia; upon the under side of stones in the Delaware and Schuylkill Rivers, abundant.
Variety a. Brownish, indistinctly maculated.
Length 8 lines.
Variety b. Maculations greyish, indistinct, with the intestine blackish, brownish or greenish, frequently with a lighter stripe down the back.
Length 6 lines.
Habitation. Schuylkill River, under stones.

CATESTHIA,* *Genus novum.*

Body very soft, cylindroid. Head continuous with the body. Mouth inferoterminal; œsophagus amphoraform. Eyes two, deeply seated in the interior of an oval translucent space of the integument.

---

* Κατεσθιω, devoro.

1. CATESTHIA STELLATO-MACULATA, *Leidy*.

Body oblong, cylindroidal; anteriorly and posteriorly obtusely rounde superiorly maculated closely and regularly with very much branching, stellat black pigment cells, which cease abruptly laterally, and anteriorly form 3 lobe in the translucent whitish interspaces of which, deeply seated, are the eye which are black and globular; inferiorly translucent whitish. Mouth roun very large and dilatable; œsophagus amphoraform, very large.

Length 3 to 8 lines, breadth 1-4th to 1 line; thickness 1-5th to 4-5th line.

Habitation. Upon the under side of stones, in the Delaware and Schuylki Rivers, below tide water mark.

Remarks. Closely allied to Vertex, *Hemp.* and *Ehrenb.*, but has not 4 eye and has a differently arranged generative apparatus.

It is exceedingly voracious; I have seen an individual, of 8 lines in lengt swallow whole a Planaria maculata 6 lines in length.

Mr. Lea announced the death of RICHARD COWLING TAYLOR, whic took place on Sunday morning, the 26th inst., at his residence in 13t street, in his 62d year, after a very short illness.

Mr. Lea remarked, that it was very rarely that the members of the Academ had to deplore so severe a loss, as that sustained by the death of their distin guished fellow member Mr. Taylor.

In his particular branch of Geology (economic-geology) he stood pre-eminen and as a mining engineer, no authority in this country, or, perhaps, in Europ was superior to that of Mr. Taylor. By early education and association in Eng land, he became versed, in the most thorough manner, in these important science at an age when such education usually begins. Hence, his first literary produc tions brought him prominently before the learned world, and he was introduce into literary and scientific societies, where he took an active part. The firs work of importance which he published, was one on the Monastic remains of th county in which his father lived as a country gentleman, and on whose propert there was a noted Anglo-Norman ruin. It was this probably that induced Mr Taylor first to turn his attention to this branch of knowledge, and the result wa the "Index Monasticus, in the ancient kingdom of East Anglia," published in 1821 in 1 vol. folio,* which at once gave him a reputation for thorough investigation and exactness, which noted all his after works, and which has rarely been excel led. This work was received with so much favor, that Mr. Taylor was induced, at the request of the publishers, to undertake that thorough and learned work which he called a "General Index to Dougdale's Monasticon Anglicanum," in 1 vol. folio, with plates and maps, which was published in 1830. This took Mr Taylor two years to complete, and was said to be so perfect as to require nothing further to be added in regard to it. In his profession, he had the great advantage of a most thorough and complete education, and he was associated in business with the late Wm. Smith, who has been considered as "the father of British Geology," on account of his having been the first geologist in England who attempted to classify the rocks of that country, by their characteristic fossils; and who was sai

* At a public sale his private copy, with some notes, brought £30.

to have preceded MM. Cuvier and Brongniart in that important step, which gave such an impulse to this great branch of human knowledge. Under such auspices, and by his assiduous application, Mr. Taylor made the most rapid advances in the art of Mining and the science of Geology. The early relations of this intercourse ripened into a friendship, and sincere mutual regard, which lasted through life.

With such acquirements, he was soon called into active employment, and we find him engaged, for a time, in the important ordinance survey of England, and he was also employed by the "British Iron Company," whose extensive and valuable property in South Wales, he investigated and reported upon. That portion of the Ordinance Survey which he executed, was finished in a most masterly manner, and his drafts were of the most exact and perfect kind. His report of the topography and geology of the mineral lands of the British Iron Company, were so admirably executed, that the Geological Society of London published the map and descriptive parts in its Transactions. In connection with this, he executed a model in plaster of that part of Wales,* which received so much approbation, that the Society of Arts awarded to him their *gold Isis Medal*, which is now in possession of his family. Subsequently to this, he was engaged for some years, in England, in the examination of various mining properties, after which he was induced to accept an appointment by Hardman Phillips, Esq., an intimate friend of the family, to remove to this country, and reside in Phillipsburg, Pennsylvania, where he remained four years, under the expectation of the professional employment promised him there. This was an unfortunate movement for himself and family, which now consisted of a wife and four daughters. Having lost, in this residence, both time and money, he removed to Philadelphia, for the purpose of seeking that employment in his profession, in which he was so well qualified to excel. Previous to this, however, he was engaged in the survey of the Bossburgh District, and the line of railroad, which he completed, and made an extensive and able report in 1832.

It was after this time, in 1834, Mr. Lea first became personally acquainted with Mr. Taylor, which acquaintance immediately grew into a friendship, which increased through life. Shortly after this, Mr. Lea had it in his power to have Mr. Taylor placed in charge of the exploration of the extensive coal and iron property of the Dauphin and Susquehanna Coal Co., in Dauphin county, Pa., in which Mr. Lea had a large interest. Here Mr. Taylor remained about three years, and developed the mineral resources of this extensive mineral district, to the entire satisfaction of the Board of Directors. The whole of the lands embraced 42,000 acres, in a rugged, mountainous district, which required an experience and perseverance which few men had more of than Mr. Taylor. The result of this great labor was an elaborate report, of 187 pages in 8vo., together with about 150 maps, drafts, surveys and sections, which are invaluable to the Company, and in whose possession they now are. In connexion with this, during a period of cessation, in this country, of activity in such works, he employed himself in the execution of a model of this part of the coal basin and its surrounding mountains, which occupied him many months. This subsequently became the property of the Dauphin Company. It embraces in length about 45

* This was the first model of the kind executed in England.

miles, and in breadth 15 miles of the district it represents, and is about 14 fe long. It is a complete geological and topographical representation of this impor ant district, and would be alone a monument to a man of science, if he had nev executed any other labor.

As soon as the mining interests of the country had become relieved from th pressure which had prevailed for a few years, he again was called on to explo and investigate many mineral districts, connected with the working of gold, silve lead, copper, coal, asphaltum, &c. Most of these reports were published, and is believed that, in every case, they were so correctly executed as to leave n doubt in the minds of those who employed him, as to his judgment, his candc and his scrupulous representations of that which he was employed to examin It was one of the characteristics of Mr. Taylor, as all his intimate friends wer perfectly aware, that his openness and frankness were such as to induce hi never to hesitate to express a candid opinion, or to make known a fact, howeve much it might be against his own interests. It was this which induced the mo unbounded reliance, among his friends, on his representations. Beside the numer ous engagements he had in various States, he frequently had calls to examin important mines in other parts of America; the copper mines of Cuba, the gol mines of Panama, the asphaltum of New Brunswick, &c. In Cuba he was employe to examine and report on the vein of asphaltum near Havana, of which he pub lished an account in the Trans. of the Am. Phil. Soc., with a plan and section The last work of this nature he was engaged in, was the examination of the injecte vein of asphaltum at Hillsborough, in the Province of New Brunswick, which i now in litigation. His testimony in this case, as taken down, and since published is a specimen of such thorough knowledge in his profession, such clearness, exact ness and completeness, as to be worthy of all praise. It should have a place i all geological libraries. He was greatly interested in this singular litigation which seems, strange as it may appear to geologists and mineralogists, to depen on the decision of a jury, whether an injected vein of asphaltum be not a sean or bed of bituminous coal, belonging to true coal measures! Nothing could b more clear, nor more to the point, than Mr. Taylor's evidence to the contrary While in the examination of various districts, in his professional employment, h carefully noted every fact connected with general geology and palæontology, an the results were generally given in the form of papers to scientific bodies, an published in their Transactions. These will be found in various learned transac tions in England and this country—particularly in those of the Am. Phil. Soc the Acad. of Nat. Sciences, and the Geological Soc. of Penn., on this side of th Atlantic. They all bear internal evidence of a philosophic mind, schooled in th consideration of philosophical facts.

Notwithstanding what has been said in regard to all these labors of a mos industrious life, the reputation of Mr. Taylor will rest chiefly on a work whic has not yet been mentioned—his "*Statistics of Coal*," published in this city, i 8vo. pp. 754, in 1848. It included the geographical and geological distributio of mineral combustibles or fossil fuel, as well as notices of localities of the variou mineral bituminous substances employed in arts and manufactures, illustrated b maps and diagrams, embracing, from official reports of the great coal producin countries, the respective amounts of their production, consumption, and commer cial distribution, in all parts of the world.

The execution of this work had engaged Mr. Taylor's time, not necessarily devoted to the practice of his profession, during many years of his life. His heart was set upon the completion of it, and when approaching to a conclusion it drew his mind from all other pursuits. While it was going through the press, he became so ill that, for many weeks, his physician and his family had little expectation of his living to see it completed. During this period many of the sheets had to pass through the press without his inspection, which fact naturally produced some errors. When the work reached the hands of those interested in the statistics of coal, its geology, and its geographical distribution, it was received with the most entire satisfaction. His intimate friends were the first to congratulate him on the work he had achieved, and the criticisms of the press soon followed with their share of approbation. Dr. Fitton, the distinguished geologist, reviewed it in the Edinburgh Review, and gave o its author the credit he so well deserved, of which the following is a single paragraph.

"The inquiries of the author have been extended, with marvellous industry and perseverance, to every part of the globe; but, as might be expected of an engineer residing in America, the coal tracts of that country naturally occupy a large portion of the work. As these are probably less known, to most of our readers, than the coal producing states of Europe, while they are beyond all comparison the greatest depositories of coal in the world—affording to that fortunate region the prospect of almost unbounded wealth—we shall confine our attention chiefly to this part of the work. But our readers may be assured that the author's account of other countries gives equal proofs of his diligence in collecting information."

The *London, Edinburgh and Dublin Phil. Mag. and Jour. of Science*, in its notice of this work, says, "comprehensive as the title of this work appears, it does not yet convey a just idea of its scope, or the extent of the subject matter. Did its title stand, '*Coal the civilizer*; its natural history, productions and applications,' it would perhaps convey to the casual reader a more just idea of the object and contents of the work." * * * "A long and intimate practical acquaintance with mines and mining operations in different parts of the world, had necessarily led him to amass a great quantity of material; the value of which, as a constant object of reference for his own use, led him to feel the utility of a digested and methodized arrangement of those materials, in a permanent shape, for the use of others. But there is found, throughout these pages, a pervading spirit beyond that merely materialistic and dry one, which the title would indicate, and which the professional engagements of the author might have led us to anticipate. We perceive, impressed on every section, the idea, *not* of coal the mere *wealth producer*, the mere material instrument of the human animal, but of coal as an important agent in promoting civilization. It is in the same spirit, and imbued with the same everywhere pervading high moral sentiment, that the author more than once calls attention to the vastly greater importance of iron than of gold and silver. We cannot conclude without cordially recommending this work to the attention of our readers. While it will be an invaluable book of reference to every future inquirer into the numerous economic questions connected with our most important industrial operations, and manufactures, and into the great social questions arising out of them, it will form an indispensable part of the library of every geologist."

The *London Athenæum* in its notice says, "The work of Mr. Taylor w command attention, and become standard as a reference; especially as it is t only one which endeavors to concentrate the knowledge diffused through many channels, and often attainable only in the countries to which the statist refer."

The press in this country did not withhold its proper appreciation of a wo so important to the great coal and iron interests this side the Atlantic.

In the notice in Silliman's Journal it is said, "It is a sufficient guarantee for completeness and accuracy on all points on which it touches, that it receiv before publication, the highest and most unqualified praise at one of the meeti of the American Association of Geologists and Naturalists." • • • "... examination of the volume, now that it has appeared from the press, gives us still higher opinion of the talents and industry of its author, and the great val of his labors," &c. The Journal of the Franklin Institute stated it could scarc have been thought possible that one individual, especially in this country, co have collected together such a mass of facts, and made of them so well arrang and so delightful a book. Hunt's Merchants' Magazine says, "We venture say that, on no kindred subject, has a more complete or perfect treatise ever be produced."

Beside the proficiency which Mr. Taylor had acquired in economic geology, had devoted himself much to theoretic geology, and his knowledge of the vari formations, which make the sum of the geological series, was rarely excelled his colleagues. He had devoted himself more particularly to the strata connect with the coal formation, and he was the first person, as Prof. Silliman stated a meeting of the American Association of Geologists, who had referred the C Red Sandstone, underlying the coal of this State, to its true position, correspo ing with its place in the series of European rocks. He was unwilling to engs in State surveys, but his aid was sometimes required to assist in those particul branches in which he so much excelled. With this view he for a short time l his services to the New York State Survey.

In the year 1832 he was elected a member of this Academy, and in 1846 a l membership was conferred upon him, "as a mark of respect and a just apprec tion of its means of usefulness derived from him." His attachment to t Academy increased with his advancing years. He frequently made donations it of specimens and books. Very recently, he presented a most elaborate geo gical table in manuscript, colored to represent the different strata, and combini the analogous nomenclature of various systems. This most valuable donati was made to the Academy on condition of its never being taken from the libra and it cannot fail to be most useful for consultation and reference.

At the time of his death, Mr. Taylor was engaged in preparing a paper, for t Journal of the Academy, on the fossil plants which he had discovered in recent visit to New Brunswick. The fossil fishes which he also discovered the he left with his friend Prof. Agassiz, who was to describe the new ones for hi All these Mr. Taylor intended should be deposited in the collection of t Academy, to which he had already added many valuable specimens.

Mr. Taylor was the third son of Samuel Taylor. of New Buckenham, in N folk, England, and a descendant of Dr. John Taylor, the author of the Hebr Concordance. He was born at Banham, in Norfolk, Jan. 18th, 1789. His b

ledonous Plants in the secondary strata of Fredericksburg," (Vir.) In Transactions of the American Philosophical Society he published "Memoir of Character and Prospects of the Copper Region of Gibara, and a Sketch of Geology of the N. E. part of the Island of Cuba." "Notice of Fossil Arboresc Ferns of the family Silliquaria and other Coal Plants, exhibited in the Roof Floor of a Coal Seam in Dauphin county, Penn." "Notice of a Vein of Bi minous Coal recently explored in the vicinity of the Havana, in the Island Cuba." (This was jointly with Mr. Clemson). In Silliman's Journal he p lished, "Notes respecting certain Indian Mounds and Earthworks in the form Animal Effigies, chiefly in the Wisconsin Territory, U. S., with Plans and Ill trations." "Notice of a Model of the Western portion of the Schuylkill, Southern Coal Field of Penn., in illustration of an Address to the Association American Geologists, on the most appropriate modes for representing Geologi Phenomena," (with illustrative sections). In the Journal and Proceedings of Acad. Nat. Sciences, "Table constructed from a few Meteorological Not chiefly in regard to the daily temperature of noon, on the East Coast of the Is mus of Panama, Port Royal, in Jamaica, and on the return voyage to New Yo for the month of October, 1849." "Substance of Notes made during a Geolo cal Reconnoisance in the Auriferous Porphyry region next the Carribean sea, the Province of Veraguas and Isthmus of Panama," 1851, with maps. At time of his sudden illness he was engaged in a paper entitled, "On a Vein Asphaltum of Hillsborough, in Albert county, Province of New Brunswick which he has left in an unfinished state, but which is so far complete as to just its publication in the Journal of the Academy.

—

ELECTION.

J. L. Burtt, M. D., U. S. N., and W. L. Sherman, M. D., U. S. N were elected *Members* of the Academy.

DONATIONS TO MUSEUM

In September and October, 1851.

September 2d.

Specimen of Asphaltum, from New Brunswick. Presented by Mr. J. Price Wetherill.

Calcareous Tufa, from Laselle county, Illinois. From Mr. H. H. Sims, through Dr. B. H. Coates.

Fifty specimens of Vesuvian Minerals. From Dr. W. Sherman, U. S. N.

Crystallized Franklinite, from Sussex county, N. Y. From Mr. W. S. Vaux.

Fragment of antler and tibia of Cervus, found in a marl bed near Deal, New Jersey; and recent Cellipora, from the same locality. Presented by Prof. J. F. Frazer.

Cone from one of the Palmaceæ, from Grand Lochoo, Ireland. From J. L. Burtt, M. D., U. S. N.

Loligo ——— ? Presented by Dr. Goddard.

Four Serpents, from Aberdeen, Scotland. From Capt. Jamieson, through Dr. Watson.

September 9th.

Four specimens of Silurian Fossils, from Capon Mount, Va.; dried Conferva, from Capon Springs, Va.; Calcareous Tufa, from Falls of St. Croix River, Wisconsin. Presented by Prof. W. E. Horner.

Teeth of Walrus, large size, from Behring's Straits; specimens of Lava and Sulphur, from the Sandwich Islands; Minerals and Silurian Fossils from Ohio; Fossils from the marl of New Jersey; same, from the Drift of N. J.; fragment of a fossil Tusk from the Harbor of San Francisco; fossil shark Teeth, from the marl of New Jersey; two species of Serpula; two do. of Balanus, and a specimen of Hippocampus, from Mexico; Vegetable Tallow, from China; three specimens of the fruit of Trapa bicornis, from China; several Coleopterous Insects. Presented by Dr. J. L. Burtt, U. S. N.

One hundred and thirty-five species of Shells, from numerous localities. Presented by the same.

September 16th.

Numerous specimens of recent Shells, including two species of Anadonta, two of Bulimus, one Glandina, one Chiton, one Ampullaria, one Neretina, one Purpura, one Littorina, from the vicinity of Carthagena, S. America. Presented by J. C. Trautwine, Esq., through Prof. Frazer.

Fossil Shell. From the same.

Jaws of Sargus ovis. Presented by S. Ashmead.

Crystalline Slag: Silicate of Iron. From Mr. I. Lea.

Subterranean Fungus, from Wisconsin. From Dr. Horner.

October 7th.

Forty-two specimens of Eocene Tertiary Fossils, British; arranged on trays, with magnified views of each species; prepared by the British Nat. Hist. Society. Presented by Dr. T. B. Wilson.

Thirteen British Fossils, from the Bennett and Charlesworth Collections. From the same.

Sixty-three specimens of Echinodermata, from the West Indies, West Coast of Africa, and the Mauritius. From Edward Wilson, Esq.

Cranium of the larger Prairie Wolf, and two Silurian Fossils, from New Mexico. From Mr. Edward H. Kern.

Skin of a Polar Bear, Ursus Arctos, of very large size; the individual from

which it was obtained was killed by Dr. E. K. Kane, of Philadelphia, Surg to the late American Arctic Expedition, and presented by him to the Academ

Fine skin of the Rocky Mountain Sheep, Ovis montana. Presented by Smithsonian Institution, through Prof. Baird.

Forty specimens of Tertiary Fossils, from California. From Dr. J. LeConte.

Native Cinnabar, from California. From the same.

October 14th.

Fruit of Lycthis grandiflora, from Matanzas, and Serpentine from New Jers From Mr. D. M. Schellinger, through Dr. Watson.

Magnetic Oxide of Iron, from the West shore of Lake Champlain. Presen by Mr. Isaac Lea.

Mass of Glass, containing numerous radiated crystals of Silicate of Lin From Dr. J. C. Fisher.

Asphaltum from New Brunswick, Cuba, and Trinidad Lake. From Mr. Richa C. Taylor.

October 21st.

Two vertebræ and a jaw-fragment of a fossil Cetacean; two vertebræ and t teeth of a fossil Saurian; ten teeth of fossil Sharks; two specimens of fos Pecten, and tube of a large fossil Annelide. From Westmoreland county, V ginia. Presented by Mr. Robert H. Nash.

Mounted specimen of Mustela Vison. From Mr. Wm. Wood.

Mounted specimen of Cricetus vulgaris, from Germany; and Fiber Zibethic from Pennsylvania. Presented by Dr. J. C. Fisher.

Geophilus ——— ? from Brazil; and Scarabæus tityus, from S. Carolin From Dr. J. H. Rand.

DONATIONS TO LIBRARY

IN SEPTEMBER AND OCTOBER, 1851.

September 2d.

Proceedings of the Boston Society of Natural History. Vol. 4, pp. 1—3 From the Society.

Supreme Court, Halifax, N. S. Abraham Gesner *vs.* Halifax Gas-light C Deposition of Richard C. Taylor respecting the Asphaltum Mine at Hillsborough From Mr. Taylor.

Report on the Agricultural capabilities of the Province of New Brunswic By J. E. W. Johnston. 2d ed. From the same.

Annual Address, by Mr. Justice Carter, before the Frederikton Athenæu Feb., 1850. From the same.

Annual Address before the same, by the Rev. J. M. Brooke, Feb., 1851. Fro the same.

Dr. Wilson presented the following, on the usual condition:—

Archiv für Naturgeschichte; Herausg. von Dr. F. H. Troschel. No. 6, 184 No. 6, 1849, No. 1, 1851.

Zeitschrift für Malakozoologie von H. T. Menke, M. D., und Dr. L. Pfeiffe No. 11, 1850.

Revue et Magasin de Zoologie. Par M. Guerin-Meneville. Nos. 5 et 6, 1851.

The London Athenæum, July, 1851.

Comptes rendus. Tome 32, Nos. 20—26; Tome 33, No. 1; et index tome 31.

Illustrations Conchyliologiques. Par M. Chenu. Livs 82, 83, folio.

Aves de la Isla de Cuba. Par Juan Lembeye. Nos. 1—8, 4to.

Cosmos essai d'une description physique du Monde. Par Alex. de Humboldt, Traduit par H. Faye. Tome 3, 8vo.

September 9th.

Note sur l'experience communiquée par M. Leon Foucault a l'Académie des Sciences de Paris. Par Jean Plana. From the Author.

Pennsylvania Farm Journal, No. 6, Sept., 1851. From the Editor.

The Terrestrial Air-breathing Mollusks of the United States and the adjacent Territories of North America. By Amos Binney, M. D. Vols. 1 and 2, 4to. From the Executors of the Author, in accordance with his will.

The following were presented by Mr. Edward Wilson, on the usual condition:—

Histoire Naturelle éclaircie dans une de ces partiés principales. La Conchyliologie. Nouv. ed. 4to.

Appendix de trois nouvelles planches aux anciennes de la Conchyliologie, &c.

Narrative of a five years expedition against the revolted negroes of Surinam, in 1772 to 1777. By Capt. J. G. Stedman. 2 vols. 4to.

The American Gardener's Calender. By Bernard McMahon. 8vo.

The Silver Coins of England arranged and described. By Edward Hawkins, Esq.

An Essay on the history, practice and theory of Electricity. By John Bywater. 8vo.

An introduction to Mineralogy. By Robert Bakewell, Esq.

Malacologia terrestre et fluviale della Provincia Cornasca di Carlo Porro. 8vo.

Catalogue d'une collection de Coquilles vivantes provenant du Cabinet de M. M.

Société fraternelle. Fondation d'une Colonie agricole de jeunes détenus à Mettray.

Dissert. inaug. de Helicis Algiræ vasis sanguiferis auctore Michaelo Erdl.

Nomenclature systematique selon M. Lamarck d'une assortiment de Conchyles de J. G. Voight à Amsterdam.

Ragguaglio delle osservazioni ed esperienze fatte sulla Argonauta Argo da Madame Janetta Power del Prof. C. Maravigna.

Notice de la collection de Coquilles de M. Vignard.

Catalogue of Pictures, Casts, &c., in the Liverpool Royal Institution, June, 1836.

An Essay on the Eternal Duration of the Earth. By the Rev. F. O. Morris.

Quelques considerations sur les nègres en general. Par F. Garnot.

Observations on certain curious indentations in the Old Red Sandstone of Worcestershire and Herefordshire. By Jabez Allies, Esq.

Observations sur le projet de Loi relatif aux aliénés, par M. Fabret.

The Naturalist. Conducted by Beverly E. Morris. Nos. 1 and 2.

Rapports de l'Académie des Sciences sur les travaux de M. Duclos.

Recherches sur la population du Globe terrestre. Par J. B. Eyries.

Sur les Ichthyolites ou les Poissons fossiles. Par M. de Blainville.

Observations sur des dents fossiles trouvées à Montabusard pres Orleans. Par M. le Comte T. de Tristay.

Lettres sur la Race Noire et la Race Blanche. Par G. D'Eichthal et J. Urbain.

Notice sur une nouvelle espéce d'Haliotis fossile. Par M. Manuel de Serres.

Queries respecting the Human Race, to be addressed to Travellers and others; drawn up by a Committee of the British Association.

De Parenchymate et Vasorum Capillarium systemate. Auctore H. Koch.

Des Races Humaines, ou Elements d'Ethnographie. Par J. J. d'Omalius d'Halloy.

On the extinction of Human Races. By Dr. Prichard.

Osservazioni Zoologiche intorno ai Testacei dell'Isola di Pantellaria. Lettra del Dott. O. G. Costa al Sig Gussone.

Ornitologia Veneta, ossia Catalogo degli Uccelli della Provincia di Venezia Fortunato Luigi Naccari.

Dualism multiple de l'organisation et de ses antagonismes dans l'homme et regne animal. Par J. J. Virey.

Esclavage de la Race Noire aux Colonies Françaises. Par Charles Levava seur.

Catalogue de la collection de Coquilles exotiques de J. B. Bouillet. MSS. 8v

Recherches physiques, chemiques et physiologiques sur la Torpille. Par I Charles Matteucci.

Analysi ragionata delle opere recentamenti publicate sul Vermi del cor umano, e degli animali dei Dott. Bremser di Vienna e Prof. Rudolphi di Berlin

De la distribution par mois des conceptions et des naissances de l'homme. P L. R. Villerme.

Notice historique sur le sauvage de l'Amerique. Par P. J. Bonnaterre.

De genre Euphones. Autore Dr. P. W. Lund.

Notice sur les Indigénes de l'Amerique du Sud et en particulier sur la tribu d Indiens Charruas.

Descriptions de plusieurs nouvelles especés de coquilles du genre Rissoa. P A. C. G. Michaud.

Observations on the brumal retreat of the Swallow. By Thomas Forste 2d ed.

Considerations sur la distribution des Mammiferes terrestres fossiles dans Departement du Puy de Dome. Par A. Bravard.

Precis sur la mine de Sel Gemme de Vie et sur les principales mines de Sel l'Europe. Par M. d'Arcet.

Biographical notice of Joseph Napoleon Buonaparte. 2d ed. 8vo.

Observations on the natural history of two species of Wasps. By the Rev. I Bigge.

The Sanatory condition of Oxford. By W. P. Ormerod.

On the relation of the several parts of Mathematical Science to the fundament idea therein contained. By Bartholomew Price.

On education in the principles of Art. By the Rev. R Greswell.

Essay on the theory of the combination of observations. By W. F. Donkin.

Additional observations for determining the refractive indices for definite ra of the Solar spectrum in several media, and 2d supplement to the same. By t Rev. Baden Powell.

On the theory of ratio and proportion, by the Rev. B. Powell; on the natu and evidence of the primary laws of motion, by the same; on the theory parallel lines, by the same; on necessary and contingent Truth, by the same.

Remarks on the proportionate quantities of Rain at Oxford, by S. P. Rigaud on the Arenarius of Archimedes, by the same; account of some early proposa for Steam Navigation, by the same; A defence of Halley, by the same.

Narrative of an excursion to the Lake Ansanctus, by Charles Daubeny, M. D Sketch of the Geology of North America, by the same; on the site of the ancie city of the Aurunci, by the same.

On the Amphitheatre of Pola in Istria. By Travers Twiss.

An account of the Roman Road from Allchester to Dorchester, and oth remains in the neighborhood. By the Rev. R. Hussey.

On the earlier notices relative to the natural history of the Giraffe. By I Holme.

On the collection of Boracic Acid from the Lagoni of Tuscany. By Thom Tancred.

Notes on the Indica of Ctesias. By H. H. Wilson.

September 16th.

American Journal of Science and Arts. Sept., 1851. From the Editors.

Bulletin de la Société Imperiale des Naturalistes de Moscou. Nos. 3 et 1850. No. 1, de 1851. From the Society.

Proceedings of the Boston Soc. of Nat. History. Vol. 4, pp. 33—64. From the Society.

Transactions of the Amer. Philosoph. Soc. New series, vol. 9, pts. 3 and 4, (wanting to complete the series in the Library). From the Society.

Transactions of the Linnean Society of London. Vol. 20, pt. 3. 4to. From the Society.

List of the Linnean Society for 1851, and Proceedings of the same, No. 44. From the same.

The Charleston Medical Journal and Review. Vol. 7, No. 5. From the Editors.

Annals of the Lyceum of Natural History of New York. Vol. 5, No. 3. From the Lyceum.

Annual Report of the Trustees of the New York State Library, 1848. From the Trustees.

Second Annual Report of the Regents of the University of New York on the condition of the State Cabinet of Nat. Hist. 1849. From the Regents.

On the impregnation of the Ovum in the Amphibia, (1st ser.) By George Newport. From the Author.

Transactions of the Horticultural Society of London. 1st series. Vols. 1 to 6. 4to. From Mr. George Ord.

Same work. Vol. 7, 1st ser.; and vols. 1 and 2, 2d series. 4to. From Dr. Wilson.

October 7th.

Contributions to Ornithology. By Sir W. Jardine. Part 3 for 1851. From H. E. Strickland, Esq.

Quarterly Journal of the Geological Society of London. No. 26. From the Society.

Addittamenta ad Faunam Carcinologicam Africæ Occidentalis; Edidit J. A. Herklots. From Mr. Herklots.

Journal of the Indian Archipelago and Eastern Asia. Vol. 5, Nos. 3 and 4. From the Editor.

Memorandum respecting Choristopetalum impar and Cyathophora? elegans. By Wm. Lonsdale, Esq. From the Author.

Deutsche Ornithologie, oder Naturgeschichte aller Vögel Deutschlands. Von Dr. Bekker, Leichthammer, &c. No. 22, folio. From Dr. J. J. Kaup.

Portrait of John E. Gray, Esq. From Mr. Gray.

Ostéographie ou description iconographique comparee du squelette et du system dentaire des cinqe Classes des An. vert. et fos. Mammiferes. 2 plates. From M. Potier.

Palæontographical Society. Crag Mollusca, part 2; Mollusca from the great Oolite, part 1; British Oolitic and Liasic; Brachiopoda, part 3; Fossil Reptilia, part 3; British fossil Corals, part 2. From the Society.

Dr. Wilson presented the following, on the usual condition:—

Table des Planches Enluminees. Par M. Boddart. (MSS.) folio.

Comptes rendus. Tome 33, Nos. 2, 3, 4.

The London Athenæum. August, 1851.

Journal de Conchyliologie. 1851, No. 1.

History of the British Mollusca and their Shells. By Prof. Forbes and S. Hanley. Pts. 39 and 40.

Phycologia Britannica. By W. H. Harvey, M. D. Nos. 59, 60.

Annals and Magazine of Nat. History. Nos. 42, 43, 44.

Actes de la Société Linnéenne de Bordeaux. Livs 5 et 6. Tome 16.

Palæontologie Française. Par Alcide D'Orbigny. Terrains Jurassiques, livs. 64, 65, 66: Terrains Cretaces, livs. 163—168.

Tidschrift voor Natuurlijke Geschiedenis en Physiologie. Door J. Van der Hooven, M. D. en W. H. De Vriese, M. D. Vol. 9, (nos. 2, 3, 4,), Vols. 10, 11, 12.

Outlines of Comparative Anatomy. By Robert E. Grant, M. D. 8vo.

Journal of the Franklin Institute for September, 1851.
Conchologia iconica. By Lovell Reeve. Nos. 98, 99, 100.
Palæontographia. Beitrage zur Naturgeschichte der Vorwelt. Von Dr. Dunker und H. von Meyer. Vol. 2, No. 2.
Untersuchungen über Trilobiten. Von Dr. Ernst Beyrich. No. 2.
Illustrations of British Mycology. By Mrs. T. J. Hussey. 2d ser. N 5, 7, 8.
Exploration Scientifique de l'Algérie pendant les annees 1840, '41, ' Feuilles supplementaires 3me liv.
The genera of Diurnal Lepidoptera, by E. Doubleday; continued by J. Westwood. Nos. 43, 44, 45, 46.
Voyage en Abyssinie, pendant les annees 1839—'43; Publié sous la direct de M. Theo. Lefebvre. No. 33, and chart.
The Birds of Asia. By J. Gould. Part 3.
Index Palæontologicus. Von Dr. H. G. Bronn. Vols. 1 and 2. 8vo.
Memoires de Physique et de Chimie de la Société d'Arcueil. 3 vols. in 8vo.
Bibliotheca Zoologica et palæontologica. Edited by Wm. Englemann. 8vo.
The Viviparous Quadrupeds of North America. By J. J. Audubon and the R J. Bachman. Text. Vol. 2. Royal 8vo.
Grundzüge der Wissen. Botanik. Von M. J. Schleiden, Dr. 2 vols. 8vo.
Report of the 20th meeting of the British Association for the advancement Science. 8vo.
Memoires de la Société Nationale des Sciences, &c. de Lille. An. 1849. 8v
Cephalogenesis. Auctore J. B. Spix. Folio.
Calcutta Journal of Natural History. Vols. 5 and 7, and Vol. 8, nos. 1 and
Histoire naturelle gen. et partic. des Mollusques terrestres et fluviales, & Oeuv. post. de M. de Ferussac, continue par M. de Ferussac son fils. Liv. 42. 4
The Philosophical Magazine. By Alex. Tilloch. Vols. 1 to 23, and 56 68. 8vo.

October 14th.

Views of Louisiana: with a Journal of a voyage up the Missouri in 1811. I H. M. Brackenridge. 8vo. From Dr. G. W. Fahnestock.
Report of a Geological exploration of part of Iowa, Wisconsin and Illinois. I David Dale Owen, M. D. From U. S. Treasury Department.
The Coal Regions of Pennsylvania. Edited by Eli Bowen. 8vo. From M Samuel Powel.
Report of a Geological examination of some tracts of land in Alleghany count Md., and Hampshire county, Virginia. By Wm. E. A. Akin. From the same
Map of a part of Pennsylvania, exhibiting the surveys made by the Sunbu and Erie Railroad, under the direction of Edward Miller. From the same.
Charleston Medical Journal and Review. Vol. 5, No, 4. July 1851. Fro the Editors.
The Pennsylvania Farm Journal. Edited by S. S. Haldeman. No. 7. Oct. 185 From the Editor.
Memoires de la Soc. de Physique et d'Hist. Nat. de Genéve. Tome xii. pt. 4to. From the Society.
Map of the Anthracite Coal Fields, (1st and 2d). By Samuel R. Fisher, (1836 From Col. J. Hare Powel.
The following were presented by Mr. Wm. Haidinger, of Vienna:—
Ueber den Cordierct. Von W. Haidinger.
Ueber den Pleochroismus der Krystalle. Von W. Haidinger.
Ueber die Pseudomorphosen und ihre anogene und katogene Bildung. Von W Haidinger.
Ueber den durchsichtigen Andalusit von Minas Novas in Brasilien und de Diaspor von Schemnitz. Von W. Haidinger.
Ueber das Eisenstein-Vorkommen bei Pitten in Österreich. Von W. Hai inger.

October 21st.

Die Cephalopoden des Salzkammergutes aus der Sammlung Seines Durchlau des Fürsten von Metternich. Von W. Haidinger.

Presented by Prince Metternich, through Chevalier Hulseman.

The following were presented by Mr. Edward Wilson, of Wales :—

Verzeichniss des Gypsabgüsse von dem Ausgezeichnetsten urweltlichen Thi resten des Grossherzoglichen Museum zu Darmstadt. Von J. J. Kaup und J. Scholl.

Favorite Song Birds. Edited by H. G. Adams. 12mo.

The Treasury of Natural History. By Samuel Maunder; new edition. 8vo

Synopsis of the British Museum. 36th, 41st and 42d editions.

De Antennis Insectorum. Dissert. inaug. Auctor M. C. G. Lehman.

Domestic Fowl. Their natural history, breeding, rearing and general ma agement. By H. D. Richardson.

Remarks on the account of the late voyage of discovery to Baffin's Bay, pu lished by Capt. J. Ross, R. N. By Capt. Ed. Sabine.

An explanation of Capt. Sabine's Remarks on the late voyage of discovery Baffin's Bay. By Capt. John Ross, R. N.

Journal of a voyage of Discovery to the Arctic Regions, in 1818, by Wm. E Parry, in H. M. S. Alexander. By an Officer of the Alexander.

Revue critique de l'Ornithologie Europeenne de M. le Dr. Degland. Par Charl L. Bonaparte. 8vo.

A letter to John Barrow, Esq., on the extraordinary discoveries made by Quarterly Reviewer and Capt. Parry.

American Ornithology, by Alexander Wilson, with a continuation by Charl L. Bonaparte; the illustrative notes and life of Wilson, by Sir Wm. Jardin 3 vols. 8vo.

Descriptive catalogue of the preparations in the Museum of the Royal Colle of Surgeons in Ireland. By John Houston, M. D. Vol. 1, Anatomy.

Contributions towards a Fauna and Flora of the County of York. 8vo.

Observations on Mount Vesuvius, Mount Etna, and other Volcanos, in a seri of letters to the Royal Society, by Sir Wm. Hamilton. 8vo.

The Philosophy of Earthquakes, natural and religious. By Wm. Stukel M. D. 2d. ed.

Avium Genera. Auctore P. H. G. Moehringo. 8vo.

A voyage to Hudson's Bay, by the Dobbs Galley and California, in 1746, '4 By Henry Ellis. 8vo.

Apuntamientos para la historia Natural de los Quadrupedos del Paraguay y R de la Plata. Por Don Felix de Azara. 2 vols. 8vo.

Das Thierreich in seinen Hauptformen systematisch beschreiben von Dr. J. Kaup. 3 vols. in one. 8vo.

Drops of Water: their marvellous and beautiful inhabitants displayed by tl microscope. By Agnes Catlow. 8vo.

The impracticability of a North-West Passage for ships, impartially considere

Researches about atmospheric phenomena. By Thos. Forster. 3d ed. 8vo.

Travels in the United States of America and part of Canada. By Wm. Da ton. 8vo.

Le Regne Mineral ramené aux méthodes de l'histoire naturelle. Par L. A Necker. 2 vols. 8vo.

Observations on the probability of reaching the South Pole. By James We dell, Esq.

Cours de Physiologie générale et comparée. Par M. Ducrotay de Blainvill 3 vols. 8vo.

Delineations of the Ox Tribe. By George Vasey. 8vo.

The Geological Observer. By Sir Henry de la Beche. 8vo.

The History of Barbadoes. By Sir Robert H. Schomburgh. 8vo.

Journal of a voyage to the Northern Whale Fishery By Wm. Scoresby, jr. 8vo

Description des Alpes Pennines et Rhetiennes. Par M. T. Bourritt. 3 vols. 8vo

Enleitung zur Naturgeschichte der Eingeweidewürmer. Von J. G. H. Zeder. 8vo.

Tractatus historicus de Ascaribus et Lumbrico lato. A Stephano Goulet, M. D. 8vo.

Reflexiones imparciales sobre la humanidad de los Espanoles en las Indias contra los pretendidos Filosifos y Politicos. Por el Abate don Juan Nuix. 4to.

A treatise on Diamonds and Pearls. By David Jeffries. 8vo.

A synopsis of the British Flora. By John Lindley. 8vo.

An attempt towards a natural history of the Polype. By Henry Baker. 8vo.

An account of New Zealand, and of the formation and progress of the Church Missionary Society's Mission in the Northern Island. By the Rev. Wm Yates. 8vo.

Oppian's Halieuticks of the nature of Fishes and Fishing of the ancients, in five books, translated from the Greek. 8vo.

Recherches experimentales sur l'Inanition. Par Charles Chossat, M. D.

Skizziete Entwickelungs-geschichte und Naturliches-system der Europäischen Thierwelt. Von Jacob Kaup. 8vo.

November 4th, 1851.

Vice-President BRIDGES in the Chair.

Letters were read:

From Isaac Chipman, Esq., dated Acadie College, October 3d, 1851, acknowledging the receipt of his notice of election as a Correspondent, and announcing that he had transmitted a box of minerals from his vicinity for the Academy.

From the Librarian of the British Museum, dated October 7th, 1851, acknowledging the receipt of No. 9, Vol. 5, of the Proceedings.

From Mr. William H. Towson, of Philadelphia, stating that the collection of minerals belonging to the late Dr. William Gambel, was for sale. Referred to the Mineralogical Committee.

Dr. Leidy observed that he had examined the fossil saurian bones, consisting of two teeth, two vertebræ, a fragment of a rib and an ungual phalanx, presented to the Academy October 21st, by Mr. Robert H. Nash, who obtained them from the Miocene formation of Westmoreland county, Virginia. Dr. Leidy found them to belong to a new extinct species of Crocodile, for which he proposed the name of Crocodilus antiquus.

Mr. Theodore F. Moss read some remarks on the Geology of Texas.

Dr. Fisher announced that the Trustees of the University of Pennsylvania had granted the use of the College Hall to the Academy, for the purpose of hearing the Memoir of the late Dr. Morton read by Dr. Meigs.

November 11th.

Vice-President BRIDGES in the Chair.

Dr. Le Conte, of New York, read a paper, intended for publication in the Proceedings, entitled "Synopsis of the species of Donacia, by John L. Le Conte, M. D.," which was referred to a Committee consisting of Dr. Leidy, Dr. Hallowell, and Mr. Haldeman.

Dr. Le Conte read a second paper, also intended for publication in the Proceedings, entitled "Zoological Notes," which was likewise referred to the above Committee.

A letter was read from Mr. Alexander Vattemare, dated Paris, October 19th, 1851, announcing that he had addressed to the Academy a box, containing three crania, procured from the Museum of Natural History of Paris, at the request of the late Dr. Morton, and calling the attention of the Academy to the importance of a universal system of international exchanges between scientific institutions.

Letters were also read:—

From the Trustees of the New York State Library, dated Albany, November 3d, 1851, acknowledging the receipt of No. 10, Vol. 5, of the Proceedings.

From the Librarian of the Boston Society of Natural History, dated

November 5th, 1851, requesting certain numbers of the Proceedings the Academy necessary to complete the series in the Library of t Institution.

From Dr. J. L. Burtt, U. S. N., dated U. S. Naval Hospital, N York, November 8th, 1851, acknowledging the receipt of his notice election as a Member.

Dr. Leidy presented a list of minerals offered by the Bavarian Gove ment, and also a list of minerals of this country desired by the sa in exchange. Referred to the Mineralogical Committee.

Dr. Leidy called the attention of the members to some fossil bones from Miocene formation of Virginia, which he characterized as having belonged to t species of Whale, as follows :—

BALAENA PALÆATLANTICA, *Leidy*. This species is proposed upon a fragm of a lower jaw, a dorsal vertebra, and the zygomatic portion of the temporal bo The specimens were discovered by Dr. R. Eppes in Virginia, and presented Prof. W. E. Horner, to whom they belong. They were found in association w Pecten Jeffersonius, Venus tridacnoides, etc. The fragment of lower jaw, inches long, is stout in its proportions, is relatively straight, with no tende to curve downwards. In section it is vertically ellipsoid, but becomes m cylindroid anteriorly. Internally it is convex, externally demicylindroid. T upper margin is elevated, obtuse, and irregular. Just within it, in the specim situated about two inches apart, are three gingeval foramina, about four lines diameter, and slightly oblique forwards in their direction. External to the per margin at the anterior half of the specimen, about one inch apart, are t large labial foramina, one four lines, the other five lines in diameter, direc very obliquely forward.

Measurements of the fragment.

	Post.	Ant.
Vertical diameter,	4½ inches,	3½ inches,
Transverse "	2½ "	2 " 10 lin

The dorsal vertebra indicates an adult animal. Its articular faces are flat compressed circular. The transverse processes and neural arch are brol away.

Measurements:

Length of the body,	6¾ inches,
Breadth "	ant. 6, post. 7 "
Depth "	" 5½, " 6 "
Breadth of transverse process,	4½ "
" neural arch,	4½ "
" spinal canal,	2½ "

BALAENA PRISCA, *Leidy*. This species is proposed upon a fragment of a low jaw and a caudal vertebra, found in association with Crocodilus antiquus, Pect Jeffersonius, &c., in Westmoreland county, Virginia. The specimens were c tained by Mr. Robert H. Nash, and presented by him to the Academy.

The fragment of lower jaw, fourteen inches long, is of much more slender p

portions than that of the preceding, it is also more uniform in its breadth and depth, and has a strong curve downwards as in B. rorqual, *Lac.* It is very nearly flat internally and demi-cylindrical externally. The upper margin is angular but not prominent, and forms the boundary between the inner and outer side. The gingeval foramina, five in number in the specimen, are placed below the upper margin internally, are about one line in diameter, and open very obliquely forward into grooves almost horizontal, from half an inch to one inch long. The labial foramina of which there are the remains of seven in the specimen, are about half an inch external to the upper margin, are about two lines in diameter, and open very obliquely forward.

Measurements of the fragment.

Vertical diameter, ...	3 inches.
Transverse "	2 "

The caudal vertebra found associated with the above fragment, and which I suppose to belong to the same animal, is adult, and indicates a larger species than the B. palæatlantica, for it is as large as the dorsal vertebra of the latter. Its articular faces are subcircular, and are moderately convex. The transverse processes and neural arch are broken away in the specimen, as is also the case with the abutments of the chevron bone. The transverse processes have their origin 1¼ inches posterior to the anterior articular face.

Measurements.

Length of the body,	6¼ inches.
Breadth of anterior articular face,	6¼ "
Depth " " "	6 "
Breadth of transverse process,	4 "
" neural arch,	3¾ "
" spinal canal,	7 lines.

Dr. Fisher, on behalf of the Committee on the Memoir of Dr. Morton, announced that it had been read by Dr. Meigs on Thursday evening last, November 6th, 1851, at the Hall of the University of Pennsylvania.

Whereupon the following resolutions were offered, and unanimously adopted:—

Resolved, That the sincere thanks of this Society are due, and are hereby presented to Dr. Charles D. Meigs, for his able and highly appropriate Memoir of its late President, Dr. Samuel George Morton, read before the Society on the 6th inst., at the Hall of the University of Pennsylvania.

Resolved, That the Memoir be published, and that the Committee on Proceedings have charge of the same.

November 18th.

Vice President Bridges in the Chair.

A letter was read from the Asiatic Society of Bengal, dated Calcutta, May 9th, 1851, acknowledging the receipt of Part 1, Vol. 2, new series of the Journal.

Dr. Leidy read a paper, intended for publication in the Proceedin entitled "On some American Fresh-water Polyzoa."

Also a second paper, intended for publication in the Journal, entitl "Description of a new species of fossil Crocodile."

Both communications were referred to the following Committee, D Ruschenberger, Dr. Fisher, and Dr. Le Conte.

Mr. Lea read a letter from Mr. Edward Miller, giving the localities the coal fossils presented by him this evening.

Mr. Lea also made some remarks on the scenery and geological ch racters of the White Mountains.

The following resolution was unanimously adopted :—

Resolved, That the thanks of this Society be presented to Dr. E. I Kane, for the valuable donations made by him to the Museum of tl Academy, of specimens of Natural History collected during his rece voyage to the Arctic Regions.

November 25th.

Vice President BRIDGES in the Chair.

The Committee on Dr. Leidy's description of a new species of Fos Crocodile, from the Miocene of Virginia, reported in favor of publicatic in the Journal.

The Committee on the two following papers by Dr. Le Conte, report in favor of publication in the Proceedings.

Synopsis of the species of DONACIA (*Fabr.*) *inhabiting the United States.*

By JOHN L. LE CONTE, M. D.

*Elytris depressis, triangularibus, truncatis : oculis orbito præditis.

A. Crassiusculæ, depressæ ; antennæ articulis 2^ndo^ et 3^io^ subæqualibus elytra profunde striata; femora dente postico emarginato, vel crenato.

1. D. magnifica, splendide violacea, aureo-marginata, thorace quadrat canaliculato, punctato, pedibus posticis magnis, tibiis incurvis. Long. ·34. Lak Superior.

Mas, femoribus posticis bidentatis, tibiis intus serratis. Femina fem. post. uni dentatis, tibiis non serratis. Lec. 1, 236. ?*D. dentata* (Fabr.) Lac. 1, 121.

2. D. proxima, nigro-violacea, punctis inauratis, thorace quadrato, vi punctulato, canaliculato, lateribus modice tuberculato, femoribus posticis magnis tibiis fere rectis. Long. ·35—·43. Lake Superior, and Saratoga, (N. York.)

Mas, tibiis posticis intus serratis, fem. post. tridentatis, dente anteriore parvo remoto. Femina, tibiis post. non serratis, fem. bidentatis, dentibus approximatis variat femoribus posticis unidentatis.

Kirby. 225. *D. episcopalis* Lac. 1, 105. *D. quadricollis* var. Say. J. Ac 5, 282.

B. Longiusculæ, antennis attenuatis, articulo 3^io^ 2^ndo^ multo longiore thorace vix punctato.

3. D. congener, aurea nitida, thorace quadrato, postice canaliculato, subti liter alutaceo, parceque punctulato, lateribus subsinuatis, angulis non prominulis

tundatim truncatis, antennarum articulo 3^io 2^ndo plus sesqui longiore, femoril posticis modice clavatis. Long. ·31—·37. Saratoga, Catskill.

Mas, femor. post. dente lamellato armatis, alteroque minutissime remo Femina femor. post. dente lamellato armatis. Lac. 113.

10. D. tuberculata, æneo-cuprea, thorace dense alutaceo-rugoso, post subangustato, angulis anticis prominulis, canaliculato, lateribus antice valde tub culatis, elytris valde rugosis, apice vix truncatis, antennarum articulo 3^io 2 sesqui longiore, femoribus posticis valde incrassatis, fuscis, basi rufis. Long. · —·30. Penn. Dr. Melsheimer.

Mas, femor. post. dente acuto, alteroque minuto remoto armatis. Femi brevior, crassior, femor. post. non dentatis. Lac. 155.

C. Longiusculæ, elytris versus apicem magis subito attenuatis, thora valde punctato, antennis minus attenuatis, articulo 3^io 2^ndo pau longiore.

11. D. pulchella, testacea, aureo-viridimicans, thorace quadrato, den subtiliter rugoso, angulis prominulis, canaliculato, margine basali subreflex disco versus latera vix impresso; elytris profunde striato-punctatis, rugosi antennarum articulis 2^ndo et 3^io subelongatis, hoc paulo longiore, femoribus po ticis modice incrassatis. Long. ·35. New Jersey.

Mas latet. Femina femor. post. dente acuto armatis.

Habitus omnino D. palmatæ, differt tamen thorace rugoso, antennaru articulo 3 ^o minus elongato, denteque femorali non lamellato.

12. D. subtilis, depressa, elongata, ænea, thorace dense rugose punctat quadrato, longiusculo, postice vix angustato, angulis prominulis, plus minus canaliculato, lateribus fere rectis, vix impressis, elytris triimpressis, interstiti planis, transversim dense rugosis, antennarum articulo 3^io 2^ndo sesqui longior femoribus posticis minus elongatis, magis clavatis, subtus dente acuto armati Long. ·27—·38. New York, and Pennsylvania.

Variat cupreo-ænea; variat quoque elytris non impressis. Specimina minor thorace profundius impresso gaudent. Kunze, (Nov. Act. Halens. 2, 4, 12: Lac. 147. *D. ænea* Ahrens. Nov. Act. Hal. 1, 3, 21. *D. quadricollis* Say J. Ac. 5. 282.

13. D. confluens, depressa, elongata, ænea, thorace quadrato, longius culo, postice subangustato, dense rugose punctato, angulis prominulis, medi ante basin impresso, lateribus, subsinuatis, tuberculo depresso paulo prominulo elytris antennis pedibusque sicut in D. subtili. Long. 32. Pennsylvania.

A præcedente tuberculis thoracis minus obliteratis, thoraceque non canalicu lato, et postice impresso solum differt. Forte varietas mera haberi debetur *D. confluenta* Say, J. Ac. 5, 293. Lac. 199.

14. D. fulgens, depressa, læte aurea, thorace quadrato, postice non angus tato, confertim rugose-punctato, angulis posticis non prominulis, lateribus rectis vix impressis, elytris versus suturam obsolete biimpressis antennis pedibusqu sicut in D. subtili. Long. ·32. Lake Superior.

D. subtili, paulo latior, et thorace non canaliculato differt. ‡Lec. 236.

15. D. porosicollis, valde elongata, cupreo-ænea, antennis pedibusque rufis, thorace subtiliter alutaceo, sat dense punctato, quadrato, angulis prominuli subconaliculato, lateribus rectis, elytris interstitiis planis, transversim dense

striatis versus suturam depressis, lateribus sensim declivibus, femoribus posticis minus elongatis, subtus dente acuto armatis. Long. ·34. Lake Superior. Lac. 150.

D. Crassiusculæ, elytris apicem versus magis angustatis, thorace punctato tuberculatoque, elytris valde rugosis, antennis minus attenuatis articulo 3^io^ 2^ndo^ paulo longiore.*

16. D. hirticollis, obscura, thorace dense punctulato, pubescente, lateribus bituberculatis, femoribus posticis vix unidentatis. Long. ·30—·36. Lake Superior, Saratoga. Kirby, 226; Lac. 203. D. rudicollis. Lac. 108. Variat rufa.

17. D. distincta, cupreo-ænea, thorace punctato, quadrato, postice subangustato, angulis prominulis, lateribus modice tuberculatis, canaliculato, margine apicali basalique reflexo, elytris interstitiis planis, versus suturam depressis, biimpressisque, lateribus sensim declivibus, apice minus truncatis, femoribus posticis magis clavatis, dente acuto armatis. Long. ·36. Lake Superior.

Habitus fere D. proximæ. ‡Lec. 236. D. *æqualis* ‡Kirby, 225.

** Elytra subparallela, apice subtruncata vel rotundata; antennarum articuli 2^ndus^ et 3^ius^ subæquales; femora postica paulo elongata; thorax postice angustatus.

A. Oculi orbito distincto præditi: elytra paulo convexa.

18. D. confusa, minus elongata, capite non toroso, thorace longiusculo subtiliter rugoso, postice subangustato, angulis prominulis, canaliculato, lateribus modice tuberculatis, disco versus angulos anticos profunde impresso, elytris apice truncatis, striis externis profundioribus, subtiliter rugosis, versus suturam valde biimpressis, femoribus posticis nigris, basi rufis, dente lamellato armatis. Long. ·27. Mass., Ohio, and Lake Superior.

Mas, femor. post. dente maiore armatis. Variat violacea, et nigro-ænea; interstitiis elytrorum internis sæpe lævigatis. ‡Lec. 237.

19. D. torosa, longiuscula, nigro-violacea, capite valde toroso, thorace alutaceo, parce subtiliter punctato, longiusculo, postice angustato, angulis prominulis, lateribus tuberculatis, sub-canaliculato, elytris vix triangularibus, apice rotundatim truncatis, rugosis, dorso biimpressis, femoribus posticis modice clavatis, dente minus acuto armatis. Long. ·25. Mass. Dr. Harris.

B. Oculi orbito modice distincto præditi: femora postica dente armata; corpus lineare depressum; antennæ articulo 3^io^ longiusculo.

20. D. aurifer, ænea vel læte aurea, antennis pedibusque rufis, illis fusco, annulatis, capite paulo toroso, thorace longiusculo, postice angustato, rugulosoparceque punctato, angulis vix prominulis, tuberculo laterali parvo, vix prominulo, vix canaliculato, ante basin profunde transversim impresso, elytris apice rotundatis, profunde punctato-striatis, rugosisque. Long. ·26. Lake Superior.

Variat thoracis disco utrinque impresso. ‡Lec. 237.

---

*This group approaches in form *A. but the species are more convex, and the tooth of the femora is not crenate.

C. Oculi orbito valde obsoleto, vel nullo præditi; elytra parallela con vexiuscula, vel apice rotundata, vel vix truncata: femora postica dent armata.

χ. Thorax longiusculis, minus convexus; pedes mediocres, femoribu posticis modice clavatis, basi tenuibus.

22. D. c u p r e a, subelongata, ænea, capite modice toroso, thorace dense ru guloso, postice subangustato, angulis prominulis, late canaliculato, lateribu modice tuberculatis, elytris dense rugosis, vix biimpressis, femoribus postici dente magno armatis, antennis annulatis articulo 3^io^ 4^to^ breviore. Long. ·25-·33. Lake Superior. Kirby 225: Lac. 203.

Variat ? cyanea, antennis pedibusque totis rufis.

23. D. d i v e s, subelongata, ænea, capite non toroso, thorace dense rugulos punctatoque, postice paulo angustato, angulis prominulis, vix canaliculato, an basin transversim impresso, lateribus subtuberculatis elytris leviter biimpressi femoribus posticis dente magno armatis, articulo antennarum 3^io^ tenui 4^to^ æqual Long. ·31. Lake Superior, specimen unicum.

24. D. p u s i l l a, elongata ænea, capite non toroso, thorace confertissim rugoso, postice angustato, angulis anticis subprominulis, canaliculato, ante bas transversim impresso, tuberculo laterali distincto, elytris dense rugosis, bliu pressis, impressione anteriore obliqua, antennis crassiusculis, articulis 2—4 gr datim vix longioribus, femoribus posticis dente mediocri armatis. Long. ·23—·2 Lake Superior, Mass. Penn.

Variat viridis et aurea. Say. J. Ac. 5, 293: Lac. 199.

25. D. e m a r g i n a t a, capite non toroso, thorace ruguloso, parce-puncta postice paulo angustato, angulis prominulis, late canaliculato, tubercule latera prominulo, impressione profunda separato, elytris plus minusve rugosis obsolet biimpressis, femoribus posticis dente magno armatis, ano emarginato, antennarm articulo 3^io^ 4^to^ breviore. Long. ·26. Lake Superior, Mass., and Pennsylvania

Mas linearis, angustus; femina minus elongata.

Variat aurea, cuprea, cyanea et nigra: antennis pedibusque semper obscuri Kirby 224: Lac. 202. *D. biimpressa*, Mels. P. Ac. 3, 159. *D. aurichalcea* Mels. ibid.

26. D. m e t a l l i c a, subelongata, nitida, capite non toroso, thorace rugu loso, disco utrinque lævigato, postice regulariter paulo angustato, angulis antici prominentibus, tuberculis lateralibus vix prominulis, canaliculato, ante basi transversim profunde impresso, elytris rugosis, femoribus posticis dente parv armatis antennarum articulo 3^io^ 4^to^ vix breviore. Long. ·23—·26. Penn sylvania.

Mas antennis longioribus, femorum dente distincto: femina antennis brevioribu femorum dente obsoleto. Variat aurea, ænea, viridis et æneo-nigra, antenni plus minusve rufis. Ahrens Nov. Act. Hal. 1, 3, 33: Lac. 189. *D. nana* Mels P. Ac. 3, 160.

27. D. g e n t i l i s, longiuscula, nitida viridi-ænea, capite non toroso, thorac ruguloso, disco utrinque lævigato, postice magis angustato, angulis anticis promi nentibus, tuberculo laterali prominulo, canaliculato, ante basin transversim im

presso, elytris rugosis, femoribus posticis dente parvo armatis, antennarum articulo 3^io^ 4^to^ fere æquali. Long. ·24. Pennsylvania.

Femina latet.

28. D. f l a v i p e s, subelongata, ænea, vel nigro ænea, capite subtoroso, thorace minus dense rugose-punctato, postice angustato, angulis prominulis, profunde canaliculato, tuberculo laterali prominulo, ante basin valde impresso, elytris parcius rugosis, femoribus posticis dente magno armatis, pedibus antennisque plus minusve rufis, his breviusculis, articulo 3^io^ 4^to^ vix breviore. Long. ·33. Mass. Lake Superior and Pennsylvania. Kirby, 223: Lac. 201.

β. Thorax convexus: pedes brèves crassi, femoribus posticis ellipticis, basi non attenuatis, subtus dente valido armatis.

29. D. i u c u n d a, subelongata, cupreo-ænea nitida, thorace punctato, cordato, angulis vix distinctis, tuberculis lateralibus obsoletis, profunde canaliculato ante basin valde impresso, elytris profunde seriatim punctatis, vix rugosis, pedibus antennisque rufis, his crassiusculis, articulo 3^io^ 4^to^ vix breviore. Long. ·27. Lake Superior. ‖Lec. 237.

30. D. K i r b y i, subelongata, cupreo-ænea, nitida, thorace parce-punctato, cordato, angulis rotundatis, tuberculo laterali distincto parum prominulo, subtiliter canaliculato, ante basin valde impresso, elytris interstitiis planis vix rugosis, ante medium impressis, pedibus antennisque rufis, his articulo 3^io^ 2^ndo^ sesqui longiore 4^to^ paulo breviore. Long. ·28. Georgia.

Variat tuberculo thoracis laterali minus distincto. Lac. 201. D. affinis‖ Kirby. 224.

31. D. s u l c i c o l l i s, brevis, thorace parce subtiliter punctato, cordato, angulis paulo prominulis, tuberculo laterali paulo prominulo, canaliculato, ante basin valde impresso, elytris profunde seriatim punctatis, vix rugosis, ante medium obsolete impressis, pedibus antennisque rufis, his articulis 2^ndo^ et 3^io^ æqualibus, 4^to^ vix brevioribus. Long. ·33. Mass., Maine, Pennsylvania, Drs. Melsheimer and Harris.

Præcedente brevior, thorace latiore: mas femina paulo angustior; variat cuprea viridis, et ænea, tuberculis thoracis sæpe obsoletis. Lac. 186. *D. metallica*‖Say. J. Ac. 5, 283.

***Elytra parallela, vix truncata; antennæ articulo 2^ndo^ breviore, thorax postice angustatus: oculi orbito præditi.

32. D. f e m o r a l i s, minus elongata, ænea, pedibus rufis, vel fuscis, capite toroso, thorace subtiliter rugoso: parce punctato, longiusculo, angulis prominulis, vix canaliculato, ante basin impresso, lateribus subtuberculato, elytris convexis, profunde seriatim punctatis, rugosis, antennis annulatis, articulis 3^io^ 4^toque æqualibus, 2^ndo^ sesqui breviore. Long. ·26. Lake Superior.

Mas subelongatus, femor. posticis dente acuto armatis: femina femor. post. muticis. D. c u p r e æ, et d i v i t i sectionis præcedentis similis, oculis tamen orbito præditis valde distincta. Kirby, 223: Lac. 200.

****Elongatæ, oculis vix prominulis, orbito nullo; elytra convexa ap truncata: antennæ tenues articulo 2^do breviore.

33. D. Harrisii, elongata, ænea, capite vix toroso, thorace longiusc dense rugose punctato, postice vix angustato, angulis prominulis, subtiliter ca iculato, ante basin impresso, tuberculo laterali vix prominulo, impressione post definito, elytris parallelis, versus apicem oblique angustatis, valde seriatim pa tatis; parce rugosis, antennis annulatis, articulo 2^do reliquis duplo brevio Long. ·42. Penn. rarissime.

Mas femoribus posticis incrassatis ellipticis dente acuto armatis.

Femina femor. posticis paulo incrassatis, muticis. D. inermis Harris. MSS

Species singularis, oculis parvis habitu Statyræ (Lagriarum) subsimilis.

Species mihi ignotæ.

34. D. carolina Lac.	in *B inscribendum.
35. D. militaris Lac.	*B.
36. D. erea Lac. 148.	*C. prope D. subtilum.
37. D. pallipes Lac. 149.	**A. prope D. confusam.
38. D. assimilis Lac. 153.	*C ?
39. D. vicina Lac. 154.	*C ?
40. D. chalcea Lac. 188.	**C. β.
41. D. parva Lac. 190.	**C. β.
42. D. binodosa Germ. Lac. 195.	**C. β.
43. D. æqualis Say. J. Ac. 3, 428.	**C. χ. prope D. emarginat
44. D. rufa Say. J. Ac. 5, 283.	**C. χ ?

Species dubiæ, vel descriptione non cognoscendæ.

D. fulvipes Lac. 192.	**C. χ. =?D. pusilla Say.
D. cataractæ Newman Ent. Mag. 5, 391.	**C.
D. rugifrons Newman, ib.	**C. =D. emarginata Kirb
D. cuprea Mels. P. Ac. 3, 158.	*B. =?D. tuberculata ♂.
D. indica Mels. ib.	*** =?D. femoralis Kirby.
D. rutila Mels. P. Ac. 3, 159.	*B. =? tuberculata ♀.

Works cited in abbreviation.

Lac. Monographie des Colèoptéres subpentamères, par Th. Lacorda Vol. 1.

Lec. Le Conte in Agassiz, Lake Superior. Boston, 1850.

Mels. Melsheimer in Proceedings of the Academy of Natural Sciences.

Kb. Kirby in Fauna Boreali Americana. Vol. IV.

Zoological Notes.

By John L. Le Conte, M. D.

During a visit to Panama, in December, 1849, I had frequent occasion to obs many animals of such frail texture, as to render impossible any attempt to p serve them, and took many notes respecting their appearance and habits. By

accident, my manuscript while being sent home, was rendered nearly illegible, and I am now able to recover only a few fragments of it. I have thought that the animals observed, were of sufficient importance to warrant the publication of my notes, although not relating to the subjects of my own special researches.

I had intended to prefix a few observations respecting the geographical distribution of organic beings on the Isthmus, but having recently received through the kindness of friends, collections which serve to make a more minute comparison between the production of different parts of the year, I will postpone for the present, the discussion of the phenomena observed, and merely state a single fact which appears to me of great importance, in considerations regarding the limit of the effects of physical causes. During the month of December, I labored assiduously to procure a set of the Coleoptera of the vicinity of Panama, and was surprised on looking over my collection, to find a complete absence of the genera known to be confined to the tropics. In fact, with the exception of half a dozen Chrysomelinæ, there was not a single species which might not have come from a region far north of the tropic. It is known that in the southern part of the temperate zone, the Carabica, Brachelytra, water beetles, &c., which first appear in the spring at northern localities, are most abundant in winter, and this would be naturally explained by the fact that the temperature in that season is most nearly akin to to that of the regions in which they flourish best. But it is a little alarming for the doctrine of physical causes, to find that the same arrangement in the appearance of species, is kept up in a region where climate can have nothing to do in producing these phenomena.

Ophiolepis *Müll.*

1. O. annulata, disco squamis minimis imbricatis dense tecto, radialibus 10 paulo majoribus, distantibus; brachiorum squamis dorsalibus hexagonis, latitudine sesqui brevoribus extrorsum angustatis, ventralibus subquadratis, extus submarginatis; scutis buccalibus utrinque subacutis latitudine non longioribus, postico umbone depresso, foraminisque marginalibus 8 distincto: brachiis dorso fusco-annulatis, disci diametro 7$^{\text{les}}$ longioribus. Long. 4—6½ unc.

Color grayish yellow; disc brown with closely approximated pale spots; arms seven times as long as the diameter of the disc, with every fourth dorsal plate dark; the scales of the disc are very small and imbricated, the radial ones scarcely larger, and widely separated. The oral plates are rounded on the lateral angles, and are not surrounded with papillæ; but from the apex of each, run two rows of small papillæ, which follow the inflexed margin of the fleshy part of the disc. The oral papillæ are distinct, four on each side. The tentacular pores have each two small scales, the spines are arranged in three rows, their length is equal to the diameter of the arms. This species apparently resembles O. reticulata Muller, 95. *Ophiura reticulata* Say (J. Ac. 5, 148,) but the spines are longer.

2. O. geminata, disco squamis minimis imbricato, scutis radialibus magnis, elongatis, per paria valde approximatis, brachiorum squamis dorsalibus latitudine duplo brevioribus, intus subangulatis, ventralibus transversis, subpentagonis; scutis buccalibus rhomboideis, angulis acutis, angulo aborali truncato: scuto postico umbone nullo, foramine unico apicali notato, brachiis dorso maculatis, disci diametro 6—7$^{\text{les}}$ longioribus. Long. 3—4 unc.

Pale gray; arms marked with scattered brown spots. Oral plates not surrou with papillæ, angles acute, the distal one truncate; the posterior plate is di guished by only a single marginal foramen. The inflexed margin of the disc i margined with papillæ as in the preceding species: the oral papillæ are large, there are only three on each side: the tentacular pores have two small ob scales: the spines are in three rows, and their length is only one half the dian of the arms: the spines of the middle row are rough. This species seems similar to O. elongata Mul. 95. *Ophiura elong.* Say J. Ac. 5, 146.

3. O. simplex, subtus pallida, supra obscura, disco scutis mediocribus, gr latis, subimbricatis tecto, radialibus paulo maioribus modice approximatis, i stitio scutis duobus; brachiorum scutis dorsalibus latitudine duplo breviori lateribus rotundatis, ventralibus quadratis angulis rotundatis, squama tentac rum unica; spinis lateralibus serie 5-plici sitis, scutis buccalibus taansve subrotundatis, postico foramine apicali notato: brachiis disci diametro 7ies gioribus. Long. 4 unc.

Pale beneath, above blackish brown; arms marked with a few paler ba the scales are all finely granulated, the radial ones separated by two plates. oral plates are not surrounded with papillæ, and on each side there is only a gle oral papilla; the tentacular pores are protected with single scales, the se scale being spiniform and forming the lowest of the five series of lateral spi the longest of which is scarcely equal to the diameter of the arms.

4. O. hispida, albicans, maculis parvis nigricantibus supra adspersa, disco s mis minutis imbricatis tecto, spinulisque brevissimis dense hispido: scutis rad bus elongatis, approximatis; brachiorum scutis dorsalibus latitudine triplo brev bus extorsum subrotundatis, ventralibus quadratis, transversis, angulis rotund spinis lateralibus serie triplici sitis, longitudine dimidium brachiorum dian æquantibus; scutis buccalibus rhomboideis, postico foramine apicali notato, chiis disci diametro 10ies longioribus. Long. 6 unc.

Only a single specimen found very distinct by the hispid surface of the The oral plates have on each side 3 or 4 tolerably large papillæ. The tentac pores have two small elliptical scales.

Besides the species described above, a large one was given me by Dr. Duc saing, which strongly resembles O. serpentaria, from the West Indies. The sal plates of the arms were a little more transverse, and the buccal plates n rounded. Not having had sufficient opportunity for examining whether tl should be considered as specific differences, I forbear for the present expres an opinion on this specimen.

Ophiothrix, Mul.

O. spiculata, supra obscura, subtus pallido-maculata, disco confertim spicul spiculis echinatis, spinis maioribus versus medium intermixtis, scutis radiali magnis, triangularibus, granulatis, rarius spiculatis, angulo brachiali albica per paria approximatis, brachiorum scutis dorsalibus sub-carinatis vix trans sis, angulis lateralibus acutis, margine externo fortiter rotundato, ventrali quadratis sub-transversis, lateribus rotundatis, spinis lateralibus serie 7plici s serie superiore vix breviore; oris scutis transversis, angulis lateralibus rotunds externo acuminato, brachiis diametro disci 6ies longioribus. Long. 4—5 unc.

This species is very variable as regards the closeness of the numerous sl

serrate spiculæ which clothe the disc; the radial plates are more or less distinct, sometimes nearly free from spiculæ; they are large and granulate, the angle which is above the base of the arm nearly touches the corresponding angle of the next plate, and is whitish. The oral plates are wider than long, with the oral angle distinct and the lateral angles rounded; the apex is acuminate. The inner series of plates bounding the oral plates is very narrow. The brachial spines are arranged in 7 rows, the two inferior ones being the shortest; the others are about twice as long as the diameter of the arm, and serrate from base to tip; they are transparent, with the apex frequently black. The body is dark fuscous above, and pale beneath; every fifth ventral plate on the arms is sometimes red or brown.

Some of the varieties of this species may possibly be Ophiothrix ciliaris Mul.; the young are pale colored, and very like the adults; the plates which margin the oral plates are relatively larger, being one half the size of the latter.

PLANARIÆ.

Glossostoma. n. g.

Body vermiform. Head continuous with the body. Eyes 10—16 in each side of the head. Mouth subterminal, with a retractile tentacle on each side. Intestinal tube ramose. Marine.

1. G. nematoideum, pallide flavicans, pellucidum, filiforme, ocellis utrinque 10—16 minutissimis; cæcis intestinalibus brevibus obtusis. Long ·1. unc.

This animal has so little the appearance of a Planaria, that I long hesitated to refer it to this genus; but on careful examination, I could perceive no distinct character by which to separate it. The mouth is situated near the end, and on the inferior surface of the body; it is furnished on each side with a small blunt retractile appendage. The ocelli are very minute, and situated on each side in an oblong group, about half a line from the extremity, the abdominal cœca are large and blunt.

Elasmodes. n. g.

Body dilated, flat. Head continuous with the body, without appendages. Ocelli 5 on each side. Mouth antero-inferior, œsophagus ventral; intestinal tubes reticulated, radiating. Marine.

1. E. discus, latissima, planissima, pallida, pellucida, tubulis intestinalibus reticulatis, tenuibus, e ventre oblongo radiantibus, ocellis utrinque 5 valde approximatis ab apice remotis. Long. ·34, lat ·25, unc.

Very flat and thin, pellucid, only rendered darker in the middle by the slight color of the intestinal tubes, which are very fine and numerous, radiating from a central cavity which is five times as long as wide. Ocelli five on each side, closely approximated; groups separated by a space equal to one-third the distance from them to the margin or apex.

Typhlolepta? extensa, planissima, supra purpurea vel brunnea, margine pellucido, tubulis intestinalibus tenuissimis; numerosissimis, e canali tenui orientibus. Long. 1·25, lat. ·32 unc.

Less dilated than the last, but equally thin; owing to the immense number of small intestinal tubes the color appears uniform, the central tube extends to within two lines of each extremity. There are no visible ocelli.

ZOANTHA CUV.

Z. Danai, pallide purpurascens, tentaculis brevissimis, crassitie non longi ribus, disco viridi, extrorsum purpurascente, ore parvo purpureo-marginato, te taculis externis basi pallidis. Diam. disci ·25. unc.

Remarkable for the shortness of the tentacula, which, when fully extended, a scarcely longer than the diameter of their base; they are arranged in two serie those in the outer series are pale at the base. The disc is radiately rugose, br liant green, margined both internally and externally with purple. The root broad, the animals closely associated, capable of extending 1·25 inches.

I have named this species as a feeble tribute of respect to the philosopher, whom we owe the first rational classification of Zoophyta.

The Committee on the following paper, by Dr. Leidy, reported favor of publication.

On some American fresh-water Polyzoa.

By JOSEPH LEIDY, M. D.

Since I described several species of fresh-water ciliated polyps in the la number of the Proceedings, we have received the Report of the British Associ tion for 1850, in which I find a very able and complete report upon "the prese state of our knowledge of the fresh-water Polyzoa," by Prof. Allman, M. D.

Prof. Allman has very correctly applied the term Polyzoa, of Thompson, the ciliated polyps, because it had been employed prior to the application them of the term Bryozoa, of Ehrenberg.

Prof. A. has also invented some very happy terms, applicable to differe parts of the structure of the Polyzoa. Thus for the common dermal system a solid basis of a colony of polypes he uses the word Cœnœcium. The extern tunic of the latter he calls the Ectocyst, and that lining the tubes the Endocys and the disk supporting the tentaculæ is named the Lophophore.

According to the characters given to the genus Cristatella, *Cuv.*, the speci which I described in the last number of the Proceedings as C. magnifica, cann belong to that genus, as I then suspected; for Cristatella has a "common fla tened disk adapted for locomotion," nor can it belong to Lophopus, *Dumort*, f although this has its base of attachment fixed, yet the ova of the animal have marginal spines, and it therefore must form a distinct genus between Cristatell and Lophopus, with the following diagnosis :—

PECTINATELLA, *Leidy*.

Cœnœcium massive, gelatinoid, hyaline, fixed, investing bodies. Orifice arranged in irregular lobate areolæ upon the free surface. Lophophore cre centic. Ova lenticular, with an annulus and marginal spines.

1. PECTINATELLA MAGNIFICA, *Leidy*.

Cristatella magnifica, *Leidy*. Proc. A. N. S., V. 265.

Remark.—Found only in shaded situations, always incrusting dead branch of trees.

PLUMATELLA, *Lamarck.*

1. PLUMATELLA DIFFUSA, *Leidy*. Pr. A. N. S., V. 261.

2. PLUMATELLA NITIDA, *Leidy.*

More robust than the preceding, color light olivaceous brown, consisting usually of only a few branches; tubes amphoræform, without a keel, smooth or transversely corrugated near the orifices which are entire. Length of the articuli one line, breadth one-fourth of a line. Polyp has the same form as in the preceding, and also the same number of tentaculæ.

Habitation.—Found with the preceding.

Remarks in connection with Plumatella.—Almost every stone, in many parts of the Schuylkill river, particularly below the dam at Fairmount, has adhering to it numerous eggs of Plumatella in short rows, which upon superficial inspection resemble prismatic crystals of some mineral.

PALUDICELLA, *Gervais.*

1. PALUDICELLA ELONGATA, *Leidy.*

Cœnœcium attached throughout, or attached by only a few articulations, the remainder floating; delicate, very much branching, colorless or ambreous, shining. Articulations very long, claviform; tubes of exit variable in length, placed close to the distal extremities; orifices entire.

Polyps with sixteen tentaculæ arranged in the form of an inverted cone. Stomach brown in color.

Measurements.—Articuli of cœnœcium to 1 line in length, by 1-133d in. in breadth at the dilated part, and 1-285th in. at the narrow part.

Habitation.—On the under side of stones in the Delaware and Schuylkill rivers. It is found in vast profusion below the dam of the Schuylkill at Philadelphia.

Besides the foregoing, I have observed what I suspect to be the cœnœcium of a new genus of Polyzoa, although I have never been able to detect the polyps if such exist. It resembles when viewed by the naked eye a very minute Isis hippuris, or the corraline Amphiroa corymbosa. Under the impression that it belongs to the Polyzoa, it may be characterized as follows.

URNATELLA, *Leidy.*

Cœnœcium membrano-corneous, consisting of several divergent, unbranching filaments, attached by a common basis. Filaments consisting of a series of urn-shaped articulations, with a solid axis passing through the whole, and having to each articulation one, occasionally two, tubes of exit with the orifices expanded, placed inferiorly near their commencement.

URNATELLA GRACILIS, *Leidy.*

Usually three to five filaments arising from a common basis of attachment. Articulations up to nine in number to a filament, very regularly urnform except the distal two which are inverted pyriform, decreasing in breadth from the first to the last. Body portion of each urnform articulation yellowish white, translucent, with fine transverse bands or striæ, and punctæ of brown; neck or pediculate portion, columnar, transversely contorted, expanded at base, black. Tubes of exit one, occasionally two, to each articulation except the last, which has none, placed at the lower part of the body portion of the articulation, and

curving upwards, with the orifice expanded and horizontal or nearly so, ar colored with darker punctæ. Interior axis white, opaque.

Measurements.—Length of a filament of 9 articulations 1 line; first artic tion 1-140th in. in breadth, last 1-220th in.

Habitation.—Found growing on the under side of stones in the same si tions as Plumatella and Paludicella, in the river Schuylkill below the dan Philadelphia, below low water mark.

Remarks.—A very beautiful and graceful form, as before mentioned resemb a minature Isis hippuris.

The cœnœcium is hard and resistant, and has no carbonate of lime ente into its composition as might probably be suspected. When compressed, axis or interior central, white, opaque column is squeezed out of the rupt articulations in the form of transparent colorless oleoid granules, from 1-32,000th to the 1-4,000th of an inch in diameter.

I have frequently found this enigmatic body, which I suspect to belon previously stated, to a Polyzoon, but I have never been able to detect the po The filaments appear never to go beyond nine articulations, nor have I found more than five filaments to a group.

Reference to the Figures.

All the figures are much magnified.

Fig. 1. Two articulations in outline of Paludicella elongata, with a term young articulation.

Fig. 2. One articulation of P. elongata; with a second terminal young one.

Fig. 3. Urnatella gracilis, with three of the filaments cut off from the exp ed base.

Fig. 4. A single articulation of U. gracilis with two tubes of exit.

Fig. 5. A separated articulation of U. gracilis under compression, with escape of oleoid granules below from the central axis.

The Corresponding Secretary read a Report, embracing the last months, which was adopted.

Dr. Fisher offered the following, which was adopted:—

Resolved, That a Committee of three members be appointed to inq into the expediency of enlarging the Hall of the Academy, so as to nish greater accommodation for the Museum and Library, and to re a plan for the same, together with an estimate of the expense, and to port at the annual meeting, December 30th, next.

Dr. J. C. Fisher, William S. Vaux, and Dr. Bridges, were appoin the Committee under this resolution.

The following Resolution was also adopted:—

Resolved, That the privilege of endorsing tickets of admission to Museum on public days, be granted to Mrs. Emily Taylor, widow Richard C. Taylor, late a distinguished member of this Institution, that she be authorized and invited to visit at all times the Museum Library.

ELECTION.

Robert A. Caldcleugh, Esq., of Philadelphia, was elected a *Member* of the Academy.

December 2d.

Vice-President BRIDGES in the Chair.

Letters were read :—

From Dr. E. K. Kane, acknowledging the receipt of a copy of the resolution of thanks to him, adopted at a late meeting of the Academy, and stating his intention to make also a donation of a small collection of plants from a high Northern latitude, (76° 15′.)

From the Royal Academy of Sciences of Stockholm, dated November, 1849, and October, 1850, acknowledging the receipt of several numbers of the Proceedings and Journal of this Academy.

From the same, of same dates, transmitting the Transactions of the Academy, Parts 1 and 2 for 1848, and of the Bulletin for 1849, and also a medallion in copper of the late Jacob Berzelius.

From the Royal Academy of Sciences of Madrid, transmitting Part 1, Vol. 1, third series of its Memoirs, and a Resumé of its transactions for the years 1848–49. Also inviting experimental essays on the subject of Nitrification for a *Concours*, and announcing that prizes would be awarded for the best essays.

December 9th.

Vice-President WETHERILL in the Chair.

Communications were read from :

Mrs. Emily Taylor, dated Philadelphia, December 6th, 1851, returning acknowledgments for the Resolution adopted by the Academy, conferring the right of endorsing tickets of admission to the Museum.

And from Mrs. Rebecca Morton, dated Philadelphia, Dec. 8th, 1851, returning thanks for copies of Dr. Meigs' Memoir of the late Dr. Morton, presented to her by the Academy.

Dr. David Dale Owen read a paper intended for publication in the Journal, entitled "Description of a new Mineral and a new Earth." Referred to a Committee, consisting of Mr. Vaux, Dr. C. M. Wetherill, and Dr. McEuen.

Professor Horner read a history of some cases of Articular Inflammation of the Knee, treated successfully with Urate of Ammonia. Referred to Dr. Leidy, Dr. Hallowell, and Dr. Rand.

Professor Horner introduced to the Society Monseigneur Demers, Bishop of Vancouver, who gave much interesting information respecting the habits, language, and traditions of the Indian Tribes of Oregon, forty-one of which, out of seventy-one, had been visited by him. He also offered the hospitalities of the Mission to which he was attached, to such

members as might be visiting that region, and expressed his wish to
ther the objects of the Society.

Professor Horner exhibited some specimens of Adipocire, fragmen
human bones, and mould, obtained from a cemetery which had been in
for upwards of a century, and from which the remains are now bein
moved. One specimen of crumbling bone was proved to be more than
hundred years old.

He also read the following by Mr. John Rommel, Jr., giving s
particulars in relation to the subject.

"The cemetery from which the specimens were obtained has been use
more than a century.

The ground for the depth of ten or twelve feet is of ordinary yellow clay, b
which it is of a gravelly nature. In the majority of places it is very hard
dry, but in some places it is quite moist, and in one or two places act
swampy. The workmen in removing the remains, in order to save time,
trench about eight feet wide and about twenty feet long, then the follo
eight feet are undermined, and this is thrown into the dug trench; hence th
necessarily a great confusion as to the dates of the remains.

But comparatively few remnants of coffins were found, but an immense nu
of bones still remained.

In situations which were very free from moisture, no vestige of bone or
was found after a lapse of twenty to twenty-five years, and even in less t
but as the ground became more moist, the preservation was more complete;
where it was swampy, the preservation was almost perfect; pieces of sha
from the coffin (originally left there by the undertaker) being found, which
been interred above forty years, and the soft parts adhering to the bones, i
shape of Adipocire. I saw a corpse removed (having been interred thirt
years) which was in an almost complete state of preservation: the counte
was so perfect, that the friends of the deceased might easily have recog
him; the garments were in a good state, as was also the coffin.

In removing the earth, the workmen would probably strike a skull; the g
being then carefully removed, the perfect skeleton was displayed, all the
being in their respective places, as if the anatomist had carefully arranged
previous to making an artificial skeleton; no ligament or muscle to be see

The latter were not seen in some instances in five or six years after b
Accompanying the bones, I always observed some black matter, which was
bably the remains of the coffin; and where no bones at all were found, ab
shovel full of this black earth was seen, indicating the spot where the indiv
had lain.

The Bones.—There was of course every variety of sizes, and in all stag
preservation; sometimes I only saw the shaft of the tibia, which had no
mark of distinction than the spine; sometimes the femur, known only
comparative magnitude, and by the linea aspera; some were crumbled to
pieces, and the slightest handling reduced them to powder. They were n
all brown or blackish, many looking as if they had been smoked.

The Odor.—The odor arising from the graves was not perceived unless in close contact with the remains, and then it was but faint and slightly disagreeable, and when the air came in contact with it, it was immediately dispelled. The bones, after being removed, had an earthy odor, and not at all disagreeable.

The Skull.—In all instances where the sutures of the skull had not been completely obliterated previous to death, by old age, &c., I observed the partial or complete separation of the bones, in many instances lying side by side, completely separated, and in good condition.

The Hair.—I had expected to find much more hair than I did; some few specimens were found well preserved; one belonged to a young man, and was as smooth, and in as fine a state, as if the hair-dresser had just left him, but he had not been buried many years. In the majority of cases where it was found it was only in small quantities, and was torn with the utmost facility.

The stature of many of the individuals was remarkable, judging from the bones, many were over six feet, and many over six feet five inches in size. Quite a number of iron handles (belonging to the coffins) remained, either in a state of partial or complete oxidation, and remains of breast plates were also found, but the engraving was totally unintelligible.

The interring of jewelry does not appear to have been fashionable in those days, or else the workmen overlooked it; only a piece of one ear-ring was found, and that was as highly polished as if it had just come from the hands of the jeweller.

From the discrepancy regarding dates, these are all the facts which I have been able to obtain; but having heard from good authority that a similar enterprise will be undertaken shortly, I am in hopes I shall be able to obtain more facts on this interesting subject."

Dr. Leidy exhibited a number of fossil reptilian and mammalian remains, which he characterized verbally as follows:—

CIMOLIASAURUS MAGNUS, *Leidy*. A saurian established upon thirteen vertebræ, apparently from one individual, found in the Green Sand of New Jersy, and preserved in the Museum of the Academy. Two of the vertebræ are posterior dorsal, the remainder lumbar. All of them have the processes broken off, excepting one of the dorsal, which still preserves its transverse processes nearly entire.

The vertebral bodies are broader than they are long, being compressed cylindroidal in form, gradually expanding from their middle to the angular edge of the articular surface. The latter are slightly concave, about one-half the depth of those of Poecilopleuron Bucklandii, *Desl.*, with the centre a little prominent and becoming slightly convex towards the edges.

The transverse processes remaining in one of the specimens of dorsal vertebræ are prominent, thick, irregularly cylindroid tubercles, projecting from the middle of the side of the vertebral body, with an oblique articular facet for the rib.

In the lumbar vertebræ the transverse processes incline downwards from the lower part of the bodies laterally, as in Mososaurus.

Measurements of the largest dorsal vertebra.

Length of body,	2¼ inches.
Breadth " at articular faces,	4¼ "
Heighth " " "	3¼ "
Depth of articular faces,	2 lines.
Length of transverse processes,	1 inch.
Diameter " "	1¼ "
Breadth of spinal canal,	1 "

Measurements of the smallest lumbar vertebra.

Length of body,	2 inches.
Breadth "	2¼ "
Heighth "	2 in. 10 line
Depth of articular surfaces,	2¼ lines.

DISCOSAURUS VETUSTUS, *Leidy*. A saurian founded upon a single vert with the processes broken away, obtained by Mr. Joseph Jones from the cr eeous formation of Alabama.

The body is about as large, and has a general resemblance to that of Ple saurus pachyomus, *Owen*, represeuted in fig. 3, tab. xx., of the Monograph on fossil reptiles of the Cretaceous Formation. It differs most remarkably from vertebral bodies of Plesiosaurus, in the articular faces forming distinct conc disks, separated from the body by a constriction or short neck. The bod relatively much broader in relation to its length than in Plesiosaurus. The cimen is a cervical vertebra. Upon each side it has a deep, concave, transver oval, costal pit, with a very prominent, sharp border.

Measurements.

Length of body,	2 inches.
Breadth "	2¼ "
Heighth "	
Depth of articular surfaces,	2¼ lines.
Transverse diameter of costal pit,	1¼ inches.
Vertical " "	11 lines.
Depth of costal pit,	4 "

The fragment of a vertebra described by Dr. Dekay in the Annals Lyceu Nat. Hist. of New York, Vol. 3, p. 165, and represented in Pl. 3, fig. 11, f the Green Sand of New Jersey, and observed by that gentleman to be allie the Plesiosaurus, probably belongs to the Discosaurus vetustus.

The vertebra described by Dr. Harlan in the Journal of this Academy, Vo p. 232, and represented in pl. xiv. fig. 1, was referred to the Plesiosaurus. specimen was from the Green Sand of New Jersey, and is preserved in the c net of the Academy. It does not belong to a saurian, but is a posterior do vertebra of a cetacean allied to the Delphinus. The vertebral body is relati twice the length of what it is found to be in the latter. The transverse pro is also relatively short and broad; at its extremity it has an articular facet for head of a rib.

The vertebra is probably the type of a form existing in a distinct genu ancient Cetacea, for which I propose the name PRISCODELPHINUS. The speci

dedicate to the memory of Harlan, under the name of PRISCODELPHINUS HARLANI, *Leidy*.

In the collection of the Academy there are preserved two caudal vertebræ of a young cetacean, from the Green Sand of Jersey. These specimens are larger than the dorsal vertebra just described, but from the length of their bodies, and the width antero-posteriorly of the neural arch, I suspect them to belong to the same genus of the latter, but a larger species, for which I propose the name PRISCODELPHINUS GRANDÆVUS, *Leidy*.

Measurements of the posterior dorsal vertebra of P. Harlani.

Length of body, ...	2 inches.
Breadth of articular surfaces, . . .	8 lines.
Length of transverse process, . . .	1¼ inches.

Measurements of two caudal vertebræ of P. grandævus.

Length of body, ...	2¼ inches.
Breadth of epiphysial surfaces, . . .	2½ "

The two species of Priscodelphinus possess more than ordinary interest, from their being the first mammalia which have been discovered in the cretaceous formations.

CROCODILUS FASTIGIATUS, *Leidy*. Established upon a tooth which Mr. T. Conrad informed me was obtained by Mr. Smiley from the Eocene formation of Virginia. The specimen is about the size of that of Crocodilus champsoides, *Owen*, represented in fig. 11, tab. v., of the Monograph of the fossil Reptilia of the London Clay by Prof. Owen. The crown has about the same length as in the last mentioned species, but is more robust, more curved and pointed, with more numerous ridges but not so coarse, and between the larger are from one to four fine corrugated linear ridges. The fang is also a little more robust. The enamel is jet black, shining. The osteo-dentine is thick, dark brown with a resinous lustre.

Measurements.

Length of crown, ...	9 lines.
Diameter at base, ...	4 "

Dr. L. further called the attention of the members to some very remarkable fossil remains of mammalia from Nebraska, belonging to the collection of Dr. D. D. Owen.

The fossils consisted of a nearly entire cranium of Rhinoceros occidentalis, two crania of Oreodon priscum, a large portion of the face of Archæotherium Mortoni, which has true molars resembling those of Chœropotamus and Hyracotherium, and a very perfect turtle, which was characterized as follows.

EMYS OWENI, *Leidy*. Approaches the genus Testudo in many of its characters. Carapace very convex; marginal plates nearly vertical; costal plates alternately broad and narrow. There are nine vertebral, nine costal, and eleven marginal plates each side of the pygal and nuchal.

	Straight.	Curve.
Length of Carapace, . .	11 inches.	13 inches.
Breadth " . .	8½ "	14 "
Heighth " . .	5½	

The species is named in honor of Dr. D. D. Owen, of New Harmony, Ind who has contributed this as well as numerous other objects to Palæontology.

Dr. Owen made the following observations on the locality of the fo from the "Mauvaises Terres" of Missouri.

The region of country where the remains of the fossil mammalia exhi were procured, is a part of the district known to the French Canadian voya of the Upper Missouri as the Mauvaises Terres or Bad Lands, which lie bet the Missouri river and the base of the Black Hills, and the waters of the Sl and Moreaux. It presents the appearance of the great bed of some ancient the base of which is some three hundred feet below the general level of the expanse of prairie which rises in terraces towards the Rocky Mountains.

This depressed valley of the Mauvaises Terres appears more a valley of vation than of subsidence, as is proved by the multitude of isolated pinn mounds, and curious outliers, which, having resisted the denuding fo stand in all imaginable fantastic shapes, memorials of the excavating forces have been at work. These rise to the height of from two to three hundred feet form between them a complete labyrinth of intricate passages stretching as f the eye can reach, that soon bewilder the incautious explorer.

These remarkable insulated peaks, like the sides of this great valley, are posed of horizontal beds of indurated clays, marly strata, and thin beds of q ore conglomerates, all probably belonging to the age of the Eocene tertiary are the receptacles of those unique fossil remains, presenting a most extraordi assemblage of pachyderms, some of which seem to have combined the at pr anomalous character of ruminants, associated with a few carnivorous animal

The skulls, bones, and fossil fresh-water turtles are mostly found on moun white, pale flesh-colored, and light grey and greenish marly and argillac earths, the debris of denuded strata. The Palæotherium bed lies toward base of the section, from ten to twenty feet above the bottom of this valley.

Further details concerning this curious country and its ancient fauna, tog with a section of the strata composing it, will be found in the forthcoming logical report of the North West.

The Committee on Proceedings announced that Dr. Meigs' Memo the late Dr. Morton was published, and was now ready for distributi

On motion of Dr. McEuen it was

Resolved, That the thanks of the Society be presented to M. Desm Bishop of Vancouver, for his offer of the hospitalities of his Missio the members, and of his assistance in furthering the objects of Society, and that a Committee be appointed for the purpose of secon his proposal.

Committee, Dr. McEuen, Dr. Horner, and Dr. Leidy.

Upon the right side the second and third superior molars, and the first second inferior are exposed to view, the others, excepting the first super which has been shed, are enveloped in the matrix in which the fossil was bedded. Upon the left side the three inferior molars are preserved nearly ent

The alveoli for the superior incisors remain and are very large, and leave interval between them and the canine.

The interval between the latter and the second molar is unusually large, b 7 lines.

The chin is broken away but ten lines anterior to the first molar, the ante broken margin of the jaw at its upper part is only one line thick, and present disposition to expand for the reception of the inferior canines. The coron process is very short, being only nine lines. The face above the infra-orb canals is very broad, and its anterior aspect with the forehead form a very ab angle with the parietal crest, or the forehead is very high above the post orb processes.

Measurements.

Length from occipital condyles to incisive alveoli of upper jaw,	6½ inch
Breadth of face above infra-orbiter foramina,	11 line
Breadth of canine at base of crown,	7 "
Thickness " " "	4 "

Dr. L. also made the cranium of a Musk-rat, obtained from a marl pit in N Jersey, presented this evening by Dr. Burtt, the subject of the following rema He observed, the specimen served as a hint to be cautious how we refer rem of animals of a recent character to older formations. There are preserved in cabinet of the Academy fragments of a lower jaw, tibia, and antler of a deer, the cranium of a beaver, which were also found in digging marl in New Jer All the specimens have the color of true marl fossils, but it is evident from character of the animals to which the remains belong, that they are only a dental inhabitants of the Green Sand. They may have fallen into a narrow fis of a marl bed which was afterwards closed up, or they may have sunken in n mud on the banks of a stream, whose bed afterwards may have been filled up drift material, and thus the mode of access to the marl be obliterated. In cabinet is a specimen of the distal extremity of an os femoris of a Snipe, foun the New Jersey marl, and described by Dr. Harlan* as a true fossil of the la but this is also a fragment of a recent animal belonging to the same categor the bones above mentioned. It is doubtful whether birds appeared very ante to the Eocene period; the ornithicnites of the new Red Sandstone may yet pr to be of reptilian origin.

Dr. Fisher remarked, in relation to the fruit of the Palm, presen this evening, that it was probably the fruit of the Corozo, mentioned Humboldt in his "Aspects of Nature," as being the smallest of Cocoa Palms.

---

* Med. and Phys. Researches, p. 280.

Mr. Lea exhibited a specimen of Zircon imbedded in blue Quartz, from the vicinity of the Yellow Springs, Chester county, Pennsylvania.

Mr. Vaux requested the attention of the members to the beautiful suit of specimens of Minerals from Nova Scotia, presented this evening by Isaac Chipman, Esq., many of which were not in the collection of the Society.

December 23d.

Vice-President BRIDGES in the Chair.

Dr. Leidy read a paper, intended for publication in the Proceedings, entitled "Contributions to Helminthology." Referred to Drs. Hallowell, Wilson, and Zantzinger.

Dr. Le Conte read a paper, intended for publication in the Proceedings, entitled "Synopsis of the Lampyrides of temperate North America." Referred to Dr. Leidy, Dr. McEuen, and Mr. Lea.

Dr. Leidy made some remarks upon the two species of Rhinoceros from Nebraska, which he had named R. Nebrascensis and R. occidentalis, and said he had satisfied himself they both belonged to the sub-genus Acerotherium, *Kaup.*, a good character of distinction of which, in the teeth, is the presence of a well developed basal ridge.

Mr. Lea exhibited a complete suite of specimens of Unio multiplicatus, from the Western Rivers of the United States, and made some extended remarks on the Family Naidæ.

December 30th.

Vice-President WETHERILL in the Chair.

The Committee to which was referred the following paper by Dr. Le Conte, reported in favor of publication in the Proceedings.

Synopsis of the Lampyrides of Temperate North America.

BY JOHN L. LE CONTE, M. D.

LAMPYRIDES.

Mandibulæ integræ: labrum obtectum: abdomen 6-vel 7-articulatum articulis omnibus liberis: tarsi 5-articulati articulo quarto calceato, plus minusve bilobato; femora ad trochanteris basin et latus inserta.

Div. 1ma. *Photophori.*

Abdomen sæpissime 7-articulatum,* articulis ultimis sæpius phosphoreis; antennæ approximatæ; tarsi articulo 4to subtus calceato.

---

* Colophotia has only six segments in the abdomen.

α Caput exsertum; thorax antice truncatus.

PHENGODES Hoffg.

Antennæ 11-articulatæ, longe biramosæ, articulis 2 et 3 minutis; abdom segmentulo anali aucto (an nota sexualis?), tarsi articulo 4to simplici.

1. P. plumosa Hoffmansegg. Illig. Mag. 6, 341. Laporte, Ann. E Soc. Fr. 2, 128. *Lampyris plumosa* Oliv. 28, tab. 3, 27; Fabr. Syst. 2, 105. *Phengodes testaceus* Leach, Zool. Journal, 1, 45.

Middle, Southern and Western States; very rare. Say observes (Bo Journ. 1, 157) that it is abundant for a short period in the autumn, flying i rooms at night. The coolness with which Mr. Leach places Olivier's na as a synonym to that suggested by him is remarkable, and might be w worthy of a harsher comment.

β Caput thorace obtectum; antennæ articulo 3to sequentibus æqual

POLYCLASIS Newman.

Antennæ 11-articulatæ, breviter bipectinatæ; palpi maxillares articulo ulti securiformi; tarsi articulo 4to vix lobato, ungues integri.

1. P. bifaria. *Lampyris bifaria* Say. Bost. Journ. 1, 157. *Pollacl ovata* Newman. Ent. Mag. 5, 382.

Southern States, Haldeman; very rare. I have corrected Newman's vici spelling of the generic name. This species must give but little light, only last joint of the abdomen is pale colored in my specimen.

LUCERNUTA Lap.

Lychnuris Dej.

Antennæ 11-articulatæ, dilatatæ, compressæ; palpi maxillares articulo ulti magno securiformi; tarsi articulo 4to longe lobato, ungues simplices; abdon apice phosphoreum, articulo ultimo superiore apice emarginato.

The males are distinguished by the longer and broader antennæ, and larger size of the last superior abdominal segment, which extends beyond inferior one in every direction; they have also a small additional anal segm beneath.

1. L. atra. *Lampyris atra* Fabr. Ent. Syst. 2, 101; Oliv. 28, tab. 28; *Lampyris laticornis* Fabr. Syst. El. 2, 100; *Photinus* (*Lucernuta*) *laticor* Laporte. An. Ent. Fr. 2, 144. *Lych. morio* Mels. Pr. Ac. Nat. Sc. 2, 303.

Abundant everywhere. I have restored Fabricius' older name, as I see reason mentioned for changing it; I have a variety from Georgia with whole of the posterior part of the thorax blackish.

2. L. tarda, atra, nigro-pubescens thorace apice subangulato, sca lateribus subito late reflexis, fusco-testaceis, basi late emarginato, disco l canaliculato, ante basin utrinque transversim elevato, elytris confertim mi subtiliter granulatis. Long. ·33.

Ohio, Dr. Kirtland. Very similar to the preceding; the sides of the thorax are more suddenly reflexed, and the disc is channeled; the basal elevation on each side is broader and less sudden, rather a line than a tubercle, and the elevated lines of the elytra are scarcely visible.

3. L. punctata, atra, griseo-pubescens, thorace apice vix angulato, marginibus subreflexis pallidis, punctatis, disco versus basin late foveato, cum margine basali vix emarginata nigro, utrinque ante basin macula rosea ornato, elytris grossius granulato-punctatis. Long. ·25.

Georgia, in Habersham county. The antennæ are as broad as in L. atra, and in the same manner are shorter in the female than in the male. The basal angles of the thorax are almost always dark colored; the discoidal spot is sometimes almost disconnected with the base.

ELLYCHNIA ‡Dej.

Antennæ compressæ, 11-articulatæ, palpi maxillares articulo ultimo triangulari, apice acuto; tarsi articulo 4to longe lobato, ungues simplices; abdomen articulis nullis phosphoreis, ultimo superiore apice truncato, non emarginato.

The first division of this genus approaches very closely in form to the last, and is distinguished only by the form of the last superior abdominal segment, and the absence of any light giving spot. The males are distinguished by the additional anal segment, which, with the preceding, is protected by the large superior segment.

* Corpus elongatum.

1. E. nigricans, fusco-nigra, thorace apice rotundato basi truncato, lateribus subito reflexis, apiceque punctatis, macula utrinque rosea ornato, disco ante basin angulatim impresso, elytris confertissime subtiliter granulatis. Long. ·2—·25.

Lampyris nigricans, Say. J. Ac. Nat. Sc. 3, 179.

? *Lampyris obscura* Fabr. Syst. El. 2, 100.

Abundant everywhere; the thoracic spot is sometimes obsolete. The granulation of the elytra is much finer than in the next species. The margin of the thorax is commonly fuscous but is sometimes pale.

2. E. decipiens, fusco-nigra, thorace apice rotundato, basi truncato, lateribus subsubito reflexis, roseo-testaceis, cum apice scabris, disco obsolete carinato, ante basin transversim impresso, elytris confertim minus subtiliter granulatis. Long. ·25.

Lampyris decipiens Harris. Trans. Hartford Nat. Hist. Soc. 74.

Northern and Southern States; the elytra have two slightly elevated lines. I have one specimen from Georgia in which there is a wide impression at the middle of the thorax and the carina is wanting, it may possibly be a distinct species, but in such an obscure family I am unwilling to separate it on a single specimen.

3. E. minuta, linearis, fusco-nigra, thorace apice rotundato, basi subemarginato, lateribus vix reflexis, roseo-testaceis, cum apice punctatis, disco subtiliter canaliculato, elytris minus subtiliter granulatis Long. ·17.

Georgia; rare. This small species is readily distinguished by its narro form; the disc of the thorax is much more even, than in the preceding spec

** Corpus ellipticum.

4. E. corrusca. *Lampyris corrusca* Linn. Syst. Nat.; Oliv. 28, 2, 14; Fabr. Syst. El. 2, 100. *Pyratomena fenestralis* Mels. Pr. Ac. Nat. 2, 304. Middle and Southern State

5. E. autumnalis Mels. Pr. Acad. Nat. Sc. 2, 303. Middle Sta

6. E. lacustris, elongato-elliptica, fusco-nigra, thorace semicircul disco convexo, lateribus parce punctatis, depressis, linea utrinque arcuata pal ornatis, elytris confertissime subtiliter granulatis linea elevata subobli notatis. Long. ·3.

Lake Superior; narrower than E. autumnalis, and with the sides of thorax less punctured. It is much smaller and a little narrower than E. rusca, and the pale arched spot of the thorax is much narrower.

PHOTINUS Lap. emend.

Antennæ compressæ, tenues, 11-articulatæ; palpi maxillares articulo ult triangulari, tarsi articulo 4to longe lobato, ungues simplices, abdomen artic tribus phosphoreis, ultimo superiore apice truncato, inferiore emarginato mentulo anali aucto.

The anal segment here exists in both sexes, but from the drying of the abdo the 7th segment is sometimes retracted. The males have the superior termi segment extending beyond the inferior segment, as in the other genera.

1. P. pyralis, piceo-vel nigro-fusca, thorace semicirculari, basi t cato, utrinque roseo-maculato, macula centrali nigra ornato, canalicul marginibus late punctatis, lateribus subito reflexis, elytris confertissime gra latis, margine, sutura scutelloque pallidis coxis femoribusque flavis. Lo ·38—·60.

Lap. An. Ent. Pr. 2, 141.

Lampyris pyralis Lin. Syst. Nat: De Geer 4, 52: tab. 17, 7; Fabr. S Ent. 2, 99; Syst. El. 2, 101. Oliv. 28, 2, 11.

Lampyris centrata Say. J. Ac. Nat. Sc. 5, 162. *Lamp. rosata* Germ. Nov. 62.

Rare in the Middle States, but very common in the Southern States; thoracic spot is sometimes very small; the female only differs from the m by the abdomen.

2. P. ardens, fusca vel picea thorace semicirculari, basi trunca angulis posticis acutis, sub-productis, margine laterali apicalique pallic punctatis, lateribus subito reflexis, disco subtiliter canaliculato, ante basin impresso, elytris minus subtiliter granulatis, margine, suturaque pallidis. Lo ·3—·45.

Lake Superior; the feet are pale fuscous, with the base of the femora y low; the thorax is sometimes carinated at base; such a variety is the Pygolam tædifer of my Catalogue in Agassiz' Lake Superior.

3. P. casta, pallida, thorace semicirculari basi truncato, angulis posticis non productis, lateribus minus subito reflexis, cum apice late punctatis, disco lævi, roseo, ante basin vix foveato, elytris subtiliter granulatis; antennis capite postpectoreque fuscis. Long. ·3.

Habersham Co., Georgia, May. A very pretty little species; the female is similar to the male.

4. P. scintillans, fusca, thorace pallido semicirculari, basi truncato, angulis posticis non productis, lateribus subsubito reflexis cum apice punctatis, disco obsolete biimpresso, roseo, medio infuscato, elytris subtilissime granulatis, margine, sutura, scutelloque pallidis, pedibus testaceis. Long. ·32.

Lampyris scintillans Say. J. Ac. Nat. Sc. 5, 163.

Middle States. This species is only distinguished from the next by the elytra being more finely and almost indistinctly granulate; the female has short elytra, and the antennæ but little longer than the thorax.

5. P. marginella, fusca, thorace pallido, semicirculari, basi truncato, angulis posticis non productis, marginibus subito reflexis, apiceque late punctatis, disco vix canaliculato, roseo, macula centrali fusca, elytris subtiliter granulatis, margine sutura scutelloque pallidis, pedibus testaceis. Long. ·32.

This is the common northern species, and is also found in Missouri. The female only differs from the male by the last abdominal segment. Were it not for the difference in sexual characters, I should not have separated this from the last species, from which it can hardly be distinguished; the fuscous spot of the thorax is sometimes wanting.

6. P. punctulata, fusco-picea, thorace pallido, semicirculari, basi truncato, angulis posticis non productis, marginibus minus subito reflexis apiceque punctatis, disco roseo, canaliculato, subtiliter punctato, macula centrali apiceque infuscatis, elytris confertim granulatis, margine sutura, scutelloque pallidis, femoribus coxisque testaceis. Long. ·37.

Missouri Territory; the female has short elytra; the antennæ are nearly as long as in the male.

7. P. consanguinea, fusco-picea, thorace semicirculari, pallido, basi late emarginato, angulis posticis productis, disco roseo, medio nigro-vittato, vix canaliculato, marginibus subito reflexis, apiceque punctatis, elytris confertim granulatis, margine suturaque pallidis, femoribus testaceis. Long. ·32—·42.

Southern States, abundant; the female is similar to the male, but has only the antepenultimate segment of the abdomen luminous.

8. P. obscurella, fusco-picea, thorace semicirculari, basi late emarginato, angulis posticis vix productis lateribus testaceis subito reflexis, apiceque punctatis, disco vix impresso, toto fusco, elytris confertim granulatis, margine suturaque anguste pallidis. Long. ·43.

One specimen; Missouri Territory. Very much resembles P. ardens, but differs essentially in having the base of the thorax emarginate.

9. P. lineella, linearis, fusco-picea, thorace pallido semiovali, basi truncato, angulis posticis subproductis, marginibus subito reflexis, apiceque anguste punctatis, disco vix impresso roseo, medio nigro-vittato, elytris confertim granulatis, margine suturaque anguste pallidis. Long. ·27.

Georgia, rare; this species is much narrower than any of the preceding, a the sides of the thorax are subparallel towards the base. Female unknown.

10. P. vittigera, fusco-picea, thorace breviore, semicirculari palli basi subemarginato, angulis posticis leviter productis marginibus late mir subito reflexis, apiceque punctatis, disco roseo, subcanaliculato, vitta lata ni ornato, elytris subtiliter granulatis, margine suturaque pallidis. Long. ·48.

Georgia, rare. Resembles P. consanguinea, but the thorax is shorter and elytra less distinctly granulated.

PYRACTOMENA Dej.

Antennæ 11-articulatæ, tenues, subcompressæ, articulo ultimo versus apic sinuato; palpi maxillares articulo ultimo triangulari apice acuto, tarsi artic 4to longe lobato, ungues simplices; abdomen articulis tribus subtus phosphore ultimo superiore apice emarginato.

The males are distinguished by the last superior abdominal segment be produced beyond the inferior segment, as in the other genera; the anal segm is visible only in the male, and is emarginate.

* Elytra late marginata.

1. P. flavocincta, fusco-picea thorace pallido antice subangula basi late emarginato, angulis posticis extrorsum productis, lateribus subito l reflexis, margine fusco, disco subcarinato, medio late infuscato, elytris alutac costulatis, margine late depresso, suturaque angusta pallidis. Long. ·45.

Georgia. The angles of the thorax being produced obliquely outwards, c tinguish this species from the next.

2. P. angulata. *Lampyris angulata* Say. J. Ac. Nat. Sc. 5, 16 *Lampyris lucifera* Mels. Pr. Ac. Nat. Sc. 2, 304. Middle and West States.

** Elytra minus late marginata.

3. P. angustata, fusco-picea, thorace apice angulato, pallido, b vix emarginato, angulis posticis non productis, lateribus late subito reflex disco subtiliter carinato, utrinque roseo, medio longitudinaliter infuscato, elyt subtiliter granulatis, costulatis, margine angusto reflexo, suturaque tenui pallid Long. ·42—·55.

Southern States. The thorax is usually longer than wide; in one specim (probably distorted) the reverse is the case.

4. P. linearis, elongata, fusca, thorace pallido apice vix angula basi truncato, angulis posticis vix productis, lateribus subito reflexis levi infuscatis, disco carinato pone apicem late infuscato, elytris distinctius granula costulatis, margine angusto pallidiore. Long. ·37.

Georgia; two specimens.

5. P. borealis, fusca, thorace pallido, apice angulato, basi l emarginato, angulis posticis leviter productis, lateribus late reflexis, infusca disco subcarinato, utrinque roseo, medio longitudinaliter infuscato, elyt

alutaceis, costulatis, anguste marginatis, margine suturaque tenuissime pallidis. Long. ·4—·58.

Lampyris borealis Randall. Bost. Journ. Nat. Hist. 2, 16.

Lake Superior, Cleveland and Maine. The female is luminous only at the sides of the segments. The margin of the elytra of the male is much narrower, and the sides are less suddenly deflexed; the male is P. falsa of my catalogue in Agassiz' Lake Superior.

PHAUSIS.

Antennæ 12-articulatæ breves, serratæ, compressæ; articulis 1 et 2 parvis, ultimo subulato minutissimo, vix conspicuo; palpi minuti; tarsi articulo 4^to^ brevi bilobato, unguiculari longo, ungues simplices; abdomen articulis tribus phosphoreis, segmento ultimo superiore emarginato.

1. P. reticulata. *Lampyris reticulata* Say. J. Ac. Nat. Sc. 5, 163. *L. brevicornis* ┼Dej. Cat. Georgia, rare.

PHOTURIS ┼Dej.

Antennæ 11-articulatæ, tenues, elongatæ, articulis 2 et 3 brevioribus; palpi maxillares articulo ultimo triangulari acuto, labiales articulo ultimo transverso lunato: tarsi articulo 4^to^ longe lobato, ungues externi fissi, interni simplices; abdomen articulis 3 ultimis phosphoreis, segmento superiore ultimo apice rotundatis.

This very distinct genus forms the 3d division of Laporte's genus Photinus, (An. Ent. Fr. 2, 144,) and to it he has given the uncouth name of *Telephoroides;* fortunately his Gallic patriotism has led him to print this as a French word, so that we are enabled to replace it by the hitherto unpublished name of Dejean. While on this subject I may add, that Laporte in this, as in almost every other instance, has completely overlooked the real distinguishing characters of the genus.

1. P. pensylvanica. *Lampyris pensylvanica* De Geer 4, 53, tab. 17, 8, Oliv. 25, 1, 8. Enc. Meth. 7, 455; *Lamp. versicolor* Fabr. Syst. El. 2, 105; *Photinus pensylvanicus* Laporte. An. Ent. Soc. Fr. 2, 144.

Abundant in every part of the United States; usually the elytra are marked with a discoidal pale vitta extending beyond the middle. In Southern specimens this vitta is occasionally wanting; these are *Photuris lineaticollis* of Dejean's Catalogue.

2. P. frontalis, picea, fronte valde concava, thorace pallido sat dense punctato marginibus late reflexis, vitta media fusca apicem non attingente notato, elytris confertim minus subtiliter punctatis, margine, sutura scutelloque pallidis, femoribus basi pallidis. Long. ·4.

One specimen; Georgia. The punctuation is coarser and less dense than in P. pensylvanica.

3. P. divisa, picea, fronte leviter concava, thorace pallido, sat dense punctato, marginibus late subito reflexis, disco utrinque macula magna fusca

notata, elytris confertim punctatis, margine sutura, scutelloque pallidis, fem bus testaceis. Long. ·42.

Missouri Territory. The third joint of the antennæ is longer than the 2

4. P. congener, picea, capite testaceo, valde concavo, thorace pall confertissime punctato, marginibus late subito reflexis, disco rufo utrin infuscato, elytris confertissime punctatis, margine sutura, scutelloque pall femoribus pallidis. apice fuscis. Long. ·43.

One specimen; Georgia; antennæ with the third joint a little longer t the second.

Div. 2nda *Telephori.*

Abdomen sæpius 6-articulatum,* segmentis nullis phosphoreis; antennæ tantes; tarsi articulo 4to usque ad basin fisso.

* Antennæ articulo 2ndo minuto.

CHAULIOGNATHUS Htz.

Palpi articulo ultimo paulo dilatato; antennæ articulo 2ndo minuto, 3tio seq tibus breviore; thorax margine integro; ungues simplices.

For the curious structure of the maxilla of this genus see Hentz in Tr Amer. Phil. Soc. 3, 460.

1. C. pensylvanicus. *Telephorus pensylvanicus* De Geer. 4, 17, 15; *Cantharis americana* Forster. Cent. Ins. 50; *Canth. bimaculata* F Ent. Syst. 1, 216; Syst. El. 1, 298; *Tel. bimaculatus* Ol. 26, 2, 11; *Chaul nathus bimaculatus* Hentz. Trans. Am. Phil. Soc. 3, 461. Abundant ev where.

2. C. Hentzii, luteus, thorace quadrato, subtransverso, lateri anguste marginatis, medio nigro-vittato, subcanaliculato, elytris macula utrin postica, sæpe ad basin extensa scutelloque nigris, subtus piceus, femor posticorum basi abdomineque testaceis. Long. ·4.

Very similar to the preceding, but the thorax is not margined in front, the black spot extends to the apex, the head and antennæ are black. North and Southern States; rare.

3. C. marginatus Hentz. l. l. 3, 460; *Cantharis marginata* F Ent. Syst. 1, 216; Syst. El. 1, 298.

Abundant, especially in the Southern States; a variety in which the bl occupies the whole of the elytra, leaving only a narrow marginal and sutu line yellow, is the *Callianthia philadelphica* Dej. Cat.

POLEMIUS.

Palpi articulo ultimo triangulari; antennæ compressæ, serratæ, articulo 2 minuto, 3io sequentibus non minore: thorax margine laterali ad medi interrupto: ungues simplices, externo postico ad basin dilatato.

* When it has seven articulations, the last is small and presents the appearan of an anal joint.

be made use of in dividing the genus. Those, however, which have only exterior ungues of the two posterior pairs toothed may form a separate sec

a. Ungues posteriores externi dente basali armati.

1. T. rotundicollis. *Cantharis rotundicollis* Say. J. Ac. Nat. 5, 165. Rare throughout the Atlantic slope of the United States.

2. T. Curtisii Kirby. F. Bor. Am. 4, 246. Lake Superior.

3. T. tibialis, rufo testaceus, cinereo-pubescens, thorace transv marginato, subcanaliculato versus basin subangustato, elytris fuscis, subtilis scabris, tibiis tarsisque obscuris, antennis fuscis basi rufis. Long. ·75.

California, San Diego. This fine species differs from the preceding b broader thorax; the head is immaculate; the abdomen is a little darker the pectus.

4. T. consors, rufo-testaceus, cinereo-pubescens, thorace longius marginato, subcanaliculato, versus basin subangustato, elytris fuscis subtilis scabris, tibiis tarsisque obscuris, antennis fuscis basi rufis. Long. ·57.

California, San Diego; only differs from the last by its long thorax; margin in front is broad, and the apex rounded.

5. T. lautus, niger, cinereo-pubescens, ore pedibus thoraceque flavis, hoc quadrato, antrorsum subangustato, undique anguste marginato, el scabris, subtriatis. Long. ·3.

San Francisco, California; one specimen.

6. T. grandicollis, niger, cinereo-pubescens, ore, thoraceque rufis, hoc elytris non angustiore transverso, canaliculato, marginato, later valde rotundatis, elytris subtiliter scabris, abdomine obscure testaceo. Long.

San Francisco; one specimen.

7. T. fidelis, niger, subtiliter pubescens, mandibulis, thoraceque r flavis, hoc transverso, marginato, vix canaliculato, lateribus panlo rotundatis apicem nigro, elytris scabriusculis, abdomine flavo. Long. ·33.

Santa Fe; Fendler. This species differs from all the preceding specie having the internal claw of the posterior tarsi somewhat dilated at base; i similar in form to the next species, but the second joint of the antennæ is portionally much shorter.

8. T. collaris, niger, tenniter pubescens, ore thoraceque flavis, transverso, minus late marginato lateribus subrotundatis, elytris scabris, an narum basi testaceo. Long. ·25.

Missouri Territory and Illinois; the basal joints of the antennæ are so times very dark; the abdomen is entirely black.

9. T. bilineatus Lec. Agassiz Lake Superior, 229. *Cantharis neatus* Say. J. Ac. Nat. Sc. 2, 182.

Middle States and Lake Superior. The postpectus is usually fuscous, bu variety from the Southern States has that part as light colored as the abdome

10. T. divisus, niger, griseo-pubescens, ore thoraceque flavis, hoc q rato, lateribus rectis angulis anticis rotundatis posticis rectis, margine ang reflexo, disco subcanaliculato, maculis duabus magnis fere confluentibus nbt utrinque versus angulos anticos subexcavato, elytris substriatim scabris. Long.

California, San Francisco.

11. T. impressus, niger, thorace transverso, latius marginato, di subcanaliculato ante basin late impresso, disco antice profunde transver impresso, lateribus flavis, elytris valde punctato-scabris. Long. ·24.

New York; Mr. Guex. One specimen; resembles in appearance T. rectus, lineola and several others of the third division.

12. T. tuberculatus, niger, thorace transverso, valde marginato, subcanaliculato, lateribus flavo-rufis subrotundatis, antice transversim impressis, tuberculo parvo versus angulos anticos notatis, elytris valde punctato-scabris. Long. ·23.

Georgia; one specimen. Very similar to the last; the sides of the thorax are more rounded; the little tubercle is rather on the disc than the marginal part of the thorax.

b. Ungues omnes simplices.

13. T. brevicollis, niger, mandibulis, thoracisque lateribus flavis; thorace valde transverso, marginato, antice vix impresso, lateribus subrotundatis, elytris minus subtiliter punctato-scabris. Long. ·22.

One specimen; Georgia.

14. T. undulatus, niger, thorace roseo-pallido, valde transverso, late marginato, antice subangustato, lateribus repandis, canaliculato, medio nigro, elytris valde scabris, margine, sutura, humeris abdominisque margine testaceo. Long. ·3.

Georgia; M. Guex. The thorax is as wide as the elytra; the disc has a short transverse impression on each side of the middle. This may possibly be Cantharis invalida Say. Bost. Journ. Nat. Hist. 1, 159, but the form of the thorax is not mentioned, and Say's insect appears to have been much smaller.

c. Ungues omnes dentati, sæpius fere fissi.—*Rhagonycha* Esch.

15. T. dentiger, niger, mandibulis thoraceque testaceis, hoc transverso late marginato, punctato, canaliculato, lateribus rotundatis, disco utrinque pone medium late infuscato, elytris scabris, epipleuris abdominisque margine testaceis. Long. ·35.

One specimen; Maryland. Same size and form as the following, but at once distinguished by its punctured thorax and the shortness of the ungual tooth.

16. T. carolinus. *Cantharis carolina* Fabr. Syst. El. 1, 296. Middle and Southern States.

17. T. curtus. *Podabrus curtus* Lec. Agassiz Lake Superior, 229. *?Cantharis percomis* Say. Bost. Journ. Nat. Hist. 1, 159.

18. T. cinctellus, subtus testaceus, capite postice nigro, thorace flavo, transverso, anguste marginato, lateribus rectis, elytris confertim scabro-punctatis piceis, sutura margine scutelloque pallidis, antennis obscuris basi pedibusque flavis. Long. ·2.

Georgia and Missouri Territory. This and all the following species have the tooth of the claw almost equal to the claw itself.

19. T. dichrous, niger, fronte thoraceque flavis hoc latitudine vix breviore, lateribus vix rotundatis, margine reflexo ad medium angustiore, disco ad latera antice paulo excavato, versus basin in medio paulo deplanato, elytris scabro-punctatis, pedibus antennarumque basi rufis. Long. ·2. Missouri Territory.

20. T. flavipes, niger, fronte thoraceque flavis, hoc quadrato, lateribus rectis margine reflexo ad medium angustissimo, disco nigro-vittato, postice obsolete canaliculato ad latera antice vix excavato, elytris subtilius scabro punctatis, antennarum basi pedibusque rufis. Long· ·22.

Missouri Territory. The thorax exactly resembles that of T. lineola, the color of the mouth and feet at once distinguishes this species; the elytr less coarsely scabrous than in T. lineola.

21. T. lineola. *Cantharis lineola* Fabr. Syst. El. 1, 301; *Cant parallela* Say. J. Ac. Nat. Sc. 5, 168. Common in the Northern and Sout States.

22. T. rectus Mels. Pr. Ac. Nat. Sc. 2, 305.

Middle and Southern States. Varies, with the suture and tibia at base taceous; also with the femora fuscous, tibiæ and tarsi pale. I suspect Cantharis rufipes Say. J. Ac. Nat. Sc. 3, 182, is this variety, but his des tion is excessively bad.

23. T. Sayi, niger, thorace subtransverso, antrorsum subangustato, gulis omnibus rotundatis, lateribus tenuiter marginatis, disco æqualiter conv nigro-vittato, elytris scabro-punctatis. Long. ·27.

One specimen, New York. Differs from T. lineola by the much narr reflexed thoracic margin, which is almost obsolete at the middle. The species has a thorax not at all transverse, the black part is much broader, reflexed margin less narrow, and the disc is laterally excavated before middle.

24. T. angulatus. *Cantharis angulatus* (!) Say. J. Ac. Nat. Sc. 3, Pennsylvania, Bristol.

25. T. cruralis, niger, ore thoraceque flavis, thorace transverso ant sum subangustato, angulis omnibus subrotundatis, lateribus rectis tenuiter ginatis, disco æqualiter convexo, nigro-lineato, elytris subtilius scabris, testa marginatis pedibus flavis tibiis tarsisque fuscis. Long. ·26.

One specimen, Georgia. Very much resembles in form and size T. lin &c., but very distinct; the lateral margin of the thorax becomes more indist towards the anterior angle.

26. T. marginellus, niger ore thoracisque margine flavis, thorace transverso, antrorsum subangustato, angulis omnibus subrotundatis, later leviter rotundatis marginatis, disco æqualiter convexo nigricante, elytris sca sutura margineque tenuiter pallidis, antennarum basi genubusque testa Long. ·23.

Georgia, one specimen. The margin of the thorax is more distinct and equ reflexed anteriorly; most nearly resembles T. rectus (Mels.,) but the side the thorax are not straight, the sides of the disc are not excavated anterio and the margin is wider.

27. T. excavatus, niger, thorace flavo quadrato, antrorsum angust lateribus rectis tenuiter valde marginatis, angulis vix rotundatis, disco late c liculato, nigro-vittato, antice versus latera valde excavato, ad apicem subtiliss punctulato, elytris valde scabris, pedibus fuscis, tibiis tarsis mandibulisque lidis. Long. ·26.

A very common species, which nearly resembles T. rectus, but the thora more distinctly margined, the disc much more excavated, and the black par much narrower. The elytra are sometimes black, sometimes margined with taceous. This, too, may be Canth. rufipes Say.

28. T. imbecillis, piceus, ore thoraceque flavis, hoc vix transve antrorsum subangustato, angulis posticis non rotundatis, margine anguste refl

disco nigro lineato, utrinque antice late excavato, elytris scabris, sutura margineque testaceis, pedibus pallidis, genubus infuscatis. Long. ·26.

A common species, which resembles very much T. rectus, but the elytra are more scabrous.

29. T. scitulus Lec. Agass. Lake Sup. 229. *Canth. scitula* Say. J. Ac. Nat. Sc. 5, 168; *T. nigriceps* Lec. l. c. 230.

Middle and Northern States. My Teleph. nigriceps is only a distorted specimen of this species, which is much paler than usual.

30. T. longulus, pallidus thorace latitudine longiore, tenuiter marginato, angulis posticis non rotundatis, disco late canaliculato, antice ad latera excavato, elytris subtriatim scabris, antennis fuscis, basi pallidis. Long. ·28.

One specimen, Niagara.

31. T. pusillus, niger, mandibulis pedibusque flavis, thorace vix transverso, marginato, lateribus rectis, flavis, disco subtiliter canaliculato, nigro, elytris scabris, epipleuris pallidis. Long. ·15.

One specimen, New York. The thoracic margin is not broader in front than behind. Resembles much T. rectus, but is much smaller; only the first joint of the antennæ is pale.

32. T. vilis, niger, thorace subtransverso, marginato, lateribus flavis, disco nigro, antice ad latera late excavato, postice ad angulos posticos rectos foveato, elytris valde scabro-punctatis. Long. ·15.

New York and Upper Mississippi. The margin of the thorax is broader towards the anterior angles.

33. T. fraxini. *Cantharis fraxini* Say. J. Ac. Nat. Sc. 3, 181: *Telephorus nigrita* Lec. Agass. Lake Sup. 229: *Malthacus mandibularis* Kirby. F. Bor Am. 248. Abundant at Lake Superior and Mackinaw; found also in Pennsylvania: some of the specimens have the maxillary palpi much less dilated than is usual in this genus; they are probably females.

Podabrus ¦Fischer.

Palpi articulo ultimo dilatato, securiformi, vel triangulari, antennæ articulo 2^do^ tertio vix breviore, caput pone oculos valde angustatum, thorax margine integerrimo ad apicem truncatus vel emarginatus.

I can find no description of this genus except in the synopsis at the end of Westwood's introduction to the modern Classification of Insects, p. 27. If this be the earliest publication of the characters of the genus, the name of Westwood must of course be substituted in the place of Fischer, who in his Ent. Russ. only mentions the genus by name, without giving any description. The species of the first division all have a deep transverse impression before the middle of the thorax. The second division is equivalent to Kirby's genus *Malthacus*.

a. Thorax latius marginato; ungues fere fissi: palpi art. ult. securiformi:

1. P. tricostatus. *Cantharis tricostata* Say. Bost. Journ. Nat. Hist. 1, 158: *Telephorus Bennetii* Kirby F. Bor. Am. 249. Vermont, Prof. Adams; Pennsylvania, Dr. Melsheimer.

2. P. basilaris. *Cantharis basilaris* Say. J. Ac. Nat. Sc. 3, 181. Middle States, rare.

3. P. flavicollis, niger, fascia frontali thoraceque flavo-pallidis, hoc transverso, subcanaliculato, parcius punctato, lateribus latius marginatis, subro-

tundatis, elytris confertissime scabro-punctatis, scutello, sutura, margine, femorumque basi pallidis. Long. ·47.

Middle and Southern States; rare. The antennæ are black, with the surface of the two basal joints pale: the head is very densely punctured.

4. P. discoideus, niger, thorace pallido transverso, late margi lateribus leviter rotundatis, minus parce punctato, subcanaliculato, medio maculato, elytris confertissime scabris sutura margineque tenuibus pal antennarum basi femoribusque pallidis, his apice piceis. Long. ·47.

New York: one specimen, Mr. Guex. The head is thickly punctured spot on the thorax does not extend farther than the transverse impression to the apex.

5. P. modestus Lec. Agass. Lake Sup. 228; *Cantharis modestus* J. Ac. Nat. Sc. 3, 179. New York and Lake Superior; the fuscous spot o thorax sometimes occupies nearly the whole surface; the feet and antennæ from rufous to dark fuscous.

6. P. diadema Dej. Cat. 118: Cantharis diadema Fabr. Syst. E 298. Lake Superior, Middle and Southern States. What I consider as species is distinguished from all the preceding by the head being much densely punctured, the thorax is subtransverse and smooth, and the elytra out pale margin; the feet are always black. Length ·46.

7. P. pruinosus, niger cinereo-pubescens, capite thoraceque rufis dense punctato, hoc subtransverso, late marginato, lateribus leviter rotun canaliculato, ante medium subtiliter punctato, elytris subtiliter rugose sca abdominis apice lateribus pedibusque rufis. Long. ·52.

Oregon; Mr. Wilcox. This species bears the same name in the B Museum, to which it was also sent by Mr. Wilcox.

8. P. comes, niger cinereo-pubescens, capite thoraceque rufis, illo punctato, hoc subtransverso, late marginato, lateribus rotundatis, canalicu ante medium subtiliter punctato, elytris minus subtiliter rugose scabris, vix testaceis. Long. ·4.

California, San Francisco. Very similar to the last, but in addition to characters of the diagnosis, the sides of the thorax are more rounded, and posterior angles are small and prominent.

9. P. tomentosus. *Cantharis tomentosa* Say, J. Ac. Nat. Sc. 5, *Podabrus rufiolus* Mels. Pr. Ac. Nat. Sc. 2, 304. Pennsylvania, Dr. Melshei My specimen has the abdomen rufous, with a small fuscous spot at base.

10. P. rugosulus Lec. Agass. Lake Superior, 229. Very commo every part of the United States, and is usually mistaken for P. diadema, wit description of which it does not at all agree. The thorax is narrowed in f and the whole surface is strongly punctured.

11. P. frater, niger capite confertim punctato, mandibulis, fasciaque oculari testaceis, thorace subtransverso, antrorsum vix angustato, lateribus marginatis subrotundatis rufis, disco canaliculato, ante medium subtilius punc elytris valde rugose scabris. Long. ·4.

One specimen; Georgia. Larger than the last, which it very closely res bles; the thorax, however, is not narrowed in front, and the convex part of disc is smooth; as in the preceding, the elytra are very rough, with two in tinct lines; the head is thickly punctured.

b. Caput pone oculos modice angustatum; elytra confuse puncta

3. M. n i g e r, niger vix subtiliter pubescens, thorace valde transverso, ribus rectis, angulis rotundatis, elytris subtilius scabro-punctatis, antennis dominis apice, pedibusque piceo-testaceis. Long. ·15.

Lake Superior; one male. The last superior joint of the abdomen is el ate, concave beneath, and has a short terminal appendage; the penis is exse and terminates in two large acute hooked lobes.

4. M. t r a n s v e r s u s, fuscus pubescens, thorace quadrato, an prominulis, lateribus rectis, obsolete punctulato, ad medium transversim presso, elytris subtilissime punctulatis, antennarum basi testacea. Long. Niagara.

5. M. c o n c a v u s, fuscus pubescens, thorace rufescente quadrato, an prominulis, lateribus rectis, obsolete punctulato, subcanaliculato, ad an anticos excavato, elytris subtilissime punctulatis, antennarum basi test Long. ·13. New York.

6. M. e x i l i s Mels. Pr. Ac. Nat. Sc. 2, 305. Pennsylvania and Geo

7. M. f r a g i l i s, fuscus vix pubescens, thorace transverso, tenuiter ginato, lateribus rotundatis, disco ad medium transversim impresso, el vix subtiliter punctulatis, antennarum basi pedibusque pallidis. Long. ·1.

8. Carolina and Lake Superior; differs from the preceding by the fus thorax, which is more rounded on the sides.

8. M. f u s c u l u s, fuscus vix pubescens, thorace transverso, tenuiter ginato, angulis vix rotundatis, lateribus rectis late impressis, elytris sub sime scabris. Long. ·12.

One specimen, San Francisco. The antennæ and feet are entirely fusco

8. M. p a r v u l u s, fusco-pallidus, parce pubescens, capite nigro, tho transverso lateribus rotundatis, non impresso, elytris vix punctulatis. Long.

New York and Lake Superior. In addition to the characters above, species has much shorter antennæ than the others, and the terminal artic tions are more rounded.

TRYPHERUS.

Antennæ tenues, articulo 2ndo vix breviore; palpi maxillares articulo 2ndo longiore, ultimo subtriangulari longiore; tarsi postici articulis gradatim br oribus, articulo 4to valde bilobato; ungues simplices, paranychio lato rotund intermedio muniti; elytra abdomine multo breviora; caput pone oculos angustatum.

The form of the palpi sufficiently distingnishes this genus from the preced it approaches much closer to Telephorus. The male has a small additi anal segment; the female has the penultimate joint of the abdomen de emarginate. In both sexes the superior segment is dilated, thickened at edges and emarginate at apex, so that it projects on each side of the lo segment like a lateral appendage.

Another genus with short elytra, from Panama, approaches very closely this, but the second and third joints of the antennæ together are not longer t the fourth; the palpi are strongly securiform, and the last joint of the tarsi no appendage between the claws.

1. T. l a t i p e n n i s. *Malthinus latipennis* Germ. Ins. Nov. 72; *Mo*

chus marginalis Say. Long Exped. to St. Peter's River 2, 192; *Malthinus marginalis* Say. Bost. Journ. Nat. Hist. 1, 160.

Common everywhere. Germar's description precedes Say's by several months. Say in the Bost. Journal misquotes himself, as there is no description of this species to be found in the Journal of the Academy of Natural Sciences.

TYTTHONYX.

Antennæ elongatæ, compressæ, valde serratæ, articulo 2^ndo^ sesqui minore; palpi articulo ultimo vix longiore, ovali acuto; tarsi postici articulo 1^mo^ elongato, 2—4 brevibus, omnes crassiusculi, articulo ultimo brevi, ungues parvi integri; caput pone oculos non angustatum.

1. T. erythrocephalus. *Lampyris erythrocephala* Fabr. Syst. El. 2, 105; *Malthinus serraticornis* Mels. Pr. Ac. Nat. Sc. 2, 305. Middle and Southern States.

Species unknown to me.

Lampyris ruficollis Say. J. Ac. Nat. Sc. 5, 161.
Luciola maculicollis Laporte. Ann. Soc. Ent. Fr. 2, 148.
Cantharis vittata Fabr. Ent. Syst. 1, 219.
Cantharis ligata Say. J. Ac. Nat. Sc. 5, 166.
Cantharis jactata Say. Ibid 5, 167.
Cantharis invalida Say. Bost. Journ. Nat. Hist. 1, 158.
Telephorus Westwoodii Kirby. Fauna Bor. Am. 4, 246.
Telephorus Samouelli Kirby. Ibid 246.
Telephorus fulvicollis Germ. Ins. Nov. 70.
Telephorus notatus Man. Bull. Mosc. 1843. California.
Rhagonycha piniphila Esch. Man. Bull. Mosc. 1843.
Rhagonycha sericata Man. Bull. Mosc. 1846, p. 511. These and the next are from Sitkha.
Rhagonycha binodula Man. Bull. Mosc. 1846, p. 512; an Podabrus lævicollis Lec.?

Malthinus abdominalis Dej. Cat. My specimen of this species is too imperfect for a satisfactory reference to any of the genera described above. From the form of the thorax and elytra, I think that it belongs to the genus alluded to as found at Panama. The following diagnosis will enable the species to be recognised: Rufus, capite pone oculos nigro, thorace quadrato, lateribus rectis, basi rotundato, ad medium late transversim concavo, elytris fuscis, subtilissime scabris, pedibus fuscis. Long. .26. Georgia; rare.

The Committee on Mr. Cassin's description of new species of Birds, reported in favor of publication.

Descriptions of birds of the genera Laniarius, Dicrurus, Graucalus, Manacus and Picus, specimens of which are in the collection of the Academy of Natural Sciences of Philadelphia.

BY JOHN CASSIN.

1. *Laniarius carbonarius*, nobis.

Form. Strong and rather heavy, wings short with the fourth, fifth, sixth and seventh quills longest and nearly equal, tail rather short, somewhat rounded and

with all the feathers having a crimped appearance throughout their le
Plumage of the rump long and silky. About the size of *Dryoscopus rufive*
(Swainson.)

Dimensions. Total length of skin from tip of bill to end of tail about 8¼ in
wing 3¼, tail 3¼ inches.

Colors. Entire plumage above and below brownish black, palest on the q
feathers of the rump paler at their basis, bill black.

Hab. Western Africa, discovered by Robert MacDowell, M. D., late of S
Leone.

Obs. This species resembles no other with which I am acquainted. Its r
short wings and tail give it more the general appearance of a *Thamnophilus*
I have noticed in any other African species. It is peculiar, so far as I knov
the uniform color of its plumage, which is (rump included) black.

2. *Dicrurus aculeatus*, nobis.

Form. Small, but rather larger than *D. Ludwigii*, A. Smith. Bill r
long, curved at the tip, toothed and sharply pointed; wings with the fourth
slightly longest, but the third, fourth and fifth nearly equal; tail distinctly th
not deeply forked.

Dimensions. Total length of skin from tip of bill to end of tail about 7¼ in
wing 4¼, tail 3¼ inches.

Colors. Entire plumage black with a greenish lustre, inner webs and u
surface of quills pale brownish, bill and feet black.

Hab. Fazoglo, Eastern Africa.

Obs. Resembles *D. musicus*, Vieill., but is smaller and has the bill longe
much stronger, comparatively; it is smaller also than *D. canipennis*, Swai
which it somewhat resembles in having the light colored webs of the quills
can easily be distinguished by its shorter wings and tail and stronger bill.
larger than *D. Ludwigii*, A. Smith, and differs from all the species here r
tioned in the relative lengths of the quills. Bonaparte is mistaken in ma
D. emarginatus (Licht.) a distinct species,—it is described by Lichtenste
Verzeichniss, p. 52, and there expressly stated to be the bird figured by Le
lant, p. 167, (which is *D. musicus*, Vieill.)

3. *Graucalus azureus*, nobis.

Form. Small, about the size of G. hypoleucus, Gould. Specimen now a
to be described not in good plumage, ends of quills and tail feathers worn, w
rather long.

Dimensions. Total length of skin from tip of bill to end of tail about 7¼ inc
wing 4¼, tail about 4 inches.

Colors. Front, extending to each eye, quills and tail black, entire plumag
other parts light blue, tertiaries tipped with irregular lines of white and blac

Hab. Western Africa, discovered by Robert MacDowell, M. D., late of Si
Leone.

Obs. This species which is remarkable for its color, appears to resemble
bird figured in Voyage au Pole Sud (Astrolabe & Zelèe) Ois. pl. 9, fig. 3, wl
is named in Bonaparte's Consp. Av. "*Graucalus Boyeri.*" It is however, m
smaller. I have seen only the specimen now described.

4. *Manacus flaveolus*, nobis.

Form. Very similar to those of *M. gutturosus*, (Desm.) and *M. Candei*, (Parz.)

Dimensions. Total length of skin from tip of bill to end of tail about 3¼ inches, wing 2, tail about 1¼ inches.

Colors. Very similar to those of *M. gutturosus*, but with the parts which are white in that species, pale yellow in this. Top of the head, back, wings and tail, black; throat, breast, shoulders and broad collar around the back of the neck, pale yellow, running into cinereous on the abdomen.

Hab. Bogota, New Grenada.

Obs. Two specimens of this little bird are in the collection, labelled as coming from Bogota, and both presenting the singular variation in color, from the common *M. gutturosus*, on the strength of which I have considered it specifically distinct. In point of color it may be stated as intermediate between *M. gutturosus* and *Candei*. It is smaller than the latter.

5. *Picus thyroideus*, nobis.

Form. Similar to that of *P. varius*, Linn., but rather larger and stouter, wings with the third quill longest, legs and toes rather slender, tail rather broad.

Dimensions. Total length of skin from tip of bill to end of tail about 9¼ inches, wing 5¼, tail 3¼ inches.

Colors.— ♀ Breast with a large transverse patch or belt of black; middle of the abdomen pale yellow. Head and throat brownish buff, with obscure longitudinal stripes of black, back, wing coverts, sides of the body beneath and under tail coverts striped transversely with black and sordid yellowish white, rump and upper tail coverts white, the latter with black marks on their outer webs; quills, and tail black, more or less spotted with white.

Hab. California, discovered by Mr. John G. Bell, of New York.

Obs. Mr. Bell's two specimens are females, and are as yet unique. This species is a strict congener of *Picus varius*, Linn., but does not resemble it in colors, nor any other species which I have met with.

The Committee on Dr. Leidy's paper entitled, "Contributions to Helminthology," reported in favor of publication in the Proceedings.

Contributions to Helminthology.

By Joseph Leidy, M. D.

MICROSTOMUM? *Oersted.* (Eustomum.)

Body elongated, compressed cylindroid, vibrillated; increasing by transverse segmentation in pairs. Head continuous with the body, furnished upon each side with a respiratory fovea. Mouth antero-inferior; intestinal canal produced anterior to the mouth in the form of a coecum; œsophagus amphoraform, muscular, not protractile; anus at first (after segmentation) open, afterwards becoming closed. Ocelli none. *Minute rhabdocœla inhabiting fresh water.*

This genus is the Microstomum of Oersted, if what I have observed to be

lateral respiratory foveæ of the head are, according to him and other aut ocelli destitute of pigment.

In numerous individuals of what I have considered below to be of thre tinct species of the genus, they were always observed to be in a state of div by pairs, and the primary pair of segments about their middle had al developed respiratory foveæ, and were slightly indented preparatory to div before the first pair were separated.

1. MICROSTOMUM (*Eustomum*) PHILADELPHICUM, *Leidy*.

Body linear, slightly attenuated posteriorly; head conoidal, with the surmounted by a small oval papilla; tail obtusely rounded. Respiratory sub-hemispherical, placed at the base of the cone of the head. Mouth oval tractile; œsophagus keg-shaped, intestine narrowed, cylindroid, dilated a commencement. Colorless, translucent, vibrillated; increasing by trans segmentation, always observed in the process of forming two segments.

Length 2-5ths line, by 1-500th in. broad.

Habitation. Found in the water of marshes and ditches in the neighbo of Philadelphia.

2. MICROSTOMUM (*Eustomum*) VARIABILE, *Leidy*.

Body broad, linear; anteriorly and posteriorly obtusely rounded. Respir fovea, longitudinally oval, lateral. Intestine very broad. Colorless, incre by twos.

Length from 1-80th to 1-24th of an inch by 1-800th to 1-400t broad.

Habitation. With the preceding.

3. MICROSTOMUM (*Eustomum*) CAUDATUM, *Leidy*.

Body long, narrow, linear; anteriorly obtusely rounded, posteriorly e in a narrow, blunt, elevated tail 1-400th in. long from the position of the increasing by twos, the tail of the anterior segments projecting above a whole length posterior to the head of the succeeding segment.

Length 3-4ths to 1¼ lines; breadth 1-300th to the 1-250th in.

Habitation. With the preceding.

RHYNCHODEMUS SYLVATICUS, *Leidy*: Pr. A. N. S. v, 289. Error of refere Planaria sylvatica, *Leidy*: ib. 241.

STYLARIA FOSSULARIS *Leidy*: ib. 287. A number of individuals in a sta segmentation, from which the species was first described, preserved alone glass vessel with some confervæ, upon the occurrence of cold weather p into the perfect condition as follows:

Body long, cylindroid, hyaline, permitting the ash-colored or yellowish i tine to be seen through the integument, divided into from 50 to 65 annulat furnished with a distinct girdle posterior to the third annulus from the m which extends the breadth of three annuli. Podal hooks in fasciculi of 12. Setæ commencing after the girdle, usually one often two upon each of the annuli. Head obtusely rounded and prolonged into a cylindroid, moveable, digitiform, transversely wrinkled proboscis. Caudal annulus te nating in two short lobes

Length 3-4ths to 1 inch; breadth 1-5th to 1-4th of a line. Length of proboscis 1-20th inch.

Remarks upon the habits.—When at rest the worm lies with the anterior four-fifths of the body upon the surface of the mud at the bottom of the water, with the tail fifth buried. It is very active in its movements. It also constructs tubes of mud. It is hermaphrodite, and copulates in the same manner as the earth worms.

In a number of individuals I observed bunches of spermatozoa, and in several of the same from three to five nearly completely formed ova placed just posterior to the girdle.

The eggs when extruded were attached to the inside of the vessel in which the worms were kept. They consisted of an oblong quadrilateral translucent, whitish, papyraceous web, enclosing a light amber colored, bottle-like case, with an open neck, and the body containing an opaque white globular mass; the true egg.

The perfect worm after living about two months died. Some of the ova several weeks after their extrusion were observed to have the young almost perfected, and these a few days after their escape presented the following characters:

Body cylindroid, divided into 35 annulations, each with a pair of fasciculi of 4 or 5 hooks; posterior to the first three also provided on each side with one or two setæ. Tail bilobed. Head as in the parent. No girdle; no indication of division; and no apparent developing annuli at the tail end. Length 2 lines.

The Committee on Dr. Le Conte's paper, concluding his descriptions of the Longicorn Coleoptera of the United States, reported in favor of publication in the Journal.

The Committee, consisting of Dr. J. C. Fisher, Wm. S. Vaux and Dr. Bridges, appointed at a late meeting "to inquire into the expediency of enlarging the Hall of the Academy, so as to furnish greater accommodation for the Museum and Library, and to report a plan, with an estimate of the expense," offered a report, which was adopted, recommending the raising of the roof of the building sixteen feet higher, the division of the interior of the Hall into two compartments, by a floor thrown across from the second main gallery, and the opening of two windows into each hall on the north and south sides.

The entire expense of the improvement, as estimated by a contractor, was $6,500, to meet which the Committee proposed that subscriptions be solicited, both from members and from the citizens of Philadelphia.

Two resolutions appended to the report, one that it was expedient to enlarge the Hall according to the plan submitted, and to appoint a Committee for the purpose of obtaining subscriptions; and the second giving the form of the subscription, were also adopted. Action on a third resolution was postponed for the present.

The following reports were read and adopted:

LIBRARIAN'S REPORT

For 1851.

The rapid and steady progress which the Library has made during the few years, in the departments of Natural and Physical Science, and var kindred subjects, has continued during the present year—the number of addit amounting to 2,262.

The usual table, showing the increase under each head, is herewith submitt

Subject.	Volumes.	Periodicals and Serials.	Pamphlets.
General Natural History,	148	33	28
Mammalogy,	14		11
Ornithology,	31	16	18
Entomology and Crustacea,	24	30	7
Ichthyology and Herpetology,	43	6	16
Conchology and Helminthology,	39		139
Geology and Mineralogy,	97	21	90
Botany,	17	20	10
Anatomy and Physiology,	41	5	40
Physical Science, Chemistry, and Mathematics,	32		51
Medicine,	4		8
Transactions and Proceedings of Societies, Memoirs, Magazines, &c. &c.,	379	462	4
	869	593	422

Subject.	Volumes.	Periodicals and Serials.
Brought over,	869	593
Dictionaries of Arts and Sciences,	46	41
Voyages and Travels,	43	26
Agriculture and Useful Arts,	42	
Bibliography,	12	
Biography,	9	
Education,	3	
Geography,	18	
History,	6	
Languages,	14	
Miscellaneous,	13	
Maps and Charts,	7	
	1075	660

Of the whole number, 42 have been contributed by authors; 32 by edit 77 by Societies and Corporations; 927 by Dr. Wilson; 1,025 by Mr. Edw Wilson; 87 by other members and correspondents; 7 by Departments of United States; and 65 have been derived from miscellaneous sources total 2,262.

In addition to these, nearly 700 volumes, periodicals, &c., and pamphlets sented by Mr. Edward Wilson, are also in the Hall, but not yet recorded. entire number actually contributed this year, by this most zealous friend of Institution, will not fall far short of 1,700 of all descriptions.

Although far distant from us, Mr. Wilson has manifested the liveliest inte in the success and advancement of the Academy, and has exerted his indus and given his time and attention in searching out rare productions for its Libr to an extent which entitle him to our warmest thanks. Many of these wo have been drawn from sources where they were nearly lost to science and world.

For Dr. Wilson's contributions, numerous as ever, no additional commendat is needed here; his eulogy is already written on all around us.

Upon reference to the table, it will be seen that the additions to the differ departments of Natural History form a large proportion of the whole numb Those also from authors, editors, societies, and from our own members and c respondents, are as numerous as usual. These latter have averaged, for succ

sive years, several hundred volumes, periodicals and pamphlets, and, without other aid, would soon have filled our shelves.

We most cordially invite such contributions, which are gratifying, both as evincing a regard for the Institution, and as affording us opportunities for reciprocating. From Societies abroad, however, we have yet much to ask. Although in correspondence and exchange with many of them of the highest distinction, there are others which have failed to embrace the offers which we have extended to them. On this account foreign Societies, previously receiving our Journal and Proceedings, are now no longer on the exchange list, the only return for our publications having been formal acknowledgments of their receipt by these Societies. The value which we may now justly claim for the Journal and Proceedings of this Institution, entitles us to hope for a better and more liberal feeling hereafter.

Among the members of the Academy most conspicuous this year for contributions to the Library, I may mention Mr. George Ord and Mr. Robert Pearsall. To Mr. Ord we are indebted for 27 folio and quarto volumes of works; and to Mr. Pearsall for eight 4to and folio volumes of valuable dictionaries in foreign languages. To Mr. Haidinger, of Vienna, a correspondent of the Institution, we are under obligations for numerous works, of which he is either author or editor.

This constant and rapid influx of books and pamphlets has again nearly exhausted our available room. Scarcely two years have elapsed since the adjoining apartment was fitted up for the reception of books, yet but little space remains for additions, even in single volumes, and certainly none for any large series. Under such circumstances, and should our present rate of increase continue, it will be necessary to make further provision for accommodating the books. I therefore respectfully ask the early attention of the Society to this important matter, merely suggesting, on this occasion, that the apartment to the North of the one just referred to, and adjoining it, and now occupied as a duplicate room, and used also for unpacking parcels and boxes, could be very readily altered, at a moderate expense, and made to answer the required purpose.

I would also suggest to the Society the propriety of selling the duplicate volumes, now for the most part in the room last mentioned, and also the extensive series of French Documents. This will even be necessary, should the proposed alteration be determined upon, as no space could be spared for them, except in the cellar, where they would not be likely to benefit by the change.

The proceeds of the sale of these works would, even at auction rates, form a fund which could be most advantageously applied at present to Library purposes.

I also beg again to call the attention of the Society to a proposition made in the last report, viz: to extend the prohibition of taking books from the Hall to *all the works in the Library*. No reason now exists for permitting any work to leave the Hall, every facility for consulting them here being afforded, that can be asked for. Although thus far we have sustained no losses, nor has any injury been done, since their removal to the present apartment, yet future contingencies should be guarded against, and the fact steadily kept in view, that a single careless member may occasion a loss which neither time nor money could repair. The practice of loaning keys to strangers, who are usually irresponsible persons,

and admitting them to the Library at hours when the proper officers are not sent, is of very doubtful propriety, and, unless checked, may sooner or l cause the Society great regret.

Respectfully submitted by

Wm. S. Zantzinger,
Librarian

REPORT OF THE CURATORS

For 1851.

The Museum of this Academy, placed under the charge of the Curators and Committees of the several departments, continues, up to the present time, in best state of preservation. The depredation of insects upon destructible obj appears to be completely under control, through the combined influence of vapor of ether and the oil of turpentine.

The collection of Mammalia, during the past year, has been classified arranged by Drs. Bridges and Fisher.

All departments have received valuable additions, as follows:

Mammalia.—Of this class there have been presented 28 specimens, compri 20 species, among which was a remarkably fine specimen of a Polar bear, which we are indebted to Dr. E. K. Kane, U. S. N.; also a large Rocky M tain sheep, presented by the Smithsonian Institution. The others are princip from Dr. G. Watson, Mr. W. S. Wood, Dr. J. C. Fisher, and Mr. W. S. Vau

Aves.—42 bird skins and 17 species of eggs have been presented, chiefly Col. Geo. A. McCall, U. S. A., Messrs. Joshua Lippincott, John Lambert, J. Sergeant, and Dr. G. R. B. Horner.

There were also presented 29 nests and eggs of common English birds Edward Wilson, Esq.

Reptilia.—We are under obligation to Prof. Franklin Bache, for the orig collection of reptiles formerly belonging to Dr. Jacob Green, consisting of specimens in bottles and 15 species dried Cheloniæ. Besides these we h received 25 species, chiefly from Dr. G. Watson and Mr. R. H. Kern.

Pisces.—Of these 26 species have been presented, principally by Prof. Bache.

Mollusca.—306 species of shells have been added to our collection, the pri pal donors being Dr. J. L. Burtt, U. S. N., Dr. Wier Mitchell, and Dr. Th Stewardson.

Insecta.—Of which 200 species have been received, chiefly Coleoptera Lepidoptera.

Crustacea.—To this department we have received the greatest accessi Altogether 2,384 specimens have been presented. Of these 1,482 specime comprising 410 species, constituted the collection of M. Guerin Menevil presented to the Academy by Dr. T. B. Wilson.

Annelida and Myriapoda.—Of which we have had presented 12 species.

Zoophyta.—Of this class 117 specimens have been presented, chiefly by M Edward Wilson.

Comparative Anatomy.—In this department there have been presented and deposited 43 crania of man, and other mammalia, 2 mounted skeletons, and 7 miscellaneous objects. In this collection are particularly worthy of notice, a very perfect skeleton of a Narwhal with a tusk 8 feet in length, and four crania of the polar bear, male and female, presented by Dr. E. K. Kane.

The other skeleton presented is a remarkably fine one of a dog, articulated by Mr. Robert Nash, and obtained from Dr. F. W. Lewis.

Botany.—73 species of dried plants and fruits have been added to our collection, of which 64 species consist of fresh-water and marine algæ, presented by Mr. John Hooper, of New York.

Palæontology.—380 species of fossils have been received, among which are 42 species of minute and rare Eocene tertiary British fossils, arranged upon tablets accompanied by magnified views, prepared by the British Natural History Society, presented by Dr. T. B. Wilson. Also, the specimens from which were described the Crocodilus antiquus *Leidy*, and Balæna prisca *Leidy*, from the Miocene tertiary of Virginia, presented by Mr. Robert E. Nash; and the original specimens from which was described the Platygonus compressus *Le Conte*, presented by Dr. J. L. Le Conte.

Mineralogy.—238 specimens of minerals have been presented. Among these was a remarkably fine large group of crystals of quartz, from Cochin China, presented by Dr. J. L. Burtt, and some fine specimens of Red Chabasie (Acadialite), Stilbite, &c., from Nova Scotia, presented by our correspondent, J. L. Chipman, Esq. The remainder were obtained principally from Dr. W. L. Sherman, U. S. N., and Mr. W. S. Vaux.

As valuable additions to the Academy, for the use of its members, are two excellent compound achromatic microscopes, one manufactured by Oberhaüser, and deposited by Dr. J. K. Mitchell; the other manufactured by Pritchard, and deposited by J. P. Wetherill, Esq.

Considering the very great value of the property of the Academy we cannot take too much care in its preservation, and without having the slightest wish that the access of the members themselves, to the Museum and Library, should be restricted, we think it would be of advantage if all were precluded from lending their keys of entrance to the building to any other than members or correspondents, excepting under such circumstances as a majority of the Curators and Librarian may deem advisable.

All of which is respectfully submitted by

JOSEPH LEIDY,
Chairman of Curators.

The Annual Report of the Treasurer was read, and referred to the Auditors.

A note was read from Mr. Samuel Powel, declining a re-election as Recording Secretary, in consequence of the necessity of his prolonged absence from the city.

The following Committee was appointed to solicit subscriptions for the purpose of enlarging the Hall of the Academy, under the resolution

adopted this evening: Dr. James C. Fisher, W. S. Vaux, Georg Carpenter, Dr. R. Bridges and J. Price Wetherill.

On motion of Dr. Coates, it was

Resolved, That members be precluded from lending their ke entrance to the building, to any others than members or correspon excepting under such circumstances as a majority of the Curators a Librarian may deem advisable.

The Society then proceeded to an election for officers for 1852. following were duly elected.

President, - - - - -	GEORGE ORD.
Vice Presidents, - - -	J. Price Wetherill, Robert Bridges, M. D.
Corresponding Secretary, -	John Cassin.
Recording Secretary, - -	B. Howard Rand, M. D.
Librarian, - - - - -	Wm. S. Zantzinger, M. D.
Treasurer, - - - - -	George W. Carpenter.
Curators, - - - - -	Joseph Leidy, M. D. Wm. S. Vaux, Samuel Ashmead, John Cassin.
Auditors, - - - - -	Wm. S. Vaux, Robert Pearsall, Samuel Ashmead.
Publication Committee, - -	Wm. S. Vaux, Robert Bridges, Thomas B. Wilson, M. D. Isaac Lea, W. S. W. Ruschenberger, M

ELECTION OF MEMBER.

The Rev. John Patton, of Philadelphia, was elected a *Member* o Academy.

DONATIONS TO MUSEUM

In Nov. and Dec., 1851.

November 4th.

Egg of Rhea Darwinii, and twenty-nine Nests and Eggs of English Birds. From Edward Wilson, Esq.

Megalosoma ———, from the Isthmus of Panama. From Dr. Coleman through Mr. Conrad.

Mounted Skeleton of Domestic Dog. Prepared by R. H. Nash. Presented by Dr. F. W. Lewis.

Twenty-nine specimens of Silurian Fossils, from Green Co., Kentucky. Presented by Dr. Carson.

Mounted specimens of Cercolabes myothemera and Pithecia rufibarba, ♂ and ♀. From Wm. S. Vaux, Esq.

November 11th.

One hundred and fifty-three specimens of Coleoptera, in exchange, from Prof. Bonsdorff.

Group of Mytilus, from Carthagena, and Graphic Granite, from the Wissahickon. From Mr. Isaac Lea.

Crystalline Flag, from the Iron Furnace, Spring Mills, Pa., and Micaceous Iron, from Unionville, Pa. From Mr. Charles E. Smith.

Fruit of a Coaco Palm, (Carozo, Humboldt?.) From Dr. J. C. Fisher.

Tail of Raia ———. From Mr. Ashmead.

November 18th.

Five specimens of Coal plants, from near Greensburg, Pa. From Edward Miller, Esq.

One hundred and sixty specimens of Marine Shells, chiefly from the West Coast of America. Presented by Dr. J. Wier Mitchell.

Entire Skeleton and Tusk of Monodon Monoceros, three Crania of the Polar Bear, (Ursus maritimus,) and a specimen of the Esquimaux Dog. Presented by Dr. E. K. Kane, U. S. N.

Dorsal vertebra of Balæna palæatlantica, Leidy, from Virginia. From Mr. Isaac Lea.

December 2d.

Mass of fossil Astræa, from Florida; Palm wood, from Antigua; and fissured Coal, from Lehigh, Pa. From Mr. A. N. McPherson through Dr. Watson.

Skins of Canis lupus, var. niger, from Germany; Canis lagopus, var. cæruleus, from Iceland; Canis vulpes, and Cervus capreolus, from Denmark; and Phoca cristata, from Greenland. From the Smithsonian Institution, in exchange.

Two specimens of Cygnus Americanus, killed at Long Beach, New Jersey. Presented by Mr. Joshua Lippincott, of Philadelphia.

One hundred and eighty-three species of fifty-three genera of Crustacea, being the remainder of the collection of M. Guerin Meneville. Presented by Dr. Thos. B. Wilson.

Three crania of Troglodytes gorilla, from Borneo; bones of two Skeletons of do.; and cranium of T. niger. Procured by Rev. Dr. Wilson, Missionary in Western Africa. Deposited by Dr. Wier Mitchell.

A collection of Coleoptera and Lepidoptera, from Brazil. From Mr. Isaac Lea.

The following Crania, received from Prof. Retzius, of Stockholm, were deposited as additions to the collection of the late Dr. Morton, by his Executors, Messrs. Vaux and Pearsall, viz.:—

An ancient Cimbric, an inhabitant of Sweden; two ancient Burgundians, from a tomb near Lausanne, in Switzerland, believed to have been 2000 years old; eight true Fiuns; three Swedish Finns (mixed;) two Swedes from Finland

(colonists from remote time); three Swedes from Sundermanland; one an Cimbric Swede, probably descended from the oldest Scythic Turannic in tant, (Brachycephali,) which have always black hair and are of small sta one hybrid Laplander; one true Laplander, taken in full dress from a co

Also, one Calmuc skull, presented by Charles Cramer, Esq., of St. Peters Russia; six crania of wolves, from Sweden, and one of Ovis montana.

December 9th.

Three fragments of a fossil human cranium and three teeth, from Santas, B Presented by Dr. Charles D. Meigs; previously deposited by him.

A Compound Achromatic Microscope, (Pritchard's.) Deposited by J. Wetherill, Esq.

Specimen of Algerite, from Sussex Co., New Jersey. From Mr. W. S. V

Twenty species of Unio, from Georgia. From Dr. Thos. Stewardson.

December 16th.

Original specimens of Platygonus compressus Le Conte. Presented by Le Conte.

Three fragments of the Jaw of a fossil Crocodile; several mollusks from marl of New Jersey; Cranium of Fiber Zibethicus, dug from a marl pit in Jersey; group of large Quartz crystals, of several pounds weight, from Cc China. Presented by Dr. Burtt, U. S. N.

Five species of Ophiuridæ, from Panama. From Dr. J. L. Le Conte.

Thirty-three specimens of Minerals from Nova Scotia. From Isaac Chip Esq.

Fruit of a Palm, from Liberia. From Mr. William Ward.

DONATIONS TO LIBRARY

IN NOV. AND DEC., 1851.

November 4th.

A Synopsis of the Family of Naiades. By Isaac Lea. 2d ed. 4to. From Author.

American Journal of Science and Arts. Nov., 1851. From the Editors.

Proceedings of the Boston Society of Natural History. Vol. 4. pp. 65– From the Society.

Researches upon the origin, mode of development and nature of the Sperm particles among the four classes of Vertebrate Animals. By Waldo J. Burt M. D. From the Author.

Dr. Wilson presented the following, on the usual condition:—

Reports on the Fishes, Reptiles and Birds of Massachusetts. (G. B. Emers 8vo.

Report on the Insects of Massachusetts injurious to vegetation. (T. W. Ha M. D.) 8vo.

Reports on the Herbaceous Plants, and on the Quadrupeds of Massachuse (Rev. Chester Dewey and Ebenezer Emmons, M. D.) 8vo.

History of British Mollusca and their Shells. By Prof. Forbes and S. Han Nos. 41 and 42.

Annales de la Société Entomologique de France. 2d series, Vol. 9, pt. 2.

Journal of the Royal Geographical Society of London. Vol. 20, pt. 2.

History of the British Crustacea. By Thos. Bell. Part 7.

Annals and Magazine of Natural History. 2d series, Vol. 8. Nos. 45 and

Revue et Magasin de Zoologie. 1851. Nos. 7 and 8.

Illustrations of British Mycology. By Mrs. T. J. Hussey. 2d series. pt and 10.

The London Athenæum. September, 1851.

Conchologia Iconica. By Lovell Reeve. Part. 101.

The Genera of Diurnal Lepidoptera. By E. Doubleday, continued by J. Westwood. Pts. 47 and 48.

Comptes Rendus. Tome 33. Nos. 5 and 12.

The following were presented by Edward Wilson, Esq., on the usual condition:—

Description of the British Palæozoic Fossils of the Geological Museum of the University of Cambridge. By Frederick McCoy. Part 2. 4to.

The Zoologist. Nos. 97—101.

Narrative of an ascent to the summit of Mont Blanc, Aug. 18, 1822. By Frederick Clissold.

Geological Notes. By Henry T. De la Beche. 8vo.

Histoire naturelle des Mollusques terrestres et d'eau douce qui vivent en France. Par l'Abbé D. Dupuy. Part 4. 4to.

Memoires de la Société d'Histoire naturelle de Strasbourg. Vols. 1, 2, 3, and pt. 1, Vol. 4. 4to.

Abhandlungen der König. Gesellschaft der Wissen. zu Göttingen. Vols. 1, 2 and 3. 4to.

Proceedings of the Somersetshire Archæological and Natural History Society for 1849—'50. 8vo.

Arcana Entomologica. By J. O. Westwood. 2 vols. 8vo.

The Wisdom of God manifested in the Works of the Creation. By John Ray. Parts 1—4.

C. Linnæi Systema Naturæ. 2d ed. 1740; C. Linnæi Fundamenta Botanica. 2d ed. 1740. (In one vol. 8vo.)

The General Address of the Outinian Lecturer to his Auditors. 8vo.

Traité de la génération des Vers des Intestins, et des Vermifuges. Par M. Bloch. 8vo.

Proceedings of the Royal Irish Academy. Vol. 4.

Catalogue of the Library of the Royal Dublin Society. 8vo.

History of the Inductive Sciences. By the Rev. Wm. Whewell. 3 vols. 8vo.

Consolations in Travel; or the last days of a Philosopher. By Sir Humphrey Davy. 5th ed. 12mo.

Salmonia; or the days of Fly-fishing. By an Angler. 12mo.

Voyage historique de l'Amerique Méridionale. Par Don George Juan et par Don Antoine d'Ulloa. 2 vols. 4to.

Records of the Origin, and Proceedings of the Outinian Society. Vol. 1. Parts 1 and 2, 4to.

Histoire naturelle et morale des Iles Antilles de l'Amerique. 4to.

An account of the first discovery of Florida. By Wm. Roberts. 4to.

A voyage of discovery in H. M. S. Isabella and Alexander, for the purpose of exploring Baffin's Bay, and inquiring into the probability of a N. W. Passage. By John Ross. 4to.

The Natural and Civil History of the French Dominions in North and South America. By T. Jeffreys. Folio.

The History and Antiquities of Charnwood Forest. By T. R. Potter. 4to.

Nouveau Manuel complet d'Ornithologie domestique. Par R. P. Lesson. 12mo.

Les Perroquets; leur education, physique et morale. Par Michel. 12mo.

Faune Entomologique des Environs de Paris. Par MM. le Dr. Boisduval et Th. Lacordaire. Vol. 1, 12mo.

Musæum Tradescantianum. By John Tradiscant. 12mo.

Abhandlungen über die Gavial-Artigen Reptilien der Lias-formation von Dr. H. G. Bronn et Dr. J. J. Kaup.

Naturhistorische Tafeln des Thierreichs nebst Systematischen Namensverzeichnisse der darauf enthaltenen Gegenstande, &c. Von J. G. Lumnitzer. Folio.

Designs and Drawings of Birds and Animals by Wolf. Folio.

Description d'Ossements fossiles de Mammiferes inconnus jusqu'a present. Par J. J. Kaup; and Atlas.

Tables for the registration of periodic phenomena.

Prolusio anatomica de Sinibus frontalibus. Auctore J. J. Frid. Blumenbach.

Osteologie der Vögelfusse. Von Mag. Kessler in Petersburg.

Die Vögel Europàs. Von Ludwig S. von Moranville.

God in Science. A Lecture by the Rev. John Cumming, D. D., befor Young Men's Christian Association, Jan. 1851.

Observations on the Inhabitants, Climate, &c. made by John Bartram i Travels from Pennsylvania to Canada. 8vo. 1751.

Illustrated Catalogue of hunting trophies, native arms and costumes fro far interior of South Africa, &c. By R. G. Cumming, Esq.

Facts, observations and conjectures relative to the generation of the Opo of North America.

J. F. Blumenbachii specimen Archæologiæ Telluris terrarumque imp Hanoveranarum alterum.

Dissertation Zoologique et medicale sur le Tænia humain ou ver solitaire Victor Amédée de Lisle.

De Salamandrarum corporibus adiposis ovariis et oviductibus, eorumque e tione. Auctor M. H. Rathke.

November 11*th.*

Revision du genre Cottus des Auteurs. Par Ch. Girard. From the Autl

Report of the Commissioners of Patents for 1850. From U. S. Tre Department.

Forhandlinger ved de Skandinaviske Naturforskeres femte mode der hol Kobenhavn fra den 12th til del 17th Juli, 1847. From Prof. A. Retzius.

Phrenologien bedomd frau en Anatomisk standpunkt. Af Prof. A. Re From the same.

Dr. Wilson presented the following, on the usual condition:

Annales des Sciences Naturelles. 2e serie. Zoologie 20 vols., Bota 20 vols.

Bulletin de la Société Géologique de France. 1me serie, 14 vols.; 2e 7 vols. 8vo.

Memoires de la Société Géologique de France. 1me serie, vols. 1—3; v 1me partie. 4to.

Comptes rendus. Tome 33, Nos. 13, 14 et index du tome 32.

Revue et Magazin de Zoologie, 1851, No. 9.

Encyclopedie Anatomique. Vols. 2—9, 8vo. Atlas 1, 2, 4to. Par L. Jourdan.

Memoires de la Société Ethnologique. Vols. 1 et 2, 8vo.

Traité de Physiologie considerée comme Science d'Observation. Par Burdach; traduit de l'Allemand par A. J. L. Jourdan. 9 vols. 8vo.

Memoires de la Société Linnéenne de Normandie, 1me serie, vols. 1—4; 1—3, 4to. 2e serie, vols. 1—4, 8vo.

Comptes rendus des Séances et Mémoires de la Société de Biologie. 2, 8vo.

November 18*th.*

Pennsylvania Farm Journal. Edited by S. S. Haldeman. No. 8, Nov. From the Editor.

Catalogue of the Library of Harvard University. 4 vols. 8vo. and Supple 1 vol. 8vo. From Dr. T. W. Harris, in the name of the President and Fe of Harvard College.

Dr. Wilson presented the following on the usual condition:

Deutsches Archiv für die Physiologie. Herausgeg. von J. F. Meckel serie, 8 vols.

Archiv für Anatomie und Physiologie. Von J. F. Meckel. Vols. 1 to 6

Nouveau Systéme de Physiologie végétale et de Botanique. Par F. V. Ra 2 vols. 8vo. and Atlas.

Archiv für Anatomie, Physiologie und Wissenschaftliche Medecin. Vo J. Müller. 14 vols. 8vo.

Manuel de Physiologie. Par J. Mueller. 2 vols. 8vo.

Recherches Anatomiques et Physiologiques sur les Hemiptéres; sur le thoptéres; sur les Diptéres. Par M. Leon Dufour, (in 1 vol. 4to.)

Atlas de la Société Linnéene de Bordeaux, 2e serie, Tome 7, 1e liv.

Testacea novissima Insulæ Cubanæ et Americæ Centralis. Auctore Arthur Morelet. Part 2.

Anatomie du Cerveau dans les quatres classes des Animaux vertébrés. Par E. K. A. Serres. 2 vols. 8vo. and Atlas 4to.

Histoire naturelle des Poissons d'eau douce de l'Europe Central. Par L. Agassiz. Tome 1, 8vo. Tome 2, livs. 1 et 2, folio.

Monographies d'Echinodermes vivans et fossiles. Par L. Agassiz. Livs. 1—4, 4to; Atlas, folio.

Études critiques sur les Mollusques fossiles. Par L. Agassiz. Livs. 1—4, 4to.

Systematisches Concylien-Cabinet, von Martini und Chemnitz. Neu herausgeg. und vervollstandigt von H. C. Küster. Nos. 1—100, 4to.

December 2d.

Charleston Medical Journal and Review, Nov. 1851. From the Editors.

Memorias de la Real Academia de Ciencias de Madrid. Tomo 1, 1me partie, 4to. From the Academy.

Resumen de las Actas de la Academia Real de Ciencias de Madrid en el Ano Academico de 1849 a 1850 en la Seseon del dia 11 de Oct., por el Sec. perpet. Dr. Don Mariano Lorente. From the same.

Meteorological Register for twelve years, from 1831 to '42 inclusive, from observations made at the Military Posts of the United States. Prepared under the direction of Thomas Lawson, Surgeon General U. S. A., 8vo. From the U. S. Medical Bureau.

Ofversight af Kongl. Vetenskaps, Akademiens Förhandlinger 1848, 1849, 8vo. From the Academy.

Kongl. Vetenskaps Akad. Handlinger för ar 1848, 8vo. From the same.

Medallion (in copper) of Jacob Berzelius. From the same.

The following were presented by Dr. Wilson on the usual condition:

Zeitschrift für Malakozoologie. Von K. T. Menke und L. Pfeiffer, Nos. 1—5, 1851.

Journal of the Franklin Institute for Oct. & Nov. 1851.

The London Athenæum for October, 1851.

Histoire Naturelle des Poissons. Par le Baron Cuvier et M. Valenciennes, Texte 22 vols. 4to., Planches 4 vols. 4to.

Le Regne Animal. Par George Cuvier. Edition par une reunion des disciples de Cuvier, MM. Audouin, Blanchard, Alcide D'Orbigny, &c. 20 vols. 4to.

Revue Encyclopedique: publié par MM. Carnot et Leroux, 61 vols. 8vo.

Nouveau Dictionnaire d'Histoire Naturelle, 36 vols. 8vo.

December 9th.

Observations on the Genus Unio. By Isaac Lea. Vol. 2, 4to. From the Author.

Necrological Notice of the late Richard C. Taylor. By Isaac Lea. From the Author.

On the Genus Acostæa of D'Orbigny. By Isaac Lea. From the Author.

An Eulogium on Stephen Elliott, M.D. By James Moultrie, M. D. From the Author.

Memorial from Pennsylvania on the Manufacture of Iron, with other documents: published in behalf of the Convention of Iron-Masters. From W. Parker Foulke, Esq.

The following were presented by Dr. Wilson on the usual condition:

The Cyclopædia of Anatomy and Physiology. Edited by Robert B. Todd, M.D. Parts 1 to 41, 8vo.

Footprints of the Creator, or the Asterolepis of Stromness. By Hugh Miller. 8vo.

The Edinburgh New Philosophical Journal: conducted by R. Jameson. Vols. 1 to 50. 8vo., and Nos. 101 102.

The London, Dublin and Edinburgh Philosophical Magazine and Journal of

Science, 3d series, complete to Dec. 1850; 4th series, from Jan. to Oct. and Supplement to June, 1851.

Travels in the Island of Iceland in 1810. By Sir Geo. Mackenzie. 2d ed

A Voyage round the World in H. M. Sloop Resolution, Capt. Cook, in '3, '4, '5. By George Forster. 2 vols. 4to.

A Journey from Prince of Wales' Fort in Hudson's Bay, to the Nor Ocean, in 1769, '70, '71, '72. By Samuel Hearne. 4to.

Journal of the Horticultural Society of London, vols. 1 to 5, and vol. 6 1 to 4. 8vo.

Transactions of the Horticultural Society of London. Vol. 7, 1st series; 1, 2, 3, 2d series. 4to.

Outlines of Mineralogy, Geology and Mineral Analysis. By Thomas T son, M.D. 2 vols. 8vo.

System of Geography. By M. Malte Brun. Vols. 1—9. 8vo.

December 16th.

Annales de la Société Entomologique de France. 2d series 3me No. de From Dr. Wilson.

Comptes Rendus. Tome 33. Nos. 15—18. From the same.

Annales des Mines. 4me serie, 3me liv. de 1851. From l'Ecole des Mine

Annals of the Lyceum of the Nat. History of New York. Vol. 5. Nos. 5. From the Lyceum.

Shells of New England. A revision of the Testaceous Mollusks of England. By William Stimpson. From the Author.

General Remarks upon the Coleoptera of Lake Superior. By John L conte, M.D. From the Author.

Pennsylvania Farm Journal, No. 9, Dec. 1851. From the Editor.

Annales de l'Observatoire Physique Central de Russie, publié par ordi l'Empereur Nicholas I. Par A. T. Kupffer. An 1847, Nos. 1, 2.

The following were presented by Edward Wilson, Esq., on the usual c tion:

Die Familie der Eisvögel (Alcedidæ) Von J. Kaup.

Corrigirte Uebersicht der Falconidæ. Von Kaup.

The third tribe of the Picæ may well be termed Heterodactyli.

Vertheidigung meines Systems der Falken und Eulen gegen den Consp des Prinzen Ch. Bonaparte. Von J. Kaup.

Remarks on the modes of variation of nearly affined species or races of B chiefly inhabitants of India. By E. Blyth.

Conspectus of the Ornithology of India, Burmah and the Malayan Penin By E. Blyth, Esq.

December 23d.

The following were presented by Dr. Wilson on the usual condition:

Monograph of the Trochilidæ. By John Gould. Part 2, folio.

Conchologia iconica. By Lovell Reeve. Part 102.

Annals and Magazine of Natural History. Vol. 8, 2d series, No. 47.

Susemihl's Vögel Europas. 36 Leiferung.

Transactions of the Royal Society of Edinburgh. Vol. 20. Parts 1 and 2,

Illustrations of British Mycology. By Mrs. T. J. Hussey. 2d series, Pa

The Genera of Diurnal Lepidoptera. By E. Doubleday; continued by J Westwood. Part 49.

CATALOGUE

OF THE

CAPRIMULGIDÆ

IN THE COLLECTION OF

THE ACADEMY OF NATURAL SCIENCES

OF PHILADELPHIA.

BY

JOHN CASSIN.

NOVEMBER 1, 1851.

Family CAPRIMULGIDÆ.

I. *Subfamily CAPRIMULGINÆ.*

1. Genus CAPRIMULGUS, Linn.

1. CAPRIMULGUS EUROPÆUS, Linn. *Syst. Nat.* i. p. 346. *Selby, Ill. Brit. Orn.* i. pl. 42.*
   Caprimulgus punctatus, *Meyer. Tasch.* i. p. 284.
   Caprimulgus maculatus, *Brehm. Vög. Deuts.* p. 131.
   Caprimulgus vulgaris, *Vieill. Faune Française* i. p. 140. *Roux, Orn. Prov.* i. p. 240, pl. 147.
   1. Adult male, France. Presented by Mr. W. S. Warder.
   2, 3, 4. Adult males, Europe, from the Rivoli collection.
   5. Male, Europe, from the same.
   6. Female, Europe, from the same.

2. CAPRIMULGUS SMITHI, Bonap. *Consp. Av.* p. 59. *A. Smith, Ill. S. Af. Zool. Aves*, pl. 102.
   "Caprimulgus europæus, Auct." *A. Smith, Ill. S. Af. Zool. Aves*, p. (No. 22.)
   "Caprimulgus capensis, Verreaux." *label on specimens from Mr. Verreaux.*
   1. Adult male, Cape of Good Hope. Presented by Mr. J. P. Verreaux.
   2. Adult female, Cape of Good Hope. Presented by the same.
   3. Female, Southern Africa. Presented by the same.

3. CAPRIMULGUS RUFICOLLIS, Temm. *Man.* i. p. 438. (1820.) *Gould, B. of Europe*, pl. 52.
   Caprimulgus rufitorquis, *Vieill. Ency. Meth.* ii. p. 546. (1823.)
   Caprimulgus rufitorquatus, *Vieill. Faune Française* i. p. 142.
   1, 2. Adults, Tangier, from the Rivoli collection.
   3. Younger, Northern Africa, from the same.

4. CAPRIMULGUS PECTORALIS, Cuvier. *Regne An.* i. p. 376. (1817.) *Le Vaill. Ois. d'Af.* i. pl. 49.
   Caprimulgus africanus, *Stephens. Gen. Zool.* x. pt. i. p. 157.
   "Caprimulgus asiaticus, Lath." *Vieill. Nouv. Dict.* x. p. 238. *Griff. Cuv.* vii. p. 75.
   1. Adult male, Cape of Good Hope, from the Rivoli collection.
   2, 3. Young males, Cape of Good Hope. Presented by Mr. J. P. Verreaux.
   4. Adult female, Cape of Good Hope. Presented by the same.
   5. Very young, Cape of Good Hope.

5. CAPRIMULGUS RUFIGENA, A. Smith. *Ill. Zool. S. Af. Aves*, p
(No. 22, March, 1845,) pl. 100.
1, 2. Adult males, Cape of Good Hope. Presented b
J. P. Verreaux.
3. Adult female, Cape of Good Hope. Presented b
same.
4. Young male, Cape of Good Hope. Presented b
same.
5, 6. Cape of Good Hope, from the Rivoli collection.

6. CAPRIMULGUS TRISTIGMA, Rüpp. *Neue Wirbel.* p. 105. *Syst. l*
pl. 3. (*name on plate is wrong, vide p.* 14.)
Caprimulgus lentiginosus, *A. Smith. Ill. Zool. S. Af.* pl. 10
1. Adult male, South Africa, from the Rivoli collecti
2. Adult female, country of the Namaquas, South A
Presented by Mr. J. P. Verreaux.
3. Young female, Cape of Good Hope.
4. Male, Cape of Good Hope.

7. CAPRIMULGUS POLIOCEPHALUS, Rüpp. *Neue Wirbel.* p. 106.
Caprimulgus tetrastigma, *Rüpp. Syst. Ueber*, pl. 4. (*name on*
is wrong, vide p. 15.)
1. Adult male, Abyssinia, from the Rivoli collection
2. Adult female, Abyssinia, from the same.

8. CAPRIMULGUS NATALENSIS, A. Smith. *Ill. Zool. S. Af. A*
(No. 22, March, 1845.) pl. 99.
1. Adult male, Port Natal, Eastern Africa.
2. Adult female, Port Natal.
3. Female, Port Natal. Presented by Mr. J. P. Ver

9. CAPRIMULGUS ÆGYPTIUS, Licht. *Verz. der Doubl.* p. 59, (1
Temm. Pl. col. 379.
Caprimulgus isabellinus, *Temm. Pl. col.* iv. p. (*liv.* 64.
1827.)
1. Africa, from the Rivoli collection.
2. Adult, Egypt.

10. CAPRIMULGUS NUBICUS, Licht. *Verz.* p. 59. (1823.) *Rüpp.*
Atl. pl. 6.
Caprimulgus infuscatus, *Rüpp. Zool. Atlas, Vög.* p. 9, (182
1. Africa, from the Rivoli collection.

11. CAPRIMULGUS MADAGASCARIENSIS, Sganzin. *Mem. Soc. d'*
Nat. Strasb. iii. p. 28.
1. Adult, Madagascar, from the Rivoli collection.
2. Adult male? Madagascar?

12. CAPRIMULGUS ALBONOTATUS, Tick. *Jour. As. Soc. Beng.* ii. p.
Caprimulgus nipalensis, *Hodg. Gray, Zool. Misc.* p. 82.
Caprimulgus gangeticus, *Blyth. Ann. and Mag. Nat. Hist.* x
95. (*fide Blyth ut infra.*)

"Caprimulgus macrourus, Horsf." *Blyth. Jour. As. Soc. Beng.* xi. p. 586 (not of xiv. p. 204.)
"Caprimulgus gagateus, Strick." *Blyth. Jour. As. Soc. Beng.* xiv. p. 205.
"Caprimulgus innotatus, Hodg." *J. E. Gray. Cat. Brit. Mus. Fissirostres* p. 8.
Caprimulgus bimaculatus, *Peale. Zool. Voy. Vincennes and Peacock* p. 170.

1. Adult male, India, from Capt. Boys' collection.
2. Adult female, India, from the same.
3. Adult, India, from the Rivoli collection.
4. Adult, India.

13. CAPRIMULGUS MACRURUS, Horsf. *Trans. Linn. Soc. London*, xiii. p. 142. *Gould, B. of Aust.* ii. pl. 9.
Caprimulgus atripennis, *Jerdon. Ill. Ind. Orn.* p. (*art. Cap. indicus.*)

1, 2. Adults, Sumatra.
3, 4. Younger, Sumatra, from the Rivoli collection.
5. Adult male, Port Essington, from Mr. Gould's collection.
6. Adult female, Port Essington, from the same.

14. CAPRIMULGUS ASIATICUS, Lath. *Ind. Orn.* ii. p. 588. *Gray, Ill. Ind. Zool.* pl. 34, fig. 2.
Antrostomus californianus, *Bonap. Consp. Av.* p. 61?

1, 2. Adult, India. Presented by Mr. Thomas Ryan.
3. Adult male, India, from Capt. Boys' collection.
4. Adult, India, from the Rivoli collection.
5, 6. C. asiaticus? (smaller) India, from Capt. Boys' collection.
7. the same, India. Presented by M. Burrough, M. D.

15. CAPRIMULGUS INDICUS, Lath. *Ind. Orn.* ii. p. 588.
Caprimulgus cinerascens, *Vieill. Nouv. Dict.* x. p. 233.

1. Adult female, India, from Capt. Boys' collection.
2, 3. younger, India, from the Rivoli collection.

16. CAPRIMULGUS MONTICOLUS, Franklin. *Proc. Zool. Soc. London*, 1831, p. 116.
"Caprimulgus gymnopus, Hodg. Gray, Zool. Misc. p. 82." *Gray. Cat. Fiss.* p. 8.

1. Adult male, India, from Capt. Boys' collection.
2. Adult male, India.
3. Female, India, from the Rivoli collection.
4. Adult, India.

17. CAPRIMULGUS AFFINIS, Horsfield. *Trans. Lin. Soc. London*, xiii. p. 142.
"Caprimulgus bisignatus, Boie." *Label on specimens received from the Leyden Museum.*

1, 2. Adult, Sumatra.
3, 4. 5. Adults, from the Rivoli collection.
6. Adult female, Sumatra.
7. young, Sumatra.

18. CAPRIMULGUS MAHRATTENSIS, Sykes. *Proc. Zool. Soc. Lon* 1832, p. 83. *Gould, B. of Asia*, pl.
1. Female, India, from Capt. Boys' collection.

19. CAPRIMULGUS JOTAKA, Temm. & Schleg. *Fauna Japon. Ave* 87, pl. 12.
1. Male, Northern Asia.

2. Genus SCOTORNIS, Swainson.

1. SCOTORNIS LONGICAUDUS, (Drapiez.) *Vieill. Galerie*, pl. 122.
Caprimulgus longicaudus, *Drapiez. Dict. class. d'Hist. Nat.* v 169, (1824.)
Caprimulgus climacurus, *Vieill. Gal.* i. p. 195, (1825.)
Caprimulgus longicaudis, *Stephens. Gen. Zool.* xiii. p. 89, (18
1, 2, 3, 4. Adult males, Fazogloa, Eastern Africa, from the R collection.
5, 6. Females, same locality, from the same.
7, 8. Adult males, Western Africa, from Mr. Cassin's lection.

2. SCOTORNIS TRIMACULATUS, Swainson. *B. of West. Af. (Nat. L* ii. p. 70.
1. Western Africa.

3. Genus MACRODIPTERIX, Swainson.

1. MACRODIPTERIX LONGIPENNIS, (Shaw.) *Swains. B. of W. Af* pl. 5.
Caprimulgus longipennis, *Shaw. Nat. Mis.* pl. 265.
"Caprimulgus macrodipterus, Afzelius. Desc. Sierra Leon *Swainson. (ut sup.)*
Macrodipteryx africanus, *Swains. B. of W. Af.* ii. p. 62.
1. Adult male, Senegal, from the Rivoli collection.
2. Young male, Western Africa, from the same.
3. Female, Senegal, from the same.
4, 5, 6. Males, Western Africa, from Mr. Cassin's collection.

II. *Subfamily STEATORNINÆ.*

1. Genus STEATORNIS, Humboldt.

1. STEATORNIS CARIPENSIS, Humboldt. *Nouv. Ann. du Mus. Pa* 1834, p. 321, pl. 15.
Caprimulgus steatornis, *Humboldt. Obs. Zool.*
1. Adult male, South America, from the Rivoli collecti
2. Adult male, South America.
3. Adult female, Cayenne.

2. Genus NYCTIBIUS, Vieillot.

1. NYCTIBIUS GRANDIS, (Gm.) *Gray's Genera of Birds*, pl. 16.
   Caprimulgis grandis, *Gmelin. Syst. Nat.* i. pt. ii. p. 1029.
   Caprimulgus maximus, *Shaw. Mus. Lev.* pl. 33.
   1. Adult, Surinam. Presented by C. Hering, M. D.
   2. Adult, Cayenne, from the Rivoli collection.

2. NYCTIBIUS ÆTHEREUS, (De Wied.)
   Caprimulgus æthereus, *De Weid. Reise nach Brasilien*, i. p. 236.
   "Caprimulgus longicaudatus, Spix." *De Wied. Beitr. zur Nat. von Bras.* iii. p. 303.
   1. Adult, South America, from the Rivoli collection.
   2. Adult, South America.

3. NYCTIBIUS LONGICAUDATUS, (Spix.) *Spix, Av. Bras.* ii. pl. 1.
   Caprimulgus longicaudatus, *Spix, Av. Bras.* ii. p. 1.
   1. Adult, Cayenne, from the Rivoli collection.

4. NYCTIBIUS JAMAICENSIS, (Gm.) *Gosse, Ill. B. of Jamaica*, pl. 6.
   Caprimulgus jamaicensis, *Gmelin. Syst. Nat.* i. pt. ii. p. 1029.
   Caprimulgus griseus, *Gmelin. Syst. Nat.* i. pt. ii. p. 1029. ?
   Caprimulgus cornutus, *Vieill. Nouv. Dict.*x. p. 245, (1817.)
   "Caprimulgus Gouldii," *Catalogue of Rivoli Collection*, p. 17.
   "Caprimulgus longicaudatus, Spix." *D'Orbigny. Guérin's Mag.* 1837, p. 67.
   Nyctibius pectoralis, *Gould.* ("*Proc. Zool. Soc. London*, 1838, p. ?") *Icon. Av.* pl. 16.
   Nyctibius urutau, *La Fresnaye. Guérin's Mag. de Zool.* 1837, p. 28.
   1. Adult, Surinam. Presented by Constantine Hering, M.D.
   2, 3. Adult, Cayenne, from the Rivoli collection.
   4. Adult, Bahia.
   5. younger, South America.
   6. very young, Surinam. Presented by C. Hering, M. D.

5. NYCTIBIUS LEUCOPTERUS, (De Wied.) *Des Murs, Icon. Orn.* pl. 49, 50.
   Caprimulgus leucopterus, *De Wied. Reise*, ii. p. 227.
   1. Female, South America, from the Rivoli collection.

6. NYCTIBIUS BRACTEATUS, Gould. *Proc. Zool. Soc. London*, 1846, p. 1.
   Nyctibius rufus, *Cabanis. Schomburgk Reisen Brit. Guiana*, iii. p. 711, (1848.)
   1. Adult? South America.

3. Genus BATRACHOSTOMUS, Gould.

1. BATRACHOSTOMUS JAVANENSIS, (Horsf.) *Zool. Res. Java*, pl.
   Podargus javensis, *Horsfield. Linn. Trans. London*, xiii. p. 141.
   "Podargus cornutus, Horsf." *Temm. Pl. col.* 159.
   1. Adult, Java, from the Rivoli collection.
   2. Adult male, Java.

2. BATRACHOSTOMUS STELLATUS, Gould. *Proc. Zool. Soc. Lon* 1837, p. 43.
"Podargus crinifrons, Temm." *Bonap. Consp. Av.* p. 57.

1, 2. Adult males, Borneo.
3, 4. Adult females, Borneo.
5. young female, Borneo.
6. female.

3. BATRACHOSTOMUS PARVULUS, (Bonap.) *Conspectus Avium*, p. 5
"Podargus parvulus, Temm. Mus. Lugd." *Bonap. ut sup.*
Batrachostomus affinis, *Blyth. Jour. As. Soc. Bengal*, xvi. pt p. 1180?

1. Adult male, Indian archipelago.
2. Adult female, Indian archipelago.

4. BATRACHOSTOMUS AURITUS, (Vig.) *Gould, Icones Av.* pl.
Podargus auritus, *Vigors. Griffith's Cuv.* vii. p. 114, (1829.) *R Raffles App.* p. 652, (1830.)
Bombycistomas Fullertonii, *Hay. Jour. As. Soc. Beng.* 1841 574.

1. Adult, Malay Archipelago. Presented by Mr. Th Ryan.
2. Adult male, Malacca.

4. Genus LYNCORNIS, Gould.

1. LYNCORNIS TEMMINCKII, Gould. *Icones Avium*, p. pl. (1838
"Caprimulgus imberbis, Temm." *Gould ut sup.*
Caprimulgus pulcher, *Hay. Madras Jour. Lit. & Sci.* xiii. p. (1845.)

1, 2. Adult males, Borneo.
3. Adult female, Borneo.
4. Adult female.

III. *Subfamily PODARGINÆ.*

1. Genus PODARGUS, Cuvier.

1. PODARGUS HUMERALIS, Vig. and Horsf. *Linn. Trans. London*, p. 198. *Gould B. of Aust.* ii. pl. 3.
Podargus australis, *Stephens. Gen. Zool.* xiii. p. 92, (part ii.)?
Caprimulgus gracilis et strigoides, *Lath. Ind. Orn. Supp.* p. 5
Caprimulgus podargus, *Dumont. Dict. des Sci. Nat.* xiv. p. 50
Podargus cinereus, *Vieill. Nouv. Dict.* xxvii. p. 151?

1, 2. Adult males, Australia, from Mr. Gould's collectio
3. Adult female, Australia, from the same.
4, 5. Adults, Australia, from the Rivoli collection.
6. very young, Australia.

2. PODARGUS CUVIERI, Vig. and Horsf. *Linn. Trans. London*, xv. p. 200. *Gould, B. of Aust.* ii. pl. 4.

1. Adult male, Van Diemen's Land, from Mr. Gould's collection.
2. Adult male, Australia, from the same.
3, 4. Adult females, Van Diemen's Land, from the same.
5, 6. young, Van Diemen's Land, from the same.

3. PODARGUS MEGACEPHALUS, (Lath.)
Caprimulgus megacephalus, *Latham. Index Orn. Supp.* p. 58.
"Podargus Stanleyanus, Lath. MSS." *Vig. & Horsf. Linn. Trans. London*, xv. p. 197.

1, 2. Adults, Australia, from Mr. Gould's collection.

4. PODARGUS PHALÆNOIDES, Gould. *Proc. Zool. Soc. London*, 1839, p. 142. *B. of Aust.* ii. pl. 5.

1, 2. Adult males, Port Essington, from Mr. Gould's collection.
Adult female, Port Essington, from the same.

5. PODARGUS BRACHYPTERUS, Gould. *Proc. Zool. Soc. London*, 1840, p. 163.

1. Adult male, Australia, from Mr. Gould's collection.
2. Adult female, King George's Sound, from the same.
3, 4. Adults, Port Lincoln, from the same.
5. Adult, Swan River, from the Rivoli collection.

6. PODARGUS PLUMIFERUS, Gould. *Proc. Zool. Soc. London*, 1845, p. 104. *B. of Aust.* ii. pl. 6.

1. Adult male, Australia, from Mr. Gould's collection.
2. female? Australia, from the same.

7. PODARGUS PAPUENSIS, Quoy and Gaim. *Voy. Astrolabe, Zool.* i. p. 207. *Ois.* pl. 13.

1. Adult, Cape York.

2. Genus ÆGOTHELES, Vig. & Horsf.

1. ÆGOTHELES NOVÆ-HOLLANDIÆ, (Lath.) *Gould, B. of Aust.* ii. pl. 1.
Caprimulgus novæ-Hollandiæ, *Latham. Ind. Orn.* ii. p. 588.
Caprimulgus vittatus, *Latham. Ind. Orn. Supp.* p. 58.
Caprimulgus cristatus, *Shaw. White's Voy.* p. 241, pl. 29.
Ægotheles australis, *Swainson. Cab. Cy. Birds*, ii. p. 338.
Ægotheles lunulatus, *Jard. & Sel. Ill. Orn.* pl. 149.

1, 2. Adult males, Australia, from Mr. Gould's collection.
3. Adult female, Australia, from the same.
4. Adult female, Van Diemen's Land, from the same.
5. young female, Australia, from the same.
6. female, Australia, from the Rivoli collection.
7. young male, Australia, from the same.
8. young male, Van Diemen's Land.
9. Adult, Australia.

2. ÆGOTHELES LEUCOGASTER, Gould. *Proc. Zool. Soc. London*, p. 106. *B. of Aust.* ii. pl. 2.

1. Adult male, Port Essington, from Mr. Gould's colle
2. Adult female, Port Essington, from the same.

IV. *Subfamily CHORDEILINÆ.*

1. Genus CHORDEILES, Swainson.

1. CHORDEILES VIRGINIANUS, (Briss.) *Aud. B. of Am.* pl. 147
Caprimulgus virginianus, *Brisson. Orn.* ii. p. 477.
Caprimulgus americanus, *Wilson. Am. Orn.* v. p. 65, pl. 40
Caprimulgus popetue, *Vieillot. Ois. d'Am. Sept.* i. p. 56, p

1. Adult male, Chester county, Pennsylvania. Present J. K. Townsend, M. D.
2. Adult female, same locality. Presented by the sa
3, 4. Adult males, near Philadelphia.
5, 6, 7. Adults, North America, from the Rivoli collection
8. Young male, Mexico, from the same.
9. Younger, Bogota ? from the same.
10. female, Nicaragua, from M. de Barueil's collection

2. CHORDEILES BRASILIANUS, (Gm.)
Caprimulgus brasilianus, *Gmelin. Syst. Nat.* i. pt. ii. p. 10
Caprimulgus variegatus et noitibo, *Vieill. Nouv. Dict.* x. p. 241.
"Caprimulgus jaspideus, Merrem," *Bonap. Consp. Av.* p.
"Caprimulgus Guianensis, Linn," *Sonnini. Voy. Azara*, (F ed. 1809,) iv. p. 120.
"Caprimulgus semitorquatus, Linn. Gm. Lath," *De Wied.* iii. p. 330.

1. Adult, Cayenne, from the Rivoli collection.
2. Adult male, Columbia.
3. Female, South America, from the Rivoli collection.
4. Male, South America, from the same.
5, 6. Adults, Nicaragua, from M. de Barueil's collection

3. CHORDEILES ACUTIPENNIS, (Bodd.) *Buff. Pl. Enl.* 732.
Caprimulgus acutipennis, *Boddaert. Tab. Pl. Enl.* p. 46, (1
Caprimulgus acutus, *Gmelin. Syst. Nat.* i. pt. ii. p. 1031.
Caprimulgus pruinosus, *Tschudi. Av. Consp.* p. 8. *Faun. Aves.* pl. 6.
Caprimulgus exilis, *Lesson. Rev. Zool.* 1839, p. 44. *Comp. Œuv. de Buff.* xx. p. 258.
Chordeiles labeculatus, *Jardine. Ann. & Mag. Nat. Hist.* 1 p. 118.
"Caprimulgus semitorquatus, Linn. Gm. Pr. Max," *Tsch Faun. Per. Orn.* p. 21.
Chordeiles peruvianus, *Peale. Zool. Voy. Wilkes and Pea* p. 172.

1, 2. Adult males, Peru.
3. Younger male, Peru.
4, 5. South America, from the Rivoli collection.
6. Adult, Guayaquil. Presented by W.S.W. Ruschenberger, M. D., U. S. Navy.

4. CHORDEILES RUPESTRIS, (Spix.) *Spix, Av. Bras.* ii. pl. 2.
Caprimulgus rupestris, *Spix. Av. Bras.* ii. p.
1. Male, Rio Negro, South America.
2. Female, Rio Negro, South America.
3. very young, same locality.

5. CHORDEILES SAPITI, Bonap. *Cons. Av.* p. 63.
"Caprimulgus sapiti, Natter. Mus. Vindobonens." *Bonap. (ut sup.)*
1, 2. Adults? South America.

2. Genus LUROCALIS, Cassin.

1. LUROCALIS NATTERERII, (Temm.) *Temm. Pl. Col.* 107.
Caprimulgus Nattererii, *Temm. Pl. Col.* ii. (liv. 18.)
"Caprimulgus brachyurus, Mus. Berol," *Erman. Reise, Verz.* p. 16.
1. Adult, South America, from the Rivoli collection.
2. Adult, South America. Presented by M. Burrough, M.D.
3. Adult, Brazil.

2. LUROCALIS SEMITORQUATUS, (Gm.) *Buff. Pl. Enl.* 734.
Caprimulgus semitorquatus, *Gmelin. Syst. Nat.* i. pt. ii. p. 1031.
Podager Gouldii, *G. R. Gray. Gen. of Birds*, pl. 18.
1. Adult, Cayenne, from the Rivoli collection.
2. Adult, Demarara, from Mr. Cassin's collection.

3. LEUROCALIS LEUCOPYGUS, (Spix.) *Av. Bras. Aves.* pl. 3, fig. 2.
Caprimulgus leucopygus, *Spix. Av. Bras. Aves.* p. 3.
Chordeiles minutus, *Bonap. Consp. Av.* p. 63.
1. Adult, Brazil, from the Rivoli collection.
2. Adult, Rio Negro.

3. Genus EUROSTOPODUS, Gould.

1. EUROSTOPODUS ALBOGULARIS, (Vig. & Horsf.) *Gould, B. of Aust.* ii. pl. 7.
Caprimulgus albogularis, *Vig. & Horsf. Linn. Trans. London*, xv. p. 194.
Caprimulgus mysticalis, *Temm. Pl. Col.* 410.
Caprimulgus albomaculatus, *Cuv.*
1. Adult male, Moreton bay, Australia, from Mr. Gould's collection.
2, 3. Females, same locality, from the same.
4, 5. Australia, from the Rivoli collection.

2. EUROSTOPODUS GUTTATUS, (Vig. & Horsf.) *Gould, B. of Aust* pl. 8.
Caprimulgus guttatus, *Vig. & Horsf. Linn. Trans. London,* p. 192.

1, 2, 3. Males, Australia, from Mr. Gould's Collection.
4. Female, same locality from the same.
5. Young female? same locality, from the same.
6. Very young, Port Essington, from the same.
7. Adult, Australia, from the Rivoli collection.
8. Adult, Australia.

V. *Subfamily NYCTIDROMINÆ.*

1. Genus NYCTIDROMUS, Nuttall.

1. NYCTIDROMUS AMERICANUS, (Linn.) *Sloan, Nat. Hist. Jama* ii. p. 296, pl. 255, f. 1.
Caprimulgus americanus, *Linn. Syst. Nat.* i. p. 346, (1766.)
Caprimulgus jamaicensis, *Briss. Orn.* ii. p. 480.
Caprimulgus albicollis, *Gmelin. Syst. Nat.* i. pt. ii. p. 1030.
"Caprimulgus albicollis, Gm." *Hartlaub. Syst. Index zu Azo* p. 20, (*Bremen*, 1847.)
"Caprimulgus albicollis, Linn. Gm. Lath. Vieill." *D'Orbig Guerin's Mag.* 1837. *p.* 67.
"Caprimulgus albicollis, Gm." *Lath. Gen. Hist.* vii. p. 359.
Caprimulgus laticaudatus, *Drapicz. Dict. Class. Hist. Nat.* vi 169, (1824.)
Nyctidromus Derbyanus, *Gould. Icones Avium,* part ii. p. pl (1838.)

1, 2. Adults, South America. from the Rivoli collection.
3. Adult, Mexico, from Mr. Pease's collection.
4. Nearly adult, South America, from Mr. Cassin's collecti
5. Male, Nicaragua, from M. de Barueil's collection.

2. NYCTIDROMUS GUIANENSIS, (Gm.) *Buff. Pl. Enl.* 733.
Caprimulgus guianensis, *Gmelin. Syst. Nat.* i. pt. ii. p. 1030.
"Caprimulgus albicollis, Linn. Gmel." *De Wied. Beitr.* iii. p. 3
"Caprimulgus albicollis, Gm." *Lath. Index Orn.* ii. p. 585.

1. Adult male, Cayenne, from the Rivoli collection.
2. Younger male, Cayenne, from the same.
3. Female, Cayenne, from the same.
4, 5. Adult males, South America.
6. Younger, Surinam. Presented by C, Hering, M. D.

3. NYCTIDROMUS GRALLARIUS, (Bonap.) *Consp. Av.* p. 62.
"Caprimulgus grallarius, Wied." *Bonap. ut sup.*

1, 2. Adult males, Bogota.
3 Female, South America.

2. Genus HYDROPSALIS, Wagler.

1. HYDROPSALIS TORQUATUS, (Gm.) *Temm. Pl. col.* 157, 158.
   Caprimulgus torquatus, *Gmelin. Syst. Nat.* vol. i. pt. ii. p. 1032.
   Caprimulgus brasiliensis, *Brisson. Orn.* ii. p. 481.
   Caprimulgus furcifer, *Vieill. Nouv. Dict.* x. p. 242.
   "Caprimulgus psalurus, Azara." *Temm. Pl. col.* iv. p. (27 liv.)
   "Caprimulgus fissicaudus, Merrem." *Gray. Cat. Brit. Mus. Fissiros.* p. 10.
   "Caprimulgus grandis, Linn. Gm." *Lichtenstein. Verzeichniss,* p. 58.
   Hydropsalis Azaræ, *Wagler. Isis,* 1832, p. 1222.
   Psalurus macropterus, *Swains. Cab. Cy. Birds* ii. p. 339.
   1, 2. Adult males, South America, from the Rivoli collection.
   3, 4. Adult females, Brazil, from the same.

2. HYDROPSALIS LIMBATUS, Cassin. *Proc. Acad. Philada.* Oct. 1849.
   Hydropsalis creagra, *Bonap. Consp. Av.* p. 58, (1850.)?
   1. Adult male, South America, from the Rivoli collection.
   2. Younger male, South America, from the same.
   3. Female or young male, South America.

3. HYDROPSALIS SEGMENTATUS, Cassin. *Proc. Acad. Philada.* Oct. 1849.
   1. Male, Bogota, New Grenada, from the Rivoli collection.
   2. Female, Bogota, New Grenada, from the same.
   3. Male, South America.

4. HYDROPSALIS LYRA, Bonap. *Consp. Av.* p. 59, (1850.)
   "Hydropsalis lyra, Gould." *Bonap. ut sup.*
   1. Adult male, Bogota.
   2. Young male? South America.

5. HYDROPSALIS CLIMACOCERCUS, (Tsch.) *Fauna Peru. Aves,* pl. 6. fig. 1.
   Caprimulgus climacocercus, *Tschudi. Wiegm. Archiv.* 1844, p. 269.
   1. Female, Guiana.

3. Genus STENOPSIS. Cassin.

1. STENOPSIS CAYENNENSIS, (Gm.) *Buff. Pl. Enl.* 760.
   Caprimulgus cayennensis, *Gmelin. Syst. Nat.* i. pt. ii. p. 1031.
   Caprimulgus leucurus, *Vieill. Nouv. Dict.* x. p. 246.
   Caprimulgus cayanus, *Lath. Index* ii. p. 587.
   Caprimulgus leopetes, *Jard. and Sel. Ill. Orn.* ii. pl. 87.
   Caprimulgus odontopteron, *Lesson. Rev. Zool.* 1839, p. 105. *Comp. aux Œuv. Buff.* xx. p. 260.
   Caprimulgus enicurus, *Vieill. Nouv. Dict.* x. p. 243 ?
   Hydropsalis trifurcatus, *Natt. Tschudi, Fauna Per. Orn.* p. 129?
   1, 2. Adult males, Cayenne, from the Rivoli collection.
   3. Female, South America, from the same.
   4. Male, South America. Presented by C. Herring, M. D.

2. STENOPSIS LONGIROSTRIS, (Bonap.) *Tschudi, Faun. Per. Aves.* p
fig. 1.
Caprimulgus longirostris, *Bonaparte. Journ. Acad. Philada*
p. 384, (1825.)
Caprimulgus bifasciatus, *Gould. Proc. Zool. Soc. London*, 1
p. 22.
Caprimulgus decussatus, *Tschudi. Consp. Av.* p. 8.
1. Male, South America, from the Rivoli collection.
2. Female, South America, from the same.
3. Female, South America.

3. STENOPSIS PARVULUS, (Gould.)
Caprimulgus parvulus, *Gould. Proc. Zool. Soc. London*, 1
p. 22.
Caprimulgus æquicaudatus (♂) et conterminus, (♀), *Peale.*
Voy. Vincennes and Peacock, p. 168, 169.
1, 2. Males, South America.
3. Female, South America.

4. STENOPSIS NIGRESCENS, (Cabanis.) *Gray's Genera*, pl. 17.
Caprimulgus nigrescens, *Cabanis. Schomburgk, Reisen in*
Guiana, iii. p. 710.
"Caprimulgus semitorquatus, Gm." *Gray. Gen. ut sup.*
1. Adult, South America.

5. STENOPSIS HIRUNDINACEUS, (Spix.) *Av. Bras.* ii. pl. 3, fig. 1?
Caprimulgus hirundinaceus, *Spix. Av. Bras.* ii. p. 2?
1. Young, Cayenne, from the Rivoli collection.

4. Genus PODAGER, Wagler.

1. PODAGER NACUNDA, (Vieill.) *Temm. Pl. col.* 182.
Caprimulgus nacunda, *Vieill. Nouv. Dict.* x. p. 240.
Caprimulgus campestris, *Licht. Verzeichniss*, p. 59.
Caprimulgus diurnus, *De Wied. Reise*, ii. p. 174.
1, 2, 3. Adults, South America, from the Rivoli collection.

5. Genus ANTROSTOMUS, Gould.

1. ANTROSTOMUS CAROLINENSIS, (Gm.) *Aud. B. of Am.* pl. 52.
Caprimulgus carolinensis, *Gmelin. Syst. Nat.* i. pt. ii. p. 102
Caprimulgus lucifugus, *Bartram. Trav.* p. 292.
Caprimulgus rufus, *Vieill. Ois. d'Am.* Sept. i. p. 57, pl. 25.
Caprimulgus brachypterus, *Stephens. Gen. Zool.* x. pt. i. p. 15
1. Adult, South Carolina. Presented by William Bla
ing, M. D.
2. Adult, North America, from the Rivoli collection.
3. Adult, Florida. Presented by E. A. Abadie, M.
U. S. Army.

2. ANTROSTOMUS RUFUS, (Bodd.) *Buff. Pl. Enl.* 735.

Carprimulgus rufus, *Boddaert. Tab. Pl. Enl.* p. 46, (1783.
Caprimulgus rufus, *Gmelin. Syst. Nat.* vol. i. pt. ii. p. 1030, (1788.)

1. Adult, South America?

3. ANTROSTOMUS SERICO-CAUDATUS, Cassin. *Proc. Acad. Philada.* Oct. 1849.

1. Adult, South America.
2. Younger, South America, from the Rivoli collection.

4. ANTROSTOMUS VOCIFERUS, (Wilson.) *Wilson, Am. Orn.* pl. 41.

Caprimulgus vociferus, *Wilson. Am. Orn.* v. p. 71.
Caprimulgus clamator, *Vieill. Nouv. Dict.* x. p. 234, (1817.)
Caprimulgus macromystax, *Wagler. Isis.* 1831, p. 533?
"Caprimulgus Virginianus, Linn., Gm." *Vieill. Ois d'Am. Sept.* i. p. 55, pl. 23, (1807.)

1. Adult male, near Philadelphia. Presented by J. K. Townsend, M. D.
2. Adult female, near Philadelphia, presented by the same.
3. Adult female, near New York.
4. Female, near New York.
5. A. macromystax? Vera Cruz. Presented by M. Burrough, M. D
6. The same, Mexico.

5. ANTROSTOMUS NUTTALII, [Aud.) *Audubon, B. of Am. Octavo edition*, pl. 495.

Caprimulgus Nuttalii, *Audubon. Orn. Biog.* v. p. 385.

1. Adult, Rocky Mountains. Presented by Mr. J. J. Audubon.

6. ANTROSTOMUS OCELLATUS, (Tsch.) *Fauna Peruana, Orn.* pl. 5, fig. 2.

Caprimulgus ocellatus, *Tschudi. Weigmann, Archiv.* 1844, p. 268.
"Caprimulgus brasilianis, Linn. Gm. Prinz Max." *Tsch. Faun. Per. Orn.* p. 20.

1. Adult, South America.
2. Adult, male, Brazil.
3. Adult, Brazil.



For
USE IN LIBRARY
ONLY
DO NOT REMOVE
FROM LIBRARY

570.6
A168
V.5
1852
ALCÓNER
BIOL. LIB.
NON
ITING
MOVE
IBRARY